



559-2014 ADDENDUM 3

CONSTRUCTION OF A COMMUNITY RESOURCE RECOVERY CENTRE(4R WINNIPEG DEPOT) AT THE BRADY ROAD RESOURCE MANAGEMENT FACILITY, INCLUDING ROADWORKS AND BUILDING

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: July 17, 2014
BY: Ash Raichura, P.Eng.
TELEPHONE NO. (204) 453-2301

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20131129

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

NMS SPECIFICATIONS

- Add: Section 28 23 00 Part 2.5 Computer Racks
- Add: Section 28 23 00 Part 2.5.1 Supply and install 19" free standing rack in Scale House Building. Rack shall be suitable to house video recorder hardware, Ethernet switches, Cat6 patch panels, fibre optic patch panels.
- Add: Section 28 23 00 Part 2.6.1 Supply and install wall mount 19" rack in Pre-Fabricated Kiosk Building. Rack shall be suitable to mount network switches, Cat6 patch panels, and fibre optic patch panels.
- Delete: Section 28 23 00 Part 2.2.1.2
- Delete: Section 28 23 00 Part 2.2.1.13
- Delete: Section 28 23 00 Part 2.2.1.17
- Delete: Section 28 23 00 Part 2.2.1.18

DRAWINGS

- Replace: 559-2014 _Drawing_E2-R1 with 559-2014 _Addendum_3-Drawing_E2-R2
- 559-2014 _Drawing_E5-R2 with 559-2014 _Addendum_3-Drawing_E5-R3
- 559-2014 _Drawing_C1-R1 with 559-2014 _Addendum_3-Drawing_C1-R2

GENERAL QUESTIONS AND RESPONSES FROM BIDDERS

1	What is the distance from the Scale House to the Administration Building?	Approximately 175 metres.
---	---	---------------------------