



BASEMENT MECHANICAL RENOVATION NOTES:

- 1 EXTEND EXISTING 18"x10" COMBUSTION AND 6"Ø VENTILATION AIR DUCT INTO NEW MECHANICAL ROOM. REINSTALL ESKIMO TRAP FOR COMBUSTION AIR DUCT TERMINATING AT 12" ABOVE FLOOR LEVEL. TERMINATE 6"Ø VENTILATION AIR DUCT AT HIGH LEVEL.
- NEW 8"Ø SUPPLY AND EXHAUST DUCTING TO OUTDOORS. DUCT TO RISE UP THROUGH GRADE -LEVEL GRATE OUTDOORS. SEE DETAIL 2 ON THIS DRAWING.
- PROVIDE WIRE MESH GRILLE FOR OPEN ENDED RETURN INTO HRV-1.
 CONNECT FLEXIBLE DRAIN PIPING TO HRV-1. RUN DRAIN PIPING INTO MECHANICAL ROOM AND DISCHARGE AT FLOOR LEVEL.
- RUN NEW DUCTING IN CEILING SPACE. GRILLE TO BE FLUSH WITH CFILING.
- ALL DUCTING IN STAIRWELL TO BE ENCLOSED IN FIRE-RATED ENCLOSURE. FIRE-RATING OF ENCLOSURE TO MATCH FIRE-RATING OF STAIRWELL WALL. COORDINATE WITH ARCHITECTURAL. INSULATE INTERIOR OUTDOOR AIR INTAKE DUCTING TO HRV-1 FOR FULL LENGTH.
- 6 INSTALL FIRE DAMPERS IN DUCTING AT FIRE SEPARATION
- 7 CONNECT TO EXISTING COMBUSTION AIR AND VENTILATION AIR DUCTS IN WALL CAVITY.

MECHANICAL SYMBOLS		
SYMBOL	DESCRIPTION	
	NEW DUCTWOK	
G1 GRILLE NO. 8"x4" SIZE 70 CFM FLOW RATE	GRILLE DESCRIPTION	

ME	MECHANICAL EQUIPMENT SCHEDULE	
TAG	DESCRIPTION	
HRV-1	NU-AIR HEAT RECOVERY VENTILATOR. MODEL NU305, 115V, 170W, C/W 4' POWER CORD AND DEFROST DAMPER.	
G1	PRICE 610D SINGLE DEFLECTION SUPPLY AIR GRILLE C/W OPPOSED BLADE DAMPER. PROVIDE SUITABLE BORDER AND FRAME FOR DUCT MOUNTING.	







THE CITY OF WINNIPEG
PLANNING, PROPERTY AND
DEVELOPMENT DEPARTMENT
MUNICIPAL ACCOMMODATIONS DIVISION
3-65 GARRY STREET, R3C 4K4

AMBULANCE STATION # 3

STRUCTURAL & OCCUPANCY UPGRADES DESIGN OF STRUCTURAL UPGRADES

598 ST. MARY'S ROAD
SHEET TITLE

BASEMENT FLOOR
ENGINEERS

MECHANICAL V

APEGIN

Certificate of Authorization

KGS GROUP

No. 245

BASEMENT FLOOR PLAN
MECHANICAL VENTILATION
RENOVATION

RENOVATION

CALE | PROJECT No: | SHEET No: | AS SHOWN | 2013-047

DRAWING SHEET SIZE: A1 (841mm x 594mm) PLOT 1:1

