



656-2014 ADDENDUM 3

REPLACEMENT OF STRUCTURAL CONCRETE FLOOR FOR 598 ST. MARY'S ROAD

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: August 20, 2014
BY: ANH DUONG
TELEPHONE NO. 204-986-7588 – 204-391-0872

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20131129

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 656-2014 Bid Submission with 656-2014 Addendum 3- Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission.

Form B(R1): Add Item No. 5 inclusive.

Page numbering on some forms may be changed as a result.

PART B – BIDDING PROCEDURES

Revise: B2.1 **The Submission Deadline is 4:00 p.m. Winnipeg time, August 29, 2014.**

PART D – SUPPLEMENTAL CONDITIONS

Revise: D9.1 (c) to read: all risk course of construction in the amount of one hundred percent (100%) Contract Price plus the value of the entire building of \$4, 200,000.00, written in name of the City of Winnipeg, at all times during the performance of the Work and until the date of Total Performance.

PART E – SPECIFICATIONS

Replace:	E1.3	Mechanical drawings	656-2014_M1-R0	by	656-2014_M1-R1
			656-2014_M2-R0	by	656-2014_M2-R1
			656-2014_M3-R0	by	656-2014_M3-R1
			656-2014_M4-R0	by	656-2014_M4-R1
			656-2014_M5-R0	by	656-2014_M5-R1
Add:	E1.3	Electrical drawings	656-2014_E1-R0		

656-2014_E2-R0

656-2014_E3-R0

656-2014_E4-R0

Mechanical drawings 656-2014_M6-R0

- Add: E4 Additional details:
- E4.1 Provide drywall finish on south & west walls of basement Storage Room B05 (drawing 656-2014_ A1-R0)
 - E4.2 Steel studs & tracks for new stud walls to be minimum 20 gauge (drawing 656-2014_ A1-R0)
 - E4.3 Provide 1 hour rated bulkhead to enclose new duct work running through west end of Stairwell B01 (drawing 656-2014_M5-R1).
 - E4 .4 There appears to be no existing crawlspace west of the Ambulance Bay 125 & Museum Bay 113. This area is believed to be slab-on-grade (drawing 656-2014_ A1-R0).