



432-2015 ADDENDUM 2

PAN AM INDOOR POOL PARKING LOT REDEVELOPMENT – PHASE ONE – 25 POSEIDON BAY

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: June 19, 2015
BY: Lou M. Chubenko
TELEPHONE NO. (204) 986-2727

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20150105

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

E5. CONSTRUCTION STAGING

Delete: E5.1(b) A minimum of 50 parking spaces, including 3 handicap spaces, must be available to facility users and staff at all times during construction. Any temporary parking areas shall have temporary line painting and regulatory signs installed.

E7. PEDESTRIAN SAFETY

Revise: E7.1 to read: During the project, the Contractor shall install temporary rigid construction fence and barricades around open excavations and construction areas. The Contractor shall be responsible for maintaining the rigid construction fence and barricade in a proper working condition. No separate measurement or payment will be made for supply and installation of the rigid construction fence or barricades.

E9. PERMITS

Revise: E9.1.1 to read: Further to GC:6.12, the Contractor shall give all necessary notices, obtain all necessary permits, with the exception of the Development Permit, and pay all fees in order that the Work may be carried out. The Contractor shall submit all plans required by any inspection authority and obtain approval of same before proceeding with the Work, and pay any cost attached to the inspection of such plans.

E13. DEMOLITION / REMOVALS

Revise: E13. to read: **DEMOLITION / REMOVAL / RELOCATIONS**

Revise: E13.9 to read: Tree Removal

- Revise: E13.9.1 to read: Existing trees removal will be measured on a per item basis and paid for at the Contract Unit Price for "Tree Removal". The amount to be paid for will be the total number of trees removed in accordance with this specification, accepted and measured by the Contract Administrator.
- Add: E13.10 Tree Relocation
- Add: E13.10.1 Existing trees relocation will be measured on a per item basis and paid for at the contract Unit Price for "Tree Relocation". The amount to be paid for will be the total number of trees removed in accordance with this specification, accepted and measured by the Contract Administrator.
- Add: E13.10.2 Relocate existing trees as shown on the drawings and as directed by the contract Administrator.

E14. LAND DRAINAGE SEWER

- Delete: E14.4.2 All work and materials required to install the Inlet Flow Restrictor are incidental.

E17. LANDSCAPING, FENCING, SIGNAGE AND MISCELLANEOUS

- Revise: E17.11.1 Fencing will be measured on a length basis and paid for at the Contract Unit Price per metre for the "Items of Work" listed here below. The length to be paid for will be the total number of metres of fence supplied and installed in accordance with this specification and accepted and measured by the Contractor Administrator.
Item of Works:
i) Light Proof Screen Fence.

E20. CRUSHED STONE SURFACING

- Revise: E.20 to read: **STONE SURFACING**
- Delete: E20.1(a) Decorative Stone Mulch
(i) Limestone Cobble: Hard, dense, durable, free from seams, cracks or other structural defects, to meet following size distribution for use intended:
(i) Colour: Light Beige to Taupe.
(ii) Size: between 100 mm and 200 mm dia.
(iii) Provide photographs of cobble for approval before moving them to the proposed located.
- Delete: E20.5 **PLACING COBBLE**
(a) Place cobble to depth and details as indicated. Place cobble in manner approved by Contract Administrator create a stable mass.
- Delete: E20.6 **CLEANING**
(a) Leave unused aggregates in neat compact stockpiles as directed by Contract Administrator.

E22. TREES, SHRUBS AND GROUND COVER PLANTING

- Revise: E.22.3 to read: **ACTION AND INFORMATIONAL SUBMITTALS**
(a) Submit Mulches:
(i) All Mulches: Dyed Wood Chip.
(ii) Landscape Edging.