

Part 1 General

1.1 ADMINISTRATIVE

- .1 Submit to Contract Administrator submittals listed for review in accordance with the Specifications, or as requested by the Contract Administrator.
- .2 Submit promptly and in orderly sequence to not cause delay in Work. Failure to submit in ample time is not considered sufficient reason for extension of Contract Time and no claim for extension by reason of such default will be allowed.
 - .1 Allow 10 Working Days for review of submittals by the Contract Administrator.
- .3 Do not proceed with Work affected by submittal until review is complete.
- .4 Present shop drawings, product data, samples and mock ups in SI Metric units.
- .5 Where items or information is not produced in SI Metric units converted values are acceptable.
- .6 Review submittals prior to submission to Contract Administrator. This review represents that necessary requirements have been determined and verified, or will be, and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents. Submittals not stamped, signed, dated and identified as to specific project will be returned without being examined and considered rejected.
- .7 Notify Contract Administrator, in writing at time of submission for review, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .8 Verify:
 - .1 Field measurements
 - .2 Field construction criteria
 - .3 Catalogue numbers and similar data
 - .4 Ensure affected adjacent Work is co-ordinated.
- .9 Contractor's responsibility for errors and omissions in submission is not relieved by Contract Administrator's review of submittals.
- .10 Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Contract Administrator review.
- .11 Acceptance of Shop Drawings for a component or a subassembly does not constitute acceptance of the complete assembly of which it is a part.
- .12 The Contractor shall make any corrections required by the Contract Administrator and shall resubmit the required number of corrected copies of Shop Drawings. The Contractor shall direct specific attention in writing or on resubmitted Shop Drawings to revisions other than the corrections requested by the Contract Administrator on previous submission.
- .13 After Contract Administrator's review and return of copies, distribute copies to sub-trades as appropriate.
- .14 Keep one reviewed copy of each submission on site.

1.2 SHOP DRAWINGS AND PRODUCT DATA

- .1 The term "shop drawings" means drawings, diagrams, illustrations, schedules, performance charts, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.
- .2 The Contractor shall arrange for the preparation of clearly identified Shop Drawings as specified or as the Contract Administrator may reasonably request. Shop Drawings are to clearly indicate materials, weights, dimensions, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of the Work. Where articles or equipment attach or connect to other articles or equipment, clearly indicate that all such attachments and connections have been properly coordinated, regardless of the trade under which the adjacent articles or equipment will be supplied and installed. Shop Drawings are to indicate their relationship to design Drawings and Specifications. Notify the Contract Administrator in writing of any deviations in Shop Drawings from the requirements of the Contract Documents.
- .3 Have Shop Drawings stamped, signed and dated by a Professional Engineer licensed to practice in the Province of Manitoba where required in the Specifications or by the Contract Administrator.
- .4 The Contractor shall examine all Shop Drawings prior to submission to the Contract Administrator to ensure that all necessary requirements have been determined and verified and that each Shop Drawing has been checked and coordinated with the requirements of the Work and the Contract Documents. Examination of each Shop Drawing shall be indicated by stamp, date and signature of a responsible person of the sub-contractor for supplied items and of the General Contractor for fabricated items. Shop Drawings not stamped, signed and dated will be returned without being reviewed and stamped "Re-submit". Ensure that the following are verified:
 - .1 Field measurements.
 - .2 Field construction criteria.
 - .3 Catalogue numbers and similar data.
- .5 Submittals shall be in one of the following formats:
 - .1 Submit three (3) copies of white prints and three (3) copies of all fixture cuts and brochures.
 - .2 Submit one electronic PDF copy.
- .6 Shop Drawing reviews by the Contract Administrator is solely to ascertain conformance with the general design concept. Responsibility for approval of detail design inherent in Shop Drawings rests with the Contractor and review by the Contract Administrator shall not imply such approval.
- .7 Shop Drawings will be returned to the Contractor with one of the following notations:
 - .1 When stamped "REVIEWED" or "NO EXCEPTIONS TAKEN", distribute additional copies as required for execution of the Work.
 - .2 When stamped "REVIEWED AS MODIFIED" or "MAKE NOTED CORRECTIONS", ensure that all copies for use are modified and distributed, same as specified for "REVIEWED".
 - .3 When stamped "REVISE AND RESUBMIT", make the necessary revisions, as indicated, consistent with the Contract Documents and submit again for review.

- .4 When stamped "NOT REVIEWED" or "REJECTED", submit other Drawings, brochures, etc., for review consistent with the Contract Documents.
- .5 Only Shop Drawings bearing "REVIEWED", "NO EXCEPTIONS TAKEN", "MAKE NOTED CORRECTIONS", or "REVIEWED AS MODIFIED" shall be used on the Work unless otherwise authorized by the Contract Administrator.
- .8 After submittals are stamped "REVIEWED", "NO EXCEPTIONS TAKEN", "MAKE NOTED CORRECTIONS" or "REVIEWED AS MODIFIED", no further revisions are permitted unless re-submitted to the Contract Administrator for further review.
- .9 Any adjustments made on Shop Drawings by the Contract Administrator are not intended to change the Contract Price. If it is deemed that such adjustments affect the Contract Price, clearly state as such in writing prior to proceeding with fabrication and installation of Work.
- .10 Make changes in Shop Drawings, which the Contract Administrator may require, consistent with Contract Documents. When re-submitting, notify the Contract Administrator in writing of any revisions other than those requested by the Contract Administrator.
- .11 Only two (2) reviews of Shop Drawings will be made by the Contract Administrator at no cost. Each additional review will be charged to the Contractor at the Contract Administrator's scheduled rates. The Contract Administrator's charges for the additional Work will be deducted from the Contractor's Progress Certificates.
- .12 Show the following information in lower right hand corner of shop drawings.
 - .1 Project Title.
 - .2 Tender number or other project number assigned by the Contract Administrator.
 - .3 Name of the depicted item in accordance with the Specifications and Drawings.
 - .4 Project series number and location where the item is used if applicable.
 - .5 Specification section number if applicable
 - .6 Proposed option if applicable.
 - .7 Name of Contractor.
- .13 Accompany submissions with transmittal letter, containing:
 - .1 Date.
 - .2 Project title and number.
 - .3 Contractor's name and address.
 - .4 Identification and quantity of each shop drawing, product data and sample.
 - .5 Specification Section, Title, Number, and Clause
 - .6 Other pertinent data.
 - .7 Date and revision dates.
 - .8 Project title and Bid Opportunity number.
 - .9 Name of:
 - .1 Contractor
 - .2 Subcontractor
 - .3 Supplier
 - .4 Manufacturer
 - .5 Separate detailer when pertinent
 - .10 Identification of product of material.

- .11 Relation to adjacent structure or materials.
- .12 Field dimensions, clearly identified as such.
- .13 Specification section name, number and clause number or drawing number and detail/section number.
- .14 Applicable standards, such as CSA or CGSB numbers.
- .15 Contractor's stamp, initialled or signed, certifying review of submission, verification of field measurements and compliance with Contract Documents.

1.3 PROCEDURES

- .1 The Contractor shall, if required by the Contract Administrator, submit for the review of the Contract Administrator method statements which describe in detail, supplement with Drawings where necessary, the methods to be adopted for executing any portion of Work.
- .2 These statements shall also include details of constructional plant and labour to be employed. Acceptance by the Contract Administrator shall not relieve the Contractor of any of his responsibilities, nor shall reasonable refusal to approve entitle the Contractor to extra payment or an extension of time.
- .3 Other Considerations
 - .1 Fabrication, erection, installation or commissioning may require modifications to equipment or systems to conform to the design intent. Revise pertinent shop drawings and resubmit.
 - .2 Material and equipment delivered to the site of the works will not be paid for at least until pertinent shop drawings have been submitted and reviewed.
 - .3 Incomplete shop drawing information will be considered as stipulated deductions for the purposes of progress payment certificates.
 - .4 No delay or cost claims will be allowed that arise because of delays in submissions, re-submissions and review of shop drawings.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 REFERENCE STANDARDS

- .1 Within the text of the specifications, reference may be made to the following standards:
 - .1 ANSI American National Standards Institute
 - .2 CEC Canadian Electrical Code (published by CSA)
 - .3 CEMA Canadian Electrical Manufacturer's Association
 - .4 CSA Canadian Standards Association
 - .5 IEEE Institute of Electrical and Electronic Engineers
 - .6 NBC National Building Code
 - .7 NEMA National Electrical Manufacturers Association
 - .8 NFPA – National Fire Protection Association
 - .9 ULC Underwriters' Laboratories of Canada

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 INSPECTION

- .1 Allow Contract Administrator access to Work. If part of Work is in preparation at locations other than Place of Work, allow access to such Work whenever it is in progress.
- .2 Give timely notice requesting inspection if Work is designated for special tests, inspections or approvals by Contract Administrator instructions, or law of Place of Work.
- .3 If Contractor covers or permits to be covered Work that has been designated for special tests, inspections or approvals before such is made, uncover such Work, have inspections or tests satisfactorily completed and make good such Work.
- .4 The Contract Administrator will order part of Work to be examined if Work is suspected to be not in accordance with Contract Documents. If, upon examination such work is found not in accordance with Contract Documents, correct such Work and pay cost of examination and correction. If such Work is found in accordance with Contract Documents, the City shall pay cost of examination and replacement.

1.2 INDEPENDENT INSPECTION AGENCIES

- .1 As per Specification 02 82 12 Section 3.6, the Contractor is to engage the services of a third party Asbestos Abatement Monitoring & Inspection Agent.
- .2 In addition to the inspections required in 1.2.1, Independent Inspection/Testing Agencies may be engaged by the City for purpose of inspecting and/or testing portions of Work. Cost of such services will be borne by the City. Costs of additional tests required due to defective Work shall be paid by the Contractor.
- .3 All equipment required for executing inspection and testing will be provided by the respective agencies.
- .4 Employment of inspection/testing agencies does not relieve or relax responsibility to perform Work in accordance with Contract Documents.
- .5 If defects are revealed during inspection and/or testing, appointed agency will request additional inspection and/or testing to ascertain full degree of defect. Correct defect and irregularities as advised by the Contract Administrator at no cost to the City. Pay costs for retesting and reinspection.

1.3 ACCESS TO WORK

- .1 The City, the Contract Administrator, and other authorities having jurisdiction shall have access to the work.

1.4 REJECTED WORK

- .1 Remove defective Work, whether result of poor workmanship, use of defective products or damage and whether incorporated in Work or not, which has been rejected by the Contract Administrator as failing to conform to Contract Documents. Replace or re-execute in accordance with Contract Documents.
- .2 Make good other Contractor's work damaged by such removals or replacements promptly.
- .3 If in opinion of the Contract Administrator it is not expedient to correct defective Work or Work not performed in accordance with Contract Documents, the City will deduct

from Contract Price difference in value between Work performed and that called for by Contract Documents, amount of which will be determined by Contract Administrator.

1.5 REPORTS

- .1 Submit draft inspection and test reports to Contract Administrator, prior to inclusion with the O&M manuals, in accordance with Section 01 33 00 - Submittal Procedures.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

1.2 INSTALLATION AND REMOVAL

- .1 Provide temporary utilities controls in order to execute work expeditiously.
- .2 Remove from site all such work after use.

1.3 TEMPORARY HEATING AND VENTILATION

- .1 Provide temporary heating required during construction period, including attendance, maintenance and fuel.
- .2 Construction heaters used inside building must be vented to outside or be non-flameless type. Solid fuel salamanders are not permitted.
- .3 Provide temporary heat and ventilation in enclosed areas as required to:
 - .1 Facilitate progress of Work.
 - .2 Protect Work and products against dampness and cold.
 - .3 Prevent moisture condensation on surfaces.
 - .4 Provide ambient temperatures and humidity levels for storage, installation and curing of materials.
 - .5 Provide adequate ventilation to meet health regulations for safe working environment.
- .4 Maintain temperatures of minimum 10 degrees C in areas where construction is in progress.
- .5 Ventilating:
 - .1 Prevent accumulations of dust, fumes, mists, vapours or gases in areas occupied during construction.
 - .2 Provide local exhaust ventilation to prevent harmful accumulation of hazardous substances into atmosphere of occupied areas.
 - .3 Dispose of exhaust materials in manner that will not result in harmful exposure to persons.
 - .4 Ventilate storage spaces containing hazardous or volatile materials.
 - .5 Ventilate temporary sanitary facilities.
 - .6 Continue operation of ventilation and exhaust system for time after cessation of work process to assure removal of harmful contaminants.
 - .7 If exterior doorways are used for temporary ventilation, they should be covered with plywood with a grille for the ventilation opening.
- .6 Maintain strict supervision of operation of temporary heating and ventilating equipment to:
 - .1 Conform with applicable codes and standards.
 - .2 Enforce safe practices.
 - .3 Prevent abuse of services.

- .4 Prevent damage to finishes.
- .5 Vent direct-fired combustion units to outside.
- .7 Be responsible for damage to Work due to failure in providing adequate heat and protection during construction.

1.4 TEMPORARY POWER AND LIGHT

- .1 The existing power supply may be utilized for power, provided that there are no operational impacts associated with the use of the power.

1.5 TEMPORARY COMMUNICATION FACILITIES

- .1 Provide and pay for temporary telephone, fax, data hook up, line and equipment necessary for own use.

1.6 FIRE PROTECTION

- .1 Provide and maintain temporary fire protection equipment during performance of Work required by insurance companies having jurisdiction and governing codes, regulations and bylaws.
- .2 Burning rubbish and construction waste materials is not permitted on site.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Canadian Standards Association (CSA)
 - .1 CAN/CSA-S269.2-M1987(R2003), Access Scaffolding for Construction Purposes.

1.2 CONTRACTOR'S OFFICE

- .1 Accommodation for the Contractor's office, plant, tools, equipment, and materials (including fuel) shall be the responsibility of the Contractor. Such accommodation at the Site shall be located after consultation with the Contract Administrator. The Contractor shall be responsible for the protection of its plant, tools, equipment, and materials stored on-site. Materials stored on the City's premises shall be neatly stacked and protected from the weather.
- .2 The Contractor shall confine their activities to the minimum area necessary for undertaking and completing the Work. Material and equipment storage areas shall be at locations acceptable to the Contract Administrator.
- .3 The Contractor's construction activities shall not encroach or enter onto private property without written consent from the owner of the property concerned. The Contractor shall provide the Contract Administrator with a copy of the written agreement with the property owner.

1.3 LAYDOWN AND STORAGE

- .1 All construction materials shall be stored at designated storage areas. Stored combustible materials shall be separated by clear space to prevent fire spread and allow access for manual fire fighting equipment, including fire hoses, extinguishers, hydrants, etc.
- .2 Designated areas shall be used for storage of flammable and combustible liquids and gases. Spills shall be contained as required by Provincial Regulations.
- .3 Pressurized dry chemical fire extinguishers of suitable capacity or equally effective extinguishers as per NFPA 10 shall be provided where:
 - .1 Flammable liquids are stored or handled.
 - .2 Welding or flame cutting is performed.

1.4 TEMPORARY CONSTRUCTION MATERIALS

- .1 Tarpaulins and plastic coverings shall consist of fire retardant materials, which are UL or FM listed or approved, or which have passed the Large Scale Test specified in NFPA-701.

1.5 TOILETS AND WASHROOMS

- .1 Provide sanitary facilities for work force in accordance with governing regulations and ordinances.
- .2 Post notices and take precautions as required by local health authorities. Keep area and premises in sanitary condition.

1.6 DISPOSAL OF WASTE MATERIALS

- .1 Spoiled and waste materials shall not be dumped, under any circumstances, in any locations other than those approved by the local authorities. Any cost for permits and fees for disposing of waste materials shall be at the Contractor's expense.
- .2 Disposal of all excavated and waste materials shall be in accordance with the requirements of the appropriate provincial regulatory agencies.
- .3 When working anywhere within the Works the Contractor shall at the end of each working day remove the rubbish and leave the Site in a clean and tidy state, to the satisfaction of the Contract Administrator. If this is not done, the City will clean the Site and charge the Contractor.

1.7 PARKING

- .1 The Contractor parking shall be as designated by the Contract Administrator. The parking shall be arranged and maintained so that it does not disrupt the plant's operation and access for the City's operations and maintenance staff.

1.8 USE OF PERMANENT WATER SUPPLY, HEAT, POWER LIGHT, AND TELEPHONE

- .1 The Contractor shall not make use of permanent water supply, heat, power, or telephone inside the SEWPCC without permission from the Contract Administrator.

1.9 SITE SECURITY

- .1 The City does not normally provide security forces to the plant Site. Contractor is responsible for all material and equipment stored on the site.

1.10 SCAFFOLDING

- .1 Provide and maintain adequate scaffolding as required. Scaffolding is to be rigid, secure, and constructed to ensure adequate safety for workers. Erect without damage to the building or finishes.
- .2 Scaffolding in accordance with CAN/CSA-S269.2.

1.11 FACILITY ELECTRICAL SUPPLY AND DISTRIBUTION

- .1 If service interruptions are necessary, such interruptions shall be made only at times approved by the Contract Administrator.

1.12 HOISTING

- .1 Provide, operate and maintain hoists and cranes required for moving of workers, materials and equipment. Hoists and cranes to be operated by qualified operator.

1.13 WORK SCHEDULING AND PLANT OPERATIONS

- .1 Plan and schedule work to minimize outages on the plant operations.
- .2 Provide Work Plan for approval to Contract Administrator a minimum of 7 days prior to start of planned work. Detail work date, start/stop times, duration and required equipment or system shutdowns.
- .3 Do not start work until approval is provided from the Contract Administrator.

1.14 WARNINGS AND TRAFFIC SIGNS

- .1 When Work is performed within public areas, provide and erect adequate warning signs as necessary to give proper warning. Place signs sufficiently in advance to enable public to respond to directions.

1.15 Provide and maintain signs and other devices required to indicate construction activities or other temporary or unusual conditions resulting from the Work.

Part 2 Products

- .1 Not Used.

Part 3 Execution

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Conform to reference standards, in whole or in part as specifically requested in specifications.
- .2 If there is question as to whether products or systems are in conformance with applicable standards, the Contract Administrator reserves the right to have such products or systems tested to prove or disprove conformance.
- .3 Cost for such testing will be born by the City in event of conformance with Contract Documents or by the Contractor in event of non-conformance.

1.2 QUALITY

- .1 Products, materials, equipment and articles incorporated in Work shall be new, not damaged or defective, and of best quality for purpose intended. If requested, furnish evidence as to type, source and quality of products provided.
- .2 Defective products, whenever identified prior to completion of Work, will be rejected, regardless of previous inspections. Inspection does not relieve responsibility, but is precaution against oversight or error. Remove and replace defective products at own expense and be responsible for delays and expenses caused by rejection. Should disputes arise as to quality or fitness of products, decision rests strictly with the Contract Administrator based upon requirements of Contract Documents.
- .3 Unless otherwise indicated in specifications, maintain uniformity of manufacture for any particular or like item throughout building.
- .4 Permanent labels, trademarks and nameplates on products are not acceptable in prominent locations, except where required for operating instructions, or when located in mechanical or electrical rooms.

1.3 AVAILABILITY

- .1 Immediately upon signing Contract, review product delivery requirements and anticipate foreseeable supply delays for items. If delays in supply of products are foreseeable, notify the Contract Administrator of such, in order that substitutions or other remedial action may be authorized in ample time to prevent delay in performance of Work.
- .2 In event of failure to notify the Contract Administrator at commencement of Work and should it subsequently appear that Work may be delayed for such reason, the Contract Administrator reserves right to substitute more readily available products of similar character, at no increase in Contract Price or Contract Time.

1.4 METRIC PROJECT

- .1 Unless otherwise noted, this project has been designed and is to be constructed in the International System (SI) of Units metric system of measurements.
- .2 During construction, when specified metric elements are unattainable at the time they are required to meet the construction schedule, the Contractor shall notify the Contract Administrator in writing and suggest alternative substitutions. Costs due to these substitutions shall be borne by the Contractor.

1.5 STORAGE, HANDLING AND PROTECTION

- .1 Handle and store products in manner to prevent damage, adulteration, deterioration and soiling and in accordance with manufacturer's instructions when applicable.
- .2 Store packaged or bundled products in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until required in Work.
- .3 Store products subject to damage from weather in weatherproof enclosures.
- .4 Store cementitious products clear of earth or concrete floors, and away from walls.
- .5 Keep sand, when used for grout or mortar materials, clean and dry. Store sand on wooden platforms and cover with waterproof tarpaulins during inclement weather.
- .6 Store sheet materials, lumber and similar products on flat, solid supports and keep clear of ground. Slope to shed moisture.
- .7 Store and mix paints in heated and ventilated room. Remove oily rags and other combustible debris from site daily. Take every precaution necessary to prevent spontaneous combustion.
- .8 Remove and replace damaged products at own expense and to satisfaction of the Contract Administrator.
- .9 Touch-up damaged factory finished surfaces to Contract Administrator's satisfaction. Use touch-up materials to match original. Do not paint over name plates.

1.6 TRANSPORTATION

- .1 Pay costs of transportation of products required in performance of Work.

1.7 MANUFACTURER'S INSTRUCTIONS

- .1 Unless otherwise indicated in specifications, install or erect products in accordance with manufacturer's instructions. Do not rely on labels or enclosures provided with products. Obtain written instructions directly from manufacturers.
- .2 Notify the Contract Administrator in writing, of conflicts between specifications and manufacturer's instructions, so that the Contract Administrator will establish the course of action.
- .3 Improper installation or erection of products, due to failure in complying with these requirements, authorizes the Contract Administrator to require removal and re-installation at no increase in Contract Price or Contract Time.

1.8 CO-ORDINATION

- .1 Ensure co-operation of workers in laying out Work. Maintain efficient and continuous supervision.
- .2 Be responsible for coordination and placement of openings, sleeves and accessories.

1.9 REMEDIAL WORK

- .1 Perform remedial work required to repair or replace parts or portions of Work identified as defective or unacceptable. Co-ordinate adjacent affected Work as required.
- .2 Perform remedial work by specialists familiar with materials affected. Perform in a manner to neither damage nor put at risk any portion of Work.

1.10 PROTECTION OF WORK IN PROGRESS

- .1 Prevent overloading of parts of building. Do not cut, drill or sleeve load bearing structural member, unless specifically indicated without written approval of the Contract Administrator.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 WORKMANSHIP

- .1 Ensure Quality of Work is of highest standard, executed by workers experienced and skilled in respective duties for which they are employed. Immediately notify the Contract Administrator if required Work is such as to make it impractical to produce required results.
- .2 Do not employ anyone unskilled in their required duties. The Contract Administrator reserves the right to require dismissal from site, workers deemed incompetent or careless.
- .3 Decisions as to standard or fitness of Quality of Work in cases of dispute rest solely with the Contract Administrator, whose decision is final.

END OF SECTION

Part 1 General

1.1 SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit written request in advance of cutting or alteration which affects:
 - .1 Structural integrity of elements of project.
 - .2 Integrity of weather-exposed or moisture-resistant elements.
 - .3 Efficiency, maintenance, or safety of operational elements.
 - .4 Visual qualities of sight-exposed elements.
 - .5 Work of City or separate contractor.
- .3 Include in request:
 - .1 Identification of project.
 - .2 Location and description of affected Work.
 - .3 Statement on necessity for cutting or alteration.
 - .4 Description of proposed Work, and products to be used.
 - .5 Alternatives to cutting and patching.
 - .6 Effect on Work of City or separate contractor.
 - .7 Written permission of affected separate contractor.
 - .8 Date and time work will be executed.

1.2 MATERIALS

- .1 Required for original installation.
- .2 Change in Materials: Submit request for substitution in accordance with Section 01 33 00 - Submittal Procedures.

1.3 PREPARATION

- .1 Inspect existing conditions, including elements subject to damage or movement during cutting and patching.
- .2 After uncovering, inspect conditions affecting performance of Work.
- .3 Beginning of cutting or patching means acceptance of existing conditions.
- .4 Provide supports to assure structural integrity of surroundings; provide devices and methods to protect other portions of project from damage.

1.4 EXECUTION

- .1 Remove and replace defective and non-conforming Work.
- .2 Execute Work by methods to avoid damage to other Work, and which will provide proper surfaces to receive patching and finishing.

Part 2 Products

2.1 NOT USED

.1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

Part 1 General

1.1 PROJECT CLEANLINESS

- .1 Maintain Work in tidy condition, free from accumulation of waste products and debris, other than that caused by City or other Contractors.
- .2 Remove waste materials from site at daily regularly scheduled times or dispose of as directed by the Contract Administrator. Do not burn waste materials on site.
- .3 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .4 Provide on-site containers for collection of waste materials and debris.
- .5 Dispose of waste materials and debris off site.
- .6 Clean interior areas prior to start of finishing work, and maintain areas free of dust and other contaminants during finishing operations.
- .7 Store volatile waste in covered metal containers, and remove from premises at end of each working day.
- .8 Provide adequate ventilation during use of volatile or noxious substances. Use of building ventilation systems is not permitted for this purpose.
- .9 Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.
- .10 Schedule cleaning operations so that resulting dust, debris and other contaminants will not fall on wet, newly painted surfaces nor contaminate building systems.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Prepare instructions and data using personnel experienced in maintenance and operation of described products.
- .3 Copy will be returned after final inspection, with Contract Administrator's comments.
- .4 Revise content of documents as required prior to final submittal.
- .5 Furnish evidence, if requested, for type, source and quality of products provided.
- .6 Defective products will be rejected, regardless of previous inspections. Replace products at own expense.
- .7 Pay costs of transportation.

1.2 OPERATING AND MAINTENANCE MANUALS

- .1 Prepare using personnel experienced in maintenance and operation of described products.
- .2 Operation and maintenance instructions and technical data to be sufficiently detailed with respect to design elements, construction features, component function, correct installation procedure and maintenance requirements, to permit effective start-up, operation, maintenance, repair, modification, extension and expansion of any portion or feature of installation. Technical data to be in form of approved shop drawings, product data, supplemented by bulletins, component illustrations, exploded views, technical descriptions of items, and parts lists.
- .3 One (1) advance copy of the manuals shall be submitted prior to Substantial Performance of the Work for review and comments. After review, four (4) copies of the final manuals and two (2) copies on CD shall be submitted. Electronic copies shall be in pdf format, searchable, and have an index included in the file.
- .4 For the guidance of the City's operating and maintenance personnel, the Contractor shall prepare O&M Manuals for the Work, describing in detail the construction of each part of the Work and the recommended procedure for operation, servicing and maintenance.
- .5 All instructions in these manuals shall be in simple language to guide the City in the proper operating and maintenance of this installation.
- .6 In addition to information called for in the Specifications, include the following:
 - .1 Overall Title sheet, labelled "Operation and Maintenance Instructions", and containing project name and date, facility's covered in the manual, City's Contract number, the name and address of the Contractor, and the issue date.
 - .2 Overall list of contents, indicating the facilities upgraded by the project.
 - .3 Title sheet for each section, labelled "Operation and Maintenance Instructions", the applicable facility, and containing project name and date.
 - .4 List of contents for each section.
 - .5 Include:
 - .1 Brochures/catalogue excerpts of all components of the Work.

- .2 All certificates and results from the Asbestos Abatement Monitoring & Inspection Agent.
- .3 Documentation of all test results.
- .4 Any specific requirements from the Specifications
- .5 Include sections for the as-built drawings of all installations. Drafted as-built drawings of size 432x279mm (11 x 17") will be inserted by the Contract Administrator, based on the as-built drawings marked up by the Contractor.
- .6 Names, addresses, and telephone numbers of all major sub-contractors and suppliers.
- .7 Modify and supplement the manual as required by the Contract Administrator.
- .8 Format to be as follows:
 - .1 Organize data as instructional manual.
 - .2 Binders: vinyl, hard covered, 3 'D' ring, with spine and face pockets.
 - .3 When multiple binders are used correlate data into related consistent groupings. Identify contents of each binder on spine.
 - .4 Drawings: provide with reinforced punched binder tab. Bind in with text; fold larger drawings to size of text pages.

1.3 AS-BUILT DRAWINGS

- .1 After award of Contract, the Contract Administrator will provide a complete set of Drawings for the purpose of maintaining Project As-Built Drawings. Accurately record significant deviations from Contract Documents caused by Site conditions and changes ordered by the Contract Administrator. Update daily.
- .2 Record locations of concealed elements of mechanical and electrical services.
- .3 Identify Drawings as "Project As-Built Copy". Maintain in good condition and make available for inspection on-site by Contract Administrator at all times.
- .4 On completion of the Work, two weeks prior to final inspection, submit As-Built Drawings to Contract Administrator for review.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Comply with requirements of this Section when performing following Work:
 - .1 Removal of asbestos-containing material (ACM) from ducting and domestic hot water lines in the Primary Clarifier Building North East Stairwell and Primary Clarifier Building Tank Area as indicated on the drawings.

1.2 SECTION INCLUDES

- .1 Requirements and procedures for asbestos abatement of minor amounts of chrysotile asbestos-containing materials of the type describe within.

1.3 RELATED SECTIONS

- .1 Section 01 33 00 - Submittal Procedures.

1.4 STANDARDS

- .1 Comply with Federal, Provincial and local requirements including “Manitoba Guidelines for Working With Asbestos.”
- .2 The Worker's Compensation Act, Safety Regulations Governing Building, Construction and Demolition.
- .3 Workplace Health and Safety Act, (most recent edition).

1.5 REFERENCES

- .1 Canadian General Standards Board (CGSB).
 - .1 CAN/CGSB-1.205-2003, Sealer for Application of Asbestos-Fibre Releasing Materials.
- .2 Department of Justice Canada (Jus).
 - .1 Canadian Environmental Protection Act, 1999 (CEPA).
- .3 Health Canada/Workplace Hazardous Materials Information System (WHMIS).
 - .1 Material Safety Data Sheets (MSDS).
- .4 Transport Canada (TC).
 - .1 Transportation of Dangerous Goods Act, 1992 (TDGA).
- .5 Underwriters' Laboratories of Canada (ULC).

1.6 DEFINITIONS

- .1 HEPA vacuum: High Efficiency Particulate Air filtered vacuum equipment with filter system capable of collecting and retaining fibres greater than 0.3 microns in any dimension at 99.97% efficiency.
- .2 Amended Water: water with non-ionic surfactant wetting agent added to reduce water tension to allow wetting of fibres.
- .3 Asbestos-Containing Materials (ACMs):

- .1 a friable material containing 0.1% or greater asbestos, including fallen materials and settled dust.
- .2 a non-friable material containing 1.0% or greater asbestos, including fallen materials and settled dust.
- .4 Minor Amounts of ACMs: less than or equal to 0.1 m² of friable material containing chrysotile asbestos.
- .5 Asbestos Work Area: area where work takes place which will, or may disturb ACMs.
- .6 Authorized Visitors: Contract Administrator, or designated representative, and representative of regulatory agencies.
- .7 Friable Material: material that when dry can be crumbled, pulverized or powdered by hand pressure and includes such material that is crumbled, pulverized or powdered.
- .8 Occupied Area: any area of building or work site that is outside Asbestos Work Area.
- .9 Polyethylene: polyethylene sheeting or rip-proof polyethylene sheeting with tape along edges, around penetrating objects, over cuts and tears, and elsewhere as required to provide protection and isolation.
- .10 Glove Bag: prefabricated glove bag as follows:
 - .1 Minimum thickness 0.25 mm (10 mil) polyvinyl-chloride bag.
 - .2 Integral 0.25 mm (10 mil) thick polyvinyl-chloride gloves and elastic ports.
 - .3 Equipped with reversible double-pull double throw zipper on top and at approximately mid-section of the bag.
 - .4 Straps for sealing ends around pipe.
 - .5 Must incorporate internal closure strip if it is to be moved or used in more than one specific location.
- .11 Sprayer: garden reservoir type sprayer or airless spray equipment capable of producing mist or fine spray. Must have appropriate capacity for scope of work.
- .12 DOP Test: testing method used to determine integrity of Negative Pressure unit using dioctyl phthalate (DOP) HEPA-filter leak test.
- .13 Negative pressure: system that extracts air directly from work area, filters such extracted air through High Efficiency Particulate Air filtering system, and discharges this air directly outside work area to exterior of building.
 - .1 System to maintain minimum pressure differential of 5 Pa relative to adjacent areas outside of work areas, be equipped with alarm to warn of system breakdown, and be equipped with instrument to continuously monitor and automatically record pressure differences.
- .14 Airlock: system for permitting ingress or egress without permitting air movement between contaminated area and uncontaminated area, typically consisting of two curtained doorways at least 2 m apart.
- .15 Curtained doorway: arrangement of closures to allow ingress and egress from one room to another while permitting minimal air movement between rooms, typically constructed as follows:
 - .1 Place two overlapping sheets of polyethylene over existing or temporarily framed doorway, secure each along top of doorway, secure vertical edge of one sheet along one vertical side of doorway, and secure vertical edge of other sheet along opposite vertical side of doorway.

- .2 Reinforce free edges of polyethylene with duct tape and weight bottom edge to ensure proper closing.

1.7 SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit proof satisfactory to Asbestos Abatement Monitoring & Inspection Agent that suitable arrangements have been made to dispose of asbestos-containing waste in accordance with requirements of authority having jurisdiction.
- .3 Submit Provincial and/or local requirements for Notice of Project Form.
- .4 Submit proof of Contractor's Asbestos Liability Insurance.
- .5 Submit to Asbestos Abatement Monitoring & Inspection Agent necessary permits for transportation and disposal of asbestos-containing waste and proof that asbestos-containing waste has been received and properly disposed.
- .6 Submit proof satisfactory to Asbestos Abatement Monitoring & Inspection Agent that employees have had instruction on hazards of asbestos exposure, respirator use, dress, entry and exit from Asbestos Work Area, and aspects of work procedures and protective measures.
- .7 Submit proof that supervisory personnel have attended asbestos abatement course, of not less than two days duration, approved by Asbestos Abatement & Inspection Agent. Minimum of one supervisor for every ten workers.
- .8 Submit Worker's Compensation Board status and transcription of insurance.
- .9 Submit documentation including test results, fire and flammability data, and Material Safety Data Sheets (MSDS) for chemicals or materials including:
 - .1 encapsulants;
 - .2 amended water;
 - .3 slow-drying sealer.

1.8 QUALITY ASSURANCE

- .1 Regulatory Requirements: comply with Federal, Provincial/Territorial and local requirements pertaining to asbestos, provided that in case of conflict among these requirements or with these specifications more stringent requirement applies. Comply with regulations in effect at the time work is performed.
- .2 Health and Safety:
 - .1 Safety Requirements: worker and visitor protection.
 - .1 Protective equipment and clothing to be worn by workers while in Asbestos Work Area include:
 - .1 Non-powered reusable or replaceable filter-type respirator equipped with HEPA filter cartridges, personally issued to worker and marked as to efficiency and purpose, suitable for protection against asbestos and acceptable to Provincial Authority having jurisdiction.
 - .2 Disposable-type protective clothing that does not readily retain or permit penetration of asbestos fibres, consisting of full-body covering including head covering with snug-fitting cuffs at wrists, ankles, and neck.

- .2 Requirements for each worker:
 - .1 Remove street clothes in clean change room and put on respirator with new filters or reusable filters that have been tested as satisfactory, clean coveralls and head covers before entering Equipment and Access Rooms or Asbestos Work Area. Store street clothes, uncontaminated footwear, towels, and similar uncontaminated articles in clean change room.
 - .2 Remove gross contamination from clothing before leaving work area then proceed to Equipment and Access Room and remove clothing except respirators. Place contaminated worksuits in receptacles for disposal with other asbestos - contaminated materials. Leave reusable items except respirator in Equipment and Access Room. Still wearing the respirator proceed naked to showers. Using soap and water wash body and hair thoroughly. Clean outside of respirator with soap and water while showering; remove respirator; remove filters and wet them and dispose of filters in container provided for purpose; and wash and rinse inside of respirator. When not in use in work area, store work footwear in Equipment and Access Room. Upon completion of asbestos abatement, dispose of footwear as contaminated waste or clean thoroughly inside and out using soap and water before removing from work area or from Equipment and Access Room.
 - .3 After showering and drying off, proceed to clean change room and dress in street clothes at end of each day's work, or in clean coveralls before eating, smoking, or drinking. If re-entering work area, follow procedures outlined in paragraphs above.
 - .4 Enter unloading room from outside dressed in clean coveralls to remove waste containers and equipment from Holding Room of Container and Equipment Decontamination Enclosure system. Workers must not use this system as means to leave or enter work area.
- .3 Eating, drinking, chewing, and smoking are not permitted in Asbestos Work Area.
- .4 Before leaving Asbestos Work Area, dispose of protective clothing as contaminated waste as specified.
- .5 Ensure workers are fully protected with respirators and protective clothing during preparation of system of enclosures prior to commencing actual asbestos abatement.
- .6 Provide and post in Clean Change Room and in Equipment and Access Room the procedures described in this Section.
- .7 Ensure that no person required to enter an Asbestos Work Area has facial hair that affects seal between respirator and face.
- .2 Visitor Protection:
 - .1 Provide protective clothing and approved respirators to Authorized Visitors to work areas.
 - .2 Instruct Authorized Visitors in the use of protective clothing, respirators and procedures.
 - .3 Instruct Authorized Visitors in proper procedures to be followed in entering into and exiting from Asbestos Work Area.

1.9 WASTE MANAGEMENT AND DISPOSAL

- .1 Place materials defined as hazardous or toxic in designated containers.
- .2 Handle and dispose of hazardous materials in accordance with the CEPA, TDGA, Regional and Municipal regulations.
- .3 Disposal of asbestos waste generated by removal activities must comply with Federal, Provincial/Territorial and Municipal regulations. Dispose of asbestos waste in sealed double thickness 6 mil bags or leak proof drums. Label containers with appropriate warning labels.
- .4 Provide manifests describing and listing waste created. Transport containers by approved means to licensed landfill for burial.

1.10 EXISTING CONDITIONS

- .1 Notify Contract Administrator of friable material discovered during Work and not apparent from drawings, specifications, or report pertaining to Work. Do not disturb such material until instructed by Contract Administrator.

1.11 SCHEDULING

- .1 Co-ordinate work schedule with the Asbestos Abatement Monitoring & Inspection Agent and Asbestos Abatement Work Plan.

1.12 INSTRUCTIONS

- .1 Before beginning Work, provide Asbestos Abatement Monitoring & Inspection Agent satisfactory proof that every worker has had instruction and training in hazards of asbestos exposure, in personal hygiene and work practices, in use of glove bag procedures, and in use, cleaning, and disposal of respirators and protective clothing.
- .2 Instruction and training related to respirators includes, at minimum:
 - .1 Fitting of equipment.
 - .2 Inspection and maintenance of equipment.
 - .3 Disinfecting of equipment.
 - .4 Limitations of equipment.
- .3 Instruction and training must be provided by competent, qualified person.
- .4 Supervisory personnel to complete required training.

Part 2 Products

2.1 MATERIALS

- .1 Drop and Enclosure Sheets.
 - .1 Polyethylene: 0.15 mm thick.
 - .2 FR polyethylene: 0.15 mm thick woven fibre reinforced fabric bonded both sides with polyethylene.
- .2 Tape: fibreglass - reinforced duct tape suitable for sealing polyethylene under both dry conditions and wet conditions using amended water.
- .3 Wetting Agent: 50% polyoxyethylene ester and 50% polyoxyethylene ether mixed with water in concentration to provide thorough wetting of asbestos-containing material.

- .4 Waste Containers: contain waste in two separate containers.
 - .1 Inner container: 0.15 mm thick sealable polyethylene bag, or where glove bag method is used, glove bag itself.
 - .2 Outer container: sealable metal or fibre type where there are sharp objects included in waste material; otherwise outer container may be sealable metal or fibre type or second 0.15 mm thick sealable polyethylene bag.
 - .3 Labelling requirements: affix preprinted cautionary asbestos warning, in both official languages, that is visible when ready for removal to disposal site.
- .5 Glove bag:
 - .1 Acceptable materials: safe-T-Strip products in configuration suitable for Work, or approved equal in accordance with B7.
 - .2 Glove bags intended for use in more than one location must be equipped with reversible, double-pull, double-throw zipper on top and at approximately mid-section of bag.
- .6 Slow - drying sealer: non-staining, clear, water - dispersible type that remains tacky on surface for at least 8 hours and designed for purpose of trapping residual asbestos fibres.
 - .1 Sealer: flame spread and smoke developed rating less than 5.
- .7 Encapsulant: Serpiflex Shield or approved equal in accordance with B7.

Part 3 Execution

3.1 PREPARATION

- .1 Work Areas:
 - .1 Shut off and isolate air handling and ventilation systems to prevent fibre dispersal to other building areas during work phase. Conduct smoke tests to ensure that duct work is airtight. Seal and caulk joints and seams of active return air ducts within Asbestos Work Area.
 - .2 Preclean moveable furniture within proposed work areas using HEPA vacuum and remove from work areas to temporary location.
 - .3 Preclean fixed casework, plant, and equipment within proposed work areas, using HEPA vacuum and cover with polyethylene sheeting sealed with tape.
 - .4 Clean proposed work areas using, where practicable, HEPA vacuum cleaning equipment. If not practicable, use wet cleaning method. Do not use methods that raise dust, such as dry sweeping, or vacuuming using other than HEPA vacuum equipment.
 - .5 Put negative pressure system in operation and operate continuously from time first polyethylene is installed to seal openings until final completion of work including final cleanup. Provide continuous monitoring of pressure difference using automatic recording instrument.
 - .6 Seal off openings such as corridors, doorways, windows, skylights, ducts, grilles, and diffusers, with polyethylene sheeting sealed with tape.
 - .7 Cover floor and wall surfaces with polyethylene sheeting sealed with tape. Use one layer of FR polyethylene on floors. Cover floors first so that polyethylene extends at least 300 mm up walls then cover walls to overlap floor sheeting.

- .8 Build airlocks at entrances to and exits from work areas so that work areas are always closed off by one curtained doorway when workers enter or exit.
 - .9 At each access to work areas install warning signs in English in upper case "Helvetica Medium" letters reading as follows where number in parentheses indicates font size to be used : "CAUTION ASBESTOS HAZARD AREA (25 mm) NO UNAUTHORIZED ENTRY (19 mm) WEAR ASSIGNED PROTECTIVE EQUIPMENT (19 mm) BREATHING ASBESTOS DUST MAY CAUSE SERIOUS BODILY HARM (7 mm)".
 - .10 After work area isolation, remove heating, ventilating, and air conditioning filters, pack in sealed plastic bags 0.15 mm minimum thick and treat as contaminated asbestos waste. Remove ceiling - mounted objects such as lights, partitions, other fixtures not previously sealed off, and other objects that interfere with asbestos removal, as directed by Contract Administrator. Use localized water spraying during fixture removal to reduce fibre dispersal.
 - .11 Maintain emergency and fire exits from work areas or establish alternative exits satisfactory to Authority having jurisdiction.
 - .12 Where application of water is required for wetting asbestos-containing materials, shut off electrical power, provide 24 volt safety lighting and ground fault interrupter circuits on power source for electrical tools, in accordance with applicable CSA Standard. Ensure safe installation of electrical lines and equipment.
- .2 Worker Decontamination Enclosure System:
- .1 Worker Decontamination Enclosure System includes Equipment and Access Room, Shower Room, and Clean Room, as follows:
 - .1 Equipment and Access Room: build Equipment and Access Room between Shower Room and work area, with two curtained doorways, one to Shower Room and one to work area. Install portable toilet, waste receptor, and storage facilities for workers' shoes and protective clothing to be reworn in work area. Build Equipment and Access Room large enough to accommodate specified facilities, other equipment needed, and at least one worker allowing him /her sufficient space to undress comfortably.
 - .2 Shower Room: build Shower Room between Clean Room and Equipment and Access Room, with two curtained doorways, one to Clean Room and one to Equipment and Access Room. Provide one shower for every five workers. Provide constant supply of hot and cold or warm water. Provide piping and connect to water sources and drains. Pump waste water through 5 micrometre filter system acceptable to Contract Administrator before directing into drains. Provide soap, clean towels, and appropriate containers for disposal of used respirator filters.
 - .3 Clean Room: build Clean Room between Shower Room and clean areas outside of enclosures, with two curtained doorways, one to outside of enclosures and one to Shower Room. Provide lockers or hangers and hooks for workers' street clothes and personal belongings. Provide storage for clean protective clothing and respiratory equipment. Install mirror to permit workers to fit respiratory equipment properly.
- .3 Container and Equipment Decontamination Enclosure System:
- .1 Container and Equipment Decontamination Enclosure System consists of Staging Area within work area, Washroom, Holding Room, and Unloading Room.

Purpose of system is to provide means to decontaminate waste containers, scaffolding, waste and material containers, vacuum and spray equipment, and other tools and equipment for which Worker Decontamination Enclosure System is not suitable.

- .1 Staging Area: designate Staging Area in work area for gross removal of dust and debris from waste containers and equipment, labelling and sealing of waste containers, and temporary storage pending removal to Washroom. Equip Staging Area with curtained doorway to Washroom.
 - .2 Washroom: build Washroom between Staging Area and Holding Room with two curtained doorways, one to Staging Area and one to Holding Room. Provide high - pressure low - volume sprays for washing of waste containers and equipment. Pump waste water through 5 micrometre filter system before directing into drains. Provide piping and connect to water sources and drains.
 - .3 Holding Room: build Holding Room between Washroom and Unloading Room, with two curtained doorways, one to Washroom and one to Unloading Room. Build Holding Room sized to accommodate at least two waste containers and largest item of equipment used.
 - .4 Unloading Room: build Unloading Room between Holding Room and outside, with two curtained doorways, one to Holding Room and one to outside.
- .4 Construction of Decontamination Enclosures:
- .1 Build suitable framing for enclosures or use existing rooms where convenient, and line with polyethylene sheeting sealed with tape. Use one layer of FR polyethylene on floors.
 - .2 Build curtained doorways between enclosures so that when people move through or when waste containers and equipment are moved through doorway, one of two closures comprising doorway always remains closed.
- .5 Separation of Work Areas from Occupied Areas:
- .1 Separate parts of building required to remain in use from parts of building used for asbestos abatement by means of airtight barrier system constructed as follows:
 - .1 Build suitable floor to ceiling lumber or metal stud framing, cover with polyethylene sheeting sealed with tape, and apply 9 mm minimum thick plywood. Seal joints between plywood sheets and between plywood and adjacent materials with surface film forming type sealer, to create airtight barrier.
 - .2 Cover plywood barrier with polyethylene sealed with tape, as specified for work areas.
- .6 Maintenance of Enclosures:
- .1 Maintain enclosures in tidy condition.
 - .2 Ensure that barriers and polyethylene linings are effectively sealed and taped. Repair damaged barriers and remedy defects immediately upon discovery.
 - .3 Visually inspect enclosures at beginning of each working period.
 - .4 Use smoke methods to test effectiveness of barriers when directed by Contract Administrator or Asbestos Abatement Monitoring & Inspection Agent.
- .7 Do not begin Asbestos Abatement work until:

- .1 Arrangements have been made for disposal of waste.
- .2 For wet stripping techniques, arrangements have been made for containing, filtering, and disposal of waste water.
- .3 Work areas and decontamination enclosures and parts of building required to remain in use are effectively segregated.
- .4 Tools, equipment, and materials waste containers are on hand.
- .5 Arrangements have been made for building security.
- .6 Warning signs are displayed where access to contaminated areas is possible.
- .7 Notifications have been completed and other preparatory steps have been taken.

3.2 SUPERVISION

- .1 Minimum of one supervisor for every ten workers is required.
- .2 Approved supervisor must remain within Asbestos Work Area during disturbance, removal, or other handling of asbestos-containing materials.

3.3 ASBESTOS REMOVAL

- .1 Before removing asbestos:
 - .1 Prepare site.
 - .2 Spray asbestos material with water containing specified wetting agent, using airless spray equipment capable of providing "mist" application to prevent release of fibres. Saturate asbestos material sufficiently to wet it to substrate without causing excess dripping. Spray asbestos material repeatedly during work process to maintain saturation and to minimize asbestos fibre dispersion.
- .2 Remove saturated asbestos material in small sections. Do not allow saturated asbestos to dry out. As it is being removed pack material in sealable plastic bags 0.15 mm minimum thick and place in labelled containers for transport.
- .3 Seal filled containers. Clean external surfaces thoroughly by wet sponging. Remove from immediate working area to Staging Area. Clean external surfaces thoroughly again by wet sponging before moving containers to decontamination Washroom. Wash containers thoroughly in decontamination Washroom, and store in Holding Room pending removal to Unloading Room and outside. Ensure that containers are removed from Holding Room by workers who have entered from uncontaminated areas dressed in clean coveralls.
- .4 After completion of stripping work, wire brushed and wet-sponged surfaces from which asbestos has been removed to remove visible material. During this work keep surfaces wet.
- .5 After wire brushing and wet sponging to remove visible asbestos, wet clean entire work area including Equipment and Access Room, and equipment used in process.

3.4 FINAL CLEANUP

- .1 Following cleaning specified in above, and when air sampling shows that asbestos levels on both sides of seals do not exceed 0.01 fibres/cc as determined by membrane filter method at 400-500X magnification phase contrast illumination, as described in NIOSH 94-113 or equivalent, proceed with final cleanup.
- .2 Remove polyethylene sheet by rolling it away from walls to centre of work area. Vacuum visible asbestos-containing particles observed during cleanup, immediately, using HEPA vacuum equipment.

- .3 Place polyethylene seals, tape, cleaning material, clothing, and other contaminated waste in plastic bags and sealed labelled waste containers for transport.
- .4 Include in clean-up Work areas, Equipment and Access Room, Washroom, Shower Room, and other contaminated enclosures.
- .5 Include in clean-up sealed waste containers and equipment used in Work and remove from work areas, via Container and Equipment Decontamination Enclosure System, at appropriate time in cleaning sequence.
- .6 Conduct final check to ensure that no dust or debris remains on surfaces as result of dismantling operations and carry out air-monitoring again to ensure that asbestos levels in building do not exceed 0.01 fibres/cc. Repeat cleaning using HEPA vacuum equipment, or wet cleaning methods where feasible, in conjunction with sampling until levels meet this criteria.
- .7 As work progresses, and to prevent exceeding available storage capacity on site, remove sealed and labelled containers containing asbestos waste and dispose of to authorized disposal area in accordance with requirements of disposal authority. Ensure that each shipment of containers transported to dump is accompanied by Contractor's representative to ensure that dumping is done in accordance with governing regulations.

3.5 RE-ESTABLISHMENT OF OBJECTS AND SYSTEMS

- .1 When cleanup is complete:
 - .1 Re-establish objects and furniture moved to temporary locations in course of Work, in their proper positions.
 - .2 Re-secure mounted objects removed in course of Work in their former positions.
 - .3 Re-establish mechanical and electrical systems in proper working order. Install new filters.
 - .4 Repair or replace objects damaged in the course of Work, as directed by Contract Administrator.

3.6 AIR MONITORING

- .1 Contractor is to engage the services of a third party Asbestos Abatement Monitoring & Inspection Agent.
- .2 From beginning of Work until completion of cleaning operations, Asbestos Abatement Monitoring & Inspection Agent to take air samples on daily basis outside of Asbestos Work Area enclosure in accordance with Health Canada recommendations.
 - .1 Contractor will be responsible for monitoring inside enclosure in accordance with applicable Provincial Occupational Health and Safety Regulations.
- .3 If air monitoring shows that areas outside Asbestos Work Area enclosure are contaminated, enclose, maintain and clean these areas in same manner as that applicable to Asbestos Work Area.
- .4 Ensure that respiratory safety factors are not exceeded.

END OF SECTION