



# 582-2015 ADDENDUM 1

## ANNABELLA WALKWAY PROJECT – ANNABELLA STREET, WINNIPEG, MB

### URGENT

**PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY**

ISSUED: October 13, 2015  
BY: ENG-TECH Consulting Limited  
TELEPHONE NO. 204 233-1694

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS**

Template Version: A20150806

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.**

### PART A – BID SUBMISSION

Replace: 582-2015 Bid Submission with 582-2015 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

- Form B(R1):        Revise Approximate Quantity of Upper Staircase Rocks to 9 tons.
- Revise Approximate Quantity of Lower Staircase Rocks to 28 tons.

### PART E – SPECIFICATIONS

- Revise: E5.6 to read:        The galvanized gabion baskets shall be installed below the staircase rocks as shown on Drawing Nos. 2 and 3. Three (3) gabion baskets sized 3.0 m x 1.0 m x 0.3 m and four (4) gabion baskets sized 2.0 m x 1.0 m x 0.3 m will be required to complete the staircase. The baskets shall be a Standard mesh-wire, with an internal wire diameter of 2.70 mm, an external wire diameter of 3.70 mm, and a tensile strength of at least 500 MPa, as per ASTM A641.03. **Gabion filling stones shall be 100 mm to 200 mm in diameter. Approximately 10 m<sup>3</sup> of excavated material will be required to be removed from site for the installation of the gabion baskets.**
  
- Revise: E6.4 to read:        Rip-rap is to be added to the existing rip-rap at the toe of the bank at the locations shown on Drawing No. 2 **using 150 mm to 300 mm diameter rock** to achieve a rip-rap thickness of approximately 0.5 m. An estimated 120 tons of rip-rap will be required along the toe of the slope.
  
- Add: E7.**                        SITE ACCESS AND CONTROL
  
- Add: E7.1**                      This specification shall be included in the work required under the heading Mob-Demobilization, and Site Preparation, as shown in Form B: Prices, and shall include the removal and replacement of the boulder and post at the south end of Annabella Street in order to provide access for machinery and equipment, and closing access to both sides of the bike path to the public during working hours

**Add: E8.**

**ROCKS ON DISPLAY**

**Add: E8.1**

The City of Winnipeg has purchased rocks from Mariash Quarry to put on display in the parking lot of 854 Marion Street, Winnipeg, MB. These rocks have been set up as to illustrate the concept of the walkway. The display consists of approximately 2 tons of walkway edge rocks, 1.5 tons of flag stone, 1.5 tons of upper staircase rocks, and 1.5 tons of lower staircase rocks. These quantities are included in the totals as shown on Form B: Prices. The above tonnages will be subtracted from the tonnage to be purchased from the quarry. The winning bidder will be required ship the rocks on display to the site and install. Payment will be based on the total weight on display plus the rocks purchased at the quarry.