

.51

CONTRACTOR TO VERIFY LOCATION AND TYPE OF ALL EXISTING BURIED UTILITIES.

ALL MATERIALS AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE CI
OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATION.

LDS SEWER PIPES TO BE PVC OR CONCRETE.

ALL TRENCH, MANHOLE AND CATCH BASIN BACKFILL FOR WATER, SEWER AND PVC CONDUIT
INSTALLATIONS SHALL BE CLASS 2 BEDDING AND BACKFILL IN PAVEMENT AREAS AND CLASS 4
BACKFILL IN LANDSCAPED AREAS.

THE CONTRACTOR SHALL CLEAN AND VIDEO INSPECT ALL STORM AND SANITARY SEWERS PRIOR TO
FINAL INSPECTION. THE CONTRACTOR SHALL SUBMIT (2) TWO COPIES OF THE WRITTEN REPORT AND
VIDEO TO THE SITE SERVICING CONSULTANT.

ALL CATCH BASINS TO HAVE SUBDRAINS IN ACCORDANCE WITH THE DETAIL.

THIS DRAWING IS NOT TO BE USED FOR SURVEY LAYOUT.

THE CITY

GENERAL NOTES



GRADING NOTES

231.46+ 31.66+ EXTRAPOLATED GRADE

SLOPE

CONTRACTOR TO BE ADVISED THAT EXISTING GRADES ARE GIVEN AS INFORMATION ONLY AND SHOULD BE VERIFIED ON SITE. REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO ANY CONSTRUCTION. 1. ALL GRADING TO BE STAKED AND APPROVED BY CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. 2. ALL PROPOSED ELEVATIONS TO BE FINISHED ELEVATIONS. 3. ALL PROPOSED ELEVATIONS TO BE FINISHED ELEVATIONS. 4. REFER TO LAYOUT PLAN LI.1, FOR AYOUT OF PAITWAYS, CURBS, SWALES, ETC. 5. EXISTING GRADE TO BE MAINTAINED AT ALL PROPERTY LINES, LIMIT OF WORK LINE AND CITY SIDEWALKS. 6. PAITWAY SLOPES: -MAXIMUM 5% -MAXIMUM 5% -MAXIMUM 2% -MAXIMUM 2% -MAXIMUM 5% -MAXIMUM 5

- EXISTING GRADE

INVERT

HIGH POINT

CATCH PIT


CATCH BASIN

ISSUED FOR TENDER
99% CITY REVIEW
33% CITY REVIEW

08-06-15

1:200

GL



GRADING

15-031