### **DRAWING INDEX**

SHEET NUMBER	CITY OF WINNIPEG DRAWING NUMBER	DRAWING TITLE
1	D-14045	DRAWING INDEX, DESIGN NOTES, LEGEND, & ABBREVIATIONS
2	D-14046	DALY STREET NORTH - W P OF PEMBINA HIGHWAY TO E P OF PEMBINA HIGHWAY
3	D-14047	FLEET AVENUE - PEMBINA HIGHWAY TO NASSAU STREET NORTH
4	D-14048	GARWOOD AVENUE - W ₹ OF PEMBINA HIGHWAY TO € OF PEMBINA HIGHWAY
5	D-14049	MULVEY AVENUE - DALY STREET NORTH TO 49 W OF PEMBINA HIGHWAY
6	D-14050	MULVEY AVENUE - 49 W OF PEMBINA HIGHWAY TO E P OF PEMBINA HIGHWAY
7	D-14051	NASSAU STREET NORTH - WARSAW STREET TO 2 E OF PEMBINA HIGHWAY
8	D-14052	NASSAU STREET NORTH - 2 E OF PEMBINA HIGHWAY TO 17 E OF FLEET STREET
9	D-14053	PEMBINA HIGHWAY - LORETTE AVENUE TO DUDELY AVENUE
10	D-14054	PEMBINA HIGHWAY - DUDLEY AVENUE TO DALY STREET NORTH
11	D-14055	PEMBINA HIGHWAY - DALY STREET NORTH TO FLEET AVENUE

### **ABBREVIATIONS**

WWS	WASTE WATER SEWER	
cs	COMBINED SEWER	
LDS	LAND DRAINAGE SEWER	
PL	PROPERTY LINE	
<b>Q</b>	CENTER LINE	
G.I.S.	GEOGRAPHIC INFORMATION SYSTEM	
B.M.	BENCH MARK	
TH	TEST HOLE	
ELEV	ELEVATION	
INV	INVERT	
MIN	MINIMUM	
MAX	MAXIMUM	
SL	STREET LIGHTING	
TS	TRAFFIC SIGNALS	
ABAND	ABANDONED	
BLDG	BUILDING	
HSE	HOUSE	
CRN	CORNER	
OPP	OPPOSITE	
C/S OR S/C	CURB STOP	
MTS	MANITOBA TELEPHONE SYSTEM	
R.O.W.	RIGHT-OF-WAY	
WM	WATERMAIN	
CULV	CULVERT	
MH	MANHOLE	
CB	CATCH BASIN	
CI	CURB INLET	
VERT.	VERTICAL	
HORZ.	HORIZONTAL	
I.B.	IRON BAR	
FIBRE	FIBRE OPTIC	
TYP		
X-ING	TYPICAL	
	CROSSING	
HYD	HYDRANT	
EXIST	EXISTING	
N E	NORTH	
	EAST	
S	SOUTH	
W	WEST	
W/	WITH	
C/W	CONSTRUCTED WITH	
CONC	CONCRETE	
AC	ASBESTOS CEMENT	
VC OR CLAY	VITRIFIED CLAY	
CI	CAST IRON	
DI	DUCTILE IRON	
PVC	POLYVINYL CHLORIDE	
HDPE	HIGH DENSITY POLYETHYLENE	
PCCP	PRESTRESSED CONCRETE CYLINDER PIPE	

### **LEGEND**

DESCRIPTION	EXISTING	PROPOSED
WATER PIPE	·	
FIRE HYDRANT	- <del>-</del>	+
VALVE	⊗ .	8
CURB STOP	o`	•
REDUCER	4	<b>◆</b>
COUPLING OR SLIDDER  CROSS	⊕ X	<b>X</b> ⊕
BEND - 11.25°, 22.5°, 45°, 90°	# H H H T	H 4 4 5
TEE 71.25, 22.5, 45, 90	H.	A
VERTICAL BEND	н	н
ANODE	Ð	<del>-</del> >
REPAIR MARKER	₿	
PLUG	3	3
SEWER PIPE		
MANHOLE	0	•
CATCH BASIN		
CURB INLET	∇ .	▼ .
JUNCTION	<del></del>	
€ DITCH		
CULVERT		
SURVEY BAR	#	±
SURVEY MONUMENT	Ψ <b>(Δ</b> )	<b>∓</b> <b>▲</b>
		9
TREE - DECIDUOUS	₹ <u>·</u> )	
TREE CONFERDATIO		
TREE - CONIFEROUS		
HYDRO		
HYDRO POLE	•н	
LAMP STANDARD	•-•	
HYDRO POLE W/STREET LIGHTING	H <b>⊕</b> —•	
POLE	•	
GUY ANCHOR	<del>(</del>	
M.T.S. POLE	•M ⊠	
PEDESTAL OR BOX		
CABINET		
M.T.S., SHAW, OR VIDEON		<u> </u>
TRAFFIC SIGNALS	· · ·	_ · _ · _ · _
TRAFFIC LIGHT STANDARD	•→	
GAS	···	
STEAM		
FIBRE OPTIC		
FENCE	xx	xx
EDGE OF PAVEMENT OR GUTTER		
EDGE UNPAVED OR GRAVEL ROAD		
PPO IECTED P		
PROJECTED PL LOT LINE		
LOT LINE SIDEWALK — PATHWAY		
EASEMENT		
	<i>[7]]]]]]]</i>	
EDGE OF BUILDING		
MAILBOX	M	
PARKING METER	P	
TEST HOLE	•	<b>*</b>
TREE LINE OR BUSH	~~~~~	
DESCRIPTION	PROFILE EXISTING	PROPOSED
WATER PIPE		
HYDRANT TOP	+	+
VALVE		X
· · · · · · · · · · · · · · · · · · ·		
TEE OR CROSS		()
	V	V
COUPLING OR BEND		
REDUCER		
	<del></del>	
END OF PIPE	6	δ
SEWER PIPE		
UNPAVED GROUND SURFACE		
AVED GROUND SURFACE - & PIPE	XX	
GUTTER (NORTH AND WEST)	<del></del>	
GUTTER (SOUTH AND EAST)	<del></del>	

PLAN VIEW

# **CONSTRUCTION NOTES**

- 1. EXPOSE EXISTING WATERMAIN & CONFIRM INVERTS PRIOR TO CONSTRUCTION.
- 2. LOCATION OF ALL SERVICES TO BE CONFIRMED IN THE FIELD.
- 3. INSTALL WATERMAIN BY TRENCHLESS METHODS.
- 4. TRENCHES AND EXCAVATIONS WITHIN 1 METRE OF A PAVED AREA INCLUDING SIDEWALKS SHALL BE CLASS 3 BACKFILL.
- 5. ALL MATERIALS SHALL CONFORM TO THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS.

REVISIONS

- 6. MINIMUM COVER TO TOP OF WATERMAIN SHALL BE 2.4 m.
- 7. REPLACE ALL EXISTING LEAD SERVICES FROM PROPOSED WATERMAIN TO P.
- 8. NOTIFY ALL AFFECTED RESIDENTS AND BUSINESSES 24 HOURS IN ADVANCE OF ANY WATER SHUTDOWNS OR DISRUPTION OF SERVICE.

# **HATCH PATTERNS**

DESCRIPTION EXISTING PROPOSED EARTH OR GROUND ABOVE PIPE SAND OR OTHER FINE MATERIAL CONCRETE WASHED STONE OR GRANULAR MATERIAL INTERLOCKING STONE METAL GRAVEL OR STONE

ENGINEER'S SEAL LOCATION APPROVED UNDERGROUND STRUCTURES CONSTRUCTION COMPLETION DATE: YYYY MM DD ORIGINAL SIGNED SUPV. U/G STRUCTURES COMMITTEE DATE BY S.J.R. COURNOYER CHECKED DESIGNED 15/07/23 SC MK DRAWN APPROVED RS LOCATION OF UNDERGROUND STRUCTURES AS LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION. SCALE: RELEASED FOR CONSTRUCTION 1: 250 HORIZONTAL CONSULTANT DRAWING NUMBER VERTICAL 1:50

2015 07 23

PLOT DATE: 2015 07 23

DATE

DATE

DATE

Winnipeg

GUTTER (SOUTH AND EAST)

♠ DITCH (NORTH AND WEST)

€ DITCH (SOUTH AND EAST)

STRUCTURE

MANHOLE OR CATCH BASIN

## THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT

ENGINEERING DIVISION

 $\overline{\phantom{a}}$ 

2015 SUPPLEMENTAL WATERMAIN RENEWALS CONTRACT 14

INDEX PAGE

CITY DRAWING NUMBER D-14045

SHEET 1 OF 11

BID OPPORTUNITY: 648-2015 FILE PATH: R:\DRAWINGS\WATER\RENEWAL\2015 RENEWALS\Pembina Hwy\FILE NAME: Index.dwg CONTRACT NUMBER: 14