

CONSTRUCTION NOTES:

- 1. ALLOWABLE SHUTDOWN TIME: MAX. 7.0 HRS OR AS DETERMINED BY COLLECTIONS STAFF
- 2. CRITICAL BASEMENT ELEVATION: 224.318
- 3. REMOVE EXISTING CONCRETE PIPING, VALVES, FITTINGS, AND OTHER MATERIALS
- AS REQUIRED. INSTALL NEW PUMPS, MOTORS, PIPING, VALVES AND FITTINGS AS SHOWN.
- 4. PROVIDE TEMPORARY BY-PASS PUMPING OF WASTEWATER DURING CONSTRUCTION.
- 5. INSTALL MECHANICAL WORKS AS INDICATED AND ACCORDING TO MANUFACTURER'S SPECIFICATIONS. 6. EXCAVATIONS TO BE BACKFILLED WITH CLASS 3 OR CLASS 5 BACKFILL IN ACCORDANCE WITH CW 2030 AND SD-042.
- 7. FLANGE NUTS & BOLTS TO BE ASTM A307.
- 8. GASKETS TO BE FULL FACED, 3 THICK RED RUBBER.
- 9. CONTRACTOR TO CONFIRM ALL DIMENSIONS BEFORE ASSEMBLING PIPE.
- 10. ALL ANCHOR BOLTS TO BE ASTM A276 TYPE 316 SS.

MATERIALS LIST

ITEM	DESCRIPTION	ENDS	LENGTH	QUANTIT
1	* 5000 NON RISING STEM GATE VALVES W/PEDESTAL OPERATORS	FL	3462±	1
2	500Ø PIPE	FL+PE	786±	1
3	5000 CAST IRON 45° BEND	FL	_	1
4	500¢ CAST IRON TEE	FL	-	1
5	5000 DI FLANGED WALL THIMBLE	-	-	2
6	5000 DI BLIND FLANGE	_	_	2
7	500¢ UNI-FLANGE	-	_	1
8	38ø GATE VALVE	_	_	1
9	38ø CHECK VALVE	_	_	1
10	38ø TYPE 316 SS PIPE	_	_	1
(11)	75ø ONE WAY AIR VALVE	_	_	1
(12)	75ø CHECK VALVE	_	_	1
(13)	75ø TYPE 316 SS PIPE	_	_	1
(14)	110V, MIN 1/3 HP, SUMP PUMP W/FLOAT SWITCH	_	_	1

- LENGTHS & DIMENSIONS SHOWN AS \pm TO BE FIELD CONFIRMED BY CONTRACTOR * ITEMS SUPPLIED BY CITY
- CONTRACTOR TO SUPPLY CABLES & CONDUIT FROM SUMP PUMPS TO ELECTRICAL OUTLETS IN COMMINUTOR ROOM - VALVE PEDESTAL OPERATORS TO HAVE POSITION INDICATORS.

TOP VIEW

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES DECIMALIZED NUMBERS INDICATE METRES

SUPY. U/G STRUCTURES COMMITTEE DESIGNED BY NC CHECKED BY NC 15/09/25 BY N.M. CON 15/09/25	LOCATION APPROVED UNDERGROUND STRUCTURES	B.M. ELEV.						ENGINEER'S SEAL	
NOTE: LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL DESIGNED BY NC DESIGNED BY NC CHECKED BY NC SAPPROVED BY NC APPROVED BY NC SCALE: RELEASED FOR CONSTRUCTION CONSULTANT DRAWING NUMB EXISTENCE AND EXACT LOCATION OF ALL									ORIGINAL SIGNED BY N.M. CONTI
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATION ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL DRAWN BY RS SCALE: RELEASED FOR CONSTRUCTION CONSULTANT DRAWING NUMB WERTICAL NITS						-1		NC	15/09/25
EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SCALE. HORIZONTAL NTS CONSULTANT DRAWING NUMB	LOCATION OF UNDERGROUND STRUCTURES AS					- DC		NC	
LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL VERTICAL NTS CONSULTANT DRAWING NUMB									1
	LOCATIONS ARE EXACT. CONFIRMATION OF						CONSTRUCTION		CONSULTANT DRAWING NUMBER
UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION. NO. REVISIONS DATE BY DATE 2015 09 25 DATE -		NO.	REVISIONS	DATE	BY	DATE 2015 09 25	DATE		-

FRONT VIEW

-BOLT FLANGE TO
EXIST CONC AND
REMOVE EXIST. CONC
AS-REQUIRED

-INSTALL CONC REINFORCED HEADWALL

Winnipeg

THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT ENGINEERING DIVISION

2015 COMMINUTOR CHAMBER PIPING & VALVE UPGRADES HAWTHONE LIFT STATION HAWTHORNE AVENUE & KILDONAN DRIVE

SHEET 9 OF 11 CITY DRAWING NUMBER

-0145L-M0001-001

FILE PATH: R:\DRAWINGS\SEWER\2015 RENEWALS\LIFT STATIONS\FILE NAME: HAWTHONE.dwg