



# 897-2015 ADDENDUM 1

## DESIGN, MANUFACTURING AND INSTALLATION OF NEW POOL BULKHEADS AND RELATED WORKS – PAN AM INDOOR POOL – 25 POSEIDON BAY

ISSUED: January 27, 2016  
BY: Lou Chubenko  
TELEPHONE NO. 204 986-2727

### URGENT

**PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY**

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS**

Template Version: A20150806

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.**

---

### PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 4:00 p.m. Winnipeg time, February 2, 2016.

### PART E – SPECIFICATIONS

#### Appendix A

- Revise: 2.7.1 to read: The bulkheads will have 1 – 50mm timing system cable tray installed in each bulkhead. These trays will follow under each of the block positions and carry all of the in bulkhead wires.
- Revise: 2.7.3 to read: Each bulkhead will have an access panel and shelf to place a waterproof box on the west or east side for timing cable connections. The area of the box will be 300mm L x 300mm W x 100mm D. The box will be as waterproof as possible when not in use and closed with a snap latch.
- Revise: 2.9.3 to read: **Material** – the new deck anchors will be brass and railings polished 316L stainless steel.
- Revise: 2.9.4 to read: **Grounding** – The new anchors and other metal equipment within 3m of the pool must be grounded.
- Revise: 2.9.5 to read: Contractor is responsible to have a hydro inspection completed on the grounding prior to pool being filled.
- Add: 2.1.12 **REMOVAL OF HANDRAILS** – Removal of eight (8) sets (2 per set, total 16) of existing stainless steel handrails located in the competition pool down both lengths of the pool through the bulkhead travelling positions. Remove existing stainless steel railings and anchors.
- Add: 2.14 **NEW HANDRAILS** – Provide eight (8) sets (2 per set, total 16) of new stainless steel removable handrails located in the competition pool both lengths of the pool in same positions of old rails.
- Add: 2.14.1 Install in deck brass wedge anchors to accept railings. Railings must be able to be easily removed when the bulkhead needs to be moved.