

Part 1 General

1.1 REFERENCES

- .1 Not used.

1.2 SUBMITTAL

- .1 Not used.

1.3 EXISTING CONDITIONS

- .1 Underground utilities and elements: locate all underground utilities and elements prior to digging and/or driving stakes. Take care, to neither disturb nor damage any existing above ground or underground utilities or elements. Keep streets, sidewalks and site clean, free from debris and affected drains open and free flowing at all times.
- .2 Contact appropriate utility to request shut-off of pressurized or powered utilities. Verify that all appropriate services have been disconnected. The Contractor shall pay for all fees and costs associated with utility disconnect, capping of lines and meter removals required within the Public Right of Way.
- .3 Notify Contract Administrator before disrupting building access or services
- .4 Objectionable Noises: Limit use of air hammers and other noisy equipment as much as possible. Conform to local governing requirements.

Part 2 Products

2.1 NOT USED

Part 3 Execution

3.1 PROTECTION

- .1 Prevent movement, settlement, or damage to adjacent structures, utilities, and elements to remain in place. Provide bracing and shoring required.
- .2 Protect Native Forest at all times during course of Work.

3.2 DEMOLITION

- .1 Demolition and construction activities shall be in accordance with NBC 1995, Part 8.
- .2 Existing Toboggan Chute Structures:
 - .1 Remove existing toboggan chute structure and legally dispose of off site unless otherwise indicated by the City of Winnipeg, for reuse.

- .2 Existing Light Standard, Luminaires, Poles and bases:
 - .1 Remove existing Light Standard and legally dispose of off site unless otherwise indicated by the City of Winnipeg, for reuse.
 - .2 Remove a portion of the existing light standard base, to a depth that is reasonable and practicable, so that it does not pose a safety issue to the public or does not interfere with future use of the site.
- .3 Demolish Sod / Turf:
 - .1 Remove existing Sod/Turf as indicated on Drawings.
 - .2 Completely remove all organic material in new non-planted areas as indicated on drawings.
- .4 Demolish and remove any other existing elements as necessary for completion of Work as approved by Contract Administrator.

3.3 DEMOLITION SALVAGE AND DISPOSAL

- .1 Remove area to permit new construction. Sort selected materials into appropriate piles for reuse and recycling if possible.
- .2 Refer to drawings for items to be salvaged for reuse.
- .3 Dispose of removed materials, except where specified otherwise, in accordance with authority having jurisdiction.

END OF SECTION