



366-2016 ADDENDUM 1

North End Sewage Treatment Plant (NEWPCC) Headend Discharge Well Structural Upgrades

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: May 9, 2016
BY: Scott Begg
TELEPHONE NO. (204) 488-2214

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20131129

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART D – SUPPLEMENTAL CONDITIONS

REVISE:
D2.4 (e)

Provide Scaffolding and safety provisions (netting, fall protection, temporary work platforms, anchoring, tie-off points) in the Discharge Well to allow for installation of the permanent structural appurtenances described in the drawings. Do not damage or use precast roof slabs **or walls** for attachment or anchorage.

PART E – SPECIFICATIONS

ADD:
E6. RECORD DRAWINGS

- E6.1 Record drawings of the existing facility are available for review upon request. The following drawings are attached that provide a general reference for review: NEP-0003, NEP-0005, NEP-0010, NEP-0013, NEP-0016, NEP-0017, NEP-0019, NEP-2119, and NEP-2126.
- E6.2 The information contained on record drawings is based on the available record drawings and information from previous plant construction. Actual details may vary and are to be confirmed prior to their use.

SPECIFICATION SECTIONS

REVISE:
Section 01 11 00 Summary of Work - Clause 1.2 B.5.
and
Section 01 52 10 Construction Sequencing - Clause 3.2 B.5

Provide Scaffolding and safety provisions (netting, fall protection, temporary work platforms, anchoring, tie-off points) in the Discharge Well to allow for installation

of the permanent structural appurtenances described in the drawings. Do not damage or use precast roof slabs **or walls** for attachment or anchorage.

REVISE:

Section 01 35 29.01 Health and Safety Clause 1.7 A.10

Workers must wear a respirator or supplied air **if adequate ventilation is not available** when entering the Discharge Well where live sewage is present.

REVISE:

Section 02 41 13 Selective Site Demolition Clause 3.4 B.

Bracing and shoring required. Submit shop drawings sealed by a structural engineer licensed in the province of Manitoba.

DRAWING

REPLACE:

366-2016_DRAWING_1-0101M-S0012-001-R0 with 366-2016_ADDENDUM_1_DRAWING_1-0101M-S0012-001-R1

ADD:

366-2016_Addendum_1-Drawing-NEP-0003

366-2016_Addendum_1-Drawing-NEP-0005

366-2016_Addendum_1-Drawing-NEP-0010

366-2016_Addendum_1-Drawing-NEP-0013

366-2016_Addendum_1-Drawing-NEP-0016

366-2016_Addendum_1-Drawing-NEP-0017

366-2016_Addendum_1-Drawing-NEP-0019

366-2016_Addendum_1-Drawing-NEP-2119

366-2016_Addendum_1-Drawing-NEP-2126