

**Notes**  
 Existing irrigation will be located and marked by contract administrator prior to start of construction.  
 Any damage to existing irrigation system will be repaired immediately by contractor.

**Legend**

-  Irrigation Line Crossings (hand excavate)
-  Round Catch Basins
-  Square Catch Basins
-  Slit Trenches w/ approximate length
-  Mainline Trenches c/w 100mm Drainage Pipe & approx. length
-  Mainline Trenches c/w 100mm Solid Drainage Pipe & approx. length
-  Mainline Trenches c/w 150mm Solid Drainage Pipe & approx. length
-  Existing Irrigation Heads
-  Existing Irrigation Lines
-  Strip & Replace Sod b/w Works

**Material List**

	Units	Quantity
<b>Hole No. 3</b>		
100mm Perforated Drainage Pipe	lin. m.	200.0
Lateral Slit Trenches	lin. m.	147.5
150mm Round Catch Basins	each	11



Kildonan Park Golf Course

Kildonan Park Golf Course

**GRANT GOLF**  
 Golf Course Planning • Design • Construction Management  
 162 Woodfield Bay, Winnipeg, Manitoba R3R 3B1  
 Ph: (204) 229-2419 • Email: grantgolf@mac.com

Project: **Kildonan Park Golf Course**  
 2021 Main St., Winnipeg, MB.  
 Drawing Title: **Drainage Plan - Hole No. 3**

Notes: **Bid Opportunity 511-2016**

Scale: **1 : 300**  
 North: 

Drawn: **TK**  
 Checked: **DG**  
 Proj. No.: **16.09**

Date: **Feb. 25, 2016**  
 Revisions: **July 5, 2016**

Drawing No.: **L5**