


- Pick Up and Install Composite Benches (x2)
- Supply and Install 2 Tier Timber Edging to Fence (27 LM)
- Supply and Install 8' Tall 2 Bay Swings
- Supply and Install Safety Surfacing (270 SM)
- Supply and Install 2 Tier Timber Edging w/ Cap (43 LM)
- Supply and Install Trees (x5)
  - 3 x American Basswood *Tilia americana*
  - 1 x Discovery Elm *Ulmus davidiana var. Japonica 'Discovery'*
  - 1 x Japanese Tree Lilac *Syringa reticulata mandschurica*
- Supply and Install New Chainlink Fencing (9 LM) (incl. 1 baffle gate)
- Pick Up and Install Accessible Picnic Table
- Pick Up and Install Double Sided Park Sign on Chain Link Fence (by others)
- Supply and Install Granular Path & Seating Areas (230 SM)
- Pick Up and Install Metal Slat Waste Receptacles (x2)
- Supply and Install Drainage Piping and Emitter (19 LM)
- Pick Up and Install Composite Backless Bench
- Pick Up and Install Sand Box & Supply and Install Play Sand
- Supply and Install 1 Tier Timber Edging w/ Cap (10 LM) and Fill with 150mm (6") Depth of EWF Safety Surfacing
- Supply and Install Soil and Sod (307 SM)

**General Notes**

1. TOP OF TIMBERS SHALL BE 300MM (12") ABOVE EXISTING GRADE
2. EXCAVATION OF PLAY AREA BASED ON APPROX. 150mm DEPTH
3. - FOR RAISED GRANULAR AREAS REMOVE ALL EXISTING ORGANIC MATERIAL TO AN APPROX. DEPTH OF 75mm. APPROX. 375mm OF GRANULAR MATERIAL WILL BE REQUIRED TO BRING SEATING AREAS UP TO PROPER GRADE.
  - REFER TO SCD 646 FOR REFERENCE.
  - MATERIAL BREAKDOWN SHALL BE AS FOLLOWS: 200mm OF 2" DOWN CRUSHED LIMESTONE, FOLLOWED BY 150mm OF 3/4" DOWN CRUSHED LIMESTONE, WITH A 25mm TOP COAT OF 1/4" DOWN CRUSHED LIMESTONE



CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

<p>THE CITY OF WINNIPEG Planning, Property and Development Department Planning and Land Use Division Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)</p>	DESIGNED BY	IL	CHECKED BY		DRAWING TITLE <b>Stewart/Livinia Park PLAYGROUND IMPROVEMENTS Proposed</b>	DRAWING NO.  <b>S.53-C</b>	
	DRAWN BY	IL	APPROVED BY	MANAGER, PARK AND OPEN SPACES			DATE
	HORIZ. SCALE				MANAGER, PLANNING AND LAND USE DIVISION	SITE ADDRESS	670 Stewart Street
	VERT. SCALE	1:200					
DATE	JUNE 2016						