



RECONSTRUCTION OF LAFLECHE TENNIS COURTS

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: July 5, 2016
BY: Philip d'Auteuil, C.E.T.
TELEPHONE NO. 204 986-3781

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20150806

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 7 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 598-2016 Bid Submission with 598-2016 Addendum 2 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R2): Revise Item B.2 quantity

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 4:00 p.m., Winnipeg time, July 8 2016.

PART E – SPECIFICATIONS

Delete: E17

Revise: E20.2.1 to read: Pickleball posts to be DTP 37 Tennis Posts or approved equal in accordance with B7.

Revise: E23.3(a) to read: Tennis Posts as manufactured by Douglas Tennis Systems, or approved equal. Post model: DTP 37, green colour. Supply and install four (4) tennis posts. The posts will require cutting and welding to existing cut in place tennis posts.

Delete: E23.3(d)

Delete: E23.4.2(b)

Revise: E23.4.2(c) to read: If required, cut new tennis posts to that top of new post will be 1070 mm above the top of the asphalt paving. Remove paint where welds will be installed. Insert new tennis posts into old tennis posts. Weld posts together.

Revise: E23.4.2(d) to read: All welds to be continuous and ground smooth. Finish all metal with one coat of primer and two coats of paint to match the manufacturer's tennis posts.

Revise: E23.5.1(a) to read: Tennis posts, fabrication and painting shall be paid on a unit basis and paid for at the Contract Unit Price for "Tennis Posts and Nets." The item to be paid for will be the total number of completed installations. Each installation shall include fabrication, cutting,

paint, two (2) posts, one (1) net satisfactorily installed in accordance with this Specification, accepted and measured by the Contract Administrator.