



608-2016 ADDENDUM 1

PAINTING OF INTERIOR CONCRETE WALLS WITHIN SPECTATOR VIEWING AREAS – PAN AM INDOOR POOL

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: July 4, 2016
BY: Lou Chubenko
TELEPHONE NO. 204 986-2727

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20150806

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART D – SUPPLEMENTAL CONDITIONS

- Revise: D2.2(e) to read: Cover and seal all existing wall penetrations, wall mounted fire/security alarm system equipment and PVC conduits to eliminate paint splatters.
- Revise: D2.2(h) to read: Apply **two (2)** coats of specified paint for walls and concrete diving tower.
- Add: D2.2(j) Gardon Construction Ltd. shall be the Prime Contractor as per The Workplace Safety and Health Act, Chapter W210, Section 7 (3), for the 2016 Pan Am Pool shutdown period. The services include, but not limited to:
 - (a) Act as Safety Administrator.
 - (b) Conduct safety meetings and site orientations as required.
 - (c) Coordinate and organize work boundaries between contractors.
 - (d) Ensure the facility is kept secure and manage security services as required.
- Revise: D17.1 to read: Further to C6.24, Gardon Construction Ltd. shall be the Prime Contractor and shall serve as, and have the duties of the Prime Contractor in accordance with The Workplace Safety and Health Act (Manitoba).

PART E – SPECIFICATIONS

- Revise: E3.10 to read: Acceptable Product: Paint: PPG PITT GLAZE WB1 16-510C – Interior pre-catalyzed water-borne acrylic epoxy paint – two (2) coats, by PPG Protective & Marine Coatings or an approved equal in accordance with B7.
- Revise: E3.12 to read: Paint schedule shall consist of PT-1 (White), PT-2 Royal Blue) and six (6) different colors of blue in gradient pattern (located at east wall above ceramic wall tiles at existing green and purple panels).
- Add: **E5. PAINT SCHEDULE & LOCATIONS**
 - East Walls**
 - (a) East wall to be painted PT-1 (white) to replace existing green paint.
 - (b) Existing black infill panels on east wall above existing white panels to remain black.
 - (c) Existing six (6) green and purple panels above ceramic wall tiles to be painted six (6) different colours of blue in gradient pattern.

North & South Walls

- (a) Any existing green paint on a horizontal surface to be painted with PT-1 (white).
- (b) Existing Judges Box to be painted PT-1 (white).

West Walls

- (a) Existing Pan Am Games logo and green paint to be painted over with PT-2 (royal blue).
- (b) Exterior surfaces of concrete dive tower and springboard platforms with existing purple paint to be painted PT-1 (white).