

- 1. ALL EXISTING STRUCTURES, TREES, SHRUBS, SIDEWALKS, CURBS, SOD, UTILITIES AND PAVING TO BE PROTECTED (UNLESS OTHERWISE NOTED) DURING CONSTRUCTION TO CITY OF WINNIPEG STANDARDS. CONTRACTOR TO MAKE GOOD ALL DAMAGED AREA DURING CONSTRUCTION BOTH ON AND OFF SITE TO CITY OF WINNIPEG STANDARDS AT THE CONTRACTORS COST.
- 2. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.
- 3. CONTRACTOR TO CONFIRM ALL EXISTING GRADES, LAYOUT, DIMENSIONS, AND MATERIALS ON SITE AND REPORT ANY DISCREPANCIES TO THE CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION.
- 4. ALL LAYOUT TO BE APPROVED BY CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION.
- 5. ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE NOTED.
- 6. ALL DIMENSIONS ARE TO BE TAKEN FROM FINISHED FACE OF BUILDING.
- 7. PLANT LAYOUT TO STAKED AS SHOWN AND APPROVED BY CONTRACT ADMINISTRATOR PRIOR TO INSTALLATION.
- 8. CONTRACTOR TO LAYOUT SAWCUT JOINTS WITH CHALKLINES FOR REVIEW BY CONTRACT ADMINISTRATOR PRIOR TO PROCEEDING WITH WORK.

5 YY.MM.DD -4 YY.MM.DD -3 YY.MM.DD -2 YY.MM.DD -1 16.06.03 - ISSUED FOR CONSTRUCTION

**REVISION / ISSUANCE** 



No. DATE

562 Academy Road / Winnipeg, MB / R3N 0E3 (204) 930 0272 / www.plainprojects.ca

CRESCENT DRIVE PARK

**LAYOUT PLAN** 

**PAVILION** 

L102 JUNE 2016

SCALE 1:75 (@24X36)