DRAWING KEYNOTES:

- 1. EXISTING GRILLE TO REMAIN.
- DEMOLISH EXISTING GRILLE.
 DEMOLISH EXISTING DUCTWORK BACK TO THIS POINT.
- 4. EXISTING DUCTWORK TO REMAIN.
- 5. EXISTING EXHAUST RISER AND GRILLE TO BE RELOCATED TO NEW WASHROOM. REFER TO DRAWING 1/M-8 FOR NEW LOCATION.
- 6. EXHAUST FOR WORK ROOM TO REMAIN.
- EXISTING THERMOSTAT TO BE RELOCATED. REFER TO DRAWING 1/M-8 FOR NEW LOCATION.
- 8. REBALANCE ALL EXHAUST INLETS TO 50CFM.

GENERAL NOTES:

- DO NOT SCALE THIS DRAWING, CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO INSTALLATION AND REPORT ANY DISCREPANCY TO THE CONTRACT ADMINISTRATOR.
- 2. THE DRAWING ONLY SHOWS A GENERAL SCHEMATIC OF NEW PIPING SYSTEMS. ROUTING OF PIPES SHALL SUITS SITE CONDITIONS AND MAY HAVE TO BE CHANGED TO AVOID CONFLICTS WITH STRUCTURE, DUCTS AND PIPES. WHEN CONFLICT CANNOT BE AVOIDED, THE DUCTWORK SHALL BE MODIFIED AS REQUIRED.
- 3. CONTRACTOR SHALL INCLUDE FOR AND PROVIDE ALL COORDINATION BETWEEN TRADES AND CONSULTANT ON AND OFF SITE AS REQUIRED FOR INSTALLATION OF MECHANICAL AND ELECTRICAL SYSTEMS, WHERE MINOR REROUTING OF PIPE OR SERVICES IS REQUIRED DUE TO ONSITE CONDITIONS. IT SHALL BE PERFORMED AT NO ADDITIONAL COST.
- 4. COORDINATE ALL GRILLE AND DIFFUSER LOCATIONS WITH LIGHTING LAYOUT.
- 5. INSTALL FIRE DAMPERS IN ALL DUCTWORKS WHERE THEY PASS THROUGH FIRE RATED WALLS.
- 6. FIRE STOP ALL PIPE PENETRATIONS WHERE THEY PASS THROUGH FIRE RATED WALLS.
- 7. CONFORM TO SPECIFICATIONS AND MANUFACTURER GUIDELINES FOR MATERIALS AND UNITS' INSTALLATION DETAILS.
- 8. PROVIDE TESTING AND BALANCING, CONFIRM ALL NEW FLOWS AS INDICATED AND CONFIRM ALL EXISTING AIR FLOWS IN AREA OF RENOVATION ON ALL OUTLETS AND ALL VAV BOXES.
- 9. ALLOW FOR REMOVAL AND RE-INSTALLATION OF MECHANICAL WALL CONTROLS TO FACILITATE ANY ARCHITECTURAL WORK.



Certificate of Authorization
HDK Consulting Incorporated

No. 5539 Date: 04/30/2017

1 ISSUED FOR SEPT 09, 2016 CONSTRUCTION


This drawing is property of the Architect and cannot be reproduced or used without the consent of the Architect. The contractor is responsible for checking and verifying all levels and dimensions and shall report all discrepancies to the Architect and obtain clarification prior to commencing work.

Sheet No: M-3

bridgmancollaborative.ca

WINNIPEG, MB R3B 1E4 204 488 3857 tel. 204 488 0216 fax. www.

HDK CONSULTING
INCORPORATED
2633 Portage Avenue
Winniper, Manitoba
Canada, R3J 0P7
7: 204.818.0389
7: 204.818.0390
7: 204.818.0390
7: 204.818.0390
Mechanical Electrical Communications | Security Engine



THE CITY OF WINNIPEG PLANNING, PROPERTY AND DEVELOPMENT DEPARTMENT MUNICIPAL ACCOMMODATIONS DIVISION

4TH FLOOR - 185 KING STREET R3B 1J1

St. Vital Library

6 Fermor Ave., Winnipeg, Manitoba

Drawing Title:

MAIN FLOOR HVAC

DEMOLITION LAYOUT

Project Number: 16054
Bid Opportunity Number: 768-2016

Issue/Revision Date

Project: