



1049-2017ADDENDUM 4

PROVISION OF FIBRE OPTIC CABLE FROM WEST END SEWAGE TREATMENT PLANT (WEWPCC) TO PERIMETER ROAD PUMPING STATION (PRPS)

ISSUED: February 28, 2018
BY: Amanda Wolfe
TELEPHONE NO. 204 986-2808

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20160708

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART D – SUPPLEMENTAL CONDITIONS

- Revise: D10.1 to read: The Contractor shall provide and maintain the following insurance coverage:
- a) commercial general liability insurance, in the amount of at least **five million dollars (\$5,000,000.00)** inclusive, with the City of Winnipeg **and the Province of Manitoba** added as additional **insureds**, with a cross-liability clause; such liability policy to also contain contractual liability, unlicensed motor vehicle liability, non-owned automobile liability and products and completed operations, to remain in place at all times during the performance of the Work and throughout the warranty period;
 - b) **Automobile** Liability Insurance covering all motor vehicles, owned and operated and used or to be used by the Contractor directly or indirectly in the performance of the Work. The Limit of Liability shall not be less than \$2,000,000 inclusive for loss or damage including personal injuries and death resulting from any one accident or occurrence;
 - c) all risks installation floater, carrying adequate limits to cover all machinery, equipment, supplies and/or materials intended to enter into and form part of any installation.
- Add: D10.5 All policies shall be taken out with insurers licensed to carry on business in the Province of Manitoba.
- Revise: D22.1 to read: Notwithstanding C13.2, the warranty period shall begin on the date of Total Performance and shall expire two (2) years thereafter unless extended pursuant to C13.2.1 or C13.2.2, in which case it shall expire when provided for thereunder.
- Add: D25 **LIABILITY**
- D25.1 The Contractor shall be responsible for all costs that may occur because of damage the Contractor causes to the roads, utilities or underground services during the performance of the Work.
 - D25.2 The Contractor is responsible for the accuracy of all information provided by the Contractor.

D25.3 The Contractor shall indemnify and save harmless the Province of Manitoba from and against all claims arising from the construction, testing and maintenance of the Work by the Contractor, its servants or agents.

PART E – SPECIFICATIONS

Replace 1049-2017_Addendum 3_NMS_Format_Specifications_R1 with 1049-2017_Addendum_4_NMS_Format_Specifications_R2. The following is a summary of changes incorporated in the replacement specifications:

Section 01 73 03

- Add: 1.4.9 Restore any disturbed areas, surfaces and/or landscaping to the conditions that existed prior to commencement of the Work. If the Contractor should fail to restore the disturbed areas, surfaces and/or landscaping, the City may perform the restoration required and charge the Contractor the full amount thereof.
- Add: 1.4.10 The Contractor shall use due care and attention to avoid damage to property, including public and private property. In the event of damage to property during the performance of the Work, the Contractor shall immediately restore the property to a condition satisfactory to the Contract Administrator.

Section 26 05 34

- Add: 3.1.11 Provide markers for buried services along entire conduit route. The maximum distance between markers is 100 m.
- Add: 3.1.12 Provide horizontal directional drilling for all road crossings. All crossings shall be at right angles to the road.

Note that 1049-2017_Addendum_4_NMS_Format_Specifications_R2 includes the revisions made in all previous Addenda

DRAWINGS

Replace: 1049-2017_Addendum 3_Drawing_1-0103A-E0021-R1 with 1049-2017_Addendum_4_Drawing_1-0103A-E0021-R2.

QUESTIONS AND ANSWERS

Q1 Is the existing conduit from the Shaw vault into the building re-usable, or just the vault?

A1 The existing Shaw conduit cannot be used for installation of the new fibre cable.

Also note the revisions on Drawing 1-0103A-E0021-R2 note 2 regarding the Shaw handholes:

Existing Shaw handholes on City property cannot be used for installation of the new fibre cable. Locate new handhole next to WEWPCC Admin building on north side of building east of the main door.