



# 1137-2017 ADDENDUM 2

## RIVERBANK STABILIZATION AND EROSION PROTECTION WORKS AT CORNISH LIBRARY – 20 WEST GATE – PROJECT NO. 2017-149

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE BID  
OPPORTUNITY**

ISSUED: January 29, 2018  
BY: Lou Chubenko  
TELEPHONE NO. 204 986-2727

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID OPPORTUNITY AND SHALL  
FORM A PART OF THE CONTRACT  
DOCUMENTS**

Template Version: A20160708

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.**

### **PART B – BIDDING PROCEDURES**

Delete: B8.1(c)	Bid Security;
	(i) Form G1: Bid Bond and Agreement to bond, or
	(ii) Form G2: Irrevocable Standby Letter of Credit and Undertaking, or a certified cheque or draft.

### **PART E – SPECIFICATIONS**

Revise: E7.5.1 to read:	The Contractor shall erect and maintain for the duration of the project a safety fence, to restrict access to the Site. The fencing shall enclose the entire Site including on the river ice, with appropriate gates or openings that are closed at the end of each Work day. Appropriate signs shall be erected to warn all recreational users of the park and the river that construction site exists. This shall include but not limited to snowmobilers and skiers. Fence construction on the riverbank shall consist of Dupont Number L70 orange plastic safety fence or approved equal in accordance with B7 with a mesh spacing of 45 mm and a minimum height of 1.2 meters supported by wood posts driven into the ground. The wood posts shall be sized and capable of maintaining the snow fence material upright, regardless of conditions. Upon completion of the Work, all fence materials shall be removed and disposed off-site.
-------------------------	---

Revise: E8.4.1(b) to read:	Existing Trees (12) are to be removed as indicated on the Drawings. Additional trees may need to be removed as directed by the Contract Administrator.
----------------------------	--

Add: E11.2.4	The Contractor shall remove the end of the existing fence located at the south property line at the river's edge, as indicated on the Drawings, to facilitate regrading,. Upon completion, of the regrading Work, the fence shall be restored with the same materials to a condition and location to the approval of the Contract Administrator.
--------------	--

Add: E11.2.5 regraded areas shall transition smoothly to the ground surface of the adjacent property, to the approval of the Contract Administrator.

Add: E12.2.3 The excavation area shall be regraded such that final ground surface transitions smoothly to the ground surface of the adjacent property, to the approval of the Contract Administrator.

Revise: E16.2.3 to read: Riprap shall be well graded having a full range and even distribution of sizes and shall conform to the following gradation:

Canadian Metric Sieve Size (millimetres)	Percent of Total Dry Weight Passing Each Sieve
450	100
250	15 - 50
150	0 - 50