

APPENDIX C – PROJECT LOCATIONS AND TECHNICAL SCOPING

See Tables below.

Notes:

The “Additional Information” provided within the following tables relative to specific Project Packages and/or Project Locations contain specific information or issues, known to exist on Site at the time of issuance of this Request for Proposal. This information is not meant to be exhaustive and not meant to take the place of investigations and due diligence required of the Proponent.

The specific utility and agency coordination identified below notwithstanding, the successful Consultant(s) will be required to investigate and coordinate any utility requirements of the Project.

Construction adjacent schools will be avoided during the school year where possible, and otherwise coordinated with the respective school division.

Regional Streets - Ellice Av						
File No.	Package No.	Location	Treatment	Notes	Construction Estimate	Project Budget
19-C-01	1144-2017.1	Ellice Av - Arlington St/Maryland St	Rehabilitation	see all notes below	\$2,015,000	\$3,100,000
Regional Streets - Ellice Av					Total Project Package Budget	\$3,100,000
Assumed Working Days (to Substantial Performance)						50
<i>Additional Information:</i>						
General * Assume 50 Working Days to Substantial Performance for this package.						
1 Planned sewer lining in 2018 - coordination/confirmation with Water & Waste Department required.						
2 Work to occur adjacent John M. King School.						
3 Coordination with West End BIZ required.						

Regional Streets - Inkster Bv						
File No.	Package No.	Location	Treatment	Notes	Construction Estimate	Project Budget
19-C-02	1144-2017.2	Inkster Bv - Milner St/Fife St	Reconstruction	see all notes below	\$2,990,000	\$4,600,000
Regional Streets - Inkster Bv					Total Project Package Budget	\$4,600,000
Assumed Working Days (to Substantial Performance)						60
<i>Additional Information:</i>						
General * Assume 60 Working Days to Substantial Performance for this package.						
1 Consultant to provide a pavement design brief.						
2 Coordination with Manitoba Hydro required for street light upgrades.						
3 Coordination with Traffic Signals required for intersection at Fife St.						
4 Feedermain on Inkster Bv.						
5 Feedermain on Fife St.						
6 Insulation of water services required.						
7 Coordination with Water & Waste Department required.						
8 Median to include splash strips.						

Regional Streets - Main St						
File No.	Package No.	Location	Treatment	Notes	Construction Estimate	Project Budget
19-C-03	1144-2017.3	Main St N/B - McAdam Av/Kildonan Park Golf Course	Rehabilitation	see all notes below	\$4,290,000	\$6,600,000
Regional Streets - Main St					Total Project Package Budget	\$6,600,000
Assumed Working Days (to Substantial Performance)						100
<i>Additional Information:</i>						
General * Assume 100 Working Days to Substantial Performance for this package.						
1 Planned sewer lining in 2018 - coordination/confirmation with Water & Waste Department required.						
2 The University of Manitoba will be conducting non-destructive testing of the pavement in Spring 2018. Coordination/confirmation of testing results with the University required to propose rehabilitation options.						
3 Refer to T-Drawing, T-3468-R0. Pedestrian & cycling path on west side boulevard between Seven Oaks Av and Jefferson Av required.						
4 Feedermain on Main St.						
5 Planning of sewer relief work on Main St between St. Anthony St and Kingsbury Av to start in 2019 - coordination/confirmation with Water & Waste Department required.						
6 Consultant to conduct a safety audit at the intersection of Main St and Jefferson Av during preliminary design.						