



DEMOLITION - PART ROOF PLAN  
1:100

**DEMOLITION NOTES**

- DEMOLISH EXISTING AHU-M639 c/w ROOF CURB FLASHING AND INSULATION. DEMOLISH SERVICE PLATFORMS. STRUCTURAL FRAME TO REMAIN. REFER TO STRUCTURAL. DEMOLISH GAS TRAIN, CAP NATURAL GAS PIPE FOR FUTURE USE. CAP SUPPLY AIR RISER FOR FUTURE RECONNECTION.
- DEMOLISH EXISTING AHU-M651 c/w ROOF CURB. REFER TO STRUCTURAL FOR FURTHER DEMOLITION. CAP HEATING COIL HYDRONIC LINES FOR FUTURE USE. CAP SUPPLY AIR RISER FOR FUTURE RECONNECTION. DEMOLISH RETURN PLENUM. DEMOLISH EXISTING CONTROLLER AND THERMOSTAT IN MCC ROOM. PATCH WALL AND PAINT AS REQUIRED.

**GENERAL NOTES**

- 

B.M. ELEV.		DESIGNED BY	PDT		ENGINEER'S SEAL		CITY DRAWING NUMBER 1-0101M-M0014-001
		DRAWN BY	JV				
		CHECKED BY	NDC				
		APPROVED BY					
		HOR. SCALE	NONE	RELEASED FOR CONSTRUCTION DATE	CONSULTANT PROJECT NO. 163526	NORTH END SEWAGE TREATMENT PLANT NEWPCC MAIN BUILDING - HVAC REPLACEMENT  DEMOLITION - PART ROOF PLAN	SHEET 5 OF 21
0	Issued for Tender	17/04/13	PDT				
NO.	REVISIONS	DATE	BY	DATE			