ELECTRIC DUCT HEATER SCHEDULE

NO.	LOCATION	MAKE	MODEL	AIRFLOW CFM (l/s)	MAXIMUM AIRFLOW PRESSURE DROP IN. (pa)	HEATING COIL DATA						CONTROLS							FLA	MCA	MOCP	POWER						REMARKS
						TOTAL W	EAT DB °F (°C)	LAT DB °F (°C)	SCR (BY MECHANICAL)			INTERLOCK			F.A. SHUT DOWN	DATA CONN.	NOTES	PANEL				EM	V/ø	FEEDER	COND	BRKR	CCT	
									TYPE	STAGES	REMOTE FEEDER	SUPPLY	INSTALL	WITH														
EHC 0-1A	REFER TO PLAN	THERMOLEC	SC	200 (94)	0.05 (13)	2,000	65 (18)	95 (35)	PACK			MECHANICAL	MECHANICAL	FC TSTAT AUX, DDC	--	--	--		--	--	--	-- (--)	208/3	3#12	3/4"	15A/3P	PA-16,17,18	PROVIDE COMPLETE WITH AIR PROVING SWITCH AND AIR TEMPERATURE SENSOR.
EHC 0-1B	REFER TO PLAN	THERMOLEC	SC	200 (94)	0.05 (13)	1,000	65 (18)	80 (27)	PACK			MECHANICAL	MECHANICAL	TSTAT, DDC	--	--	--		--	--	--	-- (--)	208/3	3#12	3/4"	15A/3P	PA-13,14,15	PROVIDE COMPLETE WITH AIR PROVING SWITCH AND AIR TEMPERATURE SENSOR.
EHC 0-2	REFER TO PLAN	THERMOLEC	SC	635 (300)	0.05 (13)	5,000	65 (18)	80 (27)	PACK			MECHANICAL	MECHANICAL	FC TSTAT AUX, DDC	--	--	--		--	--	--	-- (--)	208/3	3#12	3/4"	20A/3P	PC-49,50,51	PROVIDE COMPLETE WITH AIR PROVING SWITCH AND AIR TEMPERATURE SENSOR.
EHC 0-3	REFER TO PLAN	THERMOLEC	SC	250 (118)	0.05 (13)	2,000	65 (18)	80 (27)	PACK			MECHANICAL	MECHANICAL	FC TSTAT AUX, DDC	--	--	--		--	--	--	-- (--)	208/3	3#12	3/4"	15A/3P	PC-18,19,20	PROVIDE COMPLETE WITH AIR PROVING SWITCH AND AIR TEMPERATURE SENSOR.
EHC 0-4	REFER TO PLAN	THERMOLEC	SC	400 (188)	0.05 (13)	5,000	65 (18)	104 (40)	PACK			MECHANICAL	MECHANICAL	FC TSTAT AUX, DDC	--	--	--		--	--	--	-- (--)	208/3	3#12	3/4"	20A/3P	PC-11,12,13	PROVIDE COMPLETE WITH AIR PROVING SWITCH AND AIR TEMPERATURE SENSOR.
EHC 1-1	REFER TO PLAN	THERMOLEC	SC	1130 (531)	0.05 (13)	12,000	65 (18)	99 (37)	PACK			MECHANICAL	MECHANICAL	FC TSTAT AUX, DDC	--	--	--		--	--	--	-- (--)	208/3	3#8	3/4"	50A/3P	MD-1	PROVIDE COMPLETE WITH AIR PROVING SWITCH AND AIR TEMPERATURE SENSOR.
EHC 1-2	REFER TO PLAN	THERMOLEC	SC	1000 (470)	0.05 (13)	6,000	65 (18)	84 (29)	PACK			MECHANICAL	MECHANICAL	FC TSTAT AUX, DDC	--	--	--		--	--	--	-- (--)	208/3	3#12	3/4"	25A/3P	PA-8,9,10	PROVIDE COMPLETE WITH AIR PROVING SWITCH AND AIR TEMPERATURE SENSOR.
EHC 1-3	REFER TO PLAN	THERMOLEC	SC	600 (282)	0.05 (13)	5,000	65 (18)	91 (33)	PACK			MECHANICAL	MECHANICAL	FC TSTAT AUX, DDC	--	--	--		--	--	--	-- (--)	208/3	3#12	3/4"	20A/3P	PC-1,2,3	PROVIDE COMPLETE WITH AIR PROVING SWITCH AND AIR TEMPERATURE SENSOR.
EHC 1-4	REFER TO PLAN	THERMOLEC	SC	1000 (470)	0.05 (13)	6,000	65 (18)	84 (29)	PACK			MECHANICAL	MECHANICAL	FC TSTAT AUX, DDC	--	--	--		--	--	--	-- (--)	208/3	3#12	3/4"	25A/3P	PC-5,6,7	PROVIDE COMPLETE WITH AIR PROVING SWITCH AND AIR TEMPERATURE SENSOR.

FAN COIL SCHEDULE (ELECTRIC)

NO.	LOCATION	MAKE	MODEL	AIRFLOW CFM (l/s)	EXTERNAL STATIC PRESS. IN. H_2O (pa)	PROVIDE HEATING COIL Y/N	HEATING DATA			COOLING DATA			UNIT WEIGHT LBS (kG)	CONTROLS				FLA	MCA	MOCP	POWER						REMARKS
							TOTAL BTUH (kW)	EAT °F (°C)	LAT °F (°C)	REFRIGERANT TYPE	TOTAL BTUH (kW)	TOTAL SENSIBLE BTUH (kW)		INTERLOCK			NOTES				EM	V/ø	FEEDER	COND	BRKR	CCT	
														SUPPLY	INSTALL	WITH												
FC 0-1	REFER TO PLAN	DAIKIN	FXMQ12PBVJU	400 (188)	0.4 (100)	YES	13,500 (4)	65 (18)	93 (34)	R-410A	12,000 (3.5)	9,700 (2.8)	62 (30)	MECHANICAL	MECHANICAL	TSTAT	--	--	1.4	15	-- (--)	208V/1ø	2#12	1/2"	15A/2P	PC-24,25	PROVIDE COMPLETE WITH ADAPTER BOARD FOR AUXILIARY HEAT CONTROL. FIELD CONSTRUCT FILTER BOX ON SUCTION SIDE OF FAN COIL AND PROVIDE MINIMUM MERV 8 FILTERS. PROVIDE FLEX CONNECTIONS AND SHUT OFFS AT EACH UNIT.
FC 0-2	REFER TO PLAN	DAIKIN	FXMQ18PBVJU	635 (300)	0.8 (200)	YES	20,000 (5.9)	65 (18)	94 (34)	R-410A	18,000 (5.3)	14,400 (4.2)	80 (27)	MECHANICAL	MECHANICAL	TSTAT	--	--	1.6	15	-- (--)	208V/1ø	2#12	1/2"	15A/2P	PC-26,27	PROVIDE COMPLETE WITH ADAPTER BOARD FOR AUXILIARY HEAT CONTROL. FIELD CONSTRUCT FILTER BOX ON SUCTION SIDE OF FAN COIL AND PROVIDE MINIMUM MERV 8 FILTERS. PROVIDE FLEX CONNECTIONS AND SHUT OFFS AT EACH UNIT.
FC 0-3	REFER TO PLAN	DAIKIN	FXMQ07PBVJU	250 (118)	0.4 (100)	YES	8,500 (2.5)	65 (18)	90 (32)	R-410A	7,500 (2.2)	6,400 (1.9)	55 (25)	MECHANICAL	MECHANICAL	TSTAT	--	--	0.6	15	-- (--)	208V/1ø	2#12	1/2"	15A/2P	PC-16,17	PROVIDE COMPLETE WITH ADAPTER BOARD FOR AUXILIARY HEAT CONTROL. FIELD CONSTRUCT FILTER BOX ON SUCTION SIDE OF FAN COIL AND PROVIDE MINIMUM MERV 8 FILTERS. PROVIDE FLEX CONNECTIONS AND SHUT OFFS AT EACH UNIT.
FC 0-4	REFER TO PLAN	DAIKIN	FXMQ12PBVJU	400 (188)	0.4 (100)	YES	13,500 (4)	65 (18)	93 (34)	R-410A	12,000 (3.5)	9,700 (2.8)	62 (30)	MECHANICAL	MECHANICAL	TSTAT	--	--	1.4	15	-- (--)	208V/1ø	2#12	1/2"	15A/2P	PC-14,15	PROVIDE COMPLETE WITH ADAPTER BOARD FOR AUXILIARY HEAT CONTROL. FIELD CONSTRUCT FILTER BOX ON SUCTION SIDE OF FAN COIL AND PROVIDE MINIMUM MERV 8 FILTERS. PROVIDE FLEX CONNECTIONS AND SHUT OFFS AT EACH UNIT.
FC 1-1	REFER TO PLAN	DAIKIN	FXMQ36BVJU	1130 (531)	0.8 (200)	YES	40,000 (12)	65 (18)	94 (34)	R-410A	36,000 (10.3)	28,000 (8.2)	102 (47)	MECHANICAL	MECHANICAL	TSTAT	--	--	2.9	15	-- (--)	208V/1ø	2#12	1/2"	15A/2P	PA-4,5	PROVIDE COMPLETE WITH ADAPTER BOARD FOR AUXILIARY HEAT CONTROL. FIELD CONSTRUCT FILTER BOX ON SUCTION SIDE OF FAN COIL AND PROVIDE MINIMUM MERV 8 FILTERS. PROVIDE FLEX CONNECTIONS AND SHUT OFFS AT EACH UNIT.
FC 1-2	REFER TO PLAN	DAIKIN	FXMQ30PBVJU	1000 (470)	0.8 (200)	YES	34,000 (10)	65 (18)	94 (34)	R-410A	30,000 (8.8)	23,800 (7)	102 (47)	MECHANICAL	MECHANICAL	TSTAT	--	--	2.8	15	-- (--)	208V/1ø	2#12	1/2"	15A/2P	PA-11,12	PROVIDE COMPLETE WITH ADAPTER BOARD FOR AUXILIARY HEAT CONTROL. FIELD CONSTRUCT FILTER BOX ON SUCTION SIDE OF FAN COIL AND PROVIDE MINIMUM MERV 8 FILTERS. PROVIDE FLEX CONNECTIONS AND SHUT OFFS AT EACH UNIT.
FC 1-3	REFER TO PLAN	DAIKIN	FXMQ18PBVJU	620 (291)	0.8 (200)	YES	20,000 (5.9)	65 (18)	94 (34)	R-410A	18,000 (5.3)	14,400 (4.2)	80 (27)	MECHANICAL	MECHANICAL	TSTAT	--	--	1.6	15	-- (--)	208V/1ø	2#12	1/2"	15A/2P	PC-7,8	PROVIDE COMPLETE WITH ADAPTER BOARD FOR AUXILIARY HEAT CONTROL. FIELD CONSTRUCT FILTER BOX ON SUCTION SIDE OF FAN COIL AND PROVIDE MINIMUM MERV 8 FILTERS. PROVIDE FLEX CONNECTIONS AND SHUT OFFS AT EACH UNIT.
FC 1-4	REFER TO PLAN	DAIKIN	FXMQ30PBVJU	1000 (470)	0.8 (200)	YES	34,000 (10)	65 (18)	94 (34)	R-410A	30,000 (8.8)	23,800 (7)	102 (47)	MECHANICAL	MECHANICAL	TSTAT	--	--	2.8	15	-- (--)	208V/1ø	2#12	1/2"	15A/2P	PC-9,10	PROVIDE COMPLETE WITH ADAPTER BOARD FOR AUXILIARY HEAT CONTROL. FIELD CONSTRUCT FILTER BOX ON SUCTION SIDE OF FAN COIL AND PROVIDE MINIMUM MERV 8 FILTERS. PROVIDE FLEX CONNECTIONS AND SHUT OFFS AT EACH UNIT.

CONDENSING UNIT SCHEDULE

NO.	LOCATION	MAKE	MODEL	COOLING CAPACITY BTUH (kW)	REFRIGERANT TYPE	OUTDOOR AMBIENT TEMP. °F (°C)		MINIMUM EER RATING (COOLING)	MINIMUM COP (HEATING)	HP	UNIT WEIGHT LBS (kG)	CONTROLS						FLA	MCA	MOCP	POWER					REMARKS
												INTERLOCK			DATA CONN.	NOTES	PANEL				V/ø	FEEDER	COND	BRKR	CCT	
						MIN	MAX					SUPPLY	INSTALL	WITH												
CU-01	OUTDOORS, REFER TO PLAN	DAIKIN	REYQ144TJU	150,000 (44)	R-410A	33 (1)	105 (41)	11.9	3.6	--	780 (355)	MECHANICAL	MECHANICAL	DDC/FAN COILS	--	--		38.8	55.0	70	208V/3ø	3#6	1"C	70A/3P	MD-1	HEAT RECOVERY SYSTEM. PROVIDE BMS INTERFACE COMPATIBLE WITH NEW DDC SYSTEM.

HRV/ERV SCHEDULE

NO.	LOCATION	MAKE	MODEL	AIRFLOW CFM (l/s)		SUPPLY AND EXHAUST EXTERNAL STATIC IN. H_2O (pa)	HP	PROVIDE PREHEAT COIL Y/N	MINIMUM TEMPERATURE EFFICIENCY %	# OF FANS	UNIT WEIGHT LBS (kG)	CONTROLS							FLA	MCA	MOCP	POWER						REMARKS
												INTERLOCK			F.A. SHUT DOWN	DATA CONN.	NOTES	PANEL				EM	V/ø	FEEDER	COND	BRKR	CCT	
				SUPPLY	RETURN							SUPPLY	INSTALL	WITH														
HRV-01	EXISTING BOILER ROOF	TEMPEFF	RGSP 1200	865 (407)	845 (397)	0.75 (187)	--	NO	85	2	770 (348)	MECHANICAL	MECHANICAL	DDC	--	--	--		11.4	13	--	-- (--)	208V/3ø	3#12	1/2"C	25A/3P	PB-23,24,25	PROVIDE WITH MERV 10 FILTERS.

PUMP SCHEDULE

NO.	LOCATION	MAKE	MODEL	PUMP TYPE	FLUID TYPE	FLOW GPM	HEAD FT	SPEED RPM	STARTER						POWER									CONTROLS											REMARKS (M)	REMARKS (E)
									SUPPLIED BY		INSTALLED BY		PACK	VSD	HP (kw)	FLA	MCA	MOCP	EM	V/ø	FEEDER	BRKR	CCT	INTERLOCK					F.A. SHUT DOWN	DATA CONN.	NOTES	PANEL				
									MECH	ELEC	MECH	ELEC												SUPPLIED BY	INSTALLED BY		WITH					INTEGRAL	REMOTE	120V CIRC		
																								MECH	ELEC	MECH	ELEC									
P-1	EXISTING BOILER ROOM	ARMSTRONG	ASTRO 225SSU	DHW RECIRCULATION	DOMESTIC HOT WATER	4	9	--	●		●				FRAC.					120/1	2#12	15A/1P	PC-28	●		●		DDC SCHEDULE							PUMP TO RUN ON OCCUPIED/UNOCCUPIED SCHEDULE THROUGH DDC. PUMP TO BE SUITABLE FOR POTABLE WATER USE.	
P-2	WEEPING TILE SUMP PIT	LIBERTY PUMPS	250 SERIES	SUBMERSIBLE	STORM WATER	25	15	--	●		●		--	--	1/3	5.2				120/1	2#12	15A/1P	PA-7	●		●		DUPLEX CONTROL PANEL					●		PUMPS P-2 AND P-3 CONTROLLED BY COMMON DUPLEX CONTROL PANEL. HIGH LEVEL ALARM TO DDC.	
P-3	WEEPING TILE SUMP PIT	LIBERTY PUMPS	250 SERIES	SUBMERSIBLE	STORM WATER	25	15	--	●		●				1/3	5.2				120/1	2#12	15A/1P	PA-7	●		●		DUPLEX CONTROL PANEL					●		PUMPS P-2 AND P-3 CONTROLLED BY COMMON DUPLEX CONTROL PANEL. HIGH LEVEL ALARM TO DDC.	

BRANCH SELECTOR BOX SCHEDULE

NO.	LOCATION	MAKE	MODEL	COOLING CAPACITY BTUH (kW)	REFRIGERANT TYPE	UNIT WEIGHT LBS (kG)	CONTROLS						FLA	MCA	MOCP	POWER					REMARKS
							INTERLOCK			DATA CONN.	NOTES	PANEL				V/ø	FEEDER	COND	BRKR	CCT	
							SUPPLY	INSTALL	WITH												
BSB-1	REFER TO PLAN	DAIKIN	BS4054TVJ	144,000 (--)	R-410A	50 (23)	MECHANICAL	MECHANICAL	FAN COILS/CU	--	--		--	0.4	15	208V/1ø	2#12	1/2"	15A/1P	PB-29,30	NO DRAIN PIPING REQUIRED. PROVIDE SHUT OFF VALVE AT EACH PORT. CAP OFF UNUSED PORTS.
BSB-2	REFER TO PLAN	DAIKIN	BS4054TVJ	144,000 (--)	R-410A	50 (23)	MECHANICAL	MECHANICAL	FAN COILS/CU	--	--		--	0.4	15	208V/1ø	2#12	1/2"	15A/1P	PA-32,33	NO DRAIN PIPING REQUIRED. PROVIDE SHUT OFF VALVE AT EACH PORT. CAP OFF UNUSED PORTS.

AIR CURTAIN SCHEDULE

NO.	LOCATION	MAKE	MODEL	AIRFLOW CFM	PROVIDE HEATING COIL Y/N	TOTAL kW	UNIT WEIGHT LBS	CONTROLS				FLA	MCA	MOCP	POWER						MECHANICAL REMARKS	ELECTRICAL REMARKS
								INTERLOCK			NOTES				EM	V/ø	FEEDER	COND	BRKR	CCT		
								SUPPLY	INSTALL	WITH												
AIR-1	ENTRY VESTIBULE 102	OUELLET	C1500ENTECO208V	740	YES	9	44	MECHANICAL	MECHANICAL	DDC		27				208V/3ø	4#8	1"C	40A/3P	MD-1	CUSTOM COLOUR, TO BE SELECTED BY ARCHITECT CONFIRM WITH ARCHITECT PRIOR TO ORDERING. PROVIDE INTERFACE CAPABLE OF COMMUNICATION WITH NEW DDC SYSTEM.	--

PUBLICCITY
Public City Architecture Inc
707 Sara Avenue
Winnipeg Manitoba
R3G 0Y8 204 475 9323
publiccityarchitecture.com

Owner

City of Winnipeg
185 King Street
Winnipeg, Manitoba, R3B 1J1
(204) 794-4418 (204) 986-4354

No.	Date	Revision Notes
1.	2017.05.02	Issued for Construction

APEGM
Certificate of Authorization
MCW/AGE Consulting Professional Engineers
No. 589
THIS IS A PRINT OF A DOCUMENT THAT HAS BEEN ELECTRONICALLY AUTHENTICATED WITH TECHNOLOGY AUTHORIZED BY THE APEGM. THE ORIGINAL IS IN ELECTRONIC FORM.

10557
MCW
MCW / AGE
Consulting Professional Engineers
215-1821 Wellington Avenue
Winnipeg, Manitoba, R3H 0G4
Phone :(204) 779-7900 Fax :(204) 779-1119
E-Mail: mcw_agg@mcw.com

PROVINCE OF MANITOBA
GARFINKEL
2017/05/02
REGISTERED PROFESSIONAL ENGINEER
ELECTRICAL ITEMS ONLY

PROVINCE OF MANITOBA
SCHELLENBERG
Member
21935
2017-05-02
REGISTERED PROFESSIONAL ENGINEER
MECHANICAL ITEMS ONLY

This drawing must not be scaled. The contractors shall verify all dimensions and other data on site prior to commencement of work. Discrepancies, errors, and omissions are to be reported to the Architect prior to proceeding with the Work.

Drawings and specifications as instruments of service are the property of the Architect; the copyright in the same being reserved to him.

No reproduction or revision to these drawings may be made without the permission of the Architect, and when made, must bear his name. All prints to be returned to the Architect upon request.

Project

St. John's Library Renovation

Drawing

Mechanical Specifications, Schedules, & Charts

Drawn By	Reviewed By
JDG	ATS
Scale	Drawing No.
NTS	ME1.1

Date	Project No.	Revision No.
2017.05.02	1503b	0