



Supply and Install new two-tier timber edging w/composite cap (70 LM) and three-tier Timber Edging w/composite cap (25 LM)

Supply and Install new Engineered Wood Fibre Safety Surfacing (281 SM). Installation is to include and additional 150 MM of drainage layer material

Supply and Install new Topsoil and Sod (404 SM) as per SCD 243

1.57m x 0.82m (62"x 32") wear mat installed directly on top of the safety surfacing, secured in place with four (4) duckbill anchors per mat

Supply and Install three (3) 65 mm (2.5") caliper Harvest Gold Linden (Tilia mongolica "Harvest Gold") as per SCD 517

Pick-up and Install Composite Tache Bench as per SCD 121

Pick-up and Install Accessible Picnic Table

Supply and Install two-tier Timber Edging (22LM)

Supply and Install Accessible Playground Ramp as per SCD 656

Supply and Install Crushed Limestone Parkway Path as per SCD 646 (71 SM)

Pick-up and Install Metal Slat Waste Receptacle as per SCD 119

Limit of new Fencing

2.5 m wide vehicle opening with 6mm galvanized chain

Pick-up and Install new Single-Sided Park Sign as per SCD 153

Limit of new Fencing

Hamilton Ave.

Existing Trees

2-12 Play Equipment

Accessible entry

Existing Trees

Supply and Install new Engineered Wood Fibre Safety Surfacing (57 SM). Installation is to include and additional 150 MM of drainage layer material

Supply and Install new two-tier timber edging w/composite cap (30 LM)

Repaint existing mushroom play elements (by others)

Repaint existing elephant play element (by others)

Pick-up and Install Composite Tache Bench on compacted crushed limestone as per SCD 121 and SCD 646

Supply and Install New Fence (141 LM)

Pick-up and Install new Double-Sided Park Sign as per SCD 153

Direction of Drainage

Direction of Drainage

5% Max.

Back Lane



CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.



THE CITY OF WINNIPEG
 Planning, Property and Development Department
 Planning and Land Use Division
 Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)

DESIGNED BY	IM	CHECKED BY	IL
DRAWN BY	IM	APPROVED BY	IL
HORIZ. SCALE	1:250		
VERT. SCALE			
DATE	May 2017		

MANAGER,
 PARK AND OPEN SPACES

DATE

MANAGER,
 PLANNING AND LAND USE DIVISION

DATE

DRAWING TITLE
**Isbister Park
 Playground Redevelopment
 Materials**

SITE ADDRESS 534 Hamilton

DRAWING NO.

I.013-3

BID OPPORTUNITY NO.
 416-2017