

PADMOUNT ENCLOSURE-FRONT ELEVATION SCALE: N.T.S.

EQUIPMENT LIST DESCRIPTION 24VDC POWER SUPPLY MANITOBA HYDRO APPROVED METER SOCKET c/w SCREW TYPE SEALING RING 240V MAIN DISTRIBUTION PANEL: PNL 'A' SURGE PROTECTION DEVICE (SPD) ENCLOSURE LUMINAIRE (NOTE 1) **6** AUTO-DIALER TANK LEVEL CONTROL PANEL WITH LEVEL DISPLAY 8 P-01 STARTER MS-1 MIXER CONTROL PANEL MS-2

MIXER STARTER — FUTURE

ANTENNA C/W ENCLOSURE (NOTE 3)

NOTES:

- 1. ENCLOSURE LUMINAIRE SHALL BE LED TYPE AND CONTROLLED BY EITHER A TOGGLE SWITCH OR DOOR SWITCH. ACCEPTABLE LUMINAIRE INCLUDES PHILIPS EW PROFILE POWERCORE SERIES OR APPROVED EQUIVALENT.
- 2. PADMOUNT ENCLOSURE TO BE SIZED APPROPRIATELY INCLUDE ALL POWER DISTRIBUTION EQUIPMENT, CONTROLS, INSTRUMENTATION, PUMP STARTER. UTILITY METER TO BE MOUNTED ON SIDE OF ENCLOSURE FOR INCOMING SERVICE CONDUCTORS BY MANITOBA HYDRO. PADMOUNT ENCLOSURE SHALL BE NEMA 4 RATED.
- 3. SEAL ENCLOSURE PENETRATION AROUND ANTENNA CABLE TO PREVENT WATER/MOISTURE INGRESS INTO THE PAD MOUNT ENCLOSURE.

FOR TENDER ONLY NOT TO BE USED FOR CONSTRUCTION

METRIC WHOLE NUMBERS INDICATE MILLIMETRES DECIMALIZED NUMBERS INDICATE METRES Certificate of Authorization KGS Group No. 245

APEGIN

CONSULTING ENGINEER'S SEAL B.M. ELEV. LOCATION APPROVED & PROJECT MANAGERS UNDERGROUND STRUCTURES CONSTRUCTION COMPLETION DATE: YYYY MM DD WINNIPEG (204) 896-1209 **GROUP** THUNDER BAY (807) 345-2233 SUPV. U/G STRUCTURES COMMITTEE DATE CHECKED M3 DESIGNED NOTE: DRAWN BY APPROVED LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL JPL SCALE: RELEASED FOR AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION. CONSTRUCTION HORIZONTAL VERTICAL 06/15/17 0 ISSUED FOR TENDER 15-0107-014_E03 DATE BY DATE 2017 06 15





THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT ENGINEERING DIVISION

BRADY ROAD RESOURCE MANAGEMENT FACILITY (BRRMF) DISPOSAL CELL CONSTRUCTION AND LEACHATE COLLECTION STORAGE (300,000 LITRE) TANK

SHEET 37 OF 44 CITY DRAWING NUMBER

1-0400A-E0018-001

ELECTRICAL CONTROL PANEL AND EQUIPMENT LIST