



## 754-2017 ADDENDUM 2

### TACHE PROMENADE RIVERBANK STABILIZATION, BELVEDERE AND SIDEWALK WIDENING

#### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE BID  
OPPORTUNITY**

ISSUED: November 8, 2017  
BY: Michael Van Helden, Ph.D., P.Eng.  
TELEPHONE NO. 204-975-9433

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID OPPORTUNITY AND SHALL  
FORM A PART OF THE CONTRACT  
DOCUMENTS**

Template Version: A20160708

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.**

---

#### **PART B – BIDDING PROCEDURES**

Revise B2.1 to read: The Submission Deadline is 12:00 noon, Winnipeg time, November 15, 2017.

#### **PART D – SUPPLEMENTAL CONDITIONS**

Revise: D16.4 to read: The City intends to award this Contract by December 6, 2017.

Add D17.1.7: No work shall be conducted on the river bottom below Elev. 221.3 m without prior authorization by the Contract Administrator, pending receipt of DFO Authorization for the work.

#### **PART E – SPECIFICATIONS**

Add E16.4.12: The Contractor is advised that Fisheries and Oceans Canada authorization is pending for work below Elev. 221.3 m of the existing river bottom.

- (a) No work shall be conducted on the river bottom below Elev. 221.3 m without prior authorization by the Contract Administrator. For bidding purposes, the Contractor shall assume such authorization is provided on or before February 15, 2018 and that the critical stage D18.1(a) applies to work to be conducted in this area.

Revise E17.5.2(a) to read: The Contractor shall install temporary sleeving as required to control sloughing and caving of the shafts.

Revise E17.6.2(a) to read: Deep sleeving shall be measured and paid for on a unit basis, per rockfill column requiring temporary sleeving. This Work shall be paid for at the Contract Unit Price per unit for the "Items of Work" listed here below, performed in accordance with this Specification and accepted by the Contract Administrator, which price shall be payment in full for supplying all materials and for performing all operations herein described and all other items incidental to the Work.

Add E22.4.6: The Contractor is advised that Fisheries and Oceans Canada authorization is pending for work below Elev. 221.3 m of the existing river bottom.

- (a) No work shall be conducted on the river bottom below Elev. 221.3 m without prior authorization by the Contract Administrator. For bidding purposes, the Contractor

shall assume such authorization is provided on or before February 15, 2018 and that the critical stage D18.1(a) applies to riprap to be placed in this area.

Revise E28.4.2(b) to read: (b) The deck type (profile) and thickness (gauge) shall be Agway Metals CD75-300 decking profile, 76 deep x 1.22 thick, or CANAM P-2432 Decking Profile, Type 18, 76 deep x 1.21 thick, or equal as accepted by the Contract Administrator, in accordance with B7 "Substitutes".

Revise E28.4.2(c) to read: (c) The deck galvanizing shall be Class Z275 for a minimum zinc coating coverage of 275 g/m<sup>2</sup>.

Add E44.6.3(b): Blocks will be placed with a randomized distribution of lengths, as directed by the Contract Administrator.

## **DRAWINGS**

Replace: 754-2017\_Drawing\_B250-17-09-R0 with 754-2017\_Addendum\_2-Drawing\_B250-17-09-R1

Replace: 754-2017\_Drawing\_B250-17-11-R0 with 754-2017\_Addendum\_2-Drawing\_B250-17-11-R1

Replace: 754-2017\_Drawing\_B250-17-12-R0 with 754-2017\_Addendum\_2-Drawing\_B250-17-12-R1

Replace: 754-2017\_Drawing\_B250-17-13-R0 with 754-2017\_Addendum\_2-Drawing\_B250-17-13-R1

Replace: 754-2017\_Drawing\_B250-17-14-R0 with 754-2017\_Addendum\_2-Drawing\_B250-17-14-R1

Replace: 754-2017\_Drawing\_B250-17-15-R1 with 754-2017\_Addendum\_2-Drawing\_B250-17-15-R2