


1
01 **TREE REMOVAL & PROTECTION PLAN**
SCALE: 1:250

- PROTECTION AND PRUNING OF EXISTING TREES:**
1. CONTRACTOR TO MARK OUT WORKING LIMITS FOR APPROVAL INCLUDING VERTICAL WORKING ROOM.
 2. NO TREES MAY BE REMOVED OR PRUNED WITHOUT APPROVAL FROM THE CONTRACT ADMINISTRATOR.
 3. ERECT 1.8M HT. GALVANIZED CHAIN LINK FENCE TREE PROTECTION BARRIER WHERE INDICATED ON THE DRAWINGS, VERIFIED IN THE FIELD BY CONTRACT ADMINISTRATOR.
 4. STRAP ALL OTHER TREES TO CW1140.
 5. ROOT CUTTING, WITH APPROVAL.
 6. PRUNING BY PROFESSIONAL ARBORIST, AS SPECIFIED.

TREE REMOVAL & PROTECTION LEGEND:

	EXTENT OF RIP-RAP - SEE GEOTECH		REMOVE EXISTING SHRUBS
	APPROX. EXTENT OF TREE PROTECTION ZONE / FENCING		REMOVE EXISTING TREES
	EXTENT OF WORKING PLATFORM - SEE GEOTECH		PROTECT & MAINTAIN EXISTING TREES - SEE NOTES & SPECS.

C:\10_0917_16_30\htfc\10_0917_16_30\HTFC_SERVER\2017\17-042_Tache_Promenade\4.2_Construction_Drawings\ACAD\17-042_LAYOUT.dwg -tab:01_02_03_Tree_Protection

LOCATIONS APPROVED UNDERGROUND STRUCTURES		G.B.M. ELEV.	DATE	BY
SIGNED BY:	DATE			
SUPV U/G STRUCTURES				
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT CONFIRMATION OF EXISTANCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING				
0	ISSUED FOR TENDER	17/10/13	JH	
NO.	REVISIONS	DATE	BY	DATE

HTFC
PLANNING & DESIGN
300-115 St. James Avenue East Winnipeg, MB R2B 0P2
PHONE: 204-944-1907

DESIGNED BY: GM	CHECKED BY: GM
DRAWN BY: JH	APPROVED BY: GM
HOR. SCALE: AS NOTED	
VERTICAL SCALE: AS NOTED	
RELEASED FOR CONSTRUCTION	
DATE: 17/10/13	DATE:

ENGINEER'S SEAL

 CONSULTANT ACAD DWG. NO.

THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION

TACHE PROMENADE

TREE REMOVAL & PROTECTION PLAN

CITY DRAWING NUMBER: B250-17-59
SHEET 59 OF 70
DRAWING No. 01 REV 0

BID OPPORTUNITY No. 754-2017