

APPENDIX 'A'

GEOTECHNICAL REPORT

CITY OF WINNIPEG

2018 ALLEY RENEWALS - CONTRACT 3

GEOTECHNICAL REPORT

MARCH 20, 2018





2018 ALLEY RENEWALS - CONTRACT 3

GEOTECHNICAL REPORT

CITY OF WINNIPEG

FINAL REPORT

PROJECT NO.: 17M-02283-00
DATE: MARCH 20, 2018

WSP
1600 BUFFALO PLACE
WINNIPEG (MANITOBA) R3T 6B8
CANADA

T: +1 204 477-6650
F: +1 204 474-2864
WSP.COM

SIGNATURES

PREPARED BY



Dana Bredin, P.Eng.
Geotechnical / Civil Engineer



REVIEWED BY



Silvestre Urbano, P.Eng.
Senior Geotechnical Engineer



This report was prepared by WSP Canada Inc. for the account of CITY OF WINNIPEG, in accordance with the professional services agreement. The disclosure of any information contained in this report is the sole responsibility of the intended recipient. The material in it reflects WSP Canada Inc.'s best judgement in light of the information available to it at the time of preparation. Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. WSP Canada Inc. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report. This limitations statement is considered part of this report.

The original of the technology-based document sent herewith has been authenticated and will be retained by WSP for a minimum of ten years. Since the file transmitted is now out of WSP's control and its integrity can no longer be ensured, no guarantee may be given with regards to any modifications made to this document.

TABLE OF CONTENTS

1	INTRODUCTION.....	1
2	SUB-SURFACE INVESTIGATION AND TESTING.....	1
3	TESTHOLE SUMMARY TABLES	2
4	CLOSURE	5

TABLES

TABLE 3-1 – MELROSE/PANDORA ALLEY	2
TABLE 3-2 – KILDARE/BRIGHTON ALLEY	2
TABLE 3-3 – HOME/ETHELBERT ALLEY	3
TABLE 3-4 – DUNDURN/WOLSELEY ALLEY	3
TABLE 3-5 – FURBY/LANGSIDE ALLEY	4
TABLE 3-6 – EVANSON/LENORE ALLEY	4

APPENDICES

A	MELROSE / PANDORA ALLEY
B	KILDARE / BRIGHTON ALLEY
C	HOME / ETHELBERT ALLEY
D	DUNDURN / WOLSELEY ALLEY
E	FURBY / LANGSIDE ALLEY
F	LENORE / EVANSON ALLEY

1 INTRODUCTION

A geotechnical investigation was conducted by WSP Canada Inc. for the proposed 2018 Alley Renewals – Contract 3 Project in Winnipeg, Manitoba. The purpose of this investigation was to assess the general subsurface conditions with respect to identifying the existing pavement structure and the underlying soil profile.

Six alleys were cored and drilled, which includes the following alleys:

- A. West/east alley between Melrose Ave W and Pandora Ave W from Bond St to Winona St
- B. West/east alley between Kildare Ave E and Brighton Court from Southampton Pl to Wayoata St
- C. Alleys bounded by Home St and Ethelbert St, Preston Ave and Westminster Ave
- D. Alleys bounded by Dundurn Pl and Wolseley Ave, Walnut St and Maryland St
- E. North/south alley between Furby St and Langside St from Westminster Ave to Sara Ave
- F. North/south alley between Lenore St and Evanson St from Wolseley Ave to Wellington Ave

2 SUB-SURFACE INVESTIGATION AND TESTING

The field investigation was undertaken on February 8, 2018 and was completed on February 14, 2018. A total of 16 test holes and cores were completed by Maple Leaf Drilling. The test holes were drilled to a depth of 3.05 m below the road surface using a truck-mounted B-40 rig equipped with a 125 mm auger as well as track-mounted GeoProbe also equipped with a 125 mm auger. The pavement was cored using a 150 mm diameter coring press. All test holes were backfilled with auger cuttings and bentonite after the completion of the drilling and patched with either cold mix asphalt or quick setting concrete. Testhole locations are noted on the testhole logs and within the test hole summary tables.

The soils encountered were visually classified to the full extent of the test hole. Representative soil samples were recovered at regular intervals, every 0.3 m to 2.1 m as well as one sample at 3.0 m. All of the soil samples were tested for their moisture contents and selected soil samples were submitted for grain size analysis (minimum one per alley). The pavement cores were measured for their thickness and each core was photographed. No groundwater seepage or sloughing was encountered in the test holes during drilling.

The photos of the pavement cores, detailed descriptions of the soil profiles for each test hole, the material test results and the testholes maps are included in Appendices, organized by alley.

3 TESTHOLE SUMMARY TABLES

Table 3-1 – Melrose/Pandora Alley

TEST HOLE NO.	TESTHOLE LOCATION	PAVEMENT SURFACE		PAVEMENT STRUCTURE MATERIAL		SOIL DESCRIPTION	BOREHOLE DEPTH (m)	No. of Samples Taken
		Type	Thickness (mm)	Type	Thickness (mm)			
A-TH1	643215.9 m E 5528733.6 m N South side of Alley behind 111 Bond St	Asphalt & Concrete	30 & 150	Fill (Clayey)	270	Clay	3.05	8

Table 3-2 – Kildare/Brighton Alley

TEST HOLE NO.	TESTHOLE LOCATION	PAVEMENT SURFACE		PAVEMENT STRUCTURE MATERIAL		SOIL DESCRIPTION	BOREHOLE DEPTH (m)	No. of Samples Taken
		Type	Thickness (mm)	Type	Thickness (mm)			
B-TH1	644433.9 m E 5529598.5 m N Centre of Alley behind 601 Kildare Ave E	Concrete	140	Clay	Bottom of testhole	Clay	3.05	8
B-TH2	644557.6 m E 5529600.4 m N Centre of Alley behind 633 Kildare Ave E	Concrete	150	Clay	Bottom of testhole	Clay	3.05	8
B-TH3	644666.9 m E 5529601.9 m N Centre of Alley beside 3 Southampton Pl	Concrete	150	Fill (Clayey)	450	Clay	3.05	8

Table 3-3 – Home/Ethelbert Alley

TEST HOLE NO.	TESTHOLE LOCATION	PAVEMENT SURFACE		PAVEMENT STRUCTURE MATERIAL		SOIL DESCRIPTION	BOREHOLE DEPTH (m)	No. of Samples Taken
		Type	Thickness (mm)	Type	Thickness (mm)			
C-TH1	631621.2 m E 5527104.9 m N Centre of Alley behind 177 Home St	Concrete	170	Fill (sandy/silty)	280	Fill/Silt/Clay	3.05	8
C-TH2	631622.0 m E 5527165.1 m N Centre of Alley behind 189 Home St	Asphalt & Concrete	60 & 120	Fill (sandy/silty)	270	Fill/Clay/Silt/Clay	3.05	8
C-TH3	631624.8 m E 5527253.7 m N Centre of Alley behind 203 Home St	Asphalt & Concrete	30 & 140	Fill (clayey)	730	Fill/Clay	3.05	8
C-TH4	631641.4 m E 5527299.8 m N South side of Alley behind 226 Ethelbert St	Concrete	170	Fill (clayey)	1030	Fill/Clay	3.05	8

Table 3-4 – Dundurn/Wolseley Alley

TEST HOLE NO.	TESTHOLE LOCATION	PAVEMENT SURFACE		PAVEMENT STRUCTURE MATERIAL		SOIL DESCRIPTION	BOREHOLE DEPTH (m)	No. of Samples Taken
		Type	Thickness (mm)	Type	Thickness (mm)			
D-TH1	631923.6 m E 5526998.5 m N Centre of Alley behind 50 Dundurn Pl	Concrete (broken)	250	Fill (clayey)	2150	Fill/Clay	3.05	8
D-TH2	632073.7 m E 5527016.2 m N East side of Alley beside 12 Dundurn Pl	Asphalt & Concrete (broken)	50 & 100	Fill (sandy/silty)	250	Fill/Clay	3.05	8

Table 3-5 – Furby/Langside Alley

TEST HOLE NO.	TESTHOLE LOCATION	PAVEMENT SURFACE		PAVEMENT STRUCTURE MATERIAL		SOIL DESCRIPTION	BOREHOLE DEPTH (m)	No. of Samples Taken
		Type	Thickness (mm)	Type	Thickness (mm)			
E-TH1	632381.6 m E 5527136.6 m N Centre of Alley behind 114 Langside St	Concrete	150	Fill (clayey)	750	Fill/Silt/Clay	3.05	8
E-TH2	632382.9 m E 5527219.4 m N Centre of Alley behind 134 Langside St	Concrete	180	Fill (clayey)	270	Fill/Clay	3.05	8
E-TH3	632384.0 m E 5527312.5 m N Centre of Alley behind 164 Langside St	Concrete	180	Fill (clayey)	910	Fill/Silt/Clay	3.05	8

Table 3-6 – Evanson/Lenore Alley

TEST HOLE NO.	TESTHOLE LOCATION	PAVEMENT SURFACE		PAVEMENT STRUCTURE MATERIAL		SOIL DESCRIPTION	BOREHOLE DEPTH (m)	No. of Samples Taken
		Type	Thickness (mm)	Type	Thickness (mm)			
F-TH1	631381.1 m E 5526856.3 m N Centre of Alley behind 77 Lenore St	Concrete	120	Fill (clayey)	630	Fill/Clay/Silt/Clay	3.05	8
F-TH2	631381.8 m E 5526947.3 m N Centre of Alley behind 97 Lenore St	Asphalt & Concrete (deteriorated)	30 & 140	Granular Fill	130	Fill/Silt/Clay	3.05	8
F-TH3	631384.0 m E 5527031.5 m N Centre of Alley behind 123 Lenore St	Asphalt & Concrete (deteriorated)	50 & 50	Granular Fill	170	Fill/Clay/Silt/Clay	3.05	8

4 CLOSURE

The findings and recommendations provided in this report were prepared by WSP Canada Inc. (the Consultant) in accordance with generally accepted professional engineering principles and practices. The recommendations are based on the results of field and laboratory investigations and are reflective only of the actual test hole(s) and/or excavation(s) examined. If conditions encountered during construction appear to be different than those shown by the test hole(s) and/or excavation(s) at this site, the Consultant should be notified immediately in order that the recommendations can be reviewed and modified as necessary to address actual site conditions.

This report is limited in scope to only those items that are specifically referenced in this report. There may be existing conditions that were not recorded in this report. Such conditions were not apparent to the Consultant due to the limitations imposed by the scope of work. The Consultant, therefore, accepts no liability for any costs incurred by the Client for subsequent discovery, manifestation or rectification of such conditions.

This report is intended solely for the Client named as a general indication of the visible or reported physical condition of the items addressed in the report at the time of the geotechnical investigation. The material in this report reflects the Consultant's best judgment in light of the information available to it at the time of preparation.

This report and the information and data contained herein are to be treated as confidential and may be used only by the Client and its officers and employees in relation to the specific project that it was prepared for. Any use a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. The Consultant accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report.


The report has been written to be read in its entirety, do not use any part of this report as a separate entity.

All files, notes, source data, test results and master files are retained by the Consultant and remain the property of the Consultant.

APPENDIX

A

MELROSE / PANDORA ALLEY



BOND ST

MELROSE AVE W

A-TH14

WINONA ST

PANDORA AVE W

2018 ALLEY RENEWALS – CONTRACT 3
MELROSE/PANDORA/BOND/WINONA ALLEY
TESTHOLE LOCATIONS

TITLE:



1600 BUFFALO PLACE
WINNIPEG, MANITOBA
CANADA, R2T 6B8
PHONE: 204-665-2864
FAX: 204-674-2864
WWW.KSPGROUP.COM

SCALE:

1:1000

REVISION:

DATE:
2018/03/20

DRAWING NO:
GT-A

PROJECT NO:
17M-Q2283-00

STAMP

KSP



WSP
1600 Buffalo Place
Winnipeg, MB R3T 6B8
Telephone: (204)-477-6650

A-TH1

PAGE 1 OF 1

CLIENT City of Winnipeg

PROJECT NUMBER 17M-02283-00

DATE STARTED 2/14/18 COMPLETED 2/14/18

DRILLING CONTRACTOR Maple Leaf Drilling

DRILLING METHOD Solid Stem Auger - CME

LOGGED BY Dana Bredin CHECKED BY Silvestre Urbano

NOTES South side of alley: 643215.9 m E, 5528733.6 m N

PROJECT NAME 2018 Alley Renewals - Contract 3

PROJECT LOCATION Melrose/Pandorra Alley

GROUND ELEVATION HOLE SIZE 125 mm

GROUND WATER LEVELS:

AT TIME OF DRILLING ---

AT END OF DRILLING ---

AFTER DRILLING ---







Figure 1 – TH1 Melrose/Pandora

PARTICLE SIZE ANALYSIS OF SOILS TEST REPORT

CLIENT:	WSP Canada Group Limited Suite 111-93 Lombard Avenue Winnipeg, MB R3B 3B1	PROJECT NO.	103-1804
ATTENTION:	Dana Bredin		
PROJECT:	17M-02283-00 Bond		

Date Sampled:	20-Feb-18	Date Received:	20-Feb-18	Sieve Analysis	Hydrometer Analysis		
Sampled By:	Client	Date Tested:	26-Feb-18	Sieve (mm)	% Passing	Diameter	% Finer
				50.00	100.0		
				37.50	100.0		
				25.00	100.0		
				19.00	100.0		
				16.00	100.0		
				12.50	100.0	0.0363	98.6
				9.50	100.0	0.0259	96.6
				4.75	100.0	0.0187	92.6
				2.00	100.0	0.0096	86.5
				1.18	100.0	0.0071	84.6
				0.425	100.0	0.0052	77.4
				0.180	99.6	0.0027	70.2
				0.075	99.2	0.0011	61.3



Remarks: Test Method: ASTM D422, D2216, D4318

Technician: GM

Reviewed by: Hermie Manalo

MOISTURE CONTENT OF SOIL (ASTM D2216)

CLIENT:	WSP	TEST NO:	18- 011	PROJECT NO:	103-1804
PROJECT:	17M-02283-00	DATE SAMPLED:	20-Feb-2018	SAMPLED BY:	Client
PROJECT CONTACT:	Dana Bredin	DATE TESTED:	23-Feb-2018	TESTED BY:	Greg Manalo
TEST LOCATION:	Bond				
Description	TH1	TH1	TH1	TH1	TH1
Depth (ft)	1	2	3	4	5
Wt Wet Sample + Tare	130.20	153.70	273.70	164.00	145.20
Wt Dry Sample + Tare	104.80	112.00	203.60	124.80	112.10
Wt Water	25.40	41.70	70.10	39.20	33.10
Wt Tare	4.20	4.20	4.10	4.10	4.20
Wt Dry Sample	100.60	107.80	199.50	120.70	107.90
Moisture Content (%)	25.2	38.7	35.1	32.5	30.7
Description	TH1	TH1	TH1		
Depth (ft)	6	7	10		
Wt Wet Sample + Tare	164.10	139.60	185.50		
Wt Dry Sample + Tare	119.90	95.90	126.00		
Wt Water	44.20	43.70	59.50		
Wt Tare	4.10	4.10	4.10		
Wt Dry Sample	115.80	91.80	121.90		
Moisture Content (%)	38.2	47.6	48.8		
Description					
Depth (ft)					
Wt Wet Sample + Tare					
Wt Dry Sample + Tare					
Wt Water					
Wt Tare					
Wt Dry Sample					
Moisture Content (%)					
Description					
Depth (ft)					
Wt Wet Sample + Tare					
Wt Dry Sample + Tare					
Wt Water					
Wt Tare					
Wt Dry Sample					
Moisture Content (%)					

APPENDIX

B

KILDARE / BRIGHTON ALLEY





WSP
1600 Buffalo Place
Winnipeg, MB R3T 6B8
Telephone: (204)-477-6650

B-TH1

PAGE 1 OF 1

CLIENT City of Winnipeg

PROJECT NUMBER 17M-02283-00

DATE STARTED 2/14/18 COMPLETED 2/14/18

DRILLING CONTRACTOR Maple Leaf Drilling

DRILLING METHOD Solid Stem Auger - CME

LOGGED BY Dana Bredin CHECKED BY Silvestre Urbano

NOTES CL of alley: 644433.9 m E, 5529598.5 m N

PROJECT NAME 2018 Alley Renewals - Contract 3

PROJECT LOCATION Brighton/Kildare Alley


GROUND ELEVATION HOLE SIZE 125 mm

GROUND WATER LEVELS:

AT TIME OF DRILLING ---

AT END OF DRILLING ---

AFTER DRILLING ---





WSP
1600 Buffalo Place
Winnipeg, MB R3T 6B8
Telephone: (204)-477-6650

B-TH2

PAGE 1 OF 1

CLIENT City of Winnipeg

PROJECT NUMBER 17M-02283-00

DATE STARTED 2/14/18 COMPLETED 2/14/18

DRILLING CONTRACTOR Maple Leaf Drilling

DRILLING METHOD Solid Stem Auger - CME

LOGGED BY Dana Bredin CHECKED BY Silvestre Urbano

NOTES CL of alley: 644557.6 m E, 5529600.4 m N

PROJECT NAME 2018 Alley Renewals - Contract 3

PROJECT LOCATION Brighton/Kildare Alley


GROUND ELEVATION HOLE SIZE 125 mm

GROUND WATER LEVELS:

AT TIME OF DRILLING ---

AT END OF DRILLING ---

AFTER DRILLING ---





WSP
1600 Buffalo Place
Winnipeg, MB R3T 6B8
Telephone: (204)-477-6650

B-TH3

PAGE 1 OF 1

CLIENT City of Winnipeg

PROJECT NUMBER 17M-02283-00

DATE STARTED 2/14/18 COMPLETED 2/14/18

DRILLING CONTRACTOR Maple Leaf Drilling

DRILLING METHOD Solid Stem Auger - CME

LOGGED BY Dana Bredin CHECKED BY Silvestre Urbano

NOTES CL of alley: 644666.9 m E, 5529601.9 m N

PROJECT NAME 2018 Alley Renewals - Contract 3

PROJECT LOCATION Brighton/Kildare Alley

GROUND ELEVATION HOLE SIZE 125 mm

GROUND WATER LEVELS:

AT TIME OF DRILLING ---

AT END OF DRILLING ---

AFTER DRILLING ---






Figure 2 - TH1 Kildare/Brighton



Figure 3 - TH2 Kildare/Brighton




Figure 4 - TH3 Kildare/Brighton

PARTICLE SIZE ANALYSIS OF SOILS TEST REPORT

CLIENT:	WSP Canada Group Limited Suite 111-93 Lombard Avenue Winnipeg, MB R3B 3B1	PROJECT NO.	103-1804
ATTENTION:	Dana Bredin		
PROJECT:	17M-02283-00 Kildare		

Date Sampled:	20-Feb-18	Date Received:	20-Feb-18	Sieve Analysis	Hydrometer Analysis		
Sampled By:	Client	Date Tested:	26-Feb-18	Sieve (mm)	% Passing	Diameter	% Finer
				50.00	100.0		
				37.50	100.0		
				25.00	100.0		
				19.00	100.0		
				16.00	100.0		
				12.50	100.0	0.0372	93.4
				9.50	100.0	0.0264	92.4
				4.75	100.0	0.0189	90.4
				2.00	100.0	0.0097	84.4
				1.18	100.0	0.0072	80.4
				0.425	100.0	0.0052	75.4
				0.180	99.6	0.0027	68.0
				0.075	99.2	0.0012	55.4



SOIL DESCRIPTION	% Composition		D10
	Gravel	Sand	
SILTY CLAY	0.8	Silt	D30
	43.8	Cu	D60
	55.4	#DIV/0!	0.00116
		Clay	Cc
			#DIV/0!

Remarks: Test Method: ASTM D422, D2216, D4318

Technician: GM



Reviewed by: Hermie Manalo

MOISTURE CONTENT OF SOIL (ASTM D2216)

CLIENT:	WSP	TEST NO:	18- 013	PROJECT NO:	103-1804
PROJECT:	17M-02283-00	DATE SAMPLED:	20-Mar-2018	SAMPLED BY:	Client
PROJECT CONTACT:	Dana Bredin	DATE TESTED:	23-Feb-2018	TESTED BY:	Irvin Araquil
TEST LOCATION:	Kildare				
Description	TH1	TH1	TH1	TH1	TH1
Depth (ft)	1	2	3	4	5
Wt Wet Sample + Tare	150.40	162.80	161.10	161.50	167.30
Wt Dry Sample + Tare	109.50	117.60	119.50	121.50	129.00
Wt Water	40.90	45.20	41.60	40.00	38.30
Wt Tare	4.20	4.20	4.20	4.20	4.20
Wt Dry Sample	105.30	113.40	115.30	117.30	124.80
Moisture Content (%)	38.8	39.9	36.1	34.1	30.7
Description	TH1	TH1	TH1		
Depth (ft)	6	7	10		
Wt Wet Sample + Tare	155.90	152.80	157.50		
Wt Dry Sample + Tare	112.00	106.60	105.60		
Wt Water	43.90	46.20	51.90		
Wt Tare	4.20	4.20	4.20		
Wt Dry Sample	107.80	102.40	101.40		
Moisture Content (%)	40.7	45.1	51.2		
Description	TH2	TH2	TH2	TH2	TH2
Depth (ft)	1	2	3	4	5
Wt Wet Sample + Tare	155.60	168.00	260.80	166.10	152.60
Wt Dry Sample + Tare	112.60	125.70	196.20	127.50	109.70
Wt Water	43.00	42.30	64.60	38.60	42.90
Wt Tare	4.20	4.20	4.20	4.20	4.20
Wt Dry Sample	108.40	121.50	192.00	123.30	105.50
Moisture Content (%)	39.7	34.8	33.6	31.3	40.7
Description	TH2	TH2	TH2		
Depth (ft)	6	7	10		
Wt Wet Sample + Tare	165.40	161.30	156.00		
Wt Dry Sample + Tare	115.60	111.70	102.50		
Wt Water	49.80	49.60	53.50		
Wt Tare	4.20	4.20	4.20		
Wt Dry Sample	111.40	107.50	98.30		
Moisture Content (%)	44.7	46.1	54.4		

MOISTURE CONTENT OF SOIL (ASTM D2216)

CLIENT:	WSP	TEST NO:	18- 013	PROJECT NO:	103-1804
PROJECT:	17M-02283-00	DATE SAMPLED:	20-Mar-2018	SAMPLED BY:	Client
PROJECT CONTACT:	Dana Bredin	DATE TESTED:	23-Feb-2018	TESTED BY:	Irvin Araquil
TEST LOCATION:	Kildare				
Description	TH3	TH3	TH3	TH3	TH3
Depth (ft)	1	2	3	4	5
Wt Wet Sample + Tare	151.00	158.90	158.50	153.60	155.60
Wt Dry Sample + Tare	113.80	115.20	118.00	116.30	117.00
Wt Water	37.20	43.70	40.50	37.30	38.60
Wt Tare	4.20	4.20	4.20	4.20	4.20
Wt Dry Sample	109.60	111.00	113.80	112.10	112.80
Moisture Content (%)	33.9	39.4	35.6	33.3	34.2
Description	TH3	TH3	TH3		
Depth (ft)	6	7	10		
Wt Wet Sample + Tare	165.60	157.90	160.20		
Wt Dry Sample + Tare	131.70	111.70	108.10		
Wt Water	33.90	46.20	52.10		
Wt Tare	4.20	4.20	4.20		
Wt Dry Sample	127.50	107.50	103.90		
Moisture Content (%)	26.6	43.0	50.1		
Description					
Depth (ft)					
Wt Wet Sample + Tare					
Wt Dry Sample + Tare					
Wt Water					
Wt Tare					
Wt Dry Sample					
Moisture Content (%)					
Description					
Depth (ft)					
Wt Wet Sample + Tare					
Wt Dry Sample + Tare					
Wt Water					
Wt Tare					
Wt Dry Sample					
Moisture Content (%)					

APPENDIX

C

HOME / ETHELBERT ALLEY





WESTMINSTER AVE

ETHELBERT ST

C-TH1

C-TH2

C-TH3

C-TH4

PRESTON AVE

HOME ST

2018 ALLEY RENEWALS – CONTRACT 3
HOME/ETHELBERT/PRESTON/WESTMINSTER ALLEY
TESTHOLE LOCATIONS

TITLE:

W.S.P.

1600 BUFFALO PLACE
WINNIPEG, MANITOBA
CANADA, R2T 6B8
PHONE: 204-677-6650 FAX: 204-674-2864
WWW.WSPGROUP.COM

SCALE:

1:1250

DATE:

2018/03/20

PROJECT NO:

17M-C2283-00

REVISION:

GT-C

DRAWING NO:

STAMP



WSP
1600 Buffalo Place
Winnipeg, MB R3T 6B8
Telephone: (204)-477-6650

C-TH1

PAGE 1 OF 1

CLIENT City of Winnipeg

PROJECT NUMBER 17M-02283-00

DATE STARTED 2/9/18 COMPLETED 2/9/18

DRILLING CONTRACTOR Maple Leaf Drilling

DRILLING METHOD Solid Stem Auger - Geoprobe

LOGGED BY Dana Bredin CHECKED BY Silvestre Urbano

NOTES CL of alley: 631621.2 m E, 5527104.9 m N

PROJECT NAME 2018 Alley Renewals - Contract 3

PROJECT LOCATION Home/Ethelbert Alley


GROUND ELEVATION HOLE SIZE 125 mm

GROUND WATER LEVELS:

AT TIME OF DRILLING ---

AT END OF DRILLING ---

AFTER DRILLING ---





WSP
1600 Buffalo Place
Winnipeg, MB R3T 6B8
Telephone: (204)-477-6650

C-TH2

PAGE 1 OF 1

CLIENT City of Winnipeg

PROJECT NUMBER 17M-02283-00

DATE STARTED 2/9/18 COMPLETED 2/9/18

DRILLING CONTRACTOR Maple Leaf Drilling

DRILLING METHOD Solid Stem Auger - Geoprobe

LOGGED BY Dana Bredin CHECKED BY Silvestre Urbano

NOTES CL of alley: 631622.0 m E, 5527165.1 m N

PROJECT NAME 2018 Alley Renewals - Contract 3

PROJECT LOCATION Home/Ethelbert Alley


GROUND ELEVATION HOLE SIZE 125 mm

GROUND WATER LEVELS:

AT TIME OF DRILLING ---

AT END OF DRILLING ---

AFTER DRILLING ---





WSP
1600 Buffalo Place
Winnipeg, MB R3T 6B8
Telephone: (204)-477-6650

C-TH3

PAGE 1 OF 1

CLIENT City of Winnipeg

PROJECT NUMBER 17M-02283-00

DATE STARTED 2/9/18 COMPLETED 2/9/18

DRILLING CONTRACTOR Maple Leaf Drilling

DRILLING METHOD Solid Stem Auger - Geoprobe

LOGGED BY Dana Bredin CHECKED BY Silvestre Urbano

NOTES CL of alley: 631624.8 m E, 5527253.7 m N

PROJECT NAME 2018 Alley Renewals - Contract 3

PROJECT LOCATION Home/Ethelbert Alley


GROUND ELEVATION HOLE SIZE 125 mm

GROUND WATER LEVELS:

AT TIME OF DRILLING ---

AT END OF DRILLING ---

AFTER DRILLING ---





WSP
1600 Buffalo Place
Winnipeg, MB R3T 6B8
Telephone: (204)-477-6650

C-TH4

PAGE 1 OF 1

CLIENT City of Winnipeg

PROJECT NUMBER 17M-02283-00

DATE STARTED 2/9/18 COMPLETED 2/9/18

DRILLING CONTRACTOR Maple Leaf Drilling

DRILLING METHOD Solid Stem Auger - Geoprobe

LOGGED BY Dana Bredin CHECKED BY Silvestre Urbano

NOTES South side of alley: 631641.4 m E, 5527299.8 m N

PROJECT NAME 2018 Alley Renewals - Contract 3

PROJECT LOCATION Home/Ethelbert Alley


GROUND ELEVATION HOLE SIZE 125 mm

GROUND WATER LEVELS:

AT TIME OF DRILLING ---

AT END OF DRILLING ---

AFTER DRILLING ---



- Testhole open to bottom after completion
- Backfilled with auger cuttings and patched with concrete



Figure 5 – TH1 Home/Ethelbert



Figure 6 – TH2 Home/Ethelbert



Figure 7 - TH3 Home/Ethelbert




Figure 8 – TH4 Home/Ethelbert

PARTICLE SIZE ANALYSIS OF SOILS TEST REPORT

CLIENT:	WSP Canada Group Limited Suite 111-93 Lombard Avenue Winnipeg, MB R3B 3B1	PROJECT NO.	103-1804
ATTENTION:	Dana Bredin		
PROJECT:	17M-02283-00 Home		

Date Sampled:	12-Feb-18	Date Received:	12-Feb-18	Sieve Analysis	Hydrometer Analysis		
Sampled By:	Client	Date Tested:	15-Feb-18	Sieve (mm)	% Passing	Diameter	% Finer
				50.00	100.0		
				37.50	100.0		
				25.00	100.0		
				19.00	100.0		
				16.00	100.0		
Material Identification				12.50	100.0	0.0394	84.6
B.H./T.H. No.	TH 2 @3'			9.50	100.0	0.0284	80.6
Sample No.	8			4.75	100.0	0.0203	77.6
Sample Source				2.00	100.0	0.0103	72.8
Specific Gravity of Material:	2.65			1.18	100.0	0.0077	68.8
				0.425	100.0	0.0055	64.8
				0.180	93.8	0.0028	59.7
				0.075	89.2	0.0012	50.8



SOIL DESCRIPTION	% Composition		D10
	Gravel	D30	
SILTY CLAY	10.8	Sand	D60
	38.4	Silt	Cu
	50.8	Clay	Cc

Remarks: Test Method: ASTM D422, D2216, D4318

Technician: GM

Reviewed by: Hermie Manalo

MOISTURE CONTENT OF SOIL (ASTM D2216)

CLIENT:	WSP	TEST NO:	18- 008	PROJECT NO:	103-1804
PROJECT:	17M-02283-00	DATE SAMPLED:	12-Feb-2018	SAMPLED BY:	Client
PROJECT CONTACT:	Dana Bredin	DATE TESTED:	13-Feb-2018	TESTED BY:	Greg Manalo
TEST LOCATION:	Home				
Description	TH1	TH1	TH1	TH1	TH1
Depth (ft)	1	2	3	4	5
Wt Wet Sample + Tare	173.10	125.40	175.30	175.90	187.20
Wt Dry Sample + Tare	159.40	103.30	150.00	133.50	158.60
Wt Water	13.70	22.10	25.30	42.40	28.60
Wt Tare	4.40	4.30	4.60	4.40	4.20
Wt Dry Sample	155.00	99.00	145.40	129.10	154.40
Moisture Content (%)	8.8	22.3	17.4	32.8	18.5
Description	TH1	TH1	TH1		
Depth (ft)	6	7	10		
Wt Wet Sample + Tare	172.90	154.80	170.10		
Wt Dry Sample + Tare	127.00	109.60	115.90		
Wt Water	45.90	45.20	54.20		
Wt Tare	4.30	4.20	4.30		
Wt Dry Sample	122.70	105.40	111.60		
Moisture Content (%)	37.4	42.9	48.6		
Description	TH2	TH2	TH2	TH2	TH2
Depth (ft)	1	2	3	4	5
Wt Wet Sample + Tare	175.10	168.30	244.90	172.20	175.90
Wt Dry Sample + Tare	158.70	142.50	196.00	134.50	139.20
Wt Water	16.40	25.80	48.90	37.70	36.70
Wt Tare	4.20	4.40	4.10	4.40	4.20
Wt Dry Sample	154.50	138.10	191.90	130.10	135.00
Moisture Content (%)	10.6	18.7	25.5	29.0	27.2
Description	TH2	TH2	TH2		
Depth (ft)	6	7	10		
Wt Wet Sample + Tare	181.10	179.30	139.10		
Wt Dry Sample + Tare	148.40	146.10	101.80		
Wt Water	32.70	33.20	37.30		
Wt Tare	4.20	4.30	4.20		
Wt Dry Sample	144.20	141.80	97.60		
Moisture Content (%)	22.7	23.4	38.2		

MOISTURE CONTENT OF SOIL (ASTM D2216)

CLIENT:	WSP	TEST NO:	18- 008	PROJECT NO:	103-1804
PROJECT:	17M-02283-00	DATE SAMPLED:	12-Feb-2018	SAMPLED BY:	Client
PROJECT CONTACT:	Dana Bredin	DATE TESTED:	13-Feb-2018	TESTED BY:	Greg Manalo
TEST LOCATION:	Home				
Description	TH3	TH3	TH3	TH3	TH3
Depth (ft)	1	2	3	4	5
Wt Wet Sample + Tare	159.40	153.80	154.70	160.80	187.40
Wt Dry Sample + Tare	121.90	121.30	123.80	122.40	146.80
Wt Water	37.50	32.50	30.90	38.40	40.60
Wt Tare	4.60	4.50	4.10	4.30	4.30
Wt Dry Sample	117.30	116.80	119.70	118.10	142.50
Moisture Content (%)	32.0	27.8	25.8	32.5	28.5
Description	TH3	TH3	TH3		
Depth (ft)	6	7	10		
Wt Wet Sample + Tare	149.40	194.10	168.00		
Wt Dry Sample + Tare	107.50	132.60	112.20		
Wt Water	41.90	61.50	55.80		
Wt Tare	4.20	4.40	4.30		
Wt Dry Sample	103.30	128.20	107.90		
Moisture Content (%)	40.6	48.0	51.7		
Description	TH4	TH4	TH4	TH4	TH4
Depth (ft)	1	2	3	4	5
Wt Wet Sample + Tare	186.50	157.30	147.90	164.30	200.60
Wt Dry Sample + Tare	134.70	121.90	113.70	126.30	150.80
Wt Water	51.80	35.40	34.20	38.00	49.80
Wt Tare	4.80	4.50	4.30	7.20	4.30
Wt Dry Sample	129.90	117.40	109.40	119.10	146.50
Moisture Content (%)	39.9	30.2	31.3	31.9	34.0
Description	TH4	TH4	TH4		
Depth (ft)	6	7	10		
Wt Wet Sample + Tare	148.80	172.60	156.80		
Wt Dry Sample + Tare	106.40	116.70	113.70		
Wt Water	42.40	55.90	43.10		
Wt Tare	4.40	4.20	4.30		
Wt Dry Sample	102.00	112.50	109.40		
Moisture Content (%)	41.6	49.7	39.4		

APPENDIX

D

DUNDURN / WOLSELEY ALLEY



MARYLAND ST

DUNDURN PL

D-TH1

WALNUT ST

D-TH2

WOLSELEY AVE

NSI

2018 ALLEY RENEWALS – CONTRACT 3
DUNDURN/WOLSELEY/MARYLAND/WALNUT ALLEY
TESTHOLE LOCATIONS

1600 BUFFALO PLACE
WINNIPEG, MANITOBA
CANADA, R3T 6B8
PHONE: 204-677-6650 FAX: 204-674-2864
WWW.NSFGROUP.COM

SCALE:	1:1000	REVISION:	
DATE:	2018/03/20	DRAWING NO:	GT-D
PROJECT NO:	17M-Q2283-00		

STAMP



WSP
1600 Buffalo Place
Winnipeg, MB R3T 6B8
Telephone: (204)-477-6650

D-TH1

PAGE 1 OF 1

CLIENT City of Winnipeg

PROJECT NUMBER 17M-02283-00

DATE STARTED 2/8/18 COMPLETED 2/8/18

DRILLING CONTRACTOR Maple Leaf Drilling

DRILLING METHOD Solid Stem Auger - B40 Truck Rig

LOGGED BY Dana Bredin CHECKED BY Silvestre Urbano

NOTES CL of alley: 631923.6 m E, 5526998.5 m N

PROJECT NAME 2018 Alley Renewals - Contract 3

PROJECT LOCATION Dundurn/Wolseley Alley


GROUND ELEVATION HOLE SIZE 125 mm

GROUND WATER LEVELS:

AT TIME OF DRILLING ---

AT END OF DRILLING ---

AFTER DRILLING ---





WSP
1600 Buffalo Place
Winnipeg, MB R3T 6B8
Telephone: (204)-477-6650

D-TH2

PAGE 1 OF 1

CLIENT City of Winnipeg

PROJECT NUMBER 17M-02283-00

DATE STARTED 2/8/18 COMPLETED 2/8/18

DRILLING CONTRACTOR Maple Leaf Drilling

DRILLING METHOD Solid Stem Auger - B40 Truck Rig

LOGGED BY Dana Bredin CHECKED BY Silvestre Urbano

NOTES East side of alley: 632073.7 m E, 5527016.2 m N

PROJECT NAME 2018 Alley Renewals - Contract 3

PROJECT LOCATION Dundurn/Wolseley Alley


GROUND ELEVATION HOLE SIZE 125 mm

GROUND WATER LEVELS:

AT TIME OF DRILLING ---

AT END OF DRILLING ---

AFTER DRILLING ---



- Testhole open to bottom after completion
- Backfilled with auger cuttings and patched with asphalt



Figure 9 - TH1 Beverley/Toronto




Figure 10 - TH2 Beverley/Toronto

PARTICLE SIZE ANALYSIS OF SOILS TEST REPORT

CLIENT:	WSP Canada Group Limited Suite 111-93 Lombard Avenue Winnipeg, MB R3B 3B1	PROJECT NO.	103-1804
ATTENTION:	Dana Bredin		
PROJECT:	17M-02283-00 Dundurn		

Date Sampled:	12-Feb-18	Date Received:	12-Feb-18	Sieve Analysis	Hydrometer Analysis		
Sampled By:	Client	Date Tested:	15-Feb-18	Sieve (mm)	% Passing	Diameter	% Finer
				50.00	100.0		
				37.50	100.0		
				25.00	100.0		
				19.00	100.0		
				16.00	100.0		
				12.50	100.0	0.0389	85.3
				9.50	100.0	0.0278	83.3
				7.00	100.0	0.0199	80.3
				4.75	100.0		
				2.00	100.0	0.0101	76.4
				1.18	100.0	0.0075	73.2
				0.425	100.0	0.0054	69.3
				0.180	94.4	0.0028	63.2
				0.075	91.2	0.0012	53.7



Remarks: Test Method: ASTM D422, D2216, D4318

Technician: GM



Reviewed by: Hermie Manalo

MOISTURE CONTENT OF SOIL (ASTM D2216)

CLIENT:	WSP	TEST NO:	18- 007	PROJECT NO:	103-1804
PROJECT:	17M-02283-00	DATE SAMPLED:	12-Feb-2018	SAMPLED BY:	Client
PROJECT CONTACT:	Dana Bredin	DATE TESTED:	13-Feb-2018	TESTED BY:	Greg Manalo
TEST LOCATION:	Dundurn				
Description	TH1	TH1	TH1	TH1	TH1
Depth (ft)	1	2	3	4	5
Wt Wet Sample + Tare	141.30	263.70	139.60	162.80	147.70
Wt Dry Sample + Tare	103.80	195.40	102.30	117.70	107.80
Wt Water	37.50	68.30	37.30	45.10	39.90
Wt Tare	4.40	4.30	4.30	4.10	4.20
Wt Dry Sample	99.40	191.10	98.00	113.60	103.60
Moisture Content (%)	37.7	35.7	38.1	39.7	38.5
Description	TH1	TH1	TH1		
Depth (ft)	6	7	10		
Wt Wet Sample + Tare	153.40	158.20	149.50		
Wt Dry Sample + Tare	106.50	108.00	99.90		
Wt Water	46.90	50.20	49.60		
Wt Tare	4.50	4.20	4.30		
Wt Dry Sample	102.00	103.80	95.60		
Moisture Content (%)	46.0	48.4	51.9		
Description	TH2	TH2	TH2	TH2	TH2
Depth (ft)	1	2	3	4	5
Wt Wet Sample + Tare	166.60	158.60	151.20	178.40	142.00
Wt Dry Sample + Tare	147.50	120.70	115.30	135.80	109.00
Wt Water	19.10	37.90	35.90	42.60	33.00
Wt Tare	4.20	4.20	4.30	4.40	4.20
Wt Dry Sample	143.30	116.50	111.00	131.40	104.80
Moisture Content (%)	13.3	32.5	32.3	32.4	31.5
Description	TH2	TH2	TH2		
Depth (ft)	6	7	10		
Wt Wet Sample + Tare	160.50	164.50	157.40		
Wt Dry Sample + Tare	115.80	118.60	106.80		
Wt Water	44.70	45.90	50.60		
Wt Tare	4.20	4.20	4.20		
Wt Dry Sample	111.60	114.40	102.60		
Moisture Content (%)	40.1	40.1	49.3		

APPENDIX

E

FURBY / LANGSIDE ALLEY



WESTMINSTER AVE

LANGSIDE ST

SARA AVE

Φ E-TH1

Φ E-TH2

Φ E-TH3

FURBY ST

CONTRACT 3

2018 ALLEY RENEWALS – CONTRACT 3
FURBY/LANGSIDE/SARA/WESTMINSTER ALLEY
TESTHOLE LOCATIONS

TITLE:

W.S.F.

1600 BUFFALO PLACE
WINNIPEG, MANITOBA
CANADA, R3T 6B8
PHONE: 204-677-6650 FAX: 204-674-2864
WWW.WSFGROUP.COM

SCALE:

1:1000

REVISION:

DATE:
2018/03/20
PROJECT NO:
17M-C2283-00

DRAWING NO:
GT-E

REF

STAMP



WSP
1600 Buffalo Place
Winnipeg, MB R3T 6B8
Telephone: (204)-477-6650

E-TH1

PAGE 1 OF 1

CLIENT City of Winnipeg

PROJECT NUMBER 17M-02283-00

DATE STARTED 2/8/18 COMPLETED 2/8/18

DRILLING CONTRACTOR Maple Leaf Drilling

DRILLING METHOD Solid Stem Auger - B40 Truck Rig

LOGGED BY Dana Bredin CHECKED BY Silvestre Urbano

NOTES CL of alley: 632381.6 m E, 5527136.6 m N

PROJECT NAME 2018 Alley Renewals - Contract 3

PROJECT LOCATION Langside/Furby Alley


GROUND ELEVATION HOLE SIZE 125 mm

GROUND WATER LEVELS:

AT TIME OF DRILLING ---

AT END OF DRILLING ---

AFTER DRILLING ---





WSP
1600 Buffalo Place
Winnipeg, MB R3T 6B8
Telephone: (204)-477-6650

E-TH2

PAGE 1 OF 1

CLIENT City of Winnipeg

PROJECT NUMBER 17M-02283-00

DATE STARTED 2/8/18 COMPLETED 2/8/18

DRILLING CONTRACTOR Maple Leaf Drilling

DRILLING METHOD Solid Stem Auger - B40 Truck Rig

LOGGED BY Dana Bredin CHECKED BY Silvestre Urbano

NOTES CL of alley: 632382.9 m E, 5527219.4 m N

PROJECT NAME 2018 Alley Renewals - Contract 3

PROJECT LOCATION Langside/Furby Alley


GROUND ELEVATION HOLE SIZE 125 mm

GROUND WATER LEVELS:

AT TIME OF DRILLING ---

AT END OF DRILLING ---

AFTER DRILLING ---





WSP
1600 Buffalo Place
Winnipeg, MB R3T 6B8
Telephone: (204)-477-6650

E-TH3

PAGE 1 OF 1

CLIENT City of Winnipeg

PROJECT NUMBER 17M-02283-00

DATE STARTED 2/8/18 COMPLETED 2/8/18

DRILLING CONTRACTOR Maple Leaf Drilling

DRILLING METHOD Solid Stem Auger - B40 Truck Rig

LOGGED BY Dana Bredin CHECKED BY Silvestre Urbano

NOTES CL of alley: 632384.0 m E, 5527312.5 m N

PROJECT NAME 2018 Alley Renewals - Contract 3

PROJECT LOCATION Langside/Furby Alley

GROUND ELEVATION HOLE SIZE 125 mm

GROUND WATER LEVELS:

AT TIME OF DRILLING ---

AT END OF DRILLING ---

AFTER DRILLING ---






Figure 11 – TH1 Furby/Langside



Figure 12 – TH2 Furby/Langside



Figure 13 – TH3 Furby/Langside


PARTICLE SIZE ANALYSIS OF SOILS TEST REPORT

CLIENT: WSP Canada Group Limited
Suite 111-93 Lombard Avenue
Winnipeg, MB R3B 3B1

PROJECT NO. 103-1804

ATTENTION: Dana Bredin
PROJECT: 17M-02283-00
Langside

Date Sampled:	12-Feb-18	Date Received:	12-Feb-18	Sieve Analysis		Hydrometer Analysis	
Sampled By:	Client	Date Tested:	15-Feb-18	Sieve (mm)	% Passing	Diameter	% Finer
				50.00	100.0		
				37.50	100.0		
				25.00	100.0		
				19.00	100.0		
				16.00	100.0		
				12.50	100.0	0.0424	66.8
				9.50	100.0	0.0304	62.8
				6.30	100.0	0.0220	56.8
				4.75	100.0		
				2.00	100.0	0.0115	44.8
				1.18	100.0	0.0086	39.0
				0.425	100.0	0.0061	35.1
				0.180	99.4	0.0031	29.8
				0.075	95.0	0.0013	24.9



SOIL DESCRIPTION	% Composition		D10
	Gravel	Sand	
SILT LOAM	5.0	Silt	D30
	70.1	Cu	0.02202
	24.9	Cc	#DIV/0!
		Clay	#DIV/0!

Remarks: Test Method: ASTM D422, D2216, D4318

Technician: GM



Reviewed by: Hermie Manalo

MOISTURE CONTENT OF SOIL (ASTM D2216)

CLIENT:	WSP	TEST NO:	18- 006	PROJECT NO:	103-1804
PROJECT:	17M-02283-00	DATE SAMPLED:	12-Feb-2018	SAMPLED BY:	Client
PROJECT CONTACT:	Dana Bredin	DATE TESTED:	13-Feb-2018	TESTED BY:	Greg Manalo
TEST LOCATION:	Langside				
Description	TH1	TH1	TH1	TH1	TH1
Depth (ft)	1	2	3	4	5
Wt Wet Sample + Tare	134.00	132.40	278.20	173.20	137.50
Wt Dry Sample + Tare	105.30	96.50	231.40	143.00	107.40
Wt Water	28.70	35.90	46.80	30.20	30.10
Wt Tare	4.30	4.10	4.20	4.20	4.20
Wt Dry Sample	101.00	92.40	227.20	138.80	103.20
Moisture Content (%)	28.4	38.9	20.6	21.8	29.2
Description	TH1	TH1	TH1		
Depth (ft)	6	7	10		
Wt Wet Sample + Tare	151.00	193.50	143.50		
Wt Dry Sample + Tare	107.50	135.50	96.20		
Wt Water	43.50	58.00	47.30		
Wt Tare	4.20	4.40	4.20		
Wt Dry Sample	103.30	131.10	92.00		
Moisture Content (%)	42.1	44.2	51.4		
Description	TH2	TH2	TH2	TH2	TH2
Depth (ft)	1	2	3	4	5
Wt Wet Sample + Tare	174.40	134.20	148.90	171.40	166.10
Wt Dry Sample + Tare	138.00	99.50	111.00	126.40	122.50
Wt Water	36.40	34.70	37.90	45.00	43.60
Wt Tare	4.40	4.30	4.00	4.30	4.20
Wt Dry Sample	133.60	95.20	107.00	122.10	118.30
Moisture Content (%)	27.2	36.4	35.4	36.9	36.9
Description	TH2	TH2	TH2		
Depth (ft)	6	7	10		
Wt Wet Sample + Tare	161.30	165.30	137.80		
Wt Dry Sample + Tare	115.70	115.20	92.60		
Wt Water	45.60	50.10	45.20		
Wt Tare	4.20	4.20	4.40		
Wt Dry Sample	111.50	111.00	88.20		
Moisture Content (%)	40.9	45.1	51.2		

MOISTURE CONTENT OF SOIL (ASTM D2216)

CLIENT:	WSP	TEST NO:	18- 006	PROJECT NO:	103-1804
PROJECT:	17M-02283-00	DATE SAMPLED:	12-Feb-2018	SAMPLED BY:	Client
PROJECT CONTACT:	Dana Bredin	DATE TESTED:	13-Feb-2018	TESTED BY:	Greg Manalo
TEST LOCATION:	Langside				
Description	TH3	TH3	TH3	TH3	TH3
Depth (ft)	1	2	3	4	5
Wt Wet Sample + Tare	138.40	162.60	151.70	158.80	161.10
Wt Dry Sample + Tare	116.50	120.00	116.30	128.40	131.00
Wt Water	21.90	42.60	35.40	30.40	30.10
Wt Tare	4.70	4.20	4.50	4.20	4.20
Wt Dry Sample	111.80	115.80	111.80	124.20	126.80
Moisture Content (%)	19.6	36.8	31.7	24.5	23.7
Description	TH3	TH3	TH3		
Depth (ft)	6	7	10		
Wt Wet Sample + Tare	140.20	171.10	147.10		
Wt Dry Sample + Tare	98.60	118.00	96.80		
Wt Water	41.60	53.10	50.30		
Wt Tare	4.20	4.20	4.30		
Wt Dry Sample	94.40	113.80	92.50		
Moisture Content (%)	44.1	46.7	54.4		
Description					
Depth (ft)					
Wt Wet Sample + Tare					
Wt Dry Sample + Tare					
Wt Water					
Wt Tare					
Wt Dry Sample					
Moisture Content (%)					
Description					
Depth (ft)					
Wt Wet Sample + Tare					
Wt Dry Sample + Tare					
Wt Water					
Wt Tare					
Wt Dry Sample					
Moisture Content (%)					

APPENDIX

F

LENORE / EVANSON ALLEY



WOLSELEY AVE

EVANSON ST

F-TH1

F-TH2

F-TH3

LENORE ST

WESTMINSTER AVE

2018 ALLEY RENEWALS – CONTRACT 3
LENORE/EVANSON/WESTMINSTER/WOLSELEY ALLEY
TESTHOLE LOCATIONS

TITLE:

W.S.F.

1600 BUFFALO PLACE
WINNIPEG, MANITOBA
CANADA, R3T 6B8
PHONE: 204-677-6650 FAX: 204-474-2864
WWW.WSFGROUP.COM

SCALE:

1:1250

DATE:

2018/03/20

PROJECT NO:

17M-C2283-00

REVISION:

GT-F

DRAWING NO:

STAMP



WSP
1600 Buffalo Place
Winnipeg, MB R3T 6B8
Telephone: (204)-477-6650

F-TH1

PAGE 1 OF 1

CLIENT City of Winnipeg

PROJECT NUMBER 17M-02283-00

DATE STARTED 2/9/18 COMPLETED 2/9/18

DRILLING CONTRACTOR Maple Leaf Drilling

DRILLING METHOD Solid Stem Auger - Geoprobe

LOGGED BY Dana Bredin CHECKED BY Silvestre Urbano

NOTES CL of alley: 631380.1 m E, 5526856.3 m N

PROJECT NAME 2018 Alley Renewals - Contract 3

PROJECT LOCATION Evanson/Lenore Alley


GROUND ELEVATION HOLE SIZE 125 mm

GROUND WATER LEVELS:

AT TIME OF DRILLING ---

AT END OF DRILLING ---

AFTER DRILLING ---



- Testhole open to bottom after completion
- Backfilled with auger cuttings and patches with concrete



WSP
1600 Buffalo Place
Winnipeg, MB R3T 6B8
Telephone: (204)-477-6650

F-TH2

PAGE 1 OF 1

CLIENT City of Winnipeg

PROJECT NUMBER 17M-02283-00

DATE STARTED 2/9/18 COMPLETED 2/9/18

DRILLING CONTRACTOR Maple Leaf Drilling

DRILLING METHOD Solid Stem Auger - Geoprobe

LOGGED BY Dana Bredin CHECKED BY Silvestre Urbano

NOTES CL of alley: 631381.8 m E, 5526947.3 m N

PROJECT NAME 2018 Alley Renewals - Contract 3

PROJECT LOCATION Evanson/Lenore Alley


GROUND ELEVATION HOLE SIZE 125 mm

GROUND WATER LEVELS:

AT TIME OF DRILLING ---

AT END OF DRILLING ---

AFTER DRILLING ---





WSP
1600 Buffalo Place
Winnipeg, MB R3T 6B8
Telephone: (204)-477-6650

F-TH3

PAGE 1 OF 1

CLIENT City of Winnipeg

PROJECT NUMBER 17M-02283-00

DATE STARTED 2/9/18 COMPLETED 2/9/18

DRILLING CONTRACTOR Maple Leaf Drilling

DRILLING METHOD Solid Stem Auger - Geoprobe

LOGGED BY Dana Bredin CHECKED BY Silvestre Urbano

NOTES CL of alley: 631384.0 m E, 5527031.5 m N

PROJECT NAME 2018 Alley Renewals - Contract 3

PROJECT LOCATION Evanson/Lenore Alley


GROUND ELEVATION HOLE SIZE 125 mm

GROUND WATER LEVELS:

AT TIME OF DRILLING ---

AT END OF DRILLING ---

AFTER DRILLING ---



- Testhole open to bottom after completion
 - Backfilled with auger cuttings and patched with concrete



Figure 14 - TH1 Lenore/Evanson



Figure 15 – TH2 Lenore/Evanson




Figure 16 - TH3 Lenore/Evanson

PARTICLE SIZE ANALYSIS OF SOILS TEST REPORT

CLIENT:	WSP Canada Group Limited Suite 111-93 Lombard Avenue Winnipeg, MB R3B 3B1	PROJECT NO.	103-1804
ATTENTION:	Dana Bredin		
PROJECT:	17M-02283-00 Evanson		

Date Sampled:	12-Feb-18	Date Received:	12-Feb-18	Sieve Analysis	Hydrometer Analysis		
Sampled By:	Client	Date Tested:	15-Feb-18	Sieve (mm)	% Passing	Diameter	% Finer
				50.00	100.0		
				37.50	100.0		
				25.00	100.0		
				19.00	100.0		
				16.00	100.0		
				12.50	100.0	0.0418	69.4
				9.50	100.0	0.0298	67.4
				4.75	100.0	0.0213	64.4
				2.00	100.0	0.0110	55.2
				1.18	100.0	0.0082	51.3
				0.425	100.0	0.0059	47.2
				0.180	99.0	0.0030	41.1
				0.075	93.8	0.0013	34.7



SOIL DESCRIPTION	% Composition		D10
	Gravel	Sand	
SILTY CLAY LOAM	6.2	Silt	D30
	59.1	Cu	D60
	34.7	#DIV/0!	0.01103
		#DIV/0!	Cc
		#DIV/0!	

Remarks: Test Method: ASTM D422, D2216, D4318

Technician: GM



Reviewed by: Hermie Manalo

MOISTURE CONTENT OF SOIL (ASTM D2216)

CLIENT:	WSP	TEST NO:	18- 009	PROJECT NO:	103-1804
PROJECT:	17M-02283-00	DATE SAMPLED:	12-Feb-2018	SAMPLED BY:	Client
PROJECT CONTACT:	Dana Bredin	DATE TESTED:	13-Feb-2018	TESTED BY:	Greg Manalo
TEST LOCATION:	Evanson				
Description	TH1	TH1	TH1	TH1	TH1
Depth (ft)	1	2	3	4	5
Wt Wet Sample + Tare	161.30	165.10	164.10	178.00	188.60
Wt Dry Sample + Tare	123.60	138.00	129.30	144.60	155.20
Wt Water	37.70	27.10	34.80	33.40	33.40
Wt Tare	4.30	4.20	4.30	4.10	4.20
Wt Dry Sample	119.30	133.80	125.00	140.50	151.00
Moisture Content (%)	31.6	20.3	27.8	23.8	22.1
Description	TH1	TH1	TH1		
Depth (ft)	6	7	10		
Wt Wet Sample + Tare	155.00	170.80	156.90		
Wt Dry Sample + Tare	113.70	119.40	112.10		
Wt Water	41.30	51.40	44.80		
Wt Tare	4.20	4.10	4.10		
Wt Dry Sample	109.50	115.30	108.00		
Moisture Content (%)	37.7	44.6	41.5		
Description	TH2	TH2	TH2	TH2	TH2
Depth (ft)	1	2	3	4	5
Wt Wet Sample + Tare	156.00	152.00	274.20	166.80	196.20
Wt Dry Sample + Tare	118.80	117.50	202.00	133.60	151.50
Wt Water	37.20	34.50	72.20	33.20	44.70
Wt Tare	4.30	4.10	4.50	4.10	4.10
Wt Dry Sample	114.50	113.40	197.50	129.50	147.40
Moisture Content (%)	32.5	30.4	36.6	25.6	30.3
Description	TH2	TH2	TH2		
Depth (ft)	6	7	10		
Wt Wet Sample + Tare	153.70	162.60	165.10		
Wt Dry Sample + Tare	119.10	119.10	117.70		
Wt Water	34.60	43.50	47.40		
Wt Tare	4.20	4.10	4.10		
Wt Dry Sample	114.90	115.00	113.60		
Moisture Content (%)	30.1	37.8	41.7		

MOISTURE CONTENT OF SOIL (ASTM D2216)

CLIENT:	WSP	TEST NO:	18- 009	PROJECT NO:	103-1804
PROJECT:	17M-02283-00	DATE SAMPLED:	12-Feb-2018	SAMPLED BY:	Client
PROJECT CONTACT:	Dana Bredin	DATE TESTED:	13-Feb-2018	TESTED BY:	Greg Manalo
TEST LOCATION:	Evanson				
Description	TH3	TH3	TH3	TH3	TH3
Depth (ft)	1	2	3	4	5
Wt Wet Sample + Tare	175.00	179.70	184.00	179.50	176.30
Wt Dry Sample + Tare	140.00	149.90	149.80	147.50	140.50
Wt Water	35.00	29.80	34.20	32.00	35.80
Wt Tare	4.20	4.10	4.20	4.10	4.10
Wt Dry Sample	135.80	145.80	145.60	143.40	136.40
Moisture Content (%)	25.8	20.4	23.5	22.3	26.2
Description	TH3	TH3	TH3		
Depth (ft)	6	7	10		
Wt Wet Sample + Tare	158.10	162.20	149.90		
Wt Dry Sample + Tare	122.90	115.90	104.10		
Wt Water	35.20	46.30	45.80		
Wt Tare	4.20	4.20	4.10		
Wt Dry Sample	118.70	111.70	100.00		
Moisture Content (%)	29.7	41.5	45.8		
Description					
Depth (ft)					
Wt Wet Sample + Tare					
Wt Dry Sample + Tare					
Wt Water					
Wt Tare					
Wt Dry Sample					
Moisture Content (%)					
Description					
Depth (ft)					
Wt Wet Sample + Tare					
Wt Dry Sample + Tare					
Wt Water					
Wt Tare					
Wt Dry Sample					
Moisture Content (%)					