MECHANICAL SPECIFICATION

MECHANICAL SUB CONTRACTOR SHALL SUBMIT PRICE FOR THE COST OF SUPPLY AND INSTALLATION OF EQUIPMENT AND MATERIAL NECESSARY TO PROVIDE A COMPLETE AND OPERATING MECHANICAL PACKAGE. MECHANICAL PACKAGE TO CONSIST OF EQUIPMENT AND MATERIALS AS DESCRIBED IN THIS OUTLINE SPECIFICATION. REFER TO MECHANICAL PLANS FOR ACTUAL REQUIREMENTS OF EQUIPMENT.

MECHANICAL SCOPE OF WORK

- INCLUDE IN MECHANICAL SECTION, PROVISION OF LABOUR, NEW MATERIALS, TOOLS, TRANSPORTATION, SERVICES AND FACILITIES FOR A COMPLETE MECHANICAL INSTALLATION. THE INSTALLATION SHALL BE LEFT COMPLETE IN ALL RESPECTS AND READY FOR OPERATION. FINAL INSTALLATION SHALL BE INSTALLED TO COMPLETE SATISFACTION OF THE RESPONSIBLE PROFESSIONAL ENGINEER.
- 2. THE MECHANICAL SCOPE OF WORK INCLUDES, BUT IS NOT NECESSARILY LIMITED TO THE FOLLOWING PROVISION:
- 2.1.1. FAMILIARIZE CREW WITH SITE IN ORDER TO DETERMINE APPROPRIATE LOCATIONS, SITE CONDITIONS, ETC.
- 2.1.2. WORK MAY NEED TO BE PERFORMED AT NON-STANDARD HOURS. DETERMINE SCHEDULE WITH CITY
- REPRESENTATIVE.
- 2.1.3. PROVISION OF O&M MANUALS AND TRAINING OF CITY PERSONNEL.
- 2.1.4. RECORD DRAWINGS. 2.1.5. PROVISION OF FIRE STOPPING AT ALL PIPE, DUCT AND CONDUIT WIRING PENETRATIONS INSTALLED BY THIS TRADE (ONLY).

2.2. PLUMBING:

- 2.2.1. PROVISION OF ALL PIPING, FIXTURES, PLUMBING BRASS, PIPE FITTINGS, LABOR, INSULATION AND
- MISCELLANEOUS MATERIALS AS REQUIRE TO COMPLETE THE PROJECT. 2.2.2. PROVISION OF ALL DOMESTIC HOT WATER HEATERS, CIRCULATION PUMPS, AND ASSOCIATED PIPING.

- 2.3.1. PROVISION OF ALL AIR HANDLING EQUIPMENT, FANS, DUCTWORK, CONTROL/BALANCE FITTINGS, INSULATION, GRILLES/REGISTERS/DIFFUSERS/LOUVERS, FIRE DAMPERS, LABOR AND MISCELLANEOUS MATERIALS AS REQUIRED TO COMPLETE THE PROJECT.
- 2.3.2. PROVISION OF TAB REPORTS INCLUDING FIRE DAMPER TESTING, CERTIFICATION AND AIR FLOWS. AND PUMP PERFORMANCE.

2.4.1. PROVISION OF COMPLETE ELECTRONIC CONTROLS AS DESCRIBED.

2.4.2. COORDINATION OF ALL CONTROL INTERFACE AND POWER REQUIREMENTS WITH ELECTRICAL SUB CONTRACTOR.

GENERAL CONDITIONS

- 1. PROVIDE ALL LABOUR, MATERIALS, AND EQUIPMENT NECESSARY TO COMPLETE THE WORK SHOWN ON DRAWINGS AND AS SPECIFIED HEREIN.
- 2. ALL NECESSARY PERMITS SHALL BE OBTAINED AND ALL FEES SHALL BE PAID TO CARRY OUT THE SPECIFIED
- 3. ALL WORK SHALL BE GUARANTEED FOR ONE YEAR FROM DATE OF COMPLETED WORK ACCEPTANCE BY THE CITY. SUBMIT DOCUMENTATION IDENTIFYING ADDITIONAL EQUIPMENT WARRANTY COVERAGE AND TIME FRAMES.
- 4. ALL WORK SHALL COMPLY IN EVERY RESPECT WITH ALL NATIONAL, PROVINCIAL AND LOCAL CODES AND BY-LAWS, WHICH SHALL BE CONSIDERED PART OF THIS SPECIFICATION. IN THE CASE OF CONFLICTING
- REQUIREMENTS, BE GOVERNED BY THE MOST STRINGENT REGULATIONS. 5. ALL CUTTING, PATCHING, FLASHING FOR WORK AS REQUIRED HEREIN SHALL BE BY THE GENERAL CONTRACTOR.
- 6. THE MECHANICAL SUB CONTRACTOR SHALL INSTALL PLUMBING, HEATING, VENTILATION, AIR CONDITIONING, AND SPRINKLER SYSTEMS IN COMPLETE ACCORDANCE WITH THE RECOMMENDATIONS OF THE NATIONAL/PROVINCIAL BUILDING CODE, ASHRAE, SMACNA LATEST EDITION DUCT STANDARDS, AND LOCAL PLUMBING CODES, N.F.P.A. REQUIREMENTS, AND PART 9.36 OF THE NATIONAL BUILDING CODE.
- COORDINATE WORK WITH WORK OF OTHER TRADES TO AVOID CONFLICT.
- 8. ALTER THE LOCATION OF DUCTS OR PIPES AT THE DIRECTION OF THE CONTRACT ADMINISTRATOR WITHOUT CHARGE TO THE CITY, PROVIDED THE CHANGE IS MADE BEFORE INSTALLATION AND DOES NOT NECESSITATE ADDITIONAL MATERIALS.
- 9. QUOTATIONS SHALL BE BASED ON THE USE OF SPECIFIED MANUFACTURERS OR APPROVED EQUAL. THE USE OF AN EQUAL OR ALTERNATE MANUFACTURER SHALL IN NO WAY RELIEVE THE MECHANICAL SUB CONTRACTOR FROM THE RESPONSIBILITY OF PROVIDING ALL WORK THAT MAY BE REQUIRED BY REASON OF DIFFERENT SPACE, WEIGHT, ELECTRICAL, OR OTHER REQUIREMENT FROM THAT OF THE SPECIFIED MANUFACTURER. ALTERNATES SHALL BE APPROVED PRIOR TO THE CLOSE OF BIDS. NO SUBMITTALS RECEIVED AFTER BID CLOSING WILL BE ACCEPTED.
- 10. THE MECHANICAL SUB CONTRACTOR SHALL SUBMIT ELECTRONIC COPIES OF SHOP DRAWINGS FOR ALL EQUIPMENT FOR REVIEW AND APPROVAL BY CONTRACT ADMINISTRATORS. CONTRACTOR SHALL STAMP SHOP DRAWINGS REVIEWED BY CONTRACTOR PRIOR TO SUBMISSION. CONTRACTOR SHALL LABEL SHOP DRAWINGS WITH THE CORRESPONDING EQUIPMENT LABEL LISTED ON MECHANICAL DRAWINGS, SPECIFICATION, AND/OR SCHEDULES. FAILURE TO COMPLY WILL RESULT IN SHOP DRAWINGS BEING RETURNED "UNREVIEWED" BY CONTRACT ADMINISTRATOR.
- 11. FURNISH TO THE CONTRACT ADMINISTRATOR THREE (3) HARD-COVERED LOOSE-LEAF BINDERS CONTAINING THEREIN ONE (1) COMPLETE SET OF MANUFACTURERS' OPERATING AND MAINTENANCE INSTRUCTIONS SHOWING ALL MAJOR EQUIPMENT AND APPARATUS REQUIRING MAINTENANCE. INSTRUCTIONS SHALL BE COMPLETE FOR INSTALLATION, OPERATION AND MAINTENANCE AND SHALL INCLUDE PERTINENT INFORMATION SUCH AS DETAILED DRAWINGS AND OPERATION CURVES. SPARE PARTS, SUPPLIER LISTS AND ADDRESSES SHALL BE SUPPLIED. INSTRUCTION SHALL BE REQUIRED WITH THE CITY'S REPRESENTATIVE TO ENSURE A THOROUGH UNDERSTANDING OF THE EQUIPMENT AND ITS OPERATION.
- 12. ALL WIRING, SUPPLY AND INSTALLATION OF DISCONNECT SWITCHES FOR EQUIPMENT SPECIFIED HEREIN SHALL BE PERFORMED BY THE ELECTRICAL SUB CONTRACTOR, UNLESS OTHERWISE NOTED.
- 13. CONTRACTOR SHALL EXAMINE THE SITE AND CONDITIONS AFFECTING WORK, METHODS OF CONNECTION AND LOCATION OF ALL SERVICES INVOLVED UNDER THIS CONTRACT. FAILURE TO MAKE THIS VISIT IN NO WAY ALLEVIATES THE MECHANICAL SUB CONTRACTOR FROM RESPONSIBILITY FOR COMPLETING THE MECHANICAL WORK OF THIS CONTRACT IN A WORKMANLIKE MANNER. NO ALLOWANCE WILL BE MADE AFTER CONTRACT AWARD FOR ANY EXPENSE INCURRED THROUGH A FAILURE TO MAKE THIS EXAMINATION AND INVESTIGATION.
- 14. SCHEDULING OF ALL WORK SHALL BE ARRANGED WITH THE CITY, AND THE CITY SHALL BE NOTIFIED AND HIS APPROVAL OBTAINED PRIOR TO SHUTTING OFF EXISTING SERVICES FOR PURPOSES OF CONNECTING NEW WORK. WORK WITHIN THE BUILDING MAY HAVE TO BE PERFORMED DURING NON-REGULAR WORKING HOURS AND MUST CONFORM TO WORK RULES OF THE BUILDING AS DIRECTED BY THE CITY.

15. RECORD DRAWINGS:

- 15.1. OBTAIN SETS OF WHITE PRINTS (ONE FOR EACH SYSTEM IE. PLUMBING, HVAC, FIRE PROTECTION) AND KEEP AT JOB SITE AT ALL TIMES.
- 15.2. RECORD ALL ADDITIONS OR DEVIATIONS FROM THE CONTRACT DOCUMENTS INCLUDING ALL CHANGES INCURRED BY ADDENDA, CHANGE ORDERS, FIELD CHANGES, JOB CONDITIONS, ETC.
- 15.3. MECHANICAL SUB CONTRACTORS SHALL BE RESPONSIBLE FOR THE PRODUCTION OF RECORD RECORD DRAWINGS WHICH SHALL PROVIDE A COMPLETE AND ACCURATE RECORD OF THE ACTUAL MECHANICAL INSTALLATION. ALL PRINCIPLE BELOW GRADE OR INACCESSIBLE PIPING OR DUCT SYSTEMS, ETC. SHALL BE DIMENSIONED AT EACH CHANGE IN DIRECTION. INCLUDE ALL ROUTING OF SERVICES NOT INDICATED ON ORIGINAL DRAWINGS.
- 15.4. PROJECT RECORD DRAWINGS SHALL BE TRANSFERRED BY MECHANICAL SUB CONTRACTOR TO REPRODUCIBLE BOND DRAWINGS AND LABELED RECORD.
- 15.5. SUBMIT REPRODUCIBLE BOND DRAWINGS TO CONTRACT ADMINISTRATOR FOR REVIEW UPON COMPLETION IF CORRECTIVE MEASURES ARE REQUIRED AFTER THE SECOND CONTRACT ADMINISTRATOR REVIEW (DUE TO MISSING INFORMATION AND/OR IMPROPER DRAFTING STANDARDS), THE MECHANICAL SUB CONTRACTOR

- SHALL BE RESPONSIBLE FOR CONTRACT ADMINISTRATOR'S TIME COSTS FOR CORRECTIVE MEASURES, COURIER AND PRINTING COSTS.
- 15.6. CONTRACTOR SHALL EMPLOY CONTRACT ADMINISTRATOR (OR CAD DRAFTING SERVICE)TO PRODUCE ELECTRONIC COPY RECORD DRAWINGS. MECHANICAL SUB CONTRACTOR SHALL BEAR ALL COSTS OF
- 15.7. COPY OF FINAL RECORD DRAWING SHALL BE SUBMITTED TO ARCHITECT.
- 15.8. ALL COSTS OF RECORD DRAWINGS PRODUCTION SHALL BE BORNE BY MECHANICAL SUB CONTRACTOR.
- 16. THE CONTRACTOR SHALL, AT HIS OWN EXPENSE, PROVIDE TEMPORARY HEATING AND HOARDING AS REQUIRED FOR THE PROPER PROGRESS OF THE WORK.
- 17. VERIFY SIZES, INVERTS AND LOCATIONS OF ALL SERVICES PRIOR TO COMMENCEMENT OF WORK. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO SANITARY SEWER, STORM SEWER, DOMESTIC WATER MAINS, FORCE MAINS,
- 18. HOISTING OF ALL MECHANICAL EQUIPMENT SHALL BE BY THE MECHANICAL SUB CONTRACTOR.
- 19. ASSUME FULL RESPONSIBILITY FOR LAYING OUT ALL WORK AND ENSURING THAT NO DAMAGE IS CAUSED TO THE CITY'S EQUIPMENT AND PREMISES DUE TO IMPROPER LOCATION AND EXECUTION OF WORK IN THIS CONTRACT. PROTECT AND MAINTAIN ALL WORK UNTIL WORK HAS BEEN COMPLETED AND ACCEPTED BY THE CITY. STORE ALL MATERIALS AS REQUIRED, AND CLEAN UP REFUSE CAUSED BY ALL WORK.
- 20. IDENTIFY ALL NEW PIPING WITHIN BUILDING INSTALLED IN THIS CONTRACT SHOWING SERVICE, PIPE SIZE, AND FLOW DIRECTION. USE CAPITAL LETTERS USING EITHER FIRE RESISTANT HIGH GLOSS INTERIOR ENAMEL PAINT OR WATERPROOF, HEAT RESISTANT PLASTIC MARKER TAGS (SIMILAR TO: W.H. BRADY IDENTIFICATION TAPES, BANDS, MARKERS.) IDENTIFY AT MAXIMUM OF EVERY 50 FT. AND AT LEAST ONCE IN EACH ROOM. LOCATE AND SIZE LETTERING SUCH THAT IT CAN BE SEEN FROM FLOOR.
- 21. IN THE CASE OF DISCREPANCY BETWEEN ARCHITECTURAL AND MECHANICAL DRAWINGS TO NUMBER, TYPE, OR LOCATION OF HVAC EQUIPMENT AND SYSTEMS COMPONENTS, OBTAIN WRITTEN RULING.
- 22. ALL TIME/DATE SENSITIVE ELECTRONIC EQUIPMENT AND SOFTWARE PROVIDED ON THIS PROJECT SHALL BE 4 DIGIT YEAR INPUT COMPATIBLE AND SHALL BE BASED ON THE USE OF FULL, UNABBREVIATED, UNAMBIGUOUS
- 23. MECHANICAL SUB CONTRACTOR SHALL COORDINATE PROVISION OF POWER TO BUILDING CONTROL TRANSFORMERS WITH ELECTRICAL SUB CONTRACTOR AND CARRY ALL INCREMENTAL COSTS.
- 24. COORDINATE THE ELECTRICAL REQUIREMENTS OF ALL MECHANICAL EQUIPMENT WITH ELECTRICAL SUB-CONTRACTOR. ELECTRICAL SUB CONTRACTOR SHALL PROVIDE THE FOLLOWING: 24.1. ALL POWER WIRING TO EQUIPMENT.
- 24.2. ONE 15 AMP 120V/1PH/60HZ FUSED POWER SUPPLY TO EACH MECHANICAL EQUIPMENT AND/OR JANITOR
- 25. PROVIDE FIRE STOPPING AT ALL PIPING, CONDUIT (CONTROLS) AND DUCTWORK PENETRATIONS OF ALL REQUIRED FIRE SEPARATIONS WITH APPROVED MATERIAL SYSTEMS. ACCEPTABLE MATERIALS: 3M, DOW,
- 26. MECHANICAL CONTRACT DOCUMENTS ARE DIAGRAMMATIC AND APPROXIMATE TO SCALE; REFER TO ARCHITECTURAL AND/OR STRUCTURAL DRAWINGS, AND SITE VERIFY ALL CRITICAL DIMENSIONS. THE DRAWINGS AND SPECIFICATIONS ESTABLISH SCOPE FOR MATERIAL AND INSTALLATION QUALITY AND ARE NOT DETAILED INSTALLATION INSTRUCTIONS. ANY DISCREPANCIES MUST BE BROUGHT TO THE CONTRACT ADMINISTRATOR'S ATTENTION IN WRITING PRIOR TO THE CLOSE OF BIDS.
- 27. SHOULD ANY DISCREPANCY APPEAR BETWEEN THE DRAWINGS AND SPECIFICATIONS, WHICH LEAVE THE CONTRACTOR IN DOUBT AS TO THE TRUE INTENT AND MEANING OF THE PLANS AND SPECIFICATIONS, THE CONTRACTOR SHALL OBTAIN A WRITTEN RULING FROM THE CONTRACT ADMINISTRATOR PRIOR TO BID SUBMISSION. IF WRITTEN APPROVAL IS NOT PROVIDED, THE MOST EXPENSIVE ALTERNATIVE SHALL BE INCLUDED IN THE BID PRICE.
- 28. FIELD VERIFY ALL BUILDING AND SITE DIMENSIONS AND REVIEW MECHANICAL DRAWINGS AND SPECIFICATIONS PRIOR TO ANY FABRICATION OR INSTALLATION OF EQUIPMENT OR MATERIALS. DO NOT ATTEMPT ANY FABRICATION OR INSTALLATION UNTIL SUCH CLARIFICATION IS PROVIDED. NO CONTRACT REVISIONS WILL BE CONSIDERED FOR FAILURE TO VERIFY THESE DIMENSIONS ON SITE.
- 29. DRAWINGS AND SPECIFICATIONS ARE COMPLIMENTARY EACH TO THE OTHER, WHAT IS CALLED FOR BY ONE SHALL BE BINDING AS IF CALLED FOR BY BOTH.
- 30. MECHANICAL WORK SHALL BE COMPLETED IN CONFORMANCE WITH, AND SUBJECT TO, ALL CAUTIONARY NOTES AVAILABLE TO THE READER INCLUDING THOSE AVAILABLE ON THE WEBSITES OF THE MANUFACTURERS AND CONTRACT ADMINISTRATORS.

<u>INSULATION</u>

ALL INSULATING MATERIALS. METHODS, SIZES AND TYPES OF INSULATION FOR ALL PIPING AND DUCT WORK SHALL BE INSTALLED TO THE REQUIREMENTS OF THE ASHRAE STANDARDS 90.1-2010 "ENERGY STANDARD FOR BUILDING EXCEPT LOW-RISE RESIDENTIAL BUILDING", PART 9.36 OF THE NATIONAL BUILDING CODE AND THERMAL INSULATION ASSOCIATION OF CANADA (TIAC) STANDARDS.

1. PROVIDE THICK RIGID PIPE INSULATION ON ALL DOMESTIC WATER PIPES C/W VAPOUR BARRIER. INSULATION ON PIPING MINIMUMS:

PIPE SIZE INSULATION THICKNESS

UP TO 2" (50MM) 1" (25 MM) 2" (50MM) AND GREATER 11/2" (38 MM)

- PROVIDE 1" (25 MM) THICK PIPE INSULATION ON ALL PLUMBING VENTS PASSING THROUGH ROOF FOR A DISTANCE OF 10'-0" (3 M) INSIDE FROM POINT OF COLD TO WARM SURFACE PENETRATION. INSULATION C/W VAPOUR BARRIER.
- 3. PROVIDE 1 1/2" (38 MM) THICK KNAUF ATMOSPHERE DUCTWRAP, 1.0 PCF DENSITY R4.5 (RSI 0.80) 25% COMPRESSED FLEXIBLE DUCT INSULATION C/W RFFRK FACING ON EXHAUST DUCTWORK & ALL SUPPLY DUCTWORK FROM ALL AIR HANDLING EQUIPMENT. EXHAUST DUCTWORK SHALL BE INSULATED FOR A MINIMUM DISTANCE OF 10'-0" (3 M) FROM PENETRATION OF BUILDING THERMAL ENVELOPE. REFER TO DRAWNGS FOR ADDITIONAL INSULATION REQUIREMENTS. ALL SUPPLY AIR DUCTWORK CONVEYING AIR—CONDITIONED AIR SHALL BE INSULATED.
- 4. PROVIDE 2" (50 MM) THICK KNAUF ATMOSPHERE DUCTWRAP, 1.5 PCF DENSITY, R6.4 (RSI 1.13) 25% COMPRESSED THERMAL FACED INSULATION ON ALL DUCTWORK CONVEYING OUTSIDE AIR COMPLETE WITH RFFRK FACING FACING. DUCTWORK SHALL BE INSULATED OVER ENTIRE RUN FROM PENETRATION OF BUILDING THERMAL ENVELOPE TO UNIT CONNECTION.
- 5. ACOUSTICALLY INSULATE DUCTWORK WITH 1" (25 MM) FLEXIBLE DUCT INSULATION WITH FLAME ATTENUATED FIBRES BONDED WITH THERMOSETTING RESIN; BLACK PLASTIC-COATED MAT FINISH. PROVIDE WHERE NOTED ON DRAWINGS OR AS SHOWN AS HATCHED DUCTWORK OR ALLOW FOR UP TO 10 FT. (3 M) FROM SUPPLY AND RETURN AIR OPENINGS OF ROOF MOUNTED EQUIPMENT. ACCEPTABLE PRODUCT: KNAUF AIR DUCT BOARD.
- 6. DO NOT EXTERNALLY INSULATE ANY DUCTWORK WHICH IS SPECIFIED OR SHOWN TO BE INTERNALLY INSULATED UNLESS NOTED OTHERWISE.
- 7. INSULATION COVERINGS: DUCTWORK RUNNING OUTSIDE THE BUILDING THERMAL ENVELOPE AND EXPOSED TO THE WEATHER:
- 7.1. MASTIC FINISH OVER INSULATION SHALL BE VI-CRYL CP-10 WHITE WEATHER BARRIER COATING AS MANUFACTURED BY CHILDERS PRODUCTS COMPANY. IT SHALL BE APPLIED IN TWO COATS, THE FIRST COAT BEING A TACK COAT APPLIED AT A RATE OF TWO GALLONS PER 100 SQ. FT. (.81 L/SQ.M), AND WHILE STILL WET A LAYER OF CHIL-GLAS #5 OPEN WEAVE GLASS CLOTH MEMBRANE SHALL BE EMBEDDED WITH ALL FABRIC COAT AT A COVERAGE OF FOUR GALLONS PER 100 SQ. FT. (1.6 1/SQ.M) SHALL BE APPLIED, FULLY COVERING THE CLOTH MEMBRANE, SO THAT THE MINIMUM DRY FILM THICKNESS IS 1/16" (0.63") (1.6 MM). THERE SHALL BE NO VOIDS OR HOLLOWS AND THE MASTIC SHALL BE TOWELED,

- SPRAYED OR WET-BRUSHED TO A SMOOTH EVEN FINISH. PROVIDE ALUMINUM JACKET THREE(3) SIDES. FINISH AS PER ARCHITECT BY GENERAL CONTRACTOR.
- 7.2. ALL ADJOINING UNINSULATED SURFACES MUST BE COMPLETELY WATER-PROOFED AND FLASHED EITHER BY EXTENDING THE VI-CRYL CP-10/11 WEATHER BARRIER COATING AND FABRIC MEMBRANE A MINIMUM OF 4" (102 MM) ONTO THE ADJOINING SURFACE, OR, IF THAT SURFACE WILL ATTAIN TEMPERATURES IN EXCESS OF 180 DEGREES F (82 DEGREES C), USE CHIL—JOINT CP—70 SEALANT AS THE FLASHING COMPOUND.
- 7.3. ALL INSULATION IN EXPOSED LOCATIONS, AND ALL DUCTWORK IN FAN ROOMS, SERVICE ROOMS, GARAGES, ETC., SHALL BE COVERED WITH CANVAS WRAP. INSULATION EXPOSED TO THE MOISTURE SHALL BE COMPLETE WITH COVER PER 9.1/9.2 ABOVE.
- 7.4. ALL DUCT INSULATION AND COVERINGS SHALL MEET THE REQUIREMENTS OF CAN/ULC-S110 TEST FOR AIR DUCTS' AND HAVE A FLAME SPREAD RATING NOT EXCEEDING 25 AND A SMOKE DEVELOPED CLASSIFICATION NOT EXCEEDING 50. THIS SHALL INCLUDE ALL TAPES, SEALANTS, AND MISCELLANEOUS PRODUCTS ASSOCIATED WITH THE INSTALLATION.

- PROVIDE COMPLETE FUNCTIONAL PLUMBING SYSTEM COMPRISED OF DOMESTIC WATER PIPING, VENTS, SANITARY AND DRAINAGE PIPING, ETC.
- 2. PLUMBING SIZING SHOWN ON DRAWINGS IS BASED ON COPPER PIPING FOR DOMESTIC WATER, AND CAST IRON PIPING FOR SANITARY AND STORM. MECHANICAL SUB CONTRACTOR IS RESPONSIBLE FOR RESIZING PLUMBING AS REQUIRED WHEN USING ALTERNATE MATERIALS.
- 3. ACCEPTABLE MATERIALS SHALL BE USED AS DESCRIBED BELOW.
- 3.1. DRAINAGE WASTE AND VENT (DWV) MATERIALS
- 3.1.1.1. PVC MEETING CSA B181.2
- 3.1.1.2. CAST IRON MEETING CSA B70
- 3.1.1.1.1. HUB AND SPIGOT CONNECTIONS, THRUST BLOCKS AT CHANGES IN DIRECTION.
- 3.1.2. FOR ABOVEGROUND DWV APPLICATIONS (COMBUSTIBLE CONSTRUCTION) 3.1.1.1. ABS MEETING CSA B181.1
- 3.1.1.2. PVC MEETING CSA B181.2

3.1.1. UNDERGROUND PIPING

- 3.1.2. FOR ABOVEGROUND DWV APPLICATIONS (NON-COMBUSTIBLE CONSTRUCTION) 3.1.1.1. ALL PIPING TO HAVE A FLAME SPREAD RATING OF LESS THAN 25.
- 3.1.1.2. PVC MEETING CSA B151.2, CAN/ULC S102.2 3.1.2. FOR DWV APPLICATIONS IN AIR PLENUMS
- 3.1.1.1. ALL PIPING TO HAVE A FLAME SPREAD RATING OF LESS THAN 25 AND A SMOKE DEVELOPED
- CLASSIFICATION OF LESS THAN 50. 3.1.1.2. PVC MEETING CSA B151.2, CAN/ULC S102.2

3.2. DOMESTIC WATER PIPING MATERIALS

3.2.1. ALL PRODUCTS SHALL BE UL CLASSIFIED IN ACCORDANCE WITH ANSI/NSF-61 FOR POTABLE WATER SERVICE, AND SHALL BE CERTIFIED TO THE LOW LEAD REQUIREMENTS OF NSF-372.

- 3.2.2.1. ALL PIPE SHALL BE UPONOR HIGH-DENSITY CROSS-LINKED POLYETHYLENE MANUFACTURED USING THE HIGH-PRESSURE PEROXIDE METHOD OF CROSS-LINKING (PEX A). PIPE SHALL CONFORM TO ASTM F877, CSA B137.5 AND NSF/ANSI 61.
- 3.2.2.2. PIPE SHALL BE RATED FOR CONTINUOUS OPERATION OF 100 PSI GAUGE PRESSURE AT 180F TEMPERATURE (630 KPA @ 82°C) AND 80 PSI GAUGE PRESSURE AT 200°F TEMPERATURE (550
- 3.2.2.3. PEX PIPE IN EXPOSED LOCATIONS SHALL BE RIGID (NOT COIL).
- 3.2.2.4. PIPE SHALL BE RESISTANT TO HOT CHLORINATED WATER. PIPE TO HAVE A MINIMUM EXTRAPOLATED TIME-TO-FAILURE OF 50 YEARS.
- 3.2.2.5. PEX PIPE TO HAVE A CO-EXTRUDED COLORED UV SHIELD MADE FROM UV-RESISTANT POLYETHYLENE PROVIDING UV RESISTANCE. 3.2.2.6. PIPE TO HAVE A FLAME SPREAD INDEX OF LESS THEN 25 AND A SMOKE DEVELOPED INDEX OF LESS THAN 50 WHEN TESTED IN ACCORDANCE WITH CAN/ULC S102.2. IN ANY CASE WHERE THE

PIPE DOES NOT CONFORM WITH THESE STANDARDS, APPROPRIATE PIPING INSULATION SHALL BE

INSTALLED IN ORDER TO MEET THE STANDARD. 4. DRAINS AND VENT PIPING UNDERGROUND INSIDE BUILDING SHALL BE CAST IRON CLASS 4000, OR PVC

PLASTIC. FITTINGS SHALL BE MECHANICAL JOINT FOR CAST IRON OR SOLVENT CEMENT FOR PVC.

- 5. SANITARY WASTE STACKS, HORIZONTAL WASTE, VENT, ABOVE GROUND INSIDE BUILDING, SHALL BE CAST IRON LASS 4000. VENT PIPING AND FIXTURE RUN-OUTS MAY ALSO BE DWV COPPER OR PVC PLASTIC SHALL BE MECHANICAL JOINT FOR CAST IRON, SOLDER FOR DWV COPPER AND SOLVENT CEMENT FOR PVC.
- 6. ALL PVC PLASTIC PIPING USED SHALL HAVE A FLAME SPREAD RATING OF 25, AND A SMOKE DEVELOPED RATING OF 50. PIPING AND FITTINGS SHALL BE OF ONE MANUFACTURE; STANDARD OF ACCEPTANCE: IPEX
- 7. MECHANICAL SUB CONTRACTOR SHALL VERIFY ON SITE ALL CONNECTION POINTS TO EXISTING BUILDING SERVICES. COORDINATE ALL NEW PIPING RUNS WITH CONTRACT ADMINISTRATOR OR CITY'S REPRESENTATIVE.
- SOLDERED FITTINGS IN POTABLE WATER SYSTEMS
- 8.1. PROVIDE LEAD, ANTIMONY, CADMIUM AND ZINC FREE SOLDERS COMPOSED OF TIN. COPPER. SILVER OR NICKEL COMPONENTS THAT ARE ACCEPTABLE TO THE AUTHORITY HAVING JURISDICTION.
- 9.1. SHALL BE BY ONE MANUFACTURER. STANDARD OF ACCEPTANCE: APOLLO VALVES. 9.2. SHALL BE UL CLASSIFIED IN ACCORDANCE WITH ANSI/NSF-61 FOR POTABLE WATER SERVICE, AND SHALL
- BE CERTIFIED TO THE LOW LEAD REQUIREMENTS OF NSF-372. 10. MANUFACTURED SHOCK ABSORBERS, AUTOMATIC AIR VENTS, AND PARTITION STOPS SHALL BE INSTALLED AT
- THE TOP OF ALL RISERS, AND ON ALL FIXTURES OR BATTERY OF FIXTURES. 11. MECHANICAL SUB CONTRACTOR SHALL ALLOW FOR IN BID QUOTATION ANY ADDITIONAL LABOUR, MATERIALS, ETC. DEEMED NECESSARY DUE TO EXACT SITE CONDITIONS WHICH HAVE NOT BEEN REFLECTED IN MECHANICAL DRAWING OR IN MECHANICAL SPECIFICATION. NOTIFY CONTRACT ADMINISTRATOR OF ALL DISCREPANCIES PRIOR
- 12. ON COMPLETION, ALL PIPING SYSTEMS SHALL BE CLEANED & FLUSHED OUT TO REMOVE ANY FOREIGN MATERIAL IN THE PIPING.
- 13. CONTRACTOR SHALL COORDINATE SERVICE INSTALLATIONS AND/OR MODIFICATIONS WITH LOCAL UTILITY PRIOR TO COMMENCEMENT OF WORK. PAY ALL COSTS AND/OR FEES.
- 14. PROVIDE DIELECTRIC COUPLINGS WHEREVER PIPES OF DISSIMILAR METALS ARE JOINED.
- 15. USE THE FOLLOWING ROD DIAMETER AND SPACING SCHEDULE TO ESTABLISH MINIMUM HANGING STANDARDS FOR HORIZONTAL PIPING:

PIPE SIZE	ROD DIA	STEEL	COPPER
UP TO 3/4" 1" TO 1 1/4" 1 1/2" & 2" 2 1/2" & 3" 4" & 5"	3/8"	6	6'
	3/8"	8'	6'
	3/8"	10'	8'
	1/2"	12'	8'
	5/8"	12'	8'

- 16. PIPE HANGERS WHERE REQUIRED SHALL BE GRINNEL FIG.65 FOR STEEL PIPE AND FIG.117 EXPANSION CASE SET IN HOLES DRILLED IN CONCRETE OR ATTACHED TO FIG.225 OR 227 CLAMP ATTACHED TO FLOOR JOIST AND ROOF JOIST. FOR INSULATED PIPING, PROVIDE PROTECTION FIG.167 SADDLES SIZE HANGER TO ACCOMMODATE INSULATION WHERE APPLIED.
- 17. THE NEW BUILDING DOMESTIC WATER SERVICES ARE TO BE PROTECTED BY A BACKFLOW PREVENTION SYSTEM AS PER CSA B64.10. BASED ON THE BUILDING OCCUPANCY, THE BUILDING SHALL BE PROVIDED WITH A REDUCED PRESSURE BACKFLOW PREVENTER/ DOUBLE CHECK VALVE BACKFLOW PREVENTER. CONFIRM EXACT REQUIREMENTS WITH LOCAL AUTHORITY.

17.1. PLUMBING FIXTURES ARE TO BE PROVIDED WITH BACKFLOW PREVENTION BASED ON THE FIXTURE HAZARD TYPE DEFINED IN CSA B64. BACKFLOW PREVENTION SHALL BE A VACUUM BREAKER (HCVB) FOR MINOR HAZARD, DOUBLE CHECK VALVE BACKFLOW PREVENTER (DCVA) FOR MEDIUM HAZARD OR REDUCED PRESSURE BACKFLOW PREVENTER (RP) FOR HIGH HAZARD FIXTURES.

17.2. PROVIDE BACKFLOW PREVENTION FOR THE FLOWING FIXTURES (OR GROUP OF FIXTURES) AS DEFINED

17.2.1. BASIN 17.2.2. FLUSH TANK 17.2.3. FLUSHING EQUIPMENT DEVICE 17.2.4. HOSE CONNECTION (NON-RESIDENTIAL) DCVA/RP 17.2.5. HOT WATER SYSTEMS CONNECTION HCVB 17.2.6. LAVATORY 17.2.7. TRAP PRIMER

PLUMBING FIXTURES AND EQUIPMENT:

WC-1 WATER CLOSET - WALL HUNG - BARRIER FREE

ACORN DURA-WARE 2100-W-1-HPS-BCN, BLOWOUT JET TOILET - OFF FLOOR, WALL THICKNESS 190MM BLOCK, WALL (CONCEALED), OFF-FLOOR, WALL OUTLET, 1.6 GPF, HIGH POLISH INTEGRAL SEAT, BLIND CAP NUTS (3). SLOAN REGAL XL OPTIMA #153-1.6 ES-S, CONCEALED FLUSHOMETER FOR TOP SPUD TOILET, 6 L (1.6 US GAL) FACTORY SET FLOW, QUIET ACTION DIAPHRAGM TYPE, INFRARED SENSOR, SOLENOID OPERATED FLUSH CONTROLLER CIRCUITRY, COURTESY FLUSH ELECTRONIC OVER—RIDE BUTTON, BAK—CHEK ANGLE STOP (WHEEL HANDLE OPERATED), EXPOSED CP ELBOW FOR TOP SPUD CONNECTION, VACUUM BREAKER, SENSOR LOCATED ABOVE THE TOILET, 5 VA POWER REQUIRED PER UNIT. OFFSET P-TRAP WITH INSULATION COVERING. WATTS FLOW STOPPER. PROVIDE 4" (102 MM) SQUARE ELECTRICAL BOX FOR MOUNTING SENSOR PLATE. SLOAN #EL-342, BOX MOUNT HARD WIRED TRANSFORMER, 240 / 24 50 VA. WILL OPERATE UP TO 10 'OPTIMA' FLUSH VALVE UNITS. WATTS #SCA-101-M11 SINGLE HORIZONTAL ADJUSTABLE TOILET CARRIER, MOUNTED ON CONCRETE FLOOR, ALL EPOXY COATED CAST IRON FITTING, ADJUSTABLE ABS SLIDE NIPPLE WITH INTEGRAL TEST CAP AND NEOPRENE BOWL GASKET, WASTED PLATED HARDWARE, CHROME CAP NUTS, TILING FRAME, 102 MM (4") NO HUB WASTE, 51 MM (2") NO HUB VENT, 158.8 KG (350 LBS) STATIC LOAD. 305 MM (12") FINISHED METAL STUD WALL TO BACK OF PIPE SPACE. CHAMPION MI-TR SERIES #MI-HUB TR-440 DRAIN COUPLING. COUPLING. NO-HUB. TYPE 300 AISI STAINLESS STEEL BAND, TYPE 300 AISI STAINLESS STEEL EYELETS, ELASTOMERIC COMPOUND GASKET MEETING THE REQUIREMENTS OF ASTM C-564, TYPE 300 AISI STAINLESS STEEL SHIELD, TESTED TO MAINTAIN 4.3 PSI OF WATER PRESSURE AT 60 INCH LB MIN/MAX TORQUE BOLT TIGHTNESS, TESTED AND CERTIFIED TO ASTM STANDARD 1460-2012 AND CSA STANDAD B602-2010 AND LISTED WITH IAPMO. ALL MODELS ARE LISTED TO THE NATIONAL PLUMBING CODE OF CANADA AND RELEVANT CANADIAN STANDARD (S) AND BEAR THE CUPC MARK OF CONFORMITY. NON CONSTANT TEMPERATURE RATING IS 140°F.

L-1 LAVATORY - WALL HUNG - BARRIER FREE

ACORN MERIDIAN 3701-1-SO-DMJ-PDM STAINLESS STEEL CURVED FRONT UNI-BASIN LAVATORY, OFF-FLOOR, WALL OUTLET, SENSOR OPERATION, DECK MOUNTED SPOUTS, DECK MOUNTED J SPOUT, METERING LIQUID SOAP DISPENSER. LAWLER #TMM-1070, BELOW DECK MECHANICAL WATER MIXING VALVE, BRONZE BODY, TEMPERATURE ADJUSTING DIAL, 10 MM (3/8") INLETS AND OUTLET COMPRESSION FITTINGS, HIGH TEMPERATURE THERMOSTATIC LIMIT STOP, SHUT-OFF WITH AUTOMATIC RESET WHEN TEMPERATURE EXCEEDS 120 F (48.8 ℃), INTEGRAL CHECKS, OFFER TEMPERATURE RANGE FROM FULL COLD THROUGH 46 °C (114.8 °F). PROVIDE TEE, ADAPTORS AND FLEX. COPPER TUBING TO SUIT INSTALLATION. MCGUIRE #155A OPEN GRID DRAIN, CAST BRASS ONE PIECE TOP, 17 GA. (1.5 MM) TUBULAR 32 MM (1-1/4") TAILPIECE. MCGUIRE #LFH165LKN3 FAUCET SUPPLIES, CHROME PLATED FINISH POLISHED BRASS, HEAVY DUTY ANGLE STOPS, 10 MM (3/8") I.P.S. INLET X 76 MM (3") LONG RIGID HORIZONTAL NIPPLES, V.P. LOOSE KEYS, ESCUTCHEON AND FLEXIBLE COPPER RISERS. MCGUIRE #8872C P-TRAP, HEAVY CAST BRASS ADJUSTABLE BODY, WITH SLIP NUT, 32 MM (1-1/4") SIZE, SHALLOW WALL FLANGE AND SEAMLESS TUBULAR WALL BEND. WATTS #CA-321 FIXTURE CARRIER, MOUNTED ON CONCRETE FLOOR, EPOXY COATED TOP AND BOTTOM UNIVERSAL STEEL HANGER PLATES, HEAVY GAUGE FPOXY COATED STEEL OFFSET UPRIGHTS WITH WELDED FEET SUPPORTS. FOR ONE UNIT: 102 MM (4") FOR TWO TO SIX UNITS IN A ROW: 152 MM (6") FINISHED METAL STUD WALL TO BACK OF PIPE SPACE.

MS-1 SERVICE / MOP SINK - TWO HANDLE FAUCET

STERN WILLIAMS #MTB-2424 SQUARE SERVICE / MOP SINK, 610 MM (24") X 610 MM (24") X 254 MM (10") DEEP, FLOOR MOUNTED, TERRAZZO COMPOSED OF PEARL GRAY MARBLE CHIPS AND PORTLAND CEMENT GROUND SMOOTH, SEALED TO RESIST STAIN, CAST BRASS DRAIN WITH STAINLESS STEEL STRAINER, 3"(75MM) OUTLET. AMERICAN STANDARD #8350.243 WALL MOUNTED TWO HANDLE FAUCET, CHROME PLATED, 8" (203MM) CENTERSET, CAST BRASS BODY, SLOW COMPRESSION, UNRESTRICTED HOSE END OUTLET, SPOUT WITH ATMOSPHERIC VACUUM BREAKER AND BUCKET HOOK 173 MM (7-1/4") FROM WALL TO OUTLET REACH, LEVER HANDLES. STERN WILLIAMS T-35 HOSE AND WALL HOOK HOSE 36" (914MM) LONG WITH 3/4" (19MM) CHROME COUPLING, STAINLESS STEEL WALL BRACKET. STERN WILLIAMS T-40 MOP HANGER STAINLESS STEEL #4 FINISH, 24" (610MM) LONG WITH 3 RUBBER SPRING LOADED CLIPS. STERN WILLIAMS BP BACK SPLASH PANEL 20 GAUGE TYPE 304 STAINLESS STEEL. PROVIDE P-TRAP, SAME MATERIAL AS THE CONNECTING PIPE DRAIN.

WP-1 WELL PUMP

GRUNDFOS 'SP SERIES' SUBMERSIBLE PUMP, MODEL 25S10-7 COMPLETE WITH STAINLESS STEEL CONSTRUCTION, INTEGRAL DISCHARGE CHECK VALVE, 4"NOMINAL PUMP SIZE, 4"NOMINAL MOTOR SIZE, 1 HP, 230/1/60 SUBMERSIBLE MOTOR, 1-1/2"NPT DISCHARGE, 20 GPM @ 143 FT HEAD, 3450 RPM. PROVIDE COMPLETE WITH PRESSURE SWITCH/CONTACT AND PRESSURE GAUGE. WIRING TO PUMP BY ELECTRICAL CONTRACTOR.

WS-1 WATER SOFTENER

AQUA SURE WATER SOFTENER MODEL AS1-HUF30, 1"MALE CONNECTION, 20 GPM @ 10 PSI SERVICE FLOW RATE, 120V CONNECTION.

SMITH SERIES 2005A FLOOR DRAIN, ALL DUCO COATED CAST IRON BODY, REVERSIBLE FLASHING CLAMP WITH

SEEPAGE OPENINGS AND ADJUSTABLE 5" (127MM) DIAMETER NICKEL BRONZE 1/4" (6.35MM) THICK STRAINER, SECURED WITH S.S. SCREWS, 4" (100MM) THROAT ON STRAINER. (WHERE REQUIRED BY LOCAL CODE PROVIDE

FD-1 FLOOR DRAINS - FIN. AREAS - MED. DUTY STRAINER

TRAP SEAL). CO-1 FLOOR CLEANOUT (UNFINISHED AND OUTSIDE AREAS) SMITH 'TWIS-TO-FLOOR' SERIES 4220 FLOOR CLEANOUT, DUCO COATED CAST IRON BODY AND REMOVABLE

POSITIVE GASKET SEAL CLOSURE PLUG AND HEAVY DUTY 6" (150MM) ROUND ADJUSTABLE SCORIATED CAST

IRON COVER SECURED WITH STAINLESS STEEL SCREWS, C.O. CAST IN COVER. (FOR WATER-PROOFED AREAS

PROVIDE 'FC' FLANGE WITH FLASHING CLAMP).

CO-2 FLOOR CLEANOUT (TILED AREAS) SMITH SERIES 4140 FLOOR CLEANOUT, DUCO COATED CAST IRON BODY AND REMOVABLE POSITIVE GASKET SEAL CLOSURE PLUG AND HEAVY DUTY 6" (150MM) ROUND NICKEL BRONZE COVER AND FRAME WITH 1/8" (3MM) TILE RECESS. (FOR MEDIUM LOAD TRAFFIC) COVER CAN BE ADJUSTED TO SUIT FLOOR LINES WHEN

INSTALLING FINISHED FLOOR. (MOSAIC TILE PROVIDE SERIES 4160 WITH SQUARE COVER.)

CO-3 FLOOR CLEANOUT (TERREZZO AREAS)

SMITH SERIES 4180 FLOOR CLEANOUT, DUCO COATED CAST IRON BODY AND REMOVABLE POSITIVE GASKET SEAL CLOSURE PLUG, HEAVY DUTY 6" (150MM) ROUND NICKEL BRONZE COVER AND FRAME WITH 1/2" (12MM) TERRAZZO RECESS (FOR MEDIUM LOAD TRAFFIC). COVER CAN BE ADJUSTED TO SUIT FLOOR LINES WHEN INSTALLING FINISHED FLOOR.

CO-4 STACK CLEANOUT

SMITH SERIES 4510 STACK CLEANOUT, IN BASE OF CAST IRON STACKS WITH NEOPRENE GASKETED PLUG. WHERE CLEANOUTS ARE CONCEALED BEHIND FINISHED WALLS ACCESS SHALL BE MADE BY SMITH 4530 ROUND STAINLESS STEEL PLATE AND SLOTTED FLAT HEAD STAINLESS STEEL SCREW.

TS-1 TRAP SEAL DEVICE

WADE MODEL #4405 TRAP SEAL DEVICE (OR EQUAL), REGULARLY FURNISHED: ELASTOMERIC TRAP SEAL DEVICE WITH FITTING.

ALL DRAWINGS AND SPECIFICATIONS ARE THE PROPERTY OF THE CONSULTANT NO REPRODUCTIONS MAY BE MADE WITHOUT THE CONSENT OF THE CONSULTANT AND ALL REPRODUCTIONS MUST BEAR THE NAME OF THE CONSULTANT.

THE CONTRACTOR SHALL VERIEY ALL DIMENSIONS, DATUMS AND LEVELS NOTED ON THE DRAWNINGS WITH THE CONDITIONS ON TO THE AND SHALL BE RESPONSIBLE FOR PROPERTING ANY ERRORS OR CLASSIONS TO THE PROPER FOR ADJUSTMENTS.

NOVA 3 ENGINEERING LTD. CONSULTING ENGINEERS 201-120 FORT STREET TEL.: (204) 943-6142 WINNIPEG, MANITOBA R3C 1C7 FAX.: (204) 942-1276 WWW.NOVA3.CA JN.: 36-232 THIS DRAWING IS THE EXCLUSIVE PROPERTY OF NOVA 3 ENGINEERING LTD. AND MAY ONLY BE REPRODUCED WITH THE WRITTEN PERMISSION OF NOVA 3 ENGINEERING LTD.

THE CONCEPT AND DESIGN INCORPORATED INTO THIS DRAWING ARE BASED ON INFORMATION PROVIDED BY THE CLIENT AND OTHER RELATED SOURCES. PROFESSIONAL ENGINEER ACCEPTS NO RESPONSIBILITY FOR DRAWING AND DESIGN UNLESS DRAWING IS ACCOMPANIED BY ORIGINAL SEALED LETTER OF INTENT OR EQUIVALENT ACCEPTABLE FACSIMILE. PROFESSIONAL ENGINEER ACCEPTS NO RESPONSIBILITY FOR FINAL INSTALLATION CONFORMANCE WITHOUT ORIGINAL SEALED CERTIFICATE OF INSPECTION OR EQUIVALENT ACCEPTABLE FACSIMILE.




Issued for Construction

Northern Sky Architecture Inc.



Stamp



204.943.6767

Project

New La Barriere Park Washroom Project

La Barriere Park, Manitoba

scale	as noted	designed by	kbb
date	May, 2018	drawn by	hc
project no.	16.235	reviewed by	hc