

**Part 1            General**

**1.1                ADMINISTRATIVE**

- .1        Submit to Contract Administrator submittals listed for review. Submit promptly and in orderly sequence to not cause delay in Work. Failure to submit in ample time is not considered sufficient reason for extension of Contract Time and no claim for extension by reason of such default will be allowed.
  - .1        Allow ten (10) Work Days for review of submittals by the Contract Administrator.
- .2        Do not proceed with Work affected by submittal until review is complete.
- .3        Present shop drawings, product data, samples and mock-ups in SI Metric units.
- .4        Where items or information is not produced in SI Metric units converted values are accepted.
- .5        Review submittals prior to submission to Contract Administrator. This review represents that necessary requirements have been determined and verified, or will be, and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents. Submittals not stamped, signed, dated and identified as to specific Project will be returned without being examined and considered rejected.
- .6        Notify Contract Administrator, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .7        Verify field measurements and affected adjacent Work are co-ordinated.
- .8        Contractor's responsibility for errors and omissions in submission is not relieved by Contract Administrator's review of submittals.
- .9        Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Contract Administrator review.
- .10       The Contractor shall make any corrections required by the Contract Administrator and shall resubmit the required number of corrected copies of Shop Drawings. The Contractor shall direct specific attention in writing or on resubmitted Shop Drawings to revisions other than the corrections requested by the Contract Administrator on previous submission. .
- .11       After Contract Administrator's review and return of copies, distribute copies to sub-trades as appropriate.
- .12       Keep one reviewed copy of each submission on Site.

## **1.2 SHOP DRAWINGS AND PRODUCT DATA**

- .1 The term "shop drawings" means drawings, diagrams, illustrations, schedules, performance charts, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.
- .2 Submit one (1) electronic copy of shop drawings for each requirement requested in specification Sections and as Contract Administrator may reasonably request.
- .3 The Contractor shall arrange for the preparation of clearly identified Shop Drawings as specified or as the Contract Administrator may reasonably request. Shop Drawings are to clearly indicate materials, weights, dimensions, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of the Work. Where articles or equipment attach or connect to other articles or equipment, clearly indicate that all such attachments and connections have been properly coordinated, regardless of the trade under which the adjacent articles or equipment will be supplied and installed. Shop Drawings are to indicate their relationship to design Drawings and Specifications. Notify the Contract Administrator in writing of any deviations in Shop Drawings from the requirements of the Contract Documents.
- .4 Submit drawings stamped and signed by Professional Engineer registered or licensed in the province of Manitoba as required in the Specifications.
- .5 The Contractor shall examine all Shop Drawings prior to submission to the Contract Administrator to ensure that all necessary requirements have been determined and verified and that each Shop Drawing has been checked and coordinated with the requirements of the Work and the Contract Documents. Examination of each Shop Drawing shall be indicated by stamp, date and signature of a responsible person of the sub-contractor for supplied items and of the General Contractor for fabricated items. Shop Drawings not stamped, signed and dated will be returned without being reviewed and stamped "Re-submit". Ensure that the following are verified:
  - .1 Field Measurements.
  - .2 Field construction criteria.
  - .3 Catalogue numbers and similar data.
- .6 Submit one (1) electronic copy of product data sheets or brochures for requirements requested in specification Sections and as requested by Contract Administrator where shop drawings will not be prepared due to standardized manufacture of product.
- .7 Submit one (1) electronic copies of test reports for requirements requested in specification Sections and as requested by Contract Administrator.
  - .1 Report signed by authorized official of testing laboratory that material, product or system identical to material, product or system to be provided has been tested in accord with specified requirements.
  - .2 Testing must have been within three (3) years of date of Contract award for project.

- .8 Submit one (1) electronic copy of certificates for requirements requested in specification Sections and as requested by Contract Administrator.
  - .1 Statements printed on manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that product, system or material meets specification requirements.
  - .2 Certificates must be dated after award of Project Contract complete with Project name.
- .9 Submit one (1) electronic copy of manufacturers instructions for requirements requested in specification Sections and as requested by Contract Administrator.
  - .1 Pre-printed material describing installation of product, system or material, including special notices and Material Safety Data Sheets concerning impedances, hazards and safety precautions.
- .10 Submit one (1) electronic copy of Manufacturer's Field Reports for requirements requested in specification Sections and as requested by Contract Administrator.
  - .1 Documentation of the testing and verification actions taken by manufacturer's representative to confirm compliance with manufacturer's standards or instructions.
- .11 Submit one (1) electronic copy of Operation and Maintenance Data for requirements requested in specification Sections and as requested by Contract Administrator.
- .12 Delete information not applicable to Project.
- .13 Supplement standard information to provide details applicable to Project.
- .14 If upon review by Contract Administrator, no errors or omissions are discovered or if only minor corrections are made, copies will be returned and fabrication and installation of Work may proceed. If shop drawings are rejected, noted copy will be returned and resubmission of corrected shop, through same procedure indicated above, must be performed before fabrication and installation of Work may proceed.
- .15 Contractor will be charged for Contract Administrator subsequent reviews of submittal packages exceeding two submissions.
- .16 Accompany submissions with transmittal letter, containing:
  - .1 Date.
  - .2 Project title and number.
  - .3 Contractor's name and address.
  - .4 Identification and quantity of each shop drawing, product data and sample.
  - .5 Specification Section, Title, Number, and Clause
  - .6 Other pertinent data.
  - .7 Date and revision dates.
  - .8 Project title and Bid Opportunity number.
  - .9 Name of:

- .1 Contractor
- .2 Subcontractor
- .3 Supplier
- .4 Manufacturer
- .5 Separate detailer when pertinent
- .10 Identification of product of material.
- .11 Relation to adjacent structure or materials.
- .12 Field dimensions, clearly identified as such.
- .13 Specification section name, number and clause number or drawing number and detail/section number.
- .14 Applicable standards, such as CSA or CGSB numbers.
- .15 Contractor's stamp, initialed or signed, certifying review of submission, verification of field measurements and compliance with Contract Documents.

### **1.3 PRODECURES**

- .1 The Contractor shall, if required by the Contract Administrator, submit for the review of the Contract Administrator method statements which describe in detail, supplement with Drawings where necessary, the methods to be adopted for executing any portion of Work.
- .2 These statements shall also include details of constructional plant and labour to be employed. Acceptance by the Contract Administrator shall not relieve the Contractor of any of his responsibilities, nor shall reasonable refusal to approve entitle the Contractor to extra payment or an extension of time.
- .3 Other Considerations
  - .1 Fabrication, erection, installation or commissioning may require modifications to equipment or systems to conform to the design intent. Revise pertinent shop drawings and resubmit.
  - .2 Material and equipment delivered to the site of the works will not be paid for at least until pertinent shop drawings have been submitted and reviewed.
  - .3 Incomplete shop drawing information will be considered as stipulated deductions for the purposes of progress payment certificates.
  - .4 No delay or cost claims will be allowed that arise because of delays in submissions, re-submissions and review of shop drawings.
  - .5 Contractor to monitor the shoring for movement on a daily basis and provide a written weekly report showing the daily records to the Contract Administrator.

### **1.4 SAMPLES**

- .1 Submit for review samples in duplicate as requested in respective specification Sections. Label samples with origin and intended use.
- .2 Deliver samples prepaid to Contract Administrator's business address.

- .3 Notify Contract Administrator in writing, at time of submission of deviations in samples from requirements of Contract Documents.
- .4 Where colour, pattern or texture is criterion, submit full range of samples.
- .5 Adjustments made on samples by Contract Administrator are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Contract Administrator prior to proceeding with Work.
- .6 Make changes in samples which Contract Administrator may require, consistent with Contract Documents.
- .7 Reviewed and accepted samples will become standard of workmanship and material against which installed Work will be verified.

**1.5 MOCK-UPS**

- .1 Erect mock-ups in accordance with 01 45 00 - Quality Control.

**1.6 PROGRESS PHOTOGRAPHS**

- .1 Submit progress photographs.

**Part 2 Products NOT USED**

**Part 3 Execution NOT USED**

**END OF SECTION**

**Part 1        General**

**1.1            INSPECTION**

- .1        Allow Contract Administrator access to Work. If part of Work is in preparation at locations other than Place of Work, allow access to such Work whenever it is in progress.
- .2        Give timely notice requesting inspection if Work is designated for special tests, inspections or approvals by Contract Administrator instructions, or law of Place of Work.
- .3        If Contractor covers or permits to be covered Work that has been designated for special tests, inspections or approvals before such is made, uncover such Work, have inspections or tests satisfactorily completed and make good such Work.
- .4        The Contract Administrator will order part of Work to be examined if Work is suspected to be not in accordance with Contract Documents. If, upon examination such work is found not in accordance with Contract Documents, correct such Work and pay cost of examination and correction. If such Work is found in accordance with Contract Documents, the City shall pay cost of examination and replacement.

**1.2            INDEPENDENT INSPECTION AGENCIES**

- .1        Independent Inspection/Testing Agencies will be engaged by Contract Administrator for purpose of inspecting and/or testing portions of Work.
- .2        Provide equipment required for executing inspection and testing by appointed agencies.
- .3        Employment of inspection/testing agencies does not relax responsibility to perform Work in accordance with Contract Documents.
- .4        If defects are revealed during inspection and/or testing, appointed agency will request additional inspection and/or testing to ascertain full degree of defect. Correct defect and irregularities as advised by Contract Administrator at no cost to Contract Administrator. Pay costs for retesting and reinspection.

**1.3            ACCESS TO WORK**

- .1        Allow inspection/testing agencies access to Work, off Site manufacturing and fabrication plants.
- .2        Co-operate to provide reasonable facilities for such access.

**1.4            REJECTED WORK**

- .1        Remove defective Work, whether result of poor workmanship, use of defective products or damage and whether incorporated in Work or not, which has been rejected by the Contract Administrator as failing to conform to Contract Documents. Replace or re-execute in accordance with Contract Documents.

- .2 Make good other Contractor's work damaged by such removals or replacements promptly.
- .3 If in opinion of the Contract Administrator it is not expedient to correct defective Work or Work not performed in accordance with Contract Documents, the City will deduct from Contract Price difference in value between Work performed and that called for by Contract Documents, amount of which will be determined by Contract Administrator.

**1.5 PROCEDURES**

- .1 Notify appropriate agency and Contract Administrator in advance of requirement for tests, in order that attendance arrangements can be made.
- .2 Submit samples and/or materials required for testing, as specifically requested in specifications. Submit with reasonable promptness and in orderly sequence to not cause delays in Work.
- .3 Provide labour and facilities to obtain and handle samples and materials on Site. Provide sufficient space to store and cure test samples.

**1.6 REPORTS**

- .1 Submit four (4) copies of inspection and test reports to Contract Administrator, prior to inclusion with the O&M manuals, in accordance with Section 01 33 00 – Submittal Procedures.
- .2 Provide copies to Subcontractor of Work being inspected or tested, manufacturer or fabricator of material being inspected or tested.

**1.7 TESTS AND MIX DESIGNS**

- .1 Furnish test results and mix designs as requested.
- .2 Cost of tests and mix designs beyond those called for in Contract Documents or beyond those required by law of Place of Work will be appraised by Contract Administrator and may be authorized as recoverable.

**Part 2 Products NOT USED**

**Part 3 Execution NOT USED**

**END OF SECTION**

**Part 1      General**

**1.1          SUBMITTALS**

- .1      Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

**1.2          INSTALLATION AND REMOVAL**

- .1      Provide temporary utilities controls in order to execute Work expeditiously.
- .2      Remove from Site all such Work after use.

**1.3          DEWATERING**

- .1      Provide temporary drainage and pumping facilities to keep excavation and site free from standing water.

**1.4          WATER SUPPLY**

- .1      Provide potable water as required for construction work.

**1.5          TEMPORARY HEATING AND VENTILATION**

- .1      Provide temporary heating required during construction period, including attendance, maintenance and fuel.
- .2      Construction heaters used inside building must be vented to outside or be non-flameless type. Solid fuel salamanders are not permitted.
- .3      Provide temporary heat and ventilation in enclosed areas as required to:
  - .1      Facilitate progress of Work.
  - .2      Protect Work and products against dampness and cold.
  - .3      Prevent moisture condensation on surfaces.
  - .4      Provide ambient temperatures and humidity levels for storage, installation and curing of materials.
  - .5      Provide adequate ventilation to meet health regulations for safe working environment.
- .4      Maintain temperatures of minimum 10 degrees C in areas where construction is in progress.
- .5      Ventilating:
  - .1      Prevent accumulations of dust, fumes, mists, vapours or gases in areas occupied during construction.
  - .2      Provide local exhaust ventilation to prevent harmful accumulation of hazardous substances into atmosphere of occupied areas.
  - .3      Dispose of exhaust materials in manner that will not result in harmful exposure to persons.
  - .4      Ventilate storage spaces containing hazardous or volatile materials.
  - .5      Ventilate temporary sanitary facilities.

- .6 Continue operation of ventilation and exhaust system for time after cessation of Work process to assure removal of harmful contaminants.
- .6 Permanent heating system of building, may be used when available. Be responsible for damage to heating system if use is permitted.
- .7 On completion of Work for which permanent heating system is used, replace filters.
- .8 Ensure Date of Substantial Performance and Warranties for heating system do not commence until entire system is in as near original condition as possible and is certified by Contract Administrator.
- .9 Pay costs for maintaining temporary heat, when using permanent heating system. The City will pay utility charges when temporary heat source is existing building equipment.
- .10 Maintain strict supervision of operation of temporary heating and ventilating equipment to:
  - .1 Conform with applicable codes and standards.
  - .2 Enforce safe practices.
  - .3 Prevent abuse of services.
  - .4 Prevent damage to finishes.
  - .5 Vent direct-fired combustion units to outside.
- .11 Be responsible for damage to Work due to failure in providing adequate heat and protection during construction.

**1.6 TEMPORARY POWER AND LIGHT**

- .1 Provide construction power and light panel board. Provide circuit breaker and cabling and connect to empty circuit in panel board with spare capacity.
- .2 Provide and maintain temporary lighting throughout Project. Ensure level of illumination on all floors and stairs is not less than 162 lx.

**1.7 TEMPORARY COMMUNICATION FACILITIES**

- .1 Provide and pay for temporary telephone fax data hook up, lines, equipment necessary for own use.

**1.8 FIRE PROTECTION**

- .1 Provide and maintain temporary fire protection equipment during performance of Work required by insurance companies having jurisdiction and governing codes, regulations and bylaws.
- .2 Burning rubbish and construction waste materials is not permitted on Site.

**Part 2          Products NOT USED**

**Part 3          Execution NOT USED**

**END OF SECTION**

**Part 1      General**

**1.1          REFERENCES**

- .1 Canadian Standards Association (CSA International).
  - .1 CAN/CSA-S269.2-[M1987(R2003)], Access Scaffolding for Construction Purposes.

**1.2          ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

**1.3          INSTALLATION AND REMOVAL**

- .1 Prepare site plan indicating proposed location and dimensions of area to be fenced and used by Contractor, number of trailers to be used, avenues of ingress/egress to fenced area and details of fence installation.
- .2 Indicate use of supplemental or other staging area.
- .3 Provide construction facilities in order to execute Work expeditiously.
- .4 Remove from Site all such Work after use.

**1.4          SCAFFOLDING**

- .1 Scaffolding in accordance with CAN/CSA-S269.2.
- .2 Provide and maintain scaffolding and ladders.

**1.5          HOISTING**

- .1 Provide, operate and maintain hoists, cranes required for moving of workers, materials and equipment.
- .2 Hoists, cranes to be operated by qualified operator.

**1.6          SITE STORAGE/LOADING**

- .1 Confine Work and operations of employees by Contract Documents. Do not unreasonably encumber premises with products.
- .2 Do not load or permit to load any part of Work with weight or force that will endanger Work.

**1.7          CONSTRUCTION PARKING**

- .1 Parking will be permitted on Site in public parking areas provided it does not disrupt performance of Work.
- .2 Provide and maintain adequate access to Project Site including fire route access.

**1.8 SECURITY**

- .1 Provide and pay for responsible security personnel to guard Site and contents of Site after working hours and during holidays.

**1.9 OFFICES**

- .1 Provide office heated to 22 degrees C, lighted 750 lx and ventilated, of sufficient size to accommodate Site meetings and furnished with drawing laydown table.
- .2 Provide marked and fully stocked first-aid case in a readily available location.
- .3 Subcontractors to provide their own offices as necessary. Direct location of these offices.
- .4 Supply temporary office facilities for the Contract Administrator on site, meeting the following requirements:
  - .1 Minimum floor area of 20 square metres, with windows and a door entrance complete with suitable lock satisfactory to the Contract Administrator.
  - .2 Suitable for all-weather use and capable of maintaining a temperature range between 20 and 25 degrees C.
  - .3 Equipped with fluorescent lights and 120 volt ac electrical wall outlets
  - .4 Furnished with one desk, one filing cabinet and two chairs, all satisfactory to the Contract Administrator.
  - .5 All of the temporary structures provided by the Contractor for this project shall be stabilized in a sufficient manner to prevent the temporary structure from being overturned by wind forces as defined in the National Building Code (NBC). The stabilization provided shall be designed by a Professional Engineer registered in the Province of Manitoba. Detailed drawings and design notes for the stabilization works bearing the Engineer's seal shall be provided to the Contract Administrator for review.
  - .6 The Contractor shall be responsible for installation, maintenance, removal, operating costs, and service installation costs for the field office as described herein.

**1.10 EQUIPMENT, TOOL AND MATERIALS STORAGE**

- .1 Provide and maintain, in clean and orderly condition, lockable weatherproof sheds for storage of tools, equipment and materials.
- .2 Locate materials not required to be stored in weatherproof sheds on Site in manner to cause least interference with Work activities.

**1.11 SANITARY FACILITIES**

- .1 Provide sanitary facilities for Work force in accordance with governing regulations and ordinances.
- .2 Post notices and take precautions as required by local health authorities. Keep area and premises in sanitary condition.

**1.12 LAYDOWN AND STORAGE**

- .1 All construction materials shall be stored at designated storage areas. Stored combustible materials shall be separated by clear space to prevent fire spread and allow access for manual firefighting equipment, including fire hoses, extinguishers, hydrants, etc.
- .2 Pressurized dry chemical fire extinguishers of suitable capacity or equally effective extinguishers as per NFPA 10 shall be provided where:
  - .1 Flammable liquids are stored or handled.
  - .2 Welding or flame cutting is performed.

**1.13 DISPOSAL OF WASTE MATERIALS**

- .1 Spoiled and waste materials shall not be dumped, under any circumstances, in any locations other than those approved by the local authorities. Any cost for permits and fees for disposing of waste materials shall be at the Contractor's expense.
- .2 Disposal of all excavated and waste materials shall be in accordance with the requirements of the appropriate provincial regulatory agencies.
- .3 When working anywhere within the Works the Contractor shall at the end of each working day remove the rubbish and leave the Site in a clean and tidy state, to the satisfaction of the Contract Administrator. If this is not done, the City will clean the Site and charge the Contractor.

**1.14 FACILITY ELECTRICAL SUPPLY AND DISTRIBUTION**

- .1 If service interruptions are necessary, such interruptions shall be made only at times approved by the Contract Administrator.

**1.15 PROTECTION AND MAINTENANCE OF TRAFFIC**

- .1 Provide access and temporary relocated roads as necessary to maintain traffic.
- .2 Maintain and protect traffic on affected roads during construction period except as otherwise specifically directed by Contract Administrator.
- .3 Provide measures for protection and diversion of traffic, including provision of watch-persons and flag-persons, erection of barricades, placing of lights around and in front of equipment and work, and erection and maintenance of adequate warning, danger, and direction signs.
- .4 Protect travelling public from damage to person and property.
- .5 Contractor's traffic on roads selected for hauling material to and from Site to interfere as little as possible with public traffic.
- .6 Verify adequacy of existing roads and allowable load limit on these roads. Contractor: responsible for repair of damage to roads caused by construction operations.
- .7 Construct access and haul roads necessary.

- .8 Provide necessary lighting, signs, barricades, and distinctive markings for safe movement of traffic.
- .9 Dust control: adequate to ensure safe operation at all times.
- .10 Provide snow removal during period of Work.

**1.16 CLEAN-UP**

- .1 Remove construction debris, waste materials, packaging material from Work Site daily.
- .2 Clean dirt or mud tracked onto paved or surfaced roadways.
- .3 Store materials resulting from demolition activities that are salvageable.
- .4 Stack stored new or salvaged material not in construction facilities.

**1.17 FIRE ACCESS**

- .1 Maintain safe access for fire and rescue vehicles along south side of building.

**Part 2 Products NOT USED**

**Part 3 Execution NOT USED**

**END OF SECTION**

**Part 1            General**

**1.1                INSTALLATION AND REMOVAL**

- .1            Provide temporary controls in order to execute Work expeditiously.
- .2            Remove from Site all such Work after use.

**1.2                HOARDING**

- .1            Erect temporary Site enclosures.
- .2            Erect temporary Site enclosure .
- .3            Provide barriers around trees and plants designated to remain. Protect from damage by equipment and construction procedures.

**1.3                GUARD RAILS AND BARRICADES**

- .1            Provide secure, rigid guard rails and barricades around deep excavations, open shafts, open stair wells, open edges of floors and roofs.
- .2            Provide as required by governing authorities.

**1.4                WEATHER ENCLOSURES**

- .1            Provide weather tight closures to unfinished door and window openings, tops of shafts and other openings in floors and roofs.
- .2            Close off floor areas where walls are not finished; seal off other openings; enclose building interior work for temporary heat.
- .3            Design enclosures to withstand wind pressure and snow loading.

**1.5                DUST TIGHT SCREENS**

- .1            Provide dust tight screens or insulated partitions to localize dust generating activities, and for protection of workers, finished areas of Work and public.
- .2            Maintain and relocate protection until such Work is complete.

**1.6                ACCESS TO SITE**

- .1            Provide and maintain access roads, sidewalk crossings, ramps and construction runways as may be required for access to Work.

**1.7                PUBLIC TRAFFIC FLOW**

- .1            Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform Work and protect public.

**1.8 FIRE ROUTES**

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

**1.9 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY**

- .1 Protect surrounding private and public property from damage during performance of Work.
- .2 Be responsible for damage incurred.

**1.10 PROTECTION OF BUILDING FINISHES**

- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Confirm with Contract Administrator locations and installation schedule three (3) days prior to installation.
- .4 Be responsible for damage incurred due to lack of or improper protection.

**Part 2 Products NOT USED**

**Part 3 Execution NOT USED**

**END OF SECTION**

**Part 1      General**

**1.1          REFERENCES**

- .1 Conform to reference standards, in whole or in part as specifically requested in specifications.
- .2 If there is question as to whether products or systems are in conformance with applicable standards, the Contract Administrator reserves the right to have such products or systems tested to prove or disprove conformance.
- .3 Cost for such testing will be born by the City in event of conformance with Contract Documents or by the Contractor in event of non-conformance.

**1.2          QUALITY**

- .1 Products, materials, equipment and articles incorporated in Work shall be new, not damaged or defective, and of best quality for purpose intended. If requested, furnish evidence as to type, source and quality of products provided.
- .2 Defective products, whenever identified prior to completion of Work, will be rejected, regardless of previous inspections. Inspection does not relieve responsibility, but is precaution against oversight or error. Remove and replace defective products at own expense and be responsible for delays and expenses caused by rejection. Should disputes arise as to quality or fitness of products, decision rests strictly with the Contract Administrator based upon requirements of Contract Documents.
- .3 Unless otherwise indicated in specifications, maintain uniformity of manufacture for any particular or like item throughout building.

**1.3          AVAILABILITY**

- .1 Immediately upon signing Contract, review product delivery requirements and anticipate foreseeable supply delays for items. If delays in supply of products are foreseeable, notify the Contract Administrator of such, in order that substitutions or other remedial action may be authorized in ample time to prevent delay in performance of Work.
- .2 In event of failure to notify the Contract Administrator at commencement of Work and should it subsequently appear that Work may be delayed for such reason, the Contract Administrator reserves right to substitute more readily available products of similar character, at no increase in Contract Price or Contract Time.

**1.4          METRIC PROJECT**

- .1 Unless otherwise noted, this project has been designed and is to be constructed in the International System (SI) of Units metric system of measurements.
- .2 During construction, when specified metric elements are unattainable at the time they are required to meet the construction schedule, the Contractor shall notify the Contract.

**1.5 STORAGE, HANDLING AND PROTECTION**

- .1 Handle and store products in manner to prevent damage, adulteration, deterioration and soiling and in accordance with manufacturer's instructions when applicable.
- .2 Store packaged or bundled products in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until required in Work.
- .3 Store products subject to damage from weather in weatherproof enclosures.
- .4 Store cementitious products clear of earth or concrete floors, and away from walls.
- .5 Keep sand, when used for grout or mortar materials, clean and dry. Store sand on wooden platforms and cover with waterproof tarpaulins during inclement weather.
- .6 Store sheet materials, lumber and similar products on flat, solid supports and keep clear of ground. Slope to shed moisture.
- .7 Store and mix paints in heated and ventilated room. Remove oily rags and other combustible debris from site daily. Take every precaution necessary to prevent spontaneous combustion.
- .8 Remove and replace damaged products at own expense and to satisfaction of the Contract Administrator.
- .9 Touch-up damaged factory finished surfaces to Contract Administrator's satisfaction. Use touch-up materials to match original. Do not paint over name plates.

**1.6 TRANSPORTATION**

- .1 Pay costs of transportation of products required in performance of Work.

**1.7 MANUFACTURERS INSTRUCTIONS**

- .1 Unless otherwise indicated in specifications, install or erect products in accordance with manufacturer's instructions. Do not rely on labels or enclosures provided with products. Obtain written instructions directly from manufacturers.
- .2 Notify the Contract Administrator in writing, of conflicts between specifications and manufacturer's instructions, so that the Contract Administrator will establish the course of action.
- .3 Improper installation or erection of products, due to failure in complying with these requirements, authorizes the Contract Administrator to require removal and re-installation at no increase in Contract Price or Contract Time.

**1.8 REMEDIAL WORK**

- .1 Perform remedial work required to repair or replace parts or portions of Work identified as defective or unacceptable. Co-ordinate adjacent affected Work as required.

- .2 Perform remedial work by specialists familiar with materials affected. Perform in a manner to neither damage nor put at risk any portion of Work.

### **1.9 FASTENINGS**

- .1 Provide metal fastenings and accessories in same texture, colour and finish as adjacent materials, unless indicated otherwise.
- .2 Prevent electrolytic action between dissimilar metals and materials.
- .3 Use non-corrosive hot dip galvanized steel fasteners and anchors for securing exterior work, unless stainless steel or other material is specifically requested in affected specification Section.
- .4 Space anchors within individual load limit or shear capacity and ensure they provide positive permanent anchorage. Wood, or any other organic material plugs are not acceptable.
- .5 Keep exposed fastenings to a minimum, space evenly and install neatly.
- .6 Fastenings which cause spalling or cracking of material to which anchorage is made are not acceptable.

### **1.10 PROTECTION OF WORK IN PROGRESS**

- .1 Prevent overloading of parts of building. Do not cut, drill or sleeve load bearing structural member, unless specifically indicated without written approval of the Contract Administrator.

## **Part 2 Products**

### **2.1 NOT USED**

- .1 Not Used.

## **Part 3 Execution**

### **3.1 WORKMANSHIP**

- .1 Ensure Quality of Work is of highest standard, executed by workers experienced and skilled in respective duties for which they are employed. Immediately notify the Contract Administrator if required Work is such as to make it impractical to produce required results.
- .2 Do not employ anyone unskilled in their required duties. The Contract Administrator reserves the right to require dismissal from site, workers deemed incompetent or careless.
- .3 Decisions as to standard or fitness of Quality of Work in cases of dispute rest solely with the Contract Administrator, whose decision is final.

**END OF SECTION**

**Part 1            General**

**1.1                ACTION AND INFORMATIONAL SUBMITTALS**

- .1            Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2            Submit written request in advance of cutting or alteration which affects:
  - .1            Structural integrity of elements of Project.
  - .2            Integrity of weather-exposed or moisture-resistant elements.
  - .3            Efficiency, maintenance, or safety of operational elements.
  - .4            Visual qualities of sight-exposed elements.
  - .5            Work of the City or separate Contractor.
- .3            Include in request:
  - .1            Identification of Project.
  - .2            Location and description of affected Work.
  - .3            Statement on necessity for cutting or alteration.
  - .4            Description of proposed Work, and products to be used.
  - .5            Alternatives to cutting and patching.
  - .6            Effect on Work of the City or separate Contractor.
  - .7            Written permission of affected separate Contractor.
  - .8            Date and time Work will be executed.

**1.2                MATERIALS**

- .1            Required for original installation.
- .2            Change in Materials: Submit request for substitution in accordance with Section 01 33 00 - Submittal Procedures.

**1.3                PREPARATION**

- .1            Inspect existing conditions, including elements subject to damage or movement during cutting and patching.
- .2            After uncovering, inspect conditions affecting performance of Work.
- .3            Beginning of cutting or patching means acceptance of existing conditions.
- .4            Provide supports to assure structural integrity of surroundings; provide devices and methods to protect other portions of Project from damage.
- .5            Provide protection from elements for areas which are to be exposed by uncovering Work; maintain excavations free of water.

**1.4                EXECUTION**

- .1            Execute cutting, fitting, and patching including excavation and fill to complete Work.

- .2 Fit several parts together, to integrate with other Work.
- .3 Uncover Work to install ill-timed Work.
- .4 Remove and replace defective and non-conforming Work.
- .5 Remove samples of installed Work for testing.
- .6 Provide openings in non-structural elements of Work for penetrations of mechanical and electrical Work.
- .7 Execute Work by methods to avoid damage to other Work, and which will provide proper surfaces to receive patching and finishing.
- .8 Employ original installer to perform cutting and patching for weather-exposed and moisture-resistant elements, and sight-exposed surfaces.
- .9 Cut rigid materials using masonry saw or core drill. Pneumatic or impact tools not allowed on masonry Work without prior approval.
- .10 Restore Work with new products in accordance with requirements of Contract Documents.
- .11 Fit Work airtight to pipes, sleeves, ducts, conduit, and other penetrations through surfaces.
- .12 At penetration of fire rated wall, ceiling, or floor construction, completely seal voids with firestopping material with approved fire stopping assembly.
- .13 Refinish surfaces to match adjacent finishes: Refinish continuous surfaces to nearest intersection. Refinish assemblies by refinishing entire unit.
- .14 Conceal pipes, ducts and wiring in floor, wall and ceiling construction of finished areas except where indicated otherwise.

**Part 2 Products NOT USED**

**Part 3 Execution NOT USED**

**END OF SECTION**

**Part 1        General**

**1.1            PROJECT CLEANLINESS**

- .1        Maintain Work in tidy condition, free from accumulation of waste products and debris.
- .2        Remove waste materials from Site at daily regularly scheduled times or dispose of as directed by Contract Administrator. Do not burn waste materials on Site.
- .3        Clear snow and ice from access to building, bank/pile snow in designated areas only and remove from Site.
- .4        Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .5        Provide on-Site containers for collection of waste materials and debris.
- .6        Dispose of waste materials and debris off Site.
- .7        Clean interior areas prior to start of finishing Work, and maintain areas free of dust and other contaminants during finishing operations.
- .8        Store volatile waste in covered metal containers, and remove from premises at end of each working day.
- .9        Provide adequate ventilation during use of volatile or noxious substances. Use of building ventilation systems is not permitted for this purpose.
- .10       Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.
- .11       Schedule cleaning operations so that resulting dust, debris and other contaminants will not fall on wet, newly painted surfaces nor contaminate building systems.

**Part 2        Products**

**2.1            NOT USED**

- .1        Not Used

**Part 3        Execution**

**3.1            NOT USED**

- .1        Not Used

**END OF SECTION**

**Part 1            General**

**1.1                SECTION INCLUDES**

- .1        Text, schedules and procedures for systematic Waste Management Program for construction, deconstruction, demolition, and renovation projects that may include:
- .2        Diversion of Materials.
- .3        Materials Source Separation Program (MSSP).
- .4        Canadian Governmental Responsibility for the Environment Resources.

**1.2                DEFINITIONS**

- .1        Materials Source Separation Program (MSSP): Consists of series of ongoing activities to separate reusable and recyclable waste material into material categories from other types of waste at point of generation.
- .2        Recyclable: Ability of product or material to be recovered at end of its life cycle and re manufactured into new product for reuse by others.
- .3        Recycle: Process by which waste and recyclable materials are transformed or collected for purpose of being transferred into new products.
- .4        Recycling: Process of sorting, cleansing, treating and reconstituting solid waste and other discarded materials for purpose of using in altered form. Recycling does not include burning, incinerating, or thermally destroying waste.
- .5        Salvage: Removal of structural and non-structural materials from deconstruction/ disassembly projects for purpose of reuse or recycling.
- .6        Separate Condition: Refers to waste sorted into individual types.
- .7        Source Separation: Acts of keeping different types of waste materials separate beginning from first time they became waste.

**1.3                SUBMITTALS**

- .1        Submittals in accordance with Section 01 33 00 Submittal Procedures.

**1.4                MATERIALS SOURCE SEPARATION PROGRAM (MSSP)**

- .1        Prepare MSSP and have ready for use prior to project start up.
- .2        Implement MSSP for waste generated on project in compliance with approved methods and as reviewed by Contract Administrator. Provide onsite facilities for collection, handling, and storage of anticipated quantities of reusable and recyclable materials.
- .3        Provide containers to deposit reusable and recyclable materials.

- .4 Locate containers in locations, to facilitate deposit of materials without hindering daily operations.
- .5 Locate separated material(s) in area(s) which minimize material damage.
- .6 Collect, handle, store on site, and transport off site, salvaged materials in separate condition.
- .7 Transport to approved and authorized recycling facility.
- .8 Collect, handle, store on site, and transport off site, salvaged materials in combined condition.
- .9 Ship material(s) to site operating under Certificate of Approval or as directed by City.
- .10 Materials must be immediately separated into required categories for reuse or recycling.

**1.5 WASTE PROCESSING SITES**

- .1 Identify appropriate waste processing sites, based on municipal requirements, as required.

**1.6 STORAGE, HANDLING AND PROTECTION**

- .1 Store, materials to be reused, recycled and salvaged in locations as directed by Contract Administrator.
- .2 Unless specified otherwise, materials for removal become Contractor's property.
- .3 Protect, stockpile, store and catalogue salvaged items.
- .4 Separate non salvageable materials from salvaged items. Transport and deliver non salvageable items to licensed disposal facility.
- .5 Protect structural components not removed for demolition from movement or damage.
- .6 Support affected structures. If safety of building is endangered, cease operations and immediately notify Contract Administrator.
- .7 Protect surface drainage, mechanical and electrical from damage and blockage.
- .8 Separate and store materials produced during dismantling of structures in designated areas.
- .9 Prevent contamination of materials to be salvaged and recycled and handle materials in accordance with requirements for acceptance by designated facilities.
- .10 On site source separation is recommended.
- .11 Remove co-mingled materials to offsite processing facility for separation.
- .12 Provide waybills for separated materials.

**1.7 DISPOSAL OF WASTES**

- .1 Do not bury rubbish or waste materials.
- .2 Do not dispose of waste, volatile materials, mineral spirits, oil, paint thinner, or excavation material into waterways, storm, or sanitary sewers.
- .3 Remove materials from deconstruction as deconstruction/disassembly Work progresses.
- .4 Prepare project summary to verify destination and quantities on a material by material basis as identified in pre demolition material audit.
- .5 Dispose of waste in accordance with Municipal and Provincial regulations.

**1.8 USE OF SITE AND FACILITIES**

- .1 Execute work with least possible interference or disturbance to normal use of premises.
- .2 Maintain security measures established by existing facility and provide temporary security measures approved by Contract Administrator as required.

**1.9 SCHEDULING**

- .1 Coordinate Work with other activities at site to ensure timely and orderly progress of Work.

**Part 2 Execution**

**2.1 NOT USED**

- .1 Not Used.

**Part 3 Execution**

**3.1 APPLICATION**

- .1 Handle waste materials not reused, salvaged, or recycled in accordance with appropriate regulations and codes.

**3.2 CLEANING**

- .1 Remove tools and waste materials on completion of Work, and leave work area in clean and orderly condition.
- .2 Clean-up work area as work progresses.
- .3 Source separate materials to be reused/recycled into specified sort areas

**END OF SECTION**

**Part 1            General**

**1.1                SUBMITTALS**

- .1        Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2        Prepare instructions and data using personnel experienced in maintenance and operation of described products.
- .3        Copy will be returned after final inspection, with Contract Administrator's comments.
- .4        Revise content of documents as required prior to final submittal.
- .5        Two (2) weeks prior to Substantial Performance of the Work, submit to the Contract Administrator, four (4) final copies of operating and maintenance manuals in English.
- .6        Ensure spare parts, maintenance materials and special tools provided are new, undamaged or defective, and of same quality and manufacture as products provided in Work.
- .7        Furnish evidence, if requested, for type, source and quality of products provided.
- .8        Defective products will be rejected, regardless of previous inspections. Replace products at own expense.
- .9        Pay costs of transportation.

**1.2                FORMAT**

- .1        Organize data as instructional manual.
- .2        Binders: vinyl, hard covered, 3 'D' ring, loose leaf 219 x 279 mm with spine and face pockets.
- .3        When multiple binders are used correlate data into related consistent groupings. Identify contents of each binder on spine.
- .4        Cover: identify each binder with type or printed title 'Project Record Documents'; list title of Project and identify subject matter of contents.
- .5        Arrange content by systems under Section numbers and sequence of Table of Contents.
- .6        Provide tabbed fly leaf for each separate product and system, with typed description of product and major component parts of equipment.
- .7        Text: manufacturer's printed data, or typewritten data.
- .8        Drawings: provide with reinforced punched binder tab. Bind in with text; fold larger Drawings to size of text pages.

### **1.3 CONTENTS - EACH VOLUME**

- .1 Table of Contents: provide title of project; Date of submission; names.
  - .1 Addresses, and telephone numbers of Contract Administrator and Contractor with name of responsible parties.
  - .2 Schedule of products and systems, indexed to content of volume.
- .2 For each product or system:
  - .1 List names, addresses and telephone numbers of Subcontractors and suppliers, including local source of supplies and replacement parts.
- .3 Product Data: mark each sheet to identify specific products and component parts, and data applicable to installation; delete inapplicable information.
- .4 Drawings: supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams.
- .5 Typewritten Text: as required to supplement product data. Provide logical sequence of instructions for each procedure, incorporating manufacturer's instructions.
- .6 Training: refer to Section 01 79 00 - Demonstration and Training

### **1.4 AS-BUILTS AND SAMPLES**

- .1 Maintain, in addition to requirements in General Condition, at Site for Contract Administrator one record copy of:
  - .1 Contract Drawings.
  - .2 Specifications.
  - .3 Addenda.
  - .4 Change Orders and other modifications to Contract.
  - .5 Reviewed shop drawings, product data, and samples.
  - .6 Field test records.
  - .7 Inspection certificates.
  - .8 Manufacturer's certificates.
- .2 Store record documents and samples in field office apart from documents used for construction. Provide files, racks, and secure storage.
- .3 Label record documents and file in accordance with Section number listings in List of Contents of this Project Manual. Label each document "PROJECT RECORD" in neat, large, printed letters.
- .4 Maintain record documents in clean, dry and legible condition. Do not use record documents for construction purposes.
- .5 Keep record documents and samples available for inspection by Contract Administrator.

## **1.5 RECORDING ACTUAL SITE CONDITIONS**

- .1 Record information on set of drawings.
- .2 Provide felt tip marking pens, maintaining separate colours for each major system, for recording information.
- .3 Record information concurrently with construction progress. Do not conceal Work until required information is recorded.
- .4 Contract Drawings and shop drawings mark each item to record actual construction, including:
  - .1 Measured depths of elements of foundation in relation to finish first floor datum.
  - .2 Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
  - .3 Measured locations of internal utilities and appurtenances, referenced to visible and accessible features of construction.
  - .4 Field changes of dimension and detail.
  - .5 Changes made by change orders.
  - .6 Details not on original Contract Drawings.
  - .7 References to related shop drawings and modifications.
- .5 Specifications; mark each item to record actual construction including:
  - .1 Manufacturer, trade name, and catalogue number of each product actually installed, particularly optional items and substitute items.
  - .2 Changes made by Addenda and change orders.
- .6 Other Documents; maintain manufacturer's certifications, inspection certifications, field test records, required by individual specifications sections.

## **1.6 EQUIPMENT AND SYSTEMS**

- .1 Each Item of Equipment and Each System: include description of unit or system, and component parts. Give function, normal operation characteristics, and limiting conditions. Include performance curves, with engineering data and tests, and complete nomenclature and commercial number of replaceable parts.
- .2 Panel board circuit directories: provide electrical service characteristics, controls, and communications.
- .3 Include installed colour coded wiring diagrams.
- .4 Operating Procedures: include start-up, break-in, and routine normal operating instructions and sequences. Include regulation, control, stopping, shut-down, and emergency instructions. Include summer, winter, and any special operating instructions.
- .5 Maintenance Requirements: include routine procedures and guide for trouble-shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.

- .6 Provide servicing and lubrication schedule, and list of lubricants required.
- .7 Include manufacturer's printed operation and maintenance instructions.
- .8 Include sequence of operation by controls manufacturer.
- .9 Provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.
- .10 Provide installed control diagrams by controls manufacturer.
- .11 Provide list of original manufacturer's spare parts, current prices, and recommended quantities to be maintained in storage.
- .12 Additional requirements: as specified in individual specification sections.

**1.7 MATERIALS AND FINISHES**

- .1 Building Products, Applied Materials, and Finishes: include product data, with catalogue number, size, composition, and colour and texture designations.
- .2 Instructions for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.
- .3 Moisture-Protection and Weather-Exposed Products: include manufacturer's recommendations for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.
- .4 Additional Requirements: as specified in individual specifications sections.

**1.8 SPARE PARTS**

- .1 Provide spare parts, in quantities specified in individual specification sections.
- .2 Provide items of same manufacture and quality as items in Work.
- .3 Deliver to Site; place and store.
- .4 Receive and catalogue items. Submit inventory listing to Contract Administrator. Include approved listings in Maintenance Manual.
- .5 Obtain receipt for delivered products and submit prior to final payment.

**1.9 MAINTENANCE MATERIALS**

- .1 Provide maintenance and extra materials, in quantities specified in individual specification sections.
- .2 Provide items of same manufacture and quality as items in Work.
- .3 Deliver to Site; place and store.

- .4 Receive and catalogue items. Submit inventory listing to Contract Administrator. Include approved listings in Maintenance Manual.
- .5 Obtain receipt for delivered products and submit prior to final payment.

**1.10 SPECIAL TOOLS**

- .1 Provide special tools, in quantities specified in individual specification section.
- .2 Provide items with tags identifying their associated function and equipment.
- .3 Deliver to Site; place and store. Receive and catalogue items. Submit inventory listing to Contract Administrator. Include approved listings in Maintenance Manual.

**1.11 STORAGE, HANDLING AND PROTECTION**

- .1 Store spare parts, maintenance materials, and special tools in manner to prevent damage or deterioration.
- .2 Store in original and undamaged condition with manufacturer's seal and labels intact.
- .3 Store components subject to damage from weather in weatherproof enclosures.
- .4 Store paints and freezable materials in a heated and ventilated room.
- .5 Remove and replace damaged products at own expense and to satisfaction of Contract Administrator

**1.12 WARRANTIES**

- .1 Assemble approved information in binder and submit upon acceptance of Work. Organize binder as follows:
  - .1 Separate each warranty or bond with index tab sheets keyed to Table of Contents listing.
  - .2 List Subcontractor, supplier, and manufacturer, with name, address, and telephone number of responsible principal.
  - .3 Obtain warranties, executed in duplicate by Subcontractors, suppliers, and manufacturers, within ten (10) days after completion of applicable item of Work.
  - .4 Verify that documents are in proper form, contain full information, and are notarized.
  - .5 Co-execute submittals when required.
  - .6 Retain warranties until time specified for submittal.
- .2 Except for items put into use with City's permission, leave date of beginning of time of warranty until Date of Substantial Performance is determined.
- .3 Conduct joint 11 month warranty inspection, measured from Date of Substantial Performance, by Contract Administrator.

- .4 Respond in a timely manner to oral or written notification of required construction warranty repair Work.
- .5 Written verification will follow oral instructions. Failure to respond will be cause for the Contract Administrator to proceed with action against Contractor.

**Part 2 Products**

**2.1 NOT USED**

- .1 Not Used.

**Part 3 Execution**

**3.1 NOT USED**

- .1 Not Used.

**END OF SECTION**

**Part 1            General**

**1.1                DESCRIPTION**

- .1        Demonstrate operation and maintenance of equipment and systems to City's personnel one week prior to date of substantial performance.
- .2        The City will provide list of personnel to receive instructions, and will co-ordinate their attendance at agreed-upon times.

**1.2                QUALITY CONTROL**

- .1        When specified in individual Sections require manufacturer to provide authorized representative to demonstrate operation of equipment and systems, instruct City's personnel, and provide written report that demonstration and instructions have been completed.

**1.3                SUBMITTALS**

- .1        Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2        Submit schedule of time and date for demonstration of each item of equipment and each system two (2) weeks prior to designated dates, for Contract Administrator approval. Submit reports within one (1) week after completion of demonstration, that demonstration and instructions have been satisfactorily completed.
- .3        Give time and date of each demonstration, with list of persons present.

**1.4                CONDITIONS FOR DEMONSTRATIONS**

- .1        Equipment has been inspected and put into operation.
- .2        Provide copies of completed operation and maintenance manuals for use in demonstrations and instructions.

**1.5                PREPARATION**

- .1        Verify that conditions for demonstration and instructions comply with requirements.
- .2        Verify that designated personnel are present.

**1.6                DEMONSTRATION AND INSTRUCTIONS**

- .1        Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, and maintenance of each item of equipment.
- .2        Instruct personnel in phases of operation and maintenance using operation and maintenance manuals as basis of instruction.
- .3        Review contents of manual in detail to explain aspects of operation and maintenance.

- .4 Prepare and insert additional data in operations and maintenance manuals when need for additional data becomes apparent during instructions.

**1.7 TIME ALLOCATED FOR INSTRUCTIONS**

- .1 Ensure amount of time required for instruction of each item of equipment or system is adequate as determined by the Contract Administrator.
- .2 At a minimum allow for training of each system to two (2) separate groups of City personnel.

**Part 2 Products**

**2.1 NOT USED**

- .1 Not Used.

**Part 3 Execution**

**3.1 NOT USED**

- .1 Not Used.

**END OF SECTION**

**Part 1        General**

**1.1            REFERENCES**

- .1        CSA S350, Code of Practice for Safety in Demolition of Structures.

**1.2            EXISTING CONDITIONS**

- .1        Structures to be demolished to be based on their condition on date that tender is accepted.
- .2        Items to be salvaged, as identified by City and/or City's Representative, to be carefully removed protected and handed to City and/or City's Representative.

**1.3            DEMOLITION DRAWINGS**

- .1        Where required by authorities having jurisdiction, submit for approval Drawings, diagrams or details showing sequence of demolition work and supporting structures and underpinning.
- .2        Temporary supporting structures and shoring systems are to be designed and submittals sealed by a structural Engineer licensed to practice in the province of Manitoba.

**1.4            PROTECTION**

- .1        Prevent movement, settlement or damage of adjacent structures, services, parts of existing building to remain. Provide bracing, shoring and underpinning as required. Make good damage caused by demolition.
- .2        Take precautions to support affected structures and, if safety of building being demolished or adjacent structures or services appears to be endangered, cease operations and notify the Department Representative or designate.
- .3        Prevent physical intrusion and damage caused by environmental factors such as wind and rain and the spread of dust and contaminants by means of temporary plywood enclosures, screens, fencing, tarps and other means sealed against other areas of the building as required.

**Part 2        Products**

**Part 3        Execution**

**3.1            PREPARATION**

- .1        Disconnect and re-route electrical and telephone service lines entering areas to be demolished in accordance with authorities having jurisdiction. Post warning signs on electrical lines and equipment which must remain energized to serve other areas of the building during period of demolition.

□

- .2 Disconnect and cap designated mechanical services in accordance with authorities having jurisdiction where indicated.
- .3 Do not disrupt active or energized utilities designated to remain undisturbed.

**3.2 DEMOLITION**

- .1 Demolish and remove in general portions of exterior and interior walls, roofing, ceilings, structures, finishes, fixed furnishings and mechanical and electrical components in the area of work that are not to be incorporated in the completed Project.
- .2 At end of each day's Work, leave work in safe condition so that no part is in danger of toppling or falling. Protect interiors of parts to be demolished from exterior elements at all times.
- .3 Demolish to minimize dusting.
- .4 Do not sell or burn materials on Site.
- .5 Remove and dispose of demolished materials except where noted otherwise and in accordance with authorities having jurisdiction.

**3.3 SALVAGE**

- .1 Items to be salvaged: As directed by Department Representative or designate.
- .2 Carefully dismantle items containing materials for salvage and stockpile salvaged materials on Site.
- .3 All pumps and motors to be handed over to the City.

**END OF SECTION**

**Part 1 General**

**1.1 Related Sections**

- .1 Section 01 33 23 – Submittal Procedures for Shop Drawings, Product Data and Samples.
- .2 Section 01 61 00 – Material and Equipment.
- .3 Section 01 35 43 – Environmental Procedures.

**1.2 References**

- .1 American Society for Testing and Materials International, (ASTM).
  - .1 ASTM A307-02, Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.
- .2 Canadian General Standards Board (CGSB).
  - .1 CAN/CGSB-1.40-97, Anti-corrosive Structural Steel Alkyd Primer.
  - .2 CAN/CGSB-1.181-92, Ready-Mixed, Organic Zinc-Rich Coating.
- .3 Canadian Standards Association (CSA International).
  - .1 CAN/CSA-G40.20/G40.21-04, General Requirements for Rolled or Welded Structural Quality Steel.
  - .2 CAN/CSA-G164-M92 (R1998), Hot Dip Galvanizing of Irregularly Shaped Articles.
  - .3 CAN/CSA-S16.1-01, Limit States Design of Steel Structures.
  - .4 CSA W48-01, Filler Metals and Allied Materials for Metal Arc Welding (Developed in co-operation with the Canadian Welding Bureau).
  - .5 CSA W59-1989(R2001), Welded Steel Construction (Metal Arc Welding) (Imperial Version).

**1.3 Submittals**

- .1 Product Data:
  - .1 Submit manufacturer's printed product literature, specifications and data sheet in accordance with Section 01 33 23.
  - .2 Submit two copies of WHMIS MSDS – Material Safety Data Sheets in accordance with Section 01 33 23. Indicate VOCs:
    - .1 For finishes, coatings, primers and paints.
- .2 Shop Drawings
  - .1 Submit shop drawings including fabrication and erection documents and materials list in accordance with Section 01 33 23.
  - .2 Erection drawings: indicate details and information necessary for assembly and erection purposes including:
    - .1 Description of methods.
    - .2 Sequence of erection.

- .3 Type of equipment used in erection.
- .4 Temporary bracings.
- .5 All information necessary for fabrication of component parts, including extent of shop paint coverage.
- .6 Wall Plate and Anchor Bolt Details and Setting Out Plan.
- .7 Location and size of all members and details of field connections.
- .3 Ensure each drawing submitted bears stamp and signature of qualified Professional Engineer registered or licensed in province of Manitoba, Canada.

#### **1.4 Quality Assurance**

- .1 Test Reports: Certified test reports showing compliance with specified performance characteristics and physical properties.
- .2 Certificates: Product certificates signed by manufacturer certifying materials comply with specified performance characteristics and criteria and physical requirements.

#### **1.5 Delivery, Storage, and Handling**

- .1 Packing, Shipping, Handling and Unloading:
  - .1 Deliver, store, handle and protect materials in accordance with Section 01 61 00 – Material and Equipment

#### **1.6 Waste Management and Disposal**

- .1 Separate and recycle waste materials.
- .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .3 Collect and separate for disposal paper, plastic, polystyrene and corrugated cardboard packaging material and pallets in appropriate on-site containers for recycling in accordance with Waste Management Plan.
- .4 Divert unused metal materials from landfill to an approved metal recycling facility.

### **Part 2 Products**

#### **2.1 Materials**

- .1 All materials in contact with potable water shall be suitable for potable water application and certified to meet NSF/ANSI 61: Drinking Water System Components.
- .2 Steel sections: to CAN/CSA-G40.20/G40.21, Grade 350W.
- .3 Hollow structural sections: to CAN/CSA G40.20/G40.21, Grade 350W, Class C.
- .4 Angles, channels and plates (L, C): to CAN/CSA G40.20/G40.21, Grade 300W.

- .5 Welding materials: to CSA W59.
- .6 Welding electrodes: to CSA W48 Series.
- .7 Bolts and anchor bolts: to ASTM A325.
- .8 Grout: non-shrink, non-metallic, flowable, 15 MPa at 24 hours.
- .9 Structural aluminum: to 6063-T6 or 6351-T6 alloy, mill finish, unless otherwise noted.

## **2.2 Fabrication**

- .1 Fabricate work square, true, straight and accurate to required size, with joints closely fitted and properly secured.
- .2 Use self-tapping shake-proof round headed screws on items requiring assembly by screws or as indicated.
- .3 Where possible, fit and shop assemble work, ready for erection.
- .4 Ensure exposed welds are continuous for length of each joint. File or grind exposed welds smooth and flush.
- .5 Detailing of connections for members framing into concrete walls shall allow horizontal adjustment of connection angles.

## **2.3 Finishes**

- .1 Galvanizing: hot dipped galvanizing with zinc coating to CAN/CSA-G164.
- .2 Shop coat primer: to CAN/CGSB-1.40.
- .3 Zinc primer: zinc rich, ready mix to CAN/CGSB-1.181 suitable for final finish as specified in Section 09 91 00 – Painting.
- .4 Aluminum: mill finish unless noted.

## **2.4 Isolation Coating**

- .1 Isolate aluminum from following components, by means of bituminous paint:
  - .1 Dissimilar metals except stainless steel, zinc or white bronze of small area.
  - .2 Concrete, mortar and masonry.
  - .3 Wood.
- .2 Paint all aluminum work embedded in or in contact with concrete with two coats of an approved bituminous paint.
- .3 Prevent contact of aluminum and steel by:
  - .1 Coating contact areas with aluminum impregnated caulking compound immediately prior to assembly, or

- .2 Installing a synthetic rubber gasket or nylon washer between aluminum and steel.

## **2.5 Shop Painting**

- .1 Apply one shop coat of primer to metal items, with exception of galvanized or concrete encased items.
- .2 Use primer unadulterated, as prepared by manufacturer. Paint on dry surfaces, free from rust, scale and grease. Do not paint when temperature is lower than 7°C.
- .3 Clean surfaces to be field welded; do not paint.

## **2.6 Angle Lintels**

- .1 Steel angles: sizes as indicated for openings. Provide 150 mm minimum bearing at ends.
- .2 Weld or bolt back-to-back angles to profiles as indicated.
- .3 Finish: galvanized or shop painted as indicated on drawings and schedules.

## **2.7 Aluminum Platform Framing**

- .1 Design platform framing to support minimum live load of 4.8 kPa in addition to dead load of assembly.
- .2 Fabricate platform framing of mill finished structural aluminum sections and to landing sizes indicated on approved shop drawings.
- .3 Provide full fillet welds ground smooth.
- .4 Include aluminum pipe safety posts and chains as indicated on the drawings.
- .5 Fabricate posts of standard weight ANSI Schedule 40 aluminum pipe, 48.3 mm od, mill finish, to height indicated.
- .6 Cap top and bottom of posts with welded aluminum plate of same od as posts, and securely weld posts to face of platform framing.
- .7 Fabricate aluminum safety chains of properly sized links with aluminum or stainless steel snap hooks at one end, and fixed eyes on posts at opposite ends.
- .8 Anchor chains at top of posts and at mid-height above grating level with minimum sag.
- .9 Remove all burrs and sharp edges, grind welds and buff smooth.
- .10 Secure platform rigidly in place using stainless steel anchors in concrete as required to safely accommodate design loadings.

## **2.8 Aluminum Stairs – Grating Treads**

- .1 Supply and install grating type aluminum stairs as indicated on the Drawings.
- .2 Stairs to be open riser type with grating treads, and connections designed to support a minimum uniform live load of 4.8 kPa in addition to dead load of the Work.
- .3 Fabricate stringers from structural aluminum channels. Stringers at landings to form base 100 mm high above finished landing surface. Cap exposed ends of stringers with welded aluminum plate closures. Bolt stringer in place through clip angles.
- .4 Gratings for stair treads and landings: Borden metal Type B, Fisher and Ludlow Series GAL, or Approved Equal in accordance with B7, of pressure locked aluminum construction with serrated bearing bars, mill finish.
- .5 Treads to include grating manufacturer's standard aluminum cast abrasive safety nosings and welded lugs for bolting to stringers. Include safety nosing on landing edges overlooking stairs.
- .6 Nosing to overlap preceding treads by 25 mm.
- .7 All members to be welded or bolted into a rigid, structurally sound unit, all welds ground and buffed smooth.
- .8 Railings to be as specified under "Aluminum Piperails".

## **2.9 Aluminum Angle Framing**

- .1 Provide aluminum angle framing where cast in or bolted to concrete, to support aluminum grating or checker plate in locations shown on the Drawings.
- .2 Angle framing: to size and profile indicated, continuously along perimeter of gratings and checker plate. Assemblies to include:
  - .1 Welded anchors as shown on the Drawings.
  - .2 Mitred and welded corners to form square, level and rigid units with exposed welds ground flush and smooth.
  - .3 Running lengths straight and true without twists or warps. Butt ends square smooth and free of burrs.
  - .4 Aluminum bar welded to horizontal leg of framing angle to provide stop for grating or checker plate.
  - .5 Bituminous coating on sides of frames in contact with concrete.

## **2.10 Aluminum Pipe Rails**

- .1 Supply and install all pipe rails to locations shown on the Drawings. Design pipe rails and anchorage of system to accommodate loadings required by code.
- .2 Fabricate pipe rail of standard weight ANSI Schedule 40 aluminum pipe, 48.3 mm od, mill finish, with intermediate horizontal rails and vertical posts at not more than 1500 mm centres.

- .3 Height of top rail to be 1070 mm above floor or landing level with intermediate rail as detailed.
- .4 At stairs, height of pipe handrails shall be as indicated. Include intermediate rail along open sides of stairs. Provide at least 50 mm clearance between every handrail and any wall to which it is fastened.
- .5 Pipe rails shall be fabricated with all joints neatly and accurately fitted, welded and buffed smooth.
- .6 Provide pipe sleeves welded to anchor plates for side anchored removable railing sections predrilled for fasteners.
- .7 Provide anchor plates welded to posts for side anchored railing sections, predrilled for fasteners.
- .8 Extend posts above railings to 1800 mm above walkway surfaces for mounting of electrical light fixtures and equipment.
- .9 Pipe rails to be installed on aluminum stairs shall have posts welded to stringers or as detailed on the Drawings.

## **2.11 Aluminum Grating**

- .1 Supply and install aluminum grating where indicated on the Drawings.
- .2 Grating: Borden Metal Type B, Fisher and Ludlow Series GAL, or Approved Equal in accordance with B7, of pressure locked aluminum construction with serrated bearing bars, mill finish.
- .3 Design gratings to support minimum live load of 7.2 kPa, with maximum deflection 1/240th of the span.
- .4 Fabricate grating sections to required configurations. Weld continuous aluminum banding to ends of bearing bars, and buff all welds smooth.
- .5 Secure grating sections on supporting frames with aluminum or stainless steel saddle clips and bolts.
- .6 Fabricate hinged sections of gratings to sizes and details indicated. Provide suitable latches to hold hinged grating sections in full open position.
- .7 Where grating sections are intended or indicated to be removable, provide recessed lifting handles and limit area of sections so that individual sections do not weigh more than 30 kg.
- .8 Provide 3 mm diameter stainless steel lifting cables suitably tied to grating covers on sumps where indicated, and anchor other end of cable to stainless steel eye-bolt mounted at required height.
- .9 Install gratings true and level with full bearing on supporting frames, and all grating sections flush and level.

**2.12 Aluminum Checker Plate**

- .1 Supply and install aluminum checkered plate where indicated on the Drawings, and designed to safely withstand live load of 7.2 kPa. Provide access hatches to locations and sizes indicated on the Drawings. Access hatches to have piano hinges, recessed handles, keyed locks and internal aluminum safety grating.
- .2 Fabricate in easily removable sections, not to exceed 30 Kg. with pattern on wearing surface, minimum base metal thickness 5 mm complete with recessed handles.
- .3 Remove all burrs and sharp edges.
- .4 Install checkered plate true and level with minimum 25 mm continuous bearing on horizontal leg of supporting frame.
- .5 Provide maximum 3 mm clearance between edge of checkered plate and bar stops on supporting frame.
- .6 Ensure top of checkered plate is flush with top of bar stops on supporting frames.

**2.13 Aluminum Access Hatch – Exterior**

- .1 Provide exterior type access hatches in sizes and locations shown on the Drawings. Hatch sizes shown on the drawings are hatch clear openings.
- .2 Hatches to be MSU or Contract Administrator approved equal, of aluminum construction, designed to safely withstand a live load of 14.4 kPa. All hatches to be provided with safety grates. Double leaf hatches to be supplied with lift assist.
- .3 Hatch size shown on the drawings are minimum actual clear opening sizes with door in 90° open position. Make necessary allowances for thickness of structurally reinforced doors and frames to determine frame opening dimensions.
- .4 Aluminum to be mill finish with factory applied bituminous coating on sides of frame in contact with concrete.
- .5 Extruded aluminum frame to include anchor flange around perimeter and welded coupling for pipe drain.
- .6 Include welded aluminum brackets on frames for anchoring pump guide bars where indicated on the Drawings.
- .7 Hardware components to be Type 316 stainless steel construction. Each hatch to include cylinder lock with key way protected by threaded cover plug complete with cover plug wrench.
- .8 Installation shall be in accordance with manufacturer's instructions. Include pipe connection for frame drainage.

**2.14 Vehicle Bumper Posts**

- .1 Supply and install vehicle bumper posts where shown on the Drawings.

- .2 Posts shall be fabricated from 200 mm diameter Schedule 80 steel pipe.
- .3 Posts shall be supplied in 2400 mm lengths installed in 600 mm diameter, 25 MPa mass concrete foundations.
- .4 Posts, when in place, shall extend 1200 mm above finished floor or grade level.
- .5 Posts shall be filled solid with 25 MPa concrete and topped with a 6 mm thick steel cap plate welded to post.
- .6 Grind and buff welds to a smooth finish.

## **2.15 CONCRETE ANCHORS**

- .1 For securing metal fabrications to concrete and masonry surfaces, use Hilti "Kwik-Bolt" or Molly "Parabolt" type stainless steel anchors of size and spacing suitable to maintain the design loading requirements for the item.
- .2 For securing equipment bases to concrete pads, use "HVA Adhesive Anchor" of a size and spacing suitable to maintain loading requirements for item being anchored. Anchors shall be stainless steel.

## **Part 3 Execution**

### **3.1 Erection**

- .1 Do welding work in accordance with CSA W59 unless specified otherwise.
- .2 Erect metalwork square, plumb, straight and true, accurately fitted, with tight joints and intersections.
- .3 Provide suitable means of anchorage acceptable to Contract Administrator such as dowels, anchor clips, bar anchors, expansion bolts and shields, and toggles.
- .4 Exposed fastening devices to match finish and be compatible with material through which they pass.
- .5 Provide components for building by other sections in accordance with shop drawings and schedule.
- .6 Make field connections with bolts to CAN/CSA-S16.1, or weld.
- .7 Hand items over for casting into concrete or building into masonry to appropriate trades together with setting templates.
- .8 Touch-up rivets, field welds, bolts and burnt or scratched surfaces after completion of erection with primer.

### **3.2 Cleaning**

- .1 Perform cleaning after installation to remove construction and accumulated environmental dirt.

- .2 Upon completion of installation, remove surplus materials, rubbish, tools and equipment barriers.

**END OF SECTION**

## **PART 1 GENERAL**

### **1.1 RELATED SECTIONS**

- .1 Section 01 33 00 – Submittal Procedures.
- .2 Section 01 45 00 – Quality Control.
- .3 Section 01 61 00 – Common Product Requirements.
- .4 Section 01 74 21 – Construction/Demolition Waste Management and Disposal.
- .5 Section 05 50 00 – Metal Fabrications.

### **1.2 REFERENCES**

- .1 Canadian Standards Association (CSA International)
  - .1 CSA B111-1974(R1998), Wire Nails, Spikes and Staples.
  - .2 CAN/CSA-G164-M92 (R1998), Hot Dip Galvanizing of Irregularly Shaped Articles.
  - .3 CAN/CSA-O141-91(R1999), Softwood Lumber.
  - .4 CSA O151-M1978 (R1998), Canadian Softwood Plywood.
- .2 National Lumber Grades Authority (NLGA)
  - .1 Standard Grading Rules for Canadian Lumber 2000.

### **1.3 QUALITY ASSURANCE**

- .1 Lumber identification: by grade stamp of an agency certified by Canadian Lumber Standards Accreditation Board.
- .2 Plywood identification: by grade mark in accordance with applicable CSA standards.

### **1.4 WASTE MANAGEMENT AND DISPOSAL**

- .1 Separate and recycle waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .3 Collect and separate for disposal paper, plastic, polystyrene, corrugated cardboard, and packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan.
- .4 Divert unused wood materials from landfill to approved facility.
- .5 Do not dispose of preservative treated wood through incineration.
- .6 Do not dispose of preservative treated wood with materials destined for recycling or reuse.
- .7 Dispose of treated wood, end pieces, wood scraps and sawdust at approved sanitary.

- .8 Dispose of unused wood preservative material at official, approved hazardous material collections site.
- .9 Do not dispose of unused preservative material into sewer system, into streams, lakes, onto ground or in other locations where they will pose health or environmental hazard.

## **PART 2 PRODUCTS**

### **2.1 LUMBER MATERIAL**

- .1 Lumber: unless specified otherwise, softwood, S4S, moisture content 19% or less in accordance with following standards:
  - .1 CAN/CSA-O141.
  - .2 NLGA Standard Grading Rules for Canadian Lumber.
- .2 Furring, blocking, nailing strips and fascia backing:
  - .1 Board sizes: "Standard" or better grade.
  - .2 Dimension sizes: "Standard" light framing or better grade.

### **2.2 PANEL MATERIALS**

- .1 Canadian softwood plywood (CSP): to CSA O151, standard construction.

### **2.3 ACCESSORIES**

- .1 Nails, spikes and staples: to CSA B111, hot dipped galvanized.
- .2 Bolts: 12.5 mm diameter unless indicated otherwise, complete with nuts and washers.
- .3 Proprietary fasteners: toggle bolts, expansion shields and lag bolts, screws and lead or inorganic fibre plugs, explosive actuated fastening devices, recommended for purpose by manufacturer.
- .4 All interior fasteners to be type 304 stainless steel.

### **2.4 WOOD PRESERVATIVE**

- .1 Surface-applied wood preservative: copper naphthenate or 5% pentachlorophenol solution, water repellent preservative.
- .2 Pentachlorophenol use is restricted to building components that are in ground contact and subject to decay or insect attack only. Where used, pentachlorophenol-treated wood must be covered with two coats of an appropriate sealer.
- .3 Structures built with wood treated with pentachlorophenol and inorganic arsenicals must not be used for storing food nor should the wood come in contact with drinking water.

## **PART 3 EXECUTION**

### **3.1 PREPARATION**

- .1 Treat surfaces of material with wood preservative, before installation.

- .2 Apply preservative by dipping, or by brush to completely saturate and maintain wet film on surface for minimum three (3) minute soak on lumber and one (1) minute soak on plywood.
- .3 Re treat surfaces exposed by cutting, trimming or boring with liberal brush application of preservative before installation.
- .4 Treat material as indicated and as follows:
  - .1 Curbs, nailers, sleepers on roof deck and parapets.
  - .2 Wood furring within outside surface of exterior masonry and concrete walls.
  - .3 All wood in contact with unfinished concrete or masonry.

### **3.2 INSTALLATION**

- .1 Install furring and blocking as required to space-out and support fascia, soffit, siding and other work as required.
- .2 Align and plumb faces of furring and blocking to tolerance of 1:600.
- .3 Install rough bucks, nailers and linings to rough openings as required to provide backing for frames and other work.
- .4 Install fascia backing and nailers, and other wood supports as required and secure using galvanized steel fasteners.
- .5 Use caution when working with particle board. Use dust collectors and high quality respirator masks.
- .6 Sheathing:
  - .1 Install plywood sheathing with surface grain at right angles to roof framing, and in accordance with requirement of the National Building Code, and to the plywood manufacturer's recommendations.

### **3.3 ERECTION**

- .1 Frame, anchor, fasten, tie and brace members to provide necessary strength and rigidity.
- .2 Countersink bolts where necessary to provide clearance for other work.

### **3.4 SCHEDULES**

- .1 Provide electrical equipment backboards for mounting electrical and telecommunications/data equipment as indicated.
- .2 Use 19 mm thick fire retardant treated plywood on 19 x 38 mm furring spaced at maximum 300 mm centres and at vertical edges of mounting board.

**END OF SECTION**

## **PART 1 GENERAL**

### **1.1 SCOPE**

- .1 This Section describes the requirements for rigid insulation to be applied below concrete slabs on grade, against perimeter foundation walls, and as perimeter foundation skirting where indicated on the drawings.

### **1.2 REFERENCES**

- .1 American Society for Testing and Materials International (ASTM)
  - .1 ASTM E96/E96M-05, Standard Test Methods for Water Vapour Transmission of Materials.
- .2 Canadian General Standards Board (CGSB)
  - .1 CGSB 71-GP-24M-77 (R1983), Adhesive, Flexible, for Bonding Cellular polystyrene Insulation.
- .3 Underwriters Laboratories of Canada (ULC)
  - .1 CAN/ULC-S701-05, Standard for Thermal Insulation, Polystyrene, Boards and Pipe Coverings.
  - .2 CAN/ULC-S702-97, Standard for Thermal Insulation, Mineral Fibre, for Buildings.
- .4 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
  - .1 Material Safety Data Sheets (MSDS).

### **1.3 SUBMITTALS**

- .1 Product Data:
  - .1 Submit manufacturer's printed product literature, specifications and data sheet in accordance with Section 01 33 00 - Submittal Procedures.
  - .2 Submit two copies of WHMIS MSDS - Material Safety Data Sheets in accordance with Section 01 33 00 - Submittal Procedures. Indicate VOC's insulation products and adhesives.
- .2 Manufacturer's Instructions:
  - .1 Submit manufacturer's installation instructions.

### **1.4 WASTE MANAGEMENT AND DISPOSAL**

- .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .3 Collect and separate for disposal paper plastic polystyrene corrugated cardboard packaging material in appropriate on-site for recycling in accordance with Waste Management Plan.

## **PART 2 PRODUCTS**

### **2.1 INSULATION**

- .1 Rigid Insulation: Styrofoam HIGHLOAD by Dow Chemical Canada Inc., or approved equal, extruded closed cell polystyrene to ASTM C578 Type 6.
- .2 Provide in total thickness and depth as shown on the drawings.

### **2.2 ADHESIVE**

- .1 Adhesive (for polystyrene): to CGSB 71-GP-24, compatible with specified insulation.

## **PART 3 EXECUTION**

### **3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written data, including product technical bulletins, product catalogue installation instructions, product carton installation instructions, and data sheets.

### **3.2 WORKMANSHIP**

- .1 Install insulation after building substrate materials are dry.
- .2 Install insulation to maintain continuity of thermal protection to building elements and spaces.
- .3 Fit insulation tight around electrical boxes, plumbing and heating pipes and ducts, around exterior doors and windows and other protrusions.
- .4 Keep insulation minimum 75 mm from heat emitting devices.
- .5 Cut and trim insulation neatly to fit spaces. Butt joints tightly, offset vertical joints. Use only insulation boards free from chipped or broken edges. Use largest possible dimensions to reduce number of joints.
- .6 Offset both vertical and horizontal joints in multiple layer applications.
- .7 Do not enclose insulation until it has been inspected and approved by ~~Consultant~~Contract Administrator.

### **3.3 EXAMINATION**

- .1 Examine substrates and immediately inform ~~Consultant~~Contract Administrator in writing of defects.
- .2 Prior to commencement of work ensure:

- .1 Substrates are firm, straight, smooth, dry, free of snow, ice or frost, and clean of dust and debris.

### **3.4 RIGID INSULATION INSTALLATION**

- .1 Apply adhesive to substrate in accordance with manufacturer's recommendations.
- .2 At below grade locations on concrete walls against soil, imbed insulation boards in spots of adhesive sufficient to hold them in place until backfilled.

### **3.5 CLEANING**

- .1 Upon completion of installation, remove surplus materials, rubbish, tools and equipment barriers.

**END OF SECTION**

**Part 1        General**

**1.1            SCOPE**

- .1        This section describes the requirements for blanket insulation applied to inside walls and attic space.

**1.2            REFERENCES**

- .1        National Building Code of Canada (NBC).
- .2        American Society for Testing and Materials International (ASTM)
  - .1        ASTM C553-02, Specification for Mineral Fibre Blanket Thermal Insulation for Commercial and Industrial Applications.
  - .2        ASTM C665-01e1, Specification for Mineral-Fiber Blanket Thermal Insulation for Light Frame Construction and Manufactured Housing.
- .3        Canadian Standards Association (CSA International)
  - .1        CSA B111-1974(R2003), Wire Nails, Spikes and Staples.
- .4        Underwriters Laboratories of Canada (ULC)
  - .1        CAN/ULC-S702-1997, Standard for Mineral Fibre Insulation.

**1.3            SUBMITTALS**

- .1        Product Data:
  - .1        Submit manufacturer's printed product literature, specifications and data sheet in accordance with Section 01 33 00 - Submittal Procedures.
- .2        Manufacturer's Instructions:
  - .1        Submit manufacturer's installation instructions.

**1.4            WASTE MANAGEMENT AND DISPOSAL**

- .1        Separate waste materials for reuse and recycling in accordance with Section 01 33 00 Environmental Procedures.
- .2        Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .3        Collect and separate for disposal paper plastic polystyrene corrugated cardboard packaging material in appropriate on-site for recycling in accordance with Waste Management Plan.

**Part 2        Products**

**2.1            INSULATION**

- .1        Batt and blanket mineral fibre: to ASTM C665 and CAN/ULC S702.

- .1 Type: Owens Corning Pink Fibre glass or approved equal in accordance with B7.
- .2 Thickness: 140 mm providing total insulation value RSI 3.52 (R20), or to fill cavities as indicated on drawings.
- .3 Thickness: providing total insulation value RSI 7.04 (R40) to attic space.

## **2.2 ACCESSORIES**

- .1 Type: as recommended by manufacturer.

## **Part 3 Execution**

### **3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written data, including product technical bulletins, product catalogue installation instructions, product carton installation instructions, and data sheets.

### **3.2 INSULATION INSTALLATION**

- .1 Install insulation to maintain continuity of thermal protection to building elements and spaces and to ASTM C1320.
- .2 Fit insulation closely around electrical boxes, pipes, ducts, frames and other objects in or passing through insulation.
- .3 Do not compress insulation to fit into spaces.
- .4 Keep insulation minimum 75 mm from heat emitting devices such as recessed light fixtures, and minimum 50 mm from sidewalls of chimneys and Type B vents.
- .5 Do not enclose insulation until it has been inspected and approved by Consultant.

### **3.3 CLEANING**

- .1 Upon completion of installation, remove surplus materials, rubbish, tools and equipment barriers.

**END OF SECTION**

## **PART 1 GENERAL**

### **1.1 RELATED SECTIONS**

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

### **1.2 REFERENCES**

- .1 Canadian Urethane Foam Contractors' Association Inc. (CUFCA)
- .2 Underwriters' Laboratories of Canada (ULC)
  - .1 CAN/ULC-S101-1989, Fire Endurance Tests of Building Construction and Materials.
  - .2 CAN/ULC-S102-1988 (R2000), Surface Burning Characteristics of Building Materials and Assemblies.
  - .3 CAN/ULC-S705.1-01, Standard for Thermal Insulation Spray Applied Rigid Foam, Medium Density, Material Specification.
  - .4 CAN/ULC-S705.2-02, Standard for Thermal Insulation Spray Applied Rigid Foam, Medium Density, Installer's Responsibilities-Specification.

### **1.3 SUBMITTALS**

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
  - .1 Submit manufacturer's printed product literature, specifications and datasheet and include:
    - .1 Product characteristics.
    - .2 Performance criteria.
    - .3 Limitations.
  - .3 Submit two (2) copies of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS).

### **1.4 TEST REPORTS**

- .1 Submit test reports, verifying qualities of insulation meet or exceed requirements of this specification.
- .2 Submit test reports in accordance with CAN/ULC-S101 for fire endurance and CAN/ULC-S102 for surface burning characteristics.

### **1.5 QUALITY ASSURANCE**

- .1 Applicators to conform to CUFCA Quality Assurance Program.

## **1.6 SAFETY REQUIREMENTS**

- .1 Protect workers as recommended by CAN/ULC-S705.2 and manufacturer's recommendations:
  - .1 Workers must wear gloves respirators dust masks long sleeved clothing eye protection protective clothing when applying foam insulation.
  - .2 Workers must not eat, drink or smoke while applying foam insulation.

## **1.7 PROTECTION**

- .1 Provide temporary enclosures to prevent spray and noxious vapours from contaminating air beyond application area.
- .2 Protect adjacent surfaces and equipment from damage by overspray, fall-out, and dusting of insulation materials.

## **1.8 WASTE MANAGEMENT AND DISPOSAL**

- .1 Separate and recycle waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .2 Remove from site and dispose of all packaging materials at appropriate recycling facilities.
- .3 Dispose of waste foam daily in location approved by Contract Administrator and decontaminate empty drums in accordance with foam manufacturer's instructions CAN/ULC-S705.2.
- .4 Divert metal drums from landfill to metal recycling facility as approved by Contact Administrator and to CAN/ULC-S705.2.

## **1.9 ENVIRONMENTAL REQUIREMENTS**

- .1 Apply insulation only when surfaces and ambient temperatures are within manufacturers' prescribed limits.

## **1.10 SURFACE PREPARATION**

- .1 Surfaces must be clean and dry, as required by CAN/ULC-S705.2-98. The substrate must be free of all frost, dust, oil, grease, oxidization, or any other element that may affect adhesion of the system i.e. high moisture content.
- .2 Metallic surfaces should be checked to ensure no oxidization has occurred.
- .3 All transition membranes must be installed prior to application of the polyurethane foam. These membranes must be installed in accordance with the manufacturer's recommendations. Adhesion of the membranes to the substrate must be sufficient to resist the stress applied by the polyurethane foam during the curing time.
- .4 All of the following stages must be completed prior to application of the insulating / air barrier system:

- .1 Installation of masonry anchoring system
- .2 Installation of wood blocking required at all openings
- .3 Installation of any electrical or mechanical penetrations
- .4 Adjacent areas have been protected via drop sheets or polyethylene masking

## **PART 2 PRODUCTS**

### **2.1 MATERIALS**

- .1 Acceptable products:
  - .1 Insulation: 'Walltite', spray polyurethane to CAN/ULC-S705.1.
  - .2 Contract Administrator approved equal in accordance with .
  - .3 Primers: in accordance with manufacturer's recommendations for surface conditions.
  - .4 Transition membranes: Bakor Blueskin 4 mil (1mm) thick self adhering EPDM mebrane

### **2.2 ACCEPTABLE SOURCES**

- .1 Manufacturers of Foam-in-Place Insulations having comparable products conforming to the requirements of this Section, considered acceptable for use:
  - .1 BASF - The Chemical Company
  - .2 Contract Administrator approved equal, in accordance with B7.

## **PART 3 EXECUTION**

### **3.1 APPLICATION**

- .1 Apply insulation to clean surfaces in accordance with CAN/ULC-S705.2 and manufacturer's printed instructions. Use primer where recommended by manufacturer.
- .2 Apply sprayed foam insulation in uniform minimum thickness of 50 mm with minimum aged thermal resistance value of 1.05RSI per 25mm. (R6 per inch).
- .3 All excessively wide joints should be covered or filled before applying the polyurethane foam.
- .4 Polyurethane foam to be sprayed as per the Standard CAN/ULC-S705.2 with a tolerance of +6 /-0 mm in relation to the specified thickness, functioning as an effective and continuous air and vapour barrier.
- .5 Avoid the formation of sub-layer air pockets when applying.
- .6 Avoid spraying the foam on any surfaces other than those indicated. Use drop sheets or masking tape to protect other surfaces.
- .7 Once the foam has hardened, remove all overspray from non-prescribed surfaces.

- .8 Do not allow polyurethane foam once applied, to be damaged during work by other trades.
- .9 Ensure the subsequent coverage of the applied insulating foam will be completed within the manufacturer's prescribed time frame.
- .10 Spray the polyurethane foam in overlapping layers, so as to obtain a smooth, uniform surface.
- .11 Do not spray polyurethane foam any closer than 75 mm from chimneys, heating vents, steam pipes, recessed lighting fixtures, and other heat sources. Do not spray the interior of any exit openings or electrical junction boxes.
- .12 All mechanical fixtures should be covered with polyurethane foam in order to reduce thermal bridging.

### **3.2 CLEANING**

- .1 Upon completion of installation, remove surplus materials, rubbish, tools and equipment barriers.

**END OF SECTION**

**Part 1      General**

**1.1          SCOPE**

- .1      The scope of this section generally includes but not limited to:
  - .1      Underlayment.
  - .2      Roof panel clip system.
  - .3      Roof panel.
  - .4      Accessories including associated flashings, closures, sealants.

**1.2          RELATED SECTIONS**

- .1      Section 013300 – Submittal Procedures.

**1.3          REFERENCES**

- .1      Design of cladding system in accordance to the latest edition of:
  - .1      CSA-S136 for the design of Cold Formed Steel Structural Members
  - .2      Canadian Sheet Steel Building Institute Standards 10M and 20M
  - .3      National Building Code of Canada.
- .2      The Aluminum Association Inc. (AA)
  - .1      Aluminum Sheet Metal Work in Building Construction-2000.
  - .2      AA DAF45-97, Designation System for Aluminum Finishes.
- .3      American Society for Testing and Materials (ASTM International)
  - .1      ASTM A606-01, Standard Specification for Steel, Sheet and Strip, High-Strength, Low-Alloy, Hot-Rolled and Cold-Rolled, with Improved Atmospheric Corrosion Resistance.
  - .2      ASTM A653/A653M-01a, Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
  - .3      ASTM A792/A792M-02, Standard Specification for Steel Sheet, 55% Aluminum-Zinc Alloy-Coated by the Hot-Dip Process.
  - .4      ASTM D523-89 (1999), Standard Test Method for Specular Gloss.
  - .5      ASTM D822-01, Standard Practice for Filtered Open-Flame Carbon-Arc Exposures of Paint and Related Coatings.
- .4      Canadian Roofing Contractors Association (CRCA)
  - .1      Roofing Specifications Manual 1997.
- .5      Canadian General Standards Board (CGSB)
  - .1      CAN/CGSB-19.13-M87, sealing compound, one component, silicone base, chemical curing.

- .2 CAN/CGSB-19.24-M90, sealing compound, multi-component, chemical curing.
- .3 CAN/CGSB-37.5-M89, Cutback Asphalt Plastic Cement.
- .4 CAN/CGSB-51.32-M77, Sheathing, Membrane, Breather Type.
- .5 CAN/CGSB-93.1-M85, Sheet Aluminum Alloy, Prefinished, Residential.
- .6 Canadian Standards Association (CSA International)
  - .1 CSA A123.3-98, Asphalt Saturated Organic Roofing Felt.
  - .2 CSA B111-1974 (R1998), Wire Nails, Spikes and Staples.

### **1.5 DESIGN REQUIREMENTS**

- .1 Design roof system to resist
  - .1 Snow loads and snow build-up and rain load, expected in this geographical region OBC climatic data, 50 year probability.
  - .2 Wind loads, positive and negative, expected in this geographical region climatic data, 50 year probability.
  - .3 Dead load of roof system.
- .2 Deflection of the roof system is not to exceed  $1/180^{\text{th}}$  of the span for the specified live loading.
- .3 Thermal Movements: Allow for thermal movements from ambient and surface temperature changes by preventing buckling, overstressing of components, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and night-time sky heat loss.
  - .1 Temperature Change (Range): 20 deg C, ambient; 40 deg C, material surfaces

### **1.4 SAMPLES**

- .1 Submit samples of standard coloured metal roof for review by the contract Administrator, prior to fabrication.

### **1.5 SHOP DRAWINGS**

- .1 Submit shop drawings in accordance with Section E3.
  - .1 Indicate arrangement of pre-finished Roof Sheet, including joints, types and locations of supports, fasteners, flashing, gutters, mitres, and all metal components related to the roof installation. Include for underlayment as part of the roof system.
  - .2 Drawings shall be signed and sealed by a Contract Administrator, attesting to the ability of the metal panel's assembly to withstand the specified loads.

### **1.6 PRODUCT DELIVERY, HANDLING AND STORAGE**

- .1 Store components and materials in accordance with panel manufacturer's recommendations and protect from elements.
- .2 Protect prefinished steel during fabrication, transportation, site storage and erection, in accordance with CSSBI Standards.

## **1.7 GUARANTEE**

- .1 For the work in this section, warranty by installer against defects or deficiencies in materials or workmanship shall be for a period of one year from date of substantial completion.

## **Part 2 Products**

### **2.1 ROOF SYSTEM COMPONENTS**

- .1 Roof System: Tradition100-4 on Solid Substrate by Vicwest.
  - .1 Underlayment: Membrane shall be Ice and Water Shield by W.R. Grace or an approved equal.
- .2 Clip System
  - .1 Thermally responsive clips to be fabricated from a minimum of 0.91 mm (.036") steel, with minimum Z275 galvanized coating designed to accommodate expansion and contraction of the roof sheet.
  - .2 Roof Fasteners: As specified by manufacturer, to resist wind uplift and sliding snow forces.
- .3 Prefinished Roof Sheet, exposed to exterior.
  - .1 Profile: Tradition 100-4, with I-style ribs at 400 mm spacing.
  - .2 Panel: Z275 galvanized (zinc coated) sheet steel conforming to ASTM A653M structural quality Grade 230 having a nominal core thickness 0.76 mm (0.030").
- .4 Snap Cap
  - .1 Provide 25 mm high snap caps for full length of the roof panel and retained by panel clips, fabricated from Z275 galvanized (zinc coated) sheet steel conforming to ASTM A653M structural quality Grade 230 having a minimum nominal core thickness 0.61mm (0.024"). Finish and colour to match roof sheet.

### **2.2 PANEL FINISHES**

- .1 Coating: Prepainted with WeatherX™ on interior face

### **2.3 COLOUR**

- .1 Colour to be selected from the manufacturer's standard colour range.

## **2.4 ACCESSORIES**

- .1 Flashing: Formed from same materials as the roof sheet. Custom fabricated to suit architectural details, as required.
- .2 Closures: Foam and metal closures to suit profiles selected, to manufacturer's recommendations.
- .3 Sealants: In accordance with manufacturer's recommendation and Section 07900.
- .4 Ventilated ridge cap: prefinished, brake formed, purpose made flashing to provide continuous air vent, incorporating drip edge, snow baffle, and mesh material to allow unrestricted venting of attic space while preventing insect, rain and snow from entering. Colour and finish to match roofing.
- .5 Snow fence: Continuous double bar snow fence supported on zinc die cast metal brackets. Rails formed of swaged galvalume tubes connected with concealed joiners and pinned. Brackets secured with stainless steel screws through neoprene washers through the roofing material into solid wood blocking.

## **2.5 FABRICATION**

- .1 Fabricate roof components to comply with dimensions, profiles, gauges and details as shown on the shop drawings, including fascia and soffit panels and all companion flashing.
- .2 Fabricate all components of the system in the factory, ready for field installation.
- .3 Provide roof sheet and all accessories in longest practicable length to minimize field lapping of joints.

## **Part 3 Execution**

### **3.1 EXAMINATION**

- .1 Examine work of other Sections upon which work of this Section depends.
- .2 Report all discrepancies to Contract Administrator before beginning work on the roof system.

### **3.2 INSTALLATION**

- .1 Roof Materials:
  - .1 Underlayment: Install underlayment fully adhered to solid substrate according to manufacturer's recommendations. Ensure all joints are properly lapped and sealed. Tie in with barriers on adjacent surfaces to ensure airtight construction. Provide a continuous seal around all openings in the insulated metal roof system.

- .2 Clip: Attach Tradition clips using fasteners as recommended by the manufacturer, to suit the substrate.
- .2 Roof Panel Installation
  - .1 Install exterior prefinished roof panels on panel support clips, using manufacturer's proper construction procedure. Ensure metal roofing sheet side-lap is positively retained by clips, and proper sheet coverage is maintained.
  - .2 Install the snap-cap at all side laps as shown on the approved shop drawings. Mitre snap-cap as required to resist water entry.
  - .3 Where indicated on approved shop drawings, secure the end-lap of metal roofing sheets in accordance with the manufacturer's specifications and details to provide a weather-tight seal. Exposed fasteners to match colour of the roof sheet.
  - .4 Provide notched and formed closures, sealed against weather penetration, at changes in pitch, and at ridges and eaves, where required.
  - .5 Install all companion flashing, gutters, ventilators as shown on the shop drawings. Use concealed fasteners when possible. Exposed fasteners to match colour of roof sheet.

### **3.3 CLEAN-UP**

- .1 Clean exposed panel surfaces in accordance with manufacturer's instructions.
- .2 Repair and touch up with colour matching high grade enamel minor surface damage, only where permitted by the Architect and only where appearance after touch-up is acceptable to Architect.
- .3 Replace damaged panels and components that, in opinion of the Architect, cannot be satisfactorily repaired.

**END OF SECTION**

**Part 1        General**

**1.1        SCOPE**

- .1        The scope of this section generally includes but is not limited to:
  - .1        Pre finished metal siding and trim.
  - .2        Metal flashing at roofing perimeter and wall penetrations, openings.

**1.2        RELATED SECTIONS**

- .1        Section 01 33 00 – Submittal Procedures.

**1.3        REFERENCES**

- .1        National Building Code of Canada (NBC).
- .2        The Aluminum Association Inc. (AA)
  - .1        Aluminum Sheet Metal Work in Building Construction-2000.
  - .2        AA DAF45-97, Designation System for Aluminum Finishes.
- .3        American Society for Testing and Materials (ASTM International)
  - .1        ASTM A606-01, Standard Specification for Steel, Sheet and Strip, High-Strength, Low-Alloy, Hot-Rolled and Cold-Rolled, with Improved Atmospheric Corrosion Resistance.
  - .2        ASTM A653/A653M-01a, Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
  - .3        ASTM A792/A792M-02, Standard Specification for Steel Sheet, 55% Aluminum-Zinc Alloy-Coated by the Hot-Dip Process.
  - .4        ASTM D523-89(1999), Standard Test Method for Specular Gloss.
  - .5        ASTM D822-01, Standard Practice for Filtered Open-Flame Carbon-Arc Exposures of Paint and Related Coatings.
- .4        Canadian Roofing Contractors Association (CRCA)
  - .1        Roofing Specifications Manual 1997.
- .5        Canadian General Standards Board (CGSB)
  - .1        CAN/CGSB-19.13-M87, sealing compound, one component, silicone base, chemical curing.
  - .2        CAN/CGSB-19.24-M90, sealing compound, multi-component, chemical curing.
  - .3        CAN/CGSB-37.5-M89, Cutback Asphalt Plastic Cement.
  - .4        CAN/CGSB-51.32-M77, Sheathing, Membrane, Breather Type.
  - .5        CAN/CGSB-93.1-M85, Sheet Aluminum Alloy, Prefinished, Residential.
- .6        Canadian Standards Association (CSA International)
  - .1        CSA A123.3-98, Asphalt Saturated Organic Roofing Felt.

- .2 CSA B111-1974(R1998), Wire Nails, Spikes and Staples.

**1.4 SAMPLES**

- .1 Submit duplicate 50 mm x 50 mm samples of each type of sheet metal material, colour and finish.

**1.5 WASTE MANAGEMENT AND DISPOSAL**

- .1 Separate and recycle waste materials in accordance with Section 01 35 43 – Environmental Procedures.
- .2 Remove from site and dispose of all packaging materials at appropriate recycling facilities.
- .3 Collect and separate for disposal paper plastic polystyrene corrugated cardboard packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan.
- .4 Place materials defined as hazardous or toxic in designated containers.
- .5 Ensure emptied containers are sealed and stored safely for disposal away from children.
- .6 Divert unused metal materials from landfill to metal recycling facility as approved by Contract Administrator, in accordance with B7.
- .7 Unused paint and sealant material must be disposed of at an official hazardous material collections site as approved by Contract Administrator.
- .8 Unused paint and sealant material must not be disposed of into sewer system, into streams, lakes, onto ground or in other location where it will pose health or environmental hazard.
- .9 Fold up metal banding, flatten and place in designated area for recycling.

**Part 2 Products**

**2.1 PRE FINISHED METAL SIDING**

- .1 Zinc coated steel sheet: commercial quality to ASTM A653/A653M, grade 50, with Z275 designation zinc coating.
- .2 Exterior side prefinished with WeatherX™ Silicone modified polyester paint system by Valspar with direct from manufacturer 40 year warranty against paint defects and 30 years for fade resistance.
- .3 Interior side protected by wash coat of primer.
- .4 Product: VicWest or approved equal in accordance with B7.
- .5 Profile: 24 gauge CL 6025-SR, 36 mm deep, 900 mm wide.

- .6 Factory applied sealant in interlocking side lap joints to provide weathertight installation.

## **2.2 SHEET METAL MATERIALS**

- .1 Zinc coated steel sheet: commercial quality to ASTM A653/A653M, with Z275 designation zinc coating.

## **2.3 PREFINISHED STEEL SHEET**

- .1 Prefinished steel with factory applied silicone modified polyester paint system.
  - .1 Class F1S.
  - .2 Colour selected by Contract Administrator from manufacturer's standard range.
  - .3 Specular gloss: 30 units +/- in accordance with ASTM D523.
  - .4 Coating thickness: not less than 22 micrometres.

## **2.4 ACCESSORIES**

- .1 Isolation coating: alkali resistant bituminous paint.
- .2 Plastic cement: to CAN/CGSB 37.5.
- .3 Underlay for metal flashing: No. 15 perforated asphalt felt to CSA A123.3.
- .4 Sealants: Multi-component conforming to CGSB Specification CAN/CGSB-19.24, or single component conforming to CGSB Specification CAN/CGSB-19.13.
  - .1 Acceptable products:
    - .1 Dymeric by Tremco (Canada) Limited.
    - .2 Proglaze by Tremco (Canada) Ltd.
    - .3 1200 Sealant by CGE Canada Ltd.
    - .4 795 Sealant by Dow Corning Canada.
    - .5 Contract Administrator approved equal in accordance with B7.
- .5 Cleats: of same material, and temper as sheet metal, minimum 50 mm wide. Thickness, same as sheet metal being secured.
- .6 Fasteners: of same material as sheet metal, to CSA B111, ring thread flat head roofing nails of length and thickness suitable for metal flashing application.
- .7 Washers: of same material as sheet metal, 1 mm thick with rubber packings.
- .8 Touch-up paint: as recommended by prefinished material manufacturer.

## **2.5 FABRICATION**

- .1 Fabricate metal flashings and other sheet metal work in accordance with applicable CRCA 'FL' series details.
- .2 Form pieces in 2400 mm maximum lengths. Make allowance for expansion at joints.

- .3 Hem exposed edges on underside 12 mm. Mitre and seal corners with sealant.
- .4 Form sections square, true and accurate to size, free from distortion and other defects detrimental to appearance or performance.
- .5 Apply isolation coating to metal surfaces to be embedded in concrete or mortar.

## **2.6 METAL FLASHINGS**

- .1 Form flashings, copings and fascias to profiles indicated of 26 ga thick prefinished aluminum or prefinished galvanized steel.

## **2.7 CAP FLASHINGS**

- .1 Form metal cap flashing of 26 ga mm thick sheet metal as detailed and in accordance with CRCA FL series details. Provide slotted fixing holes and plastic washer fasteners.

## **2.8 EAVES TROUGHS and DOWNSPOUTS**

- .1 Formed from prefinished 22 gauge metal.
- .2 Secure to building with metal strap.

## **Part 3 Execution**

### **3.1 INSTALLATION**

- .1 Provide and install pre-finished metal siding materials, flashings at openings, and trim shapes as indicated in approved shop drawings.
- .2 Avoid end laps in vertical sections.
- .3 Install sheet metal work in accordance with CRCA FL series details.
- .4 Use concealed fastenings except where approved before installation.
- .5 Provide underlay under sheet metal. Secure in place and lap joints 100 mm.
- .6 Counterflash bituminous flashings at intersections of roof with vertical surfaces and curbs. Flash joints using S-lock forming tight fit over hook strips, as detailed.
- .7 Lock end joints and caulk with sealant.
- .8 Install surface mounted reglets true and level, and caulk top of reglet with sealant.
- .9 Insert metal flashing under cap flashing to form weather tight junction.
- .10 Turn top edge of flashing into recessed reglet or mortar joint minimum of 25 mm. Lead wedge flashing securely into joint.
- .11 Caulk flashing at cap flashing with sealant.

**3.2 EAVES TROUGHS AND DOWNPIPES**

- .1 Install eaves troughs and secure to building at 1220 mm on centre with galvanized metal straps.
- .2 Slope eaves troughs to down pipes.
- .3 Seal joints watertight.

**END OF SECTION**

## **PART 1 GENERAL**

### **1.1 SECTION INCLUDES**

- .1 Materials, preparation and application for caulking and sealants.
- .2 Text to complete other various Sections containing sealant or caulking specifications, including:
  - .1 Section 07 52 00 - Modified Bituminous Membrane Roofing.

### **1.2 RELATED SECTIONS**

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 45 00 - Quality Control.
- .3 Section 01 61 00 - Common Product Requirements.
- .4 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

### **1.3 REFERENCES**

- .1 American Society for Testing and Materials International, (ASTM)
  - .1 ASTM C919-02, Standard Practice for Use of Sealants in Acoustical Applications.
- .2 Canadian General Standards Board (CGSB)
  - .1 CGSB 19-GP-5M-1984, Sealing Compound, One Component, Acrylic Base, Solvent Curing (Issue of 1976 reaffirmed, incorporating Amendment No.1).
  - .2 CAN/CGSB-19.13-M87, Sealing Compound, One-component, Elastomeric, Chemical Curing.
  - .3 CGSB-19-GP-14M-1984, Sealing Compound, One Component, Butyl-Polyisobutylene Polymer Base, Solvent Curing (Reaffirmation of April 1976).
  - .4 CAN/CGSB-19.17-M90, One-Component Acrylic Emulsion Base Sealing Compound.
  - .5 CAN/CGSB-19.24-M90, Multi-component, Chemical Curing Sealing Compound, Type 2, Class B.
- .3 Department of Justice Canada (Jus)
  - .1 Canadian Environmental Protection Act, 1999 (CEPA).
- .4 General Services Administration (GSA) - Federal Specifications (FS)
  - .1 FS-SS-S-200-E (2)1993, Sealants, Joint, Two-Component, Jet-Blast-Resistant, Cold Applied, for Portland Cement Concrete Pavement.
- .5 Health Canada/Workplace Hazardous Materials Information System (WHMIS)

- .1 Material Safety Data Sheets (MSDS).

#### **1.4 SUBMITTALS**

- .1 Submit product data in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Manufacturer's product to describe.
  - .1 Caulking compound.
  - .2 Primers.
  - .3 Sealing compound, each type, including compatibility when different sealants are in contact with each other.
- .3 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
- .4 Submit duplicate samples of each type of material and colour.
- .5 Cured samples of exposed sealants for each color where required to match adjacent material.
- .6 Submit manufacturer's instructions in accordance with Section 01 33 00 - Submittal Procedures.
  - .1 Instructions to include installation instructions for each product used.

#### **1.5 QUALITY ASSURANCE**

- .1 Carry out the supply and installation of sealants and caulking work by recognized Specialist Applicators having at least five (5) years of proven satisfactory experience and having skilled workmen thoroughly trained and competent in all phases of caulking work.

#### **1.6 DELIVERY, STORAGE, AND HANDLING**

- .1 Deliver, handle, store and protect materials in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver and store materials in original wrappings and containers with manufacturer's seals and labels, intact. Protect from freezing, moisture, water and contact with ground or floor.
- .3 Store materials in dry location in such manner that no damage will be done to materials or building.

#### **1.7 WASTE MANAGEMENT AND DISPOSAL**

- .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.

- .3 Collect and separate for disposal paper, plastic, polystyrene and corrugated cardboard packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan.
- .4 Place materials defined as hazardous or toxic in designated containers.
- .5 Handle and dispose of hazardous materials in accordance with the CEPA, TDGA, Regional and Municipal regulations.
- .6 Unused sealant material must not be disposed of into sewer system, into streams, lakes, onto ground or in other location where it will pose health or environmental hazard.
- .7 Divert unused joint sealing material from landfill to an approved, official hazardous material collections site.
- .8 Empty plastic joint sealer containers are not recyclable. Do not dispose of empty containers with plastic materials destined for recycling.
- .9 Fold up metal banding, flatten, and place in designated area for recycling.

## **1.8 PROJECT CONDITIONS**

- .1 Environmental Limitations:
  - .1 Do not proceed with installation of joint sealants under following conditions:
    - .1 When ambient and substrate temperature conditions are outside limits permitted by joint sealant manufacturer or are below 4.4 degrees C.
    - .2 When joint substrates are wet.
- .2 Joint-Width Conditions:
  - .1 Do not proceed with installation of joint sealants where joint widths are less than those allowed by joint sealant manufacturer for applications indicated.
- .3 Joint-Substrate Conditions:
  - .1 Do not proceed with installation of joint sealants until contaminants capable of interfering with adhesion are removed from joint substrates.

## **1.9 ENVIRONMENTAL REQUIREMENTS**

- .1 Comply with requirements of Workplace Hazardous Materials Information System (WHMIS) regarding use, handling, storage, and disposal of hazardous materials; and regarding labelling and provision of Material Safety Data Sheets (MSDS) acceptable to Labour Canada.
- .2 Conform to manufacturer's recommended temperatures, relative humidity, and substrate moisture content for application and curing of sealants including special conditions governing use.

## **1.10 WARRANTY**

- .1 Provide written warranty covering the work of this Section for a period of two years from the date of Substantial Completion as per the Project Agreement.
- .2 Defective work shall include but not be restricted to leakage, cracking, crumbling, melting, running, loss of adhesion, loss of cohesion, staining of adjoining or adjacent surfaces or work.

## **PART 2 PRODUCTS**

### **2.1 SEALANT MATERIALS**

- .1 Do not use caulking that emits strong odours, contains toxic chemicals or is not certified as mould resistant in air handling units.
- .2 When low toxicity caulks are not possible, confine usage to areas which offgas to exterior, are contained behind air barriers, or are applied several months before occupancy to maximize offgas time.
- .3 Where sealants are qualified with primers use only these primers.

### **2.2 SEALANT MATERIAL DESIGNATIONS**

- .1 Sealants - Type A
  - .1 Multi-component sealants to meet CGSB Specification CAN/CGSB-19.24, (2-part urethane) or single component sealant to meet CGSB Specification CAN/CGSB-19.13, (silicone) to be used for:
    - .1 Exterior joints around perimeters of metal door frames including thresholds and sills.
    - .2 Exterior joints around perimeters of louvre frames and duct penetrations.
    - .3 Exterior perimeter of conduit, wire and pipe penetrations.
    - .4 Exterior control joints.
    - .5 Roof flashings.
  - .2 Use one of the following sealants:
    - .1 Dymeric by Tremco (Canada) Limited.
    - .2 1200 Sealant by CGE Canada Ltd.
    - .3 795 Sealant by Dow Corning Canada.
- .2 Sealants - Type B

- .1 Acrylic solvent release, one part sealant, to meet CGSB Specification 19-GP-5M, to be used for all other locations where caulking beads remain exposed:
  - .1 Interior perimeters of door and window frames, louvre openings, service penetrations and ducts.
  - .2 Interior movement joints in exterior masonry walls
- .2 Use one of the following sealants:
  - .1 Mono by Tremco (Canada) Limited.
  - .2 Acryflex by Sternson Ltd.
  - .3 Parr-Crylic by Parr Sealants of Canada Ltd.
  - .4 PR12-100 Vinyl Acrylic by PRC Canada Ltd.
- .3 Silicone Sealant – Type C
  - .1 Apply clear, mildew resistant silicone sealant at perimeter of backsplashes, at millwork mounted against walls, at washroom vanities, and around plumbing fixtures at floor and wall surfaces.
  - .2 Use one of the following sealants:
    - .1 Tremsil 200 by Tremco (Canada) Ltd.
    - .2 DAP 3.0
- .4 Primers
  - .1 To be of a type recommended by sealant manufacturer for the appropriate sealant and corresponding substrate.
- .5 Preformed Compressible and Non-Compressible back-up materials.
  - .1 Polyethylene, Urethane, Neoprene or Vinyl Foam.
    - .1 Extruded open closed cell foam backer rod.
    - .2 Size: oversize 30 to 50%.
  - .2 Neoprene or Butyl Rubber.
    - .1 Round solid rod, Shore A hardness 70.
  - .3 High Density Foam.
    - .1 Extruded closed cell polyvinyl chloride (PVC), extruded polyethylene, closed cell, Shore A hardness 20, tensile strength 140 to 200 kPa, extruded polyolefin foam, 32 kg/m<sup>3</sup> density, or neoprene foam backer, size as recommended by manufacturer.
  - .4 Bond Breaker Tape.
    - .1 Polyethylene bond breaker tape which will not bond to sealant.

## **2.3 COLOURS**

- .1 Colours of sealant, shall match the predominant material to which sealant is applied.

## **2.4 JOINT CLEANER**

- .1 Non-corrosive and non-taining type, compatible with joint forming materials and sealant recommended by sealant manufacturer.
- .2 Primer: as recommended by manufacturer.

### **PART 3 EXECUTION**

#### **3.1 PROTECTION**

- .1 Protect installed Work of other trades from staining or contamination.

#### **3.2 SURFACE PREPARATION**

- .1 Examine joint sizes and conditions to establish correct depth to width relationship for installation of backup materials and sealants.
- .2 Clean bonding joint surfaces of harmful matter substances including dust, rust, oil grease, and other matter which may impair Work.
- .3 Do not apply sealants to joint surfaces treated with sealer, curing compound, water repellent, or other coatings unless tests have been performed to ensure compatibility of materials. Remove coatings as required.
- .4 Ensure joint surfaces are dry and frost free.
- .5 Prepare surfaces in accordance with manufacturer's directions.

#### **3.3 PRIMING**

- .1 Where necessary to prevent staining, mask adjacent surfaces prior to priming and caulking.
- .2 Prime sides of joints in accordance with sealant manufacturer's instructions immediately prior to caulking.

#### **3.4 BACKUP MATERIAL**

- .1 Apply bond breaker tape where required to manufacturer's instructions.
- .2 Install joint filler to achieve correct joint depth and shape, with approximately 30% compression.

#### **3.5 MIXING**

- .1 Mix materials in strict accordance with sealant manufacturer's instructions.

#### **3.6 APPLICATION**

- .1 Sealant.

- .1 Apply sealant in accordance with manufacturer's written instructions.
  - .2 Mask edges of joint where irregular surface or sensitive joint border exists to provide neat joint.
  - .3 Apply sealant in continuous beads.
  - .4 Apply sealant using gun with proper size nozzle.
  - .5 Use sufficient pressure to fill voids and joints solid.
  - .6 Form surface of sealant with full bead, smooth, free from ridges, wrinkles, sags, air pockets, embedded impurities.
  - .7 Tool exposed surfaces before skinning begins to give slightly concave shape.
  - .8 Remove excess compound promptly as work progresses and upon completion.
- .2 Curing.
- .1 Cure sealants in accordance with sealant manufacturer's instructions.
  - .2 Do not cover up sealants until proper curing has taken place.
- .3 Cleanup.
- .1 Clean adjacent surfaces immediately and leave Work neat and clean.
  - .2 Remove excess and droppings, using recommended cleaners as work progresses.
  - .3 Remove masking tape after initial set of sealant.

**END OF SECTION**

## **PART 1 GENERAL**

### **1.1 RELATED SECTIONS**

- .1 Section 01 33 00 – Submittal Procedures.
- .2 Section 01 61 00 – Common Product Requirements.
- .3 Section 01 74 21 – Construction/Demolition Waste Management and Disposal.
- .4 Section 07 92 10 – Joint Sealing: Caulking of joints between frames and other building components.
- .5 Section 08 71 10 – Door Hardware: Supply of finish hardware, including weatherstripping and mounting heights.
- .6 Section 09 91 00 – Painting and Protective Coatings.

### **1.2 REFERENCES**

- .1 American Society for Testing and Materials (ASTM International)
  - .1 ASTM A653/A653M-03, Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.ASTM B29-92 (1997), Specification for Refined LeadASTM B749-97, Specification for Lead and Lead Alloy Strip, Sheet and Plate Products
- .2 Canadian General Standards Board (CGSB)
  - .1 CAN/CGSB-1.181-99, Ready-Mixed Organic Zinc-Rich Coating.CGSB 41-GP-19Ma-84, Rigid Vinyl Extrusions for Windows and Doors
- .3 Canadian Standards Association (CSA International)
  - .1 G40.20/G40.21-04, General Requirements for Rolled or Welded Structural Quality Steel/Structural Quality Steel.
  - .2 CSA W59-M1989 (R2001), Welded Steel Construction (Metal Arc Welding) (Metric Version).
- .4 Canadian Steel Door Manufacturers' Association, (CSDMA)
  - .1 CSDMA, Specifications for Commercial Steel Doors and Frames, 1990.
  - .2 CSDMA, Recommended Selection and Usage Guide for Commercial Steel Doors, 1990.
- .5 National Fire Protection Association (NFPA)
  - .1 NFPA 80-99, Standard for Fire Doors and Fire Windows.NFPA 252-99, Standard Methods of Fire Tests of Door Assemblies.
- .6 Underwriters' Laboratories of Canada (ULC)
  - .1 CAN4-S104-M80, Fire Tests of Door Assemblies.CAN4-S105-M85, Fire Door Frames Meeting the Performance Required by CAN4-S104.
  - .2 CAN/ULC-S701-01, Thermal Insulation, Polystyrene, Boards and Pipe Covering.
  - .3 CAN/ULC-S702-97, Mineral Fibre Thermal Insulation for Buildings.

- .4 CAN/ULC-S704-03, Thermal Insulation, Polyurethane and Polyisocyanurate Boards, Faced.

### **1.3 DESIGN REQUIREMENTS**

- .1 Design exterior frame assembly to accommodate to expansion and contraction when subjected to minimum and maximum surface temperature of -35°C to 35°C.
- .2 Maximum deflection for exterior steel entrance screens under wind load of 1.2 kPa not to exceed 1/175th of span.

### **1.4 SHOP DRAWINGS**

- .1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Indicate each type of door, material, steel core thicknesses, mortises, reinforcements, location of exposed fasteners, openings, glazed louvred, arrangement of hardware and fire rating and finishes.
- .3 Indicate each type frame material, core thickness, reinforcements, glazing stops, location of anchors and exposed fastenings and reinforcing firerating finishes.
- .4 Indicate details of construction and installation of all components of the Work.
- .5 Include schedule identifying each unit, with door marks and numbers relating to numbering on drawings and door schedule.
- .6 Submit test and engineering data, and installation instructions.

### **1.5 REQUIREMENTS**

- .1 Steel fire rated doors and frames: labelled and listed by an organization accredited by Standards Council of Canada in conformance with CAN4-S104M, CAN4-S105M and NFPA 252 for ratings specified or indicated.
- .2 Provide fire labelled frame products for those openings requiring fire protection ratings, as scheduled. Test products in strict conformance with CAN4-S104, ASTM E152 or NFPA 252 and list by nationally recognized agency having factory inspection service and construct as detailed in Follow-Up Service Procedures/Factory Inspection Manuals issued by listing agency to individual manufacturers.

### **1.6 WARRANTY**

- .1 Materials and workmanship shall be warranted by manufacturer in accordance with Canadian Steel Door Manufacturers' Association, (CSDMA) Standard Warranty for Steel Doors and Frames.

### **1.7 DELIVERY, STORAGE, AND HANDLING**

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Provide and maintain dry, off-ground weatherproof storage.

## **1.8 WASTE MANAGEMENT AND DISPOSAL**

- .1 Separate and recycle waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .3 Collect and separate for disposal paper, plastic, polystyrene and corrugated cardboard packaging material in appropriate on-site for recycling in accordance with Waste Management Plan.
- .4 Divert unused paint and sealant materials from landfill to an approved, official hazardous material collections site.
- .5 Do not dispose of unused paint and sealant materials into sewer systems, into lakes, streams, onto ground or in other locations where it will pose health or environmental hazard.
- .6 Divert unused metal materials from landfill to an approved metal recycling facility.
- .7 Divert unused wood materials from landfill to an approved recycling facility.
- .8 Damaged or broken glazing materials are not recyclable. These materials must not be disposed of with materials destined for recycling.

## **PART 2 PRODUCTS**

### **2.1 ACCEPTABLE MANUFACTURERS**

- .1 Only steel frame products manufactured by Canadian Steel Door Manufacturers' Association, (CSDMA) members are eligible for use on this project.

### **2.2 MATERIALS**

- .1 Hot dipped galvanized steel sheet: to ASTM A653M, ZF75, minimum base steel thickness in accordance with CSDMA Table 1 - Thickness for Component Parts.
- .2 Reinforcement channel: to CSA G40.20/G40.21, Type 44W, hot dipped galvanized .
- .3 Fire-rated doors and frames: Material and construction in accordance with listing requirements. Doors to be flush type with no face seams.

### **2.3 DOOR CORE MATERIALS**

- .1 Honeycomb construction:
  - .1 Structural small cell, 24.5 mm maximum kraft paper 'honeycomb', weight: 36.3 kg per ream minimum, density: 16.5 kg/m<sup>3</sup> minimum sanded to required thickness.
- .2 Insulated:

- .1 Expanded polystyrene: CAN/ULC-S701, density 16 to 32 kg/m<sup>3</sup>.
- .3 Temperature rise rated (TRR): core composition to limit temperature rise on unexposed side of door to 250°C at 30 minutes. Core to be tested as part of a complete door assembly, in accordance with CAN4-S104, ASTM E152 or NFPA 252, covering Standard Method of Tests of Door Assemblies and listed by nationally recognized testing agency having factory inspection service.

## **2.4 ADHESIVES**

- .1 Honeycomb cores and steel components: heat resistant, spray grade, resin reinforced neoprene/rubber (polychloroprene) based, low viscosity, contact cement.
- .2 Polystyrene cores: heat resistant, epoxy resin based, low viscosity, contact cement.
- .3 Lock-seam doors: fire resistant, resin reinforced polychloroprene, high viscosity, sealant/adhesive.

## **2.5 PRIMER**

- .1 Touch-up prime CAN/CGSB-1.181.

## **2.6 PAINT**

- .1 Field paint steel doors and frames in accordance with 09 91 00 – Painting and Protective Coatings. Protect weatherstrips from paint. Provide final finish shall be free of scratches or other blemishes.

## **2.7 ACCESSORIES**

- .1 Door silencers: single stud rubber/neoprene type.
- .2 Exterior top and bottom caps: rigid polyvinylchloride extrusion conforming to CGSB 41-GP-19Ma steel.
- .3 Door bottom seal: to Section 08 71 10 - Door Hardware.
- .4 Metallic paste filler: to manufacturer's standard.
- .5 Accessories (doors and frames) and minimum base steel thickness:
  - .1 Lock/strike reinforcements: 1.6 mm
  - .2 Hinge reinforcements: 2.7 mm
  - .3 Flush bolt reinforcements: 1.6 mm
  - .4 Reinforcements for surface applied hardware: 1.2 mm
  - .5 Top or bottom channels: 1.2 mm
  - .6 Glass trim, screw fixed or snap-in types: 0.9 mm
  - .7 Mortar guard boxes: 0.8 mm
  - .8 Floor anchors: 1.6 mm
  - .9 Jamb spreaders: 0.9 mm
- .6 Sealant: to Section 07 92 10 - Joint Sealing.

## **2.8 FRAMES FABRICATION GENERAL**

- .1 Fabricate frames in accordance with CSDMA specifications, reviewed Shop Drawings and listing requirements.
- .2 Fabricate frames to profiles and maximum face sizes as indicated.
- .3 Finish: hot dipped galvanized after fabrication.
- .4 Blank, reinforce, drill and tap frames for mortised, templated hardware, and electronic hardware using templates provided by finish hardware supplier. Reinforce frames for surface mounted hardware.
- .5 Protect mortised cutouts with steel guard boxes welded to frame.
- .6 Prepare frame for door silencers, 3 for single door, and 2 at head for double door.
- .7 Manufacturer's nameplates on frames and screens are not permitted.
- .8 Conceal fastenings except where exposed fastenings are indicated.
- .9 Provide factory-applied touch up primer at areas where zinc coating has been removed during fabrication.
- .10 Insulate exterior frame components with mineral wool insulation.

## **2.9 FRAME ANCHORAGE**

- .1 Provide appropriate anchorage to floor and wall construction.
- .2 Locate each wall anchor immediately above or below each hinge reinforcement on hinge jamb and directly opposite on strike jamb, minimum 3 anchors per jamb.
- .3 Provide 2 anchors for rebate opening heights up to 1520 mm and 1 additional anchor for each additional 760 mm of height or fraction thereof.

## **2.10 FRAMES: WELDED TYPE**

- .1 Welding in accordance with CSA W59.
- .2 Accurately mitre or mechanically joint frame product and securely weld on inside of profile.
- .3 Cope accurately and securely weld butt joints of mullions, transom bars, centre rails and sills.
- .4 Grind welded joints and corners to a flat plane; fill with metallic paste and sand to uniform smooth finish.
- .5 Securely attach floor anchors to inside of each jamb profile.
- .6 Weld in 2 temporary jamb spreaders per frame to maintain proper alignment during shipment.

## **2.11 DOOR FABRICATION GENERAL**

- .1 Fabricate doors in accordance with CSDMA specifications, reviewed Shop Drawings and listing requirements.
- .2 Doors: swing type, flush, with provision for single, sealed insulated glass units, and louvre openings as indicated.
- .3 Interior doors: honeycomb hollow steel construction
- .4 Exterior doors: insulated polystyrene core construction
- .5 Fabricate doors with longitudinal edges mechanically interlocked with visible seams.
- .6 Bevel hinge and lock edges of doors, 3 mm in 50 mm.
- .7 Blank, reinforce, drill doors and tap for mortised, templated hardware and electronic hardware.
- .8 Factory prepare holes 12.7 mm diameter and larger except mounting and through-bolt holes, on site, at time of hardware installation.
- .9 Reinforce doors where required, for surface mounted hardware.
- .10 Provide flush PVC steel top caps to exterior doors.
- .11 Provide inverted, recessed, spot welded channels to top and bottom of interior doors.
- .12 Provide factory-applied touch-up primer at areas where zinc coating has been removed during fabrication.
- .13 Provide 127 mm backset for all locksets and latchsets where indicated in the Door Schedule.

## **2.12 HOLLOW STEEL CONSTRUCTION**

- .1 Form each face sheet for exterior doors from 1.6 mm (16 gauge) galvanized sheet steel with polystyrene core laminated under pressure to face sheets.
- .2 Form each face sheet for interior doors from 1.3 mm (18 gauge) galvanized sheet steel with honeycomb or temperature rise rated core laminated under pressure to face sheets.
- .3 Reinforce doors with vertical stiffeners, securely welded to each face sheet at 150 mm on centre maximum.

## **2.13 THERMALLY BROKEN DOORS AND FRAMES**

- .1 Fabricate thermally broken doors by using insulated core and separating exterior parts from interior parts with continuous interlocking thermal break.
- .2 Thermal break: rigid polyvinylchloride extrusion conforming to CGSB 41-GP-19Ma.

- .3 Fabricate thermally broken frames separating exterior parts from interior parts with continuous interlocking thermal break.
- .4 Welding of thermally broken frames must not cause thermal transfers between exterior and interior surfaces of frame sections.
- .5 Fill voids in frame with mineral wool insulation prior to insulation.

### **PART 3 EXECUTION**

#### **3.1 INSTALLATION GENERAL**

- .1 Install labelled steel fire rated doors and frames to NFPA 80 except where specified otherwise.
- .2 Install doors and frames to CSDMA Installation Guide.

#### **3.2 FRAME INSTALLATION**

- .1 Set frames plumb, square, level and at correct elevation.
- .2 Secure anchorages and connections to adjacent construction.
- .3 Brace frames rigidly in position while building-in. Install temporary horizontal wood spreader at third points of door opening to maintain frame width. Provide vertical support at centre of head for openings over 1200 mm wide. Remove temporary spreaders after frames are built-in.
- .4 Make allowances for deflection of structure to ensure structural loads are not transmitted to frames.
- .5 Caulk perimeter of frames between frame and adjacent material.
- .6 Maintain continuity of air barrier and vapour retarder.
- .7 Install door silencers after finish painting of frame has been completed.

#### **3.3 DOOR INSTALLATION**

- .1 Install doors and hardware in accordance with hardware templates and manufacturer's instructions and Section 08 71 10 - Door Hardware.
- .2 Provide even margins between doors and jambs and doors and finished floor and thresholds as follows.
  - .1 Hinge side: 1.0 mm.
  - .2 Latchside and head: 1.5 mm.
  - .3 Finished floor and thresholds: 13 mm.
- .3 Adjust operable parts for correct function.
- .4 Install louvres.
- .5 Install vinyl top caps in out swinging exterior doors for weather protection.

**3.4 FINISH REPAIRS**

- .1 Touch up with primer finishes damaged during installation.
- .2 Fill exposed frame anchors and surfaces with imperfections with metallic paste filler and sand to a uniform smooth finish.

**END OF SECTION**

## **PART 1 GENERAL**

### **1.1 RELATED SECTIONS**

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 61 00 - Common Product Requirements.
- .3 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .4 Section 01 78 00 - Closeout Submittals.
- .5 Section 08 11 14 - Metal Doors and Frames.

### **1.2 REFERENCES**

- .1 Canadian Steel Door and Frame Manufacturers' Association (CSDFMA).
  - .1 CSDFMA Canadian Metric Guide for Steel Doors and Frames (Modular Construction): standard hardware location dimensions.
- .2 Canadian General Standards Board (CGSB).
  - .1 CAN/CGSB-69.17-M86 (R1993), Bored and Preassembled Locks and Latches.
  - .2 CAN/CGSB-69.18-M90/ANSI/BHMA A156.1-1981, Butts and Hinges.
  - .3 CAN/CGSB-69.19-93/ANSI/BHMA A156.3-1984, Exit Devices.
  - .4 CAN/CGSB-69.20-M90/ANSI/BHMA A156.4-1986, Door Controls (Closers).
  - .5 CAN/CGSB-69.21-M90/ANSI/BHMA A156.5-1984, Auxiliary Locks and Associated Products.
  - .6 CAN/CGSB-69.22-M90/ANSI/BHMA A156.6-1986, Architectural Door Trim.
  - .7 CAN/CGSB-69.24-M90/ANSI/BHMA A156.8-1982, Door Controls - Overhead Holders.
  - .8 CAN/CGSB-69.29-93/ANSI/BHMA A156.13-1987, Mortise Locks and Latches.
  - .9 CAN/CGSB-69.31-M89/ANSI/BHMA A156.15-1981, Closer/Holder Release Device.
  - .10 CAN/CGSB-69.32-M90/ANSI/BHMA A156.16-1981, Auxiliary Hardware.
  - .11 CAN/CGSB-69.34-93/ANSI/BHMA A156.18-1987, Materials and Finishes.

### **1.3 SUBMITTALS**

- .1 Product Data:
  - .1 Submit manufacturer's printed product literature, specifications and data sheet in accordance with Section 01 33 00 - Submittal Procedures.

- .2 Samples:
  - .1 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
  - .2 Identify each sample by label indicating applicable specification paragraph number, brand name and number, finish and hardware package number.
  - .3 After approval samples will be returned for incorporation in the Work.
- .3 Hardware List:
  - .1 Submit contract hardware list in accordance with Section 01 33 00 - Submittal Procedures.
  - .2 Indicate specified hardware, including make, model, material, function, size, finish and other pertinent information.
- .4 Manufacturer's Instructions:
  - .1 Submit manufacturer's installation instructions.
- .5 Closeout Submittals
  - .1 Provide operation and maintenance data for door closers, locksets, door holders for incorporation into manual specified in Section 01 78 23 – Operation and Maintenance Manual.

#### **1.4 QUALITY ASSURANCE**

- .1 Regulatory Requirements:
  - .1 Hardware for doors in fire separations and exit doors certified by a Canadian Certification Organization accredited by Standards Council of Canada.
- .2 Certificates: product certificates signed by manufacturer certifying materials comply with specified performance characteristics and criteria and physical requirements.

#### **1.5 DELIVERY, STORAGE, AND HANDLING**

- .1 Packing, Shipping, Handling and Unloading:
  - .1 Deliver, store, handle and protect materials in accordance with Section 01 61 00 - Common Product Requirements.
  - .2 Package each item of hardware including fastenings, separately or in like groups of hardware, label each package as to item definition and location.
- .2 Storage and Protection:
  - .1 Store finishing hardware in locked, clean and dry area.

#### **1.6 WASTE DISPOSAL AND MANAGEMENT**

- .1 Separate and recycle waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .3 Dispose of corrugated cardboard, polystyrene and plastic packaging material in appropriate on-site bin for recycling in accordance with site waste management program.

## 1.7 MAINTENANCE

- .1 Extra Materials:
  - .1 Provide maintenance materials in accordance with Section 01 78 00 - Closeout Submittals.
  - .2 Supply two sets of wrenches for door closers, locksets and exit hardware.

## PART 2 PRODUCTS

### 2.1 HARDWARE ITEMS

- .1 Use one manufacturer's products only for similar items.

### 2.2 DOOR HARDWARE

- .1 Butts and hinges: to CAN/CGSB-69.18, (3 per door for doors up to 2135 and 4 per door for doors up to 2440 in height or over 914 in width), NRP, ball bearing type, stainless steel.
  - .1 Acceptable products:
    - .1 Hagar AB850 x 114 x 114
    - .2 Stanley CB199 x 114 x 114
    - .3 Contract Administrator approved equal.
  - .2 Exit devices: to CAN/CGSB-69.19, rim exit device, ULC rated, with cylinder core, exterior lever handle trim and vinyl touch bar.
    - .1 Acceptable products:
      - .1 Von Duprin 98 series
      - .2 Sargent 8800 series
      - .3 Contract Administrator approved equal.
    - .2 Locksets:
      - .1 Locksets to CAN/CGSB-69.17 –M86, Grade 1 lever handle
      - .2 Provide construction cylinder cores and final cores with keying to Owners BEST master key system.
      - .3 Acceptable products for interior locksets:
        - .1 Schlage "A" series
        - .2 Stanley 9K series
        - .3 Contract Administrator approved equal.
      - .4 Acceptable products for exterior locksets:
        - .1 Schlage "D" series
        - .2 Stanley 9K series
        - .3 Contract Administrator approved equal.
  - .3 Door Closers and Accessories:
    - .1 Door controls (closers): to CAN/CGSB-69.20, one per door. All door closers shall be through bolted. Finish aluminum lacquer.
      - .1 Acceptable products:
        - .1 LCN 4040 Super Smoothee by LCN closers
        - .2 Contract Administrator approved equal.
      - .2 Door controls - overhead holders: to CAN/CGSB-69.24, extruded bronze, 110 degree hold-open and stop, one per door.
        - .1 Acceptable products:
          - .1 Sargent 598H

- .2 Contract Administrator approved equal.
- .4 Architectural door trim: to CAN/CGSB-69.22, as listed below.
  - .1 Door protection plates: kick plate type, 1.27 mm thick stainless steel.
    - .1 Acceptable products:
      - .1 Canadian Builders Hardware
      - .2 Contract Administrator approved equal.
- .5 Auxiliary hardware: to CAN/CGSB-69.32, as listed below.
  - .1 Surface bolt: (200 mm), heavy duty top and bottom.
    - .1 Acceptable products:
      - .1 Canadian Builders Hardware F67
      - .2 Ives SB1630TBL 1289
      - .3 Contract Administrator approved equal.
- .6 Thresholds: 150 mm, extruded aluminum with thermal break.
  - .1 Acceptable products:
    - .1 K. N. Crowder CT-46.
    - .2 Contract Administrator approved equal.
- .7 Weatherstripping:
  - .1 Head and jamb seal: Adjustable spring loaded, vinyl in extruded aluminum trim
    - .1 Acceptable products:
      - .1 K. N. Crowder W44.
      - .2 Contract Administrator approved equal.
  - .2 Door bottom seal: Neoprene rubber in extruded aluminum trim
    - .1 Acceptable products:
      - .1 K. N. Crowder Type CT-54 Automatic door bottom.
      - .2 Contract Administrator approved equal.
- .8 Astragal: full height mounted, interior magnetic in extruded aluminum trim and pile strip in extruded aluminum trim on exterior.
  - .1 Acceptable products:
    - .1 Zero International, No.40 Interior and No.41 Exterior.
    - .2 Contract Administrator approved equal.

### **2.3 FASTENINGS**

- .1 Use only fasteners provided by manufacturer. Failure to comply may void warranties and applicable licensed labels.
- .2 Supply screws, bolts, expansion shields and other fastening devices required for satisfactory installation and operation of hardware.
- .3 Exposed fastening devices to match finish of hardware.
- .4 Where pull is scheduled on one side of door and push plate on other side, supply fastening devices, and install so pull can be secured through door from reverse side. Install push plate to cover fasteners.
- .5 Use fasteners compatible with material through which they pass.

- .6 All fasteners to be non-corroding.

## **2.4 KEYING**

- .1 Lay out keying system in consultation with the City. Keying system shall include keying alike, keying differently, keying in groups, submaster keying and grand master keying locks as necessary to meet the requirements of the City.
- .2 Keying chart and related explanatory data shall be prepared and submitted to the City for approval, and lock work shall not be commenced until written confirmation of keying arrangements is received from the City.
- .3 Provide keys in duplicate for every lock.
- .4 Stamp keying code numbers on keys and cylinders.
- .5 Provide cabinet for key control with two tag security system complete with key loan register, three-way cross reference index, and cabinet door locking device.
- .6 All locks shall be operated by a construction master key in construction cylinder cores while the building is under construction, but shall not operate when the temporary construction cores are replaced with permanent master keyed cylinders at completion of the building.
- .7 Provide all permanent cores and keys to City.

## **PART 3 EXECUTION**

### **3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written data, including product technical bulletins, product catalogue installation instructions, product carton installation instructions, and data sheets.
- .2 Furnish metal door and frame manufacturers with complete instructions and templates for preparation of their work to receive hardware.
- .3 Furnish manufacturers' instructions for proper installation of each hardware component.

### **3.2 INSTALLATION**

- .1 Install hardware to standard hardware location dimensions in accordance with Canadian Metric Guide for Steel Doors and Frames (Modular Construction) prepared by Canadian Steel Door and Frame Manufacturers' Association.
- .2 Where door stop contacts door pulls, mount stop to strike bottom of pull.
- .3 Use only manufacturer's supplied fasteners. Failure to comply may void manufacturer's warranties and applicable licensed labels. Use of "quick" type fasteners, unless specifically supplied by manufacturer, is unacceptable.

- .4 Remove construction cores when directed by Contract Administrator; install permanent cores and check operation of locks.

### **3.3 ADJUSTING**

- .1 Adjust door hardware, operators, closures and controls for optimum, smooth operating condition, safety and for weather tight closure.
- .2 Lubricate hardware, operating equipment and other moving parts.
- .3 Adjust door hardware to provide tight fit at contact points with frames.

### **3.4 CLEANING**

- .1 Perform cleaning after installation to remove construction and accumulated environmental dirt.
- .2 Clean hardware with damp rag and approved non-abrasive cleaner, and polish hardware in accordance with manufacture's instructions.
- .3 Remove protective material from hardware items where present.
- .4 Upon completion of installation, remove surplus materials, rubbish, tools and equipment barriers.

**END OF SECTION**

**PART 1 GENERAL**

**1.1 SECTION INCLUDES**

- .1 Moisture testing of substrates.
- .2 Surface preparation of substrates as required for acceptance of paint, including cleaning, small crack repair, patching, caulking, and making good surfaces and areas to limits defined under MPI Repainting Maintenance Manual requirements.
- .3 Specific pre-treatments noted herein or specified in the MPI Repainting Maintenance Manual.
- .4 Sealing/touch-up, spot priming, and/or full priming surfaces for repainting in accordance with MPI Repainting Maintenance Manual requirements.
- .5 Provision of safe and adequate ventilation as required where toxic and/or volatile/flammable materials are being used over and above temporary ventilation supplied by others.

**1.2 REFERENCES**

- .1 Maintenance Repainting Manual by the Master Painters Institute (MPI), including Identifiers, Evaluation, Systems, Preparation and Approved Product List.
- .2 Test Method for Measuring Total Volatile Organic Compound Content of Consumer Products, Method 24 (for Surface Coatings) of the Environmental Protection Agency (EPA).
- .3 National Fire Code of Canada.

**1.3 QUALITY ASSURANCE**

- .1 Contractor shall have a minimum of five (5) years proven satisfactory experience. Provide a list of last three (3) comparable jobs including, job name and location, specifying authority, and project manager.
- .2 Qualified journeymen who have a "Tradesman Qualification Certificate of Proficiency" shall be engaged in painting work. Apprentices may be employed provided they Work under the direct supervision of a qualified journeyman in accordance with applicable trade regulations.
- .3 Conform to latest MPI requirements for interior painting work including cleaning, preparation and priming.
- .4 Materials (primers, paints, coatings, varnishes, stains, lacquers, fillers, thinners, solvents, etc.) shall be in accordance with the latest edition of the MPI Approved Product List and shall be from a single manufacturer for each system used.

- .5 Paint materials such as linseed oil, shellac, turpentine, etc. shall be the highest quality product of an approved manufacturer listed in MPI Maintenance Repainting Manual and shall be compatible with other coating materials as required.
- .6 Retain purchase orders, invoices and other documents to prove conformance with noted MPI requirements when requested by Contract Administrator.
- .7 Standard of Acceptance: When viewed using final lighting source surfaces shall indicate the following:
  - .1 Walls: No defects visible from a distance of 1000 mm at 90° to surface.
  - .2 Ceilings: No defects visible from floor at 45° to surface.
  - .3 Final coat to exhibit uniformity of colour and sheen across full surface area.

#### **1.4 ENVIRONMENTAL PERFORMANCE REQUIREMENTS**

- .1 Provide indoor paint products meeting MPI "Environmentally Friendly" E2 ratings based on VOC (EPA Method 24) content levels.

#### **1.5 INSPECTION REQUIREMENTS**

- .1 Interior surfaces requiring repainting shall be inspected by both painting contractor who will notify Contract Administrator and Contractor in writing of defects or problems, prior to commencing repainting work, or after surface preparation if unseen substrate damage is discovered.
- .2 Where an assessed degree of surface degradation of DSD-1 to DSD-3 before preparation of surfaces for repainting is revealed to be DSD-4 after preparation, repair or replacement of such unforeseen defects discovered shall be rectified by others, as mutually agreed, before repainting is started.

#### **1.6 SUBMITTALS**

- .1 Submit product data and manufacturer's installation/application instructions for each paint and coating product to be used in accordance with the requirements of Section 01 30 00 – Submittal Procedures.
- .2 Submit full range colour sample chips for review and selection. Indicate where colour availability is restricted.
- .3 Submit WHMIS MSDS - Material Safety Data Sheets for paint and coating materials in accordance with Section.
- .4 Upon completion, submit records of products used. List products in relation to finish system and include the following:
  - .1 Product name, type and use (i.e., materials and location).
  - .2 Manufacturer's product number.
  - .3 Colour code numbers.
  - .4 MPI Environmentally Friendly classification system rating.
  - .5 Manufacturer's Material Safety Data Sheets (MSDS).

## 1.7 QUALITY CONTROL

- .1 Provide a mock-up in accordance with requirements of Section 01 33 00.
- .2 Prepare and repaint mock-up designated interior room, surface or item to requirements specified herein, with specified paint or coating showing selected colours, gloss/sheen, textures and workmanship to MPI Maintenance Repainting Manual standards for review and approval.
- .3 When approved, repainted room, surface and/or item shall become acceptable standard of finish quality and workmanship for similar on-site interior repainting work.

## 1.8 DELIVERY, HANDLING AND STORAGE

- .1 Deliver and store materials in original containers, sealed, with labels intact.
- .2 Labels shall clearly indicate:
  - .1 Manufacturer's name and address.
  - .2 Type of paint or coating.
  - .3 Compliance with applicable standard.
  - .4 Colour number in accordance with established colour schedule.
- .3 Remove damaged, opened and rejected materials from Site.
- .4 Observe manufacturer's recommendations for storage and handling.
- .5 Store materials and equipment in a secure, dry, well-ventilated area with temperature range between 7°C to 30°C. Store materials and supplies away from heat generating devices and sensitive products above minimum temperature as recommended by manufacturer.
- .6 Keep areas used for storage, cleaning and preparation, clean and orderly to approval of Contract Administrator. After completion of operations, return areas to clean condition to approval of Contract Administrator.
- .7 Remove paint materials from storage in quantities required for same day use.
- .8 Comply with requirements of Workplace Hazardous Materials Information System (WHMIS) regarding use, handling storage, and disposal of hazardous materials.
- .9 Fire Safety Requirements:
  - .1 Provide one (1) 9 kg Type ABC dry chemical fire extinguisher adjacent to storage area.
  - .2 Store oily rags, waste products, empty containers and materials subject to spontaneous combustion in ULC approved, sealed containers and remove from Site on a daily basis.
  - .3 Handle, store, use and dispose of flammable and combustible materials in accordance with the National Fire Code of Canada.

## 1.9 SITE REQUIREMENTS

- .1 Heating, Ventilation and Lighting:

- .1 Perform no repainting work unless adequate and continuous ventilation and sufficient heating facilities are in place to maintain ambient air and substrate temperatures above 10°C for 24 hours before, during and after paint application and until paint has cured sufficiently.
  - .2 Ventilate enclosed spaces. Where required, provide continuous ventilation for seven (7) days after completion of application of paint.
  - .3 Provide temporary ventilating and heating equipment where permanent facilities are not available or supplemental ventilating and heating equipment if ventilation and heating from existing system is inadequate to meet minimum requirements. The use of gas-fired appliances is not permitted.
  - .4 Perform no painting work unless a minimum lighting level of 323 Lux is provided on surfaces to be painted.
- .2 Temperature, Humidity and Substrate Moisture Content Levels:
- .1 Unless specifically pre-approved by specifying body, Paint Inspection Agency and, applied product manufacturer, perform no repainting work when:
    - .1 Ambient air and substrate temperatures are below 10°C.
    - .2 Substrate temperature is over 32°C unless paint is specifically formulated for application at high temperatures.
    - .3 Relative humidity within area to be repainted is above 85%.
  - .2 Conduct moisture tests using a properly calibrated electronic Moisture Meter, except use a simple "cover patch test" on concrete floors to be repainted.
  - .3 Perform no repainting work when maximum moisture content of substrate exceeds:
    - .1 12% for concrete and masonry (clay and concrete brick/block).
    - .2 15% for wood.
    - .3 12% for plaster and gypsum board.
  - .4 Test painted concrete, masonry and plaster surfaces for alkalinity as required.
- .3 Surface and Environmental Conditions:
- .1 Apply paint finish in areas where dust is no longer being generated by related construction operations or when ventilation conditions are such that airborne particles will not affect quality of finished surface.
  - .2 Apply paint to adequately prepared surfaces and to surfaces within moisture limits noted herein.
  - .3 Apply paint when previous coat of paint is dry or adequately cured, unless otherwise pre-approved by the specific coating manufacturer.

#### **1.10 WASTE MANAGEMENT AND DISPOSAL**

- .1 Paint, stain and wood preservative finishes and related materials (thinners, solvents, etc.) are hazardous products and are subject to regulations for disposal. Information on these controls can be obtained from Provincial Ministries of Environment and Regional levels of Government.
- .2 Materials that cannot be reused must be treated as hazardous waste and disposed of in an appropriate manner.

- .3 Place materials defined as hazardous or toxic waste, including used sealant and adhesive tubes and containers, in containers or areas designated for hazardous waste.
- .4 To reduce the amount of contaminants entering waterways, sanitary/storm drain systems or into the ground the following procedures shall be strictly adhered to:
  - .1 Retain cleaning water for water-based materials to allow sediments to be filtered out. In no case shall equipment be cleaned using free draining water.
  - .2 Retain cleaners, thinners, solvents and excess paint and place in designated containers and ensure proper disposal.
  - .3 Return solvent and oil soaked rags used during painting operations for contaminant recovery, proper disposal, or appropriate cleaning and laundering.
  - .4 Dispose of contaminants in an approved legal manner in accordance with hazardous waste regulations.
  - .5 Empty paint cans are to be dry prior to disposal or recycling (where available).
  - .6 Close and seal tightly partly used cans of materials including sealant and adhesive containers and store protected in well ventilated fire-safe area at moderate temperature.
- .5 Where paint recycling is available, collect waste materials by type and provide for delivery to recycling or collection facility.
- .6 Set aside and protect surplus and uncontaminated finish materials: Deliver to or arrange collection by employees, individuals, or organizations for verifiable re-use or re-manufacturing.

### **1.11 EXTRA MATERIALS**

- .1 Submit maintenance materials in accordance with Special Provisions of the Contract.
- .2 Submit one (1), 4 L can of each type and colour of finish coating. Identify type and colour in relation to established colour schedule and finish system.
- .3 Deliver to City and store where directed.

## **PART 2 PRODUCTS**

### **2.1 MATERIALS**

- .1 Paint materials listed in the latest edition of the MPI Approved Product List (APL) as supplied by one of following manufacturers are acceptable for use on this project:
  - .1 ICI Devoe.
  - .2 Pittsburgh Paints.
  - .3 Benjamin Moore.
  - .4 Para Paints.
  - .5 Sika Paints.

- .2 Where required by authorities having jurisdiction, paints and coatings shall provide a fire resistant rating.
- .3 Paint materials for repaint systems shall be products of a single manufacturer.
- .4 Paints and coatings must be manufactured and transported in a manner that steps of processes, including disposal of waste products arising therefrom, will meet requirements of applicable governmental acts, by-laws and regulations including, for facilities located in Canada, Fisheries Act and Canadian Environmental Protection Act (CEPA).
- .5 Paints and coatings must not be formulated or manufactured with formaldehyde, halogenated solvents, mercury, lead, cadmium, hexavalent chromium or their compounds.

## **2.2 COLOURS**

- .1 Contract Administrator will provide Colour Schedule after Contract award.
- .2 Colour schedule will be based upon selection of five (5) base colours and three (3) accent colours. No more than eight (8) colours will be selected for the entire project and no more than three (3) colours will be selected in each area.
- .3 Selection of colours will be from manufacturer's full range of colours.
- .4 Where specific products are available in a restricted range of colours, selection will be based on the limited range.
- .5 First coat in a two coat (Premium) repaint system to be tinted slightly lighter colour than top coat to show visible difference between coats.

## **2.3 MIXING AND TINTING**

- .1 Perform colour tinting operations prior to delivery of paint to Site.
- .2 Paste, powder or catalyzed paint mixes shall be mixed in strict accordance with manufacturer's written instructions.
- .3 Where thinner is used, addition shall not exceed paint manufacturer's recommendations. Do not use kerosene or such organic solvents to thin water-based paints.
- .4 Thin paint for spraying according in strict accordance with paint manufacturer's instructions.
- .5 Re-mix paint in containers prior to and during application to ensure break-up of lumps, complete dispersion of settled pigment, and colour and gloss uniformity.

## **2.4 GLOSS/SHEEN RATINGS**

- .1 Paint gloss shall be defined as the sheen rating of applied paint, in accordance with the following MPI gloss / sheen standard values:

<b>GLOSS LEVEL CATEGORY</b>	<b>UNITS @ 60°</b>	<b>UNITS @ 85°</b>
G1 - matte finish	0 to 5	maximum 10
G2 - velvet finish	0 to 10	10 to 35
G3 - eggshell finish	10 to 25	10 to 35
G4 - satin finish	20 to 35	minimum 35
G5 - semi-gloss finish	35 to 70	
G6 - gloss finish	70 to 85	
G7 - high gloss finish	> 85	

.2 Gloss level ratings of repainted surfaces shall be as specified herein and as noted on Finish Schedule. **INTERIOR PAINTING SYSTEMS**

.1 Applies to new finishes over previously unpainted surfaces or new shop primed surfaces to be field painted.

.2 Refer to Finish Schedule on architectural drawings for locations.

.3 Galvanized and non-galvanized metal: doors, frames, railings, structural and miscellaneous metals (within floor to underside of ceilings)

.1 Alkyd primer/sealer – One (1) coat.

.2 Alkyd - G5 finish – Two (2) coats.

.4 Gypsum board and exposed plywood: gypsum wallboard, drywall, "sheet rock type material", plywood and wood:

.1 Latex primer/sealer – One (1) coat.

.2 Latex G3 finish – Two (2) coats.

.5 Canvas and cotton coverings.

.1 Latex G1 finish – Two (2) coats.

## **2.6 INTERIOR RE-PAINTING SYSTEMS**

.1 Applies to previously painted surfaces, not new or shop primed.

.2 Galvanized and non galvanized metal: doors, frames, railings, misc. steel, pipes, , and ducts.

.1 Prepare by mechanical means or shot blasting

.2 Alkyd primer – 1 Alkyd - G5 – Two (2) coats.

.3 Concrete and masonry surfaces:

.1 Latex block filler – One (1) thick coat to fill pores.

.2 Latex G3 finish – Two (2) coats.

.4 Canvas and cotton coverings.

.1 Latex G1 finish – Two (2) coats.

## **2.7 EXTERIOR PAINTING AND RE-PAINTING SYSTEMS**

- .1 Galvanized Metal:
  - .1 Galv, metal primer – One (1) coat.
  - .2 Alkyd G5 level finish – Two (2) coats.

## **2.8 ANTI-GRAFFITI COATING:**

- .1 Applied to exterior masonry and exposed concrete surfaces:
  - .1 Sikagard® AG, water-based Anti-Graffiti sealer (or Contract Administrator approved alternate) siloxane, non-stick transparent coating with non-glossy finish applied following suppliers instructions on sand blasted and clean surfaces.

## **PART 3 EXECUTION**

### **3.1 GENERAL**

- .1 Perform preparation and operations for interior painting in accordance with MPI Maintenance Repainting Manual requirements except where otherwise specified.
- .2 Apply paint materials in accordance with paint manufacturer's written application instructions.

### **3.2 EXISTING CONDITIONS**

- .1 Prior to commencing Work, thoroughly examine Site conditions and existing interior substrates to be repainted. Report in writing to Contract Administrator damages, defects, or unsatisfactory or unfavourable conditions or surfaces that will adversely affect this work.
- .2 Conduct moisture testing of surfaces to be painted using a properly calibrated electronic moisture meter, except test concrete floors for moisture using a simple "cover patch test" and report findings to Contract Administrator. Maximum moisture content shall not exceed limits specified herein.
- .3 No repainting work shall commence until such adverse conditions and defects have been corrected and surfaces and conditions are acceptable to the Painting Subcontractor and Inspection Agency. Commencement of Work shall not be held to imply acceptance of surfaces except as qualified herein.
- .4 Degree of surface deterioration (DSD) shall be assessed using MPI Identifiers and Assessment criteria indicated in the MPI Maintenance Repainting Manual. MPI DSD ratings and descriptions are as follows:

<b>CONDITION</b>	<b>DESCRIPTION</b>
DSD-0	Sound Surface ( includes visual (aesthetic) defects that do not affect film's protective properties).
DSD-1	Slightly Deteriorated Surface (indicating fading; gloss reduction, slight surface contamination, minor pin holes scratches, etc.).
DSD-2	Moderately Deteriorated Surface (small areas of peeling, flaking, slight cracking, staining, etc.).
DSD-3	Severely Deteriorated Surface (heavy peeling, flaking, cracking, checking, scratches, scuffs, abrasion, small holes and gouges).
DSD-4	Substrate Damage (repair or replacement of surface required by others).

### **3.3 PROTECTION**

- .1 Protect existing surfaces and adjacent fixtures and furnishings from paint spatters, markings and other damage by suitable non-staining covers or masking. If damaged, clean and restore such surfaces as directed by Contract Administrator.
- .2 Protect items that are permanently attached such as Fire Labels on doors and frames.
- .3 Protect factory finished products and equipment.
- .4 Protect general public and building occupants in and about the building.
- .5 Removal of electrical cover plates, light fixtures, surface hardware on doors, bath accessories and surface mounted equipment, fittings and fastenings shall be done prior to undertaking re-painting operations by Contractor. Items shall be securely stored and re-installed by Contractor after painting is completed.
- .6 Move and cover furniture and portable equipment as necessary to carry out repainting operations. Replace as painting operations progress.
- .7 As repainting operations progress, place "WET PAINT" signs in occupied areas to approval of Contract Administrator.

### **3.4 CLEANING AND PREPARATION**

- .1 Clean and prepare interior surfaces to be repainted in accordance with MPI Maintenance Repainting Manual requirements. Refer to MPI Manual in regard to specific requirements and as follows:
  - .1 Remove dust, dirt, and surface debris by vacuuming, wiping with dry, clean cloths or compressed air.
  - .2 Remove chipped, loose, scaling, sealants and caulking materials, fasteners, adhesive residues etc. or other surface blemishes which would impair the final results.
  - .3 Patch small holes and depressions in drywall finishes with appropriate patching compound and sand flush with adjacent finish.

- .4 Wash surfaces with a biodegradable detergent and bleach where applicable and clean warm water using a stiff bristle brush to remove dirt, oil and surface contaminants.
  - .5 Rinse scrubbed surfaces with clean water until foreign matter is flushed from surface.
  - .6 Allow surfaces to drain completely and to dry thoroughly. Allow sufficient drying time and test surfaces using an electronic moisture meter before commencing work.
  - .7 Use water-based cleaners in place of organic solvents where surfaces will be repainted using water based paints.
  - .8 Many water-based paints cannot be removed with water once dried. Minimize the use of kerosene or such organic solvents to clean up water-based paints.
- .2 Clean metal surfaces to be repainted by removing rust, dirt, oil, grease and foreign substances in accordance with MPI requirements. Remove such contaminants from surfaces, pockets and corners to be repainted by brushing with clean brushes, blowing with clean dry compressed air, or brushing/vacuum cleaning as required.
  - .3 Prevent contamination of cleaned surfaces by salts, acids, alkalis, other corrosive chemicals, grease, oil and solvents before priming and between applications of remaining coats. Touch-up, spot prime, and apply primer, paint, or pre-treatment as soon as possible after cleaning and before deterioration occurs.
  - .4 Do not apply paint until prepared surfaces have been accepted by Contract Administrator.
  - .5 Sand and dust between coats as required to provide adequate adhesion for next coat and to remove defects visible from a distance up to 1000 mm.

### **3.5 APPLICATION**

- .1 Apply paint by method that is best suited for substrate being repainted using brush roller air sprayer and/or airless sprayer. Conform to manufacturer's application instructions unless specified otherwise. Methods of application shall be as pre-approved by Contract Administrator before commencing the work.
- .2 Brush and Roller Application:
  - .1 Apply paint in a uniform layer using brush and/or roller of types suitable for application.
  - .2 Work paint into cracks, crevices and corners.
  - .3 Paint surfaces and corners not accessible to brush using spray, daubers and/or sheepskins. Paint surfaces and corners not accessible to roller using brush, daubers or sheepskins.
  - .4 Brush and/or roll out runs and sags, and over-lap marks. Rolled surfaces shall be free of roller tracking and heavy stipple.
  - .5 Remove runs, sags and brush marks from finished work and repaint.

- .3 Spray Application:
  - .1 Provide and maintain equipment that is suitable for intended purpose, capable of properly atomizing paint to be applied, and equipped with suitable pressure regulators and gauges.
  - .2 Keep paint ingredients properly mixed in containers during paint application by continuous mechanical agitation intermittent agitation frequently as necessary.
  - .3 Apply paint in a uniform layer, with overlapping at edges of spray pattern.
  - .4 Back roll spray applications and brush out runs and sags immediately.
  - .5 Use brushes to work paint into cracks, crevices and places which are not adequately painted by spray.
- .4 Use dipping, sheepskins or daubers when no other method is practical in places of difficult access and when specifically authorized by Contract Administrator.
- .5 Apply paint coats in a continuous manner and allow surfaces to dry and properly cure between coats for minimum time period as recommended by manufacturer. Minimum dry film thickness of coats shall not be less than that recommended by the manufacturer. Repaint thin spots or bare areas before next coat of paint is applied.
- .6 Sand and dust between coats to remove visible defects.
- .7 Repaint surfaces both above and below sight lines as specified for surrounding surfaces, including such surfaces as tops of interior cupboards and cabinets and projecting ledges.
- .8 Repaint top, bottom, and vertical edges of doors to be repainted.
- .9 Repaint closets and alcoves to match existing, unless otherwise scheduled or noted.

### **3.6 MECHANICAL/ELECTRICAL EQUIPMENT**

- .1 Unless otherwise noted, repainting shall also include exposed to view/previously painted mechanical and electrical equipment and components (panels, conduits, piping, hangers, ductwork, ventilation fan enclosures, etc.).
- .2 Touch up scratches and marks and repaint such mechanical and electrical equipment and components with colour, and sheen finish to match existing unless otherwise noted or scheduled.
- .3 Do not paint over name plates or instruction labels.
- .4 Leave unfinished exposed conduits, piping, hangers, ductwork and other mechanical and electrical equipment in original finish.
- .5 Keep sprinkler heads free of paint.
- .6 Do not paint interior transformers and substation equipment.

### **3.7 CLEAN-UP**

- .1 Remove paint where spilled, splashed, splattered or sprayed as Work progresses using means and materials that are not detrimental to affected surfaces.
- .2 Keep Work area free from an unnecessary accumulation of tools, equipment, surplus materials and debris.
- .3 Remove combustible rubbish materials and empty paint cans each day and safely dispose of same in accordance with requirements of authorities having jurisdiction.
- .4 Clean equipment and dispose of wash water used for water borne materials, solvents used for oil based materials as well as other cleaning and protective materials (e.g. rags, drop cloths, masking papers, etc.), paints, thinners, paint removers/strippers in accordance with the safety requirements of authorities having jurisdiction and as noted herein.
- .5 Painting equipment shall be cleaned in leak-proof containers that will permit particulate matter to settle out and be collected. Sediment remaining from cleaning operations shall be recycled or disposed of in a manner acceptable to authorities having jurisdiction.
- .6 Paint and coatings in excess of repainting requirements shall be recycled as noted herein.

### **3.8 RESTORATION**

- .1 Clean and re-install hardware items removed before undertaken painting operations.
- .2 Remove protective coverings and warning signs as soon as practical after operations cease.
- .3 Remove paint splashings on affected exposed surfaces. Remove smears and spatter immediately as operations progress, using compatible solvent.
- .4 Protect freshly completed surfaces from paint droppings and dust to approval of Contract Administrator. Avoid scuffing newly applied paint.
- .5 Restore areas used for storage, cleaning, mixing and handling of paint to clean condition as approved by Contract Administrator.

**END OF SECTION**

**Part 1        General**

**1.1            SUBMITTALS**

- .1        Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2        Shop drawings to show:
  - .1        Mounting arrangements.
  - .2        Operating and maintenance clearances.
- .3        Shop drawings and product data accompanied by:
  - .1        Detailed drawings of bases, supports, and anchor bolts.
  - .2        Acoustical sound power data, where applicable.
  - .3        Points of operation on performance curves.
  - .4        Manufacturer to certify current model production.
  - .5        Certification of compliance to applicable codes.
- .4        In addition to transmittal letter referred to in Section 01 33 00 - Submittal Procedures: use MCAC "Shop Drawing Submittal Title Sheet". Identify section and paragraph number.
- .5        Closeout Submittals:
  - .1        Provide operation and maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.
  - .2        Operation and maintenance manual approved by, and final copies deposited with, Contract Administrator before final inspection.
  - .3        Operation data to include:
    - .1        Control schematics for systems including environmental controls.
    - .2        Description of systems and their controls.
    - .3        Description of operation of systems at various loads together with reset schedules and seasonal variances.
    - .4        Operation instruction for systems and component.
    - .5        Description of actions to be taken in event of equipment failure.
  - .4        Maintenance data to include: servicing, maintenance, operation and trouble-shooting instructions for each item of equipment.
    - .1        Data to include schedules of tasks, frequency, tools required and task time.
  - .5        Performance data to include:
    - .1        Equipment manufacturer's performance datasheets with point of operation as left after commissioning is complete.
    - .2        Equipment performance verification test results.
    - .3        Special performance data as specified.
    - .4        Testing, adjusting and balancing reports as specified in Section 23 05 93 - Testing, Adjusting and Balancing for HVAC.

**1.2 MAINTENANCE**

- .1 Furnish spare parts in accordance with Section 01 78 00 - Closeout Submittals as follows:
  - .1 One (1) filter cartridge or set of filter media for each filter or filter bank in addition to final operating set.
- .2 Provide one (1) set of special tools required to service equipment as recommended by manufacturers and in accordance with Section 01 78 00 - Closeout Submittals.

**Part 2 Products**

**2.1 NOT USED**

- .1 Not Used.

**Part 3 Execution**

**3.1 PAINTING, REPAIRS AND RESTORATION**

- .1 Do painting in accordance with Section 09 91 00 - Painting.
- .2 Prime and touch up marred finished paintwork to match original.
- .3 Restore to new condition, finishes which have been damaged.

**3.2 CLEANING**

- .1 Clean interior and exterior of all systems including strainers. Vacuum interior of ductwork and air handling units.

**3.3 FIELD QUALITY CONTROL**

- .1 Site Tests: conduct following tests and submit report as described in PART 1 - SUBMITTALS.
- .2 Manufacturer's Field Services:
  - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - SUBMITTALS.
  - .2 Provide manufacturer's field services consisting of product use recommendations and periodic Site visits for inspection of product installation in accordance with manufacturer's instructions.
  - .3 Schedule Site visits, to review Work, as directed in PART 1 - QUALITY ASSURANCE.

**3.4 DEMONSTRATION**

- .1 Contract Administrator will use equipment and systems for test purposes prior to acceptance. Supply labour, material, and instruments required for testing.

- .2 Supply tools, equipment and personnel to demonstrate and instruct operating and maintenance personnel in operating, controlling, adjusting, trouble-shooting and servicing of all systems and equipment during regular work hours, prior to acceptance.
- .3 Use operation and maintenance manual, as-built drawings, and audio visual aids as part of instruction materials.
- .4 Instruction duration time requirements as specified in appropriate sections.

**3.5 PROTECTION**

- .1 Protect equipment and systems openings from dirt, dust, and other foreign materials with materials appropriate to system.

**END OF SECTION**

**Part 1 General**

**1.1 SUMMARY**

.1 Section Includes:

- .1 Thermal insulation for piping and piping accessories in commercial type applications.

**1.2 REFERENCES**

.1 American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE)

- .1 ASHRAE Standard 90.1, Energy Standard for Buildings Except Low-Rise Residential Buildings (IESNA co-sponsored; ANSI approved; Continuous Maintenance Standard).

.2 American Society for Testing and Materials International (ASTM)

- .1 ASTM C335, Standard Test Method for Steady State Heat Transfer Properties of Horizontal Pipe Insulation.
- .2 ASTM C411, Standard Test Method for Hot-Surface Performance of High-Temperature Thermal Insulation.
- .3 ASTM C449/C449M, Standard Specification for Mineral Fiber-Hydraulic-Setting Thermal Insulating and Finishing Cement.
- .4 ASTM C533, Calcium Silicate Block and Pipe Thermal Insulation.
- .5 ASTM C547, Mineral Fiber Pipe Insulation.
- .6 ASTM C795, Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel.
- .7 ASTM C921, Standard Practice for Determining the Properties of Jacketing Materials for Thermal Insulation.

.3 Canadian General Standards Board (CGSB)

- .1 CGSB 51-GP-52Ma, Vapour Barrier, Jacket and Facing Material for Pipe, Duct and Equipment Thermal Insulation.

.4 Manufacturer's Trade Associations

- .1 Thermal Insulation Association of Canada (TIAC): National Insulation Standards.

.5 Underwriters' Laboratories of Canada (ULC)

- .1 CAN/ULC-S102, Surface Burning Characteristics of Building Materials and Assemblies.
- .2 CAN/ULC-S701, Thermal Insulation, Polystyrene, Boards and Pipe Covering.
- .3 CAN/ULC-S702, Thermal Insulation, Mineral Fibre, for Buildings
- .4 CAN/ULC-S702.2, Thermal Insulation, Mineral Fibre, for Buildings, Part 2: Application Guidelines.

### **1.3 DEFINITIONS**

- .1 For purposes of this section:
  - .1 "CONCEALED" - insulated mechanical services in suspended ceilings and non-accessible chases and furred-in spaces.
  - .2 "EXPOSED" - will mean "not concealed" as specified.
- .2 TIAC:
  - .1 CRF: Code Rectangular Finish.
  - .2 CPF: Code Piping Finish.

### **1.4 SUBMITTALS**

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
  - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
- .3 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
  - .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
  - .2 Instructions: submit manufacturer's installation instructions.

## **Part 2 Products**

### **2.1 FIRE AND SMOKE RATING**

- .1 In accordance with CAN/ULC-S102.
  - .1 Maximum flame spread rating: 25.
  - .2 Maximum smoke developed rating: 50.

### **2.2 INSULATION**

- .1 Mineral fibre specified includes glass fibre, rock wool, slag wool.
- .2 Thermal conductivity ("k" factor) not to exceed specified values at twenty-four (24) degrees Celsius mean temperature when tested in accordance with ASTM C335.
- .3 TIAC Code C-2: mineral fibre blanket faced with factory applied vapour retarder jacket (as scheduled in PART 3 of this section).
  - .1 Mineral fibre: to CAN/ULC-S702.
  - .2 Jacket: to CGSB 51-GP-52Ma.
  - .3 Maximum "k" factor: to CAN/ULC-S702.
- .4 TIAC Code A-2: rigid moulded calcium silicate in sections and blocks, and with special shapes to suit Project requirements.

- .1 Insulation: to ASTM C533.
- .2 Design to permit periodic removal and re-installation.

**2.3 INSULATION SECUREMENT**

- .1 Tape: self-adhesive, aluminum, plain, 50 mm wide minimum.
- .2 Contact adhesive: quick setting.
- .3 Canvas adhesive: washable.
- .4 Tie wire: 1.5 mm diameter stainless steel.
- .5 Bands: stainless steel, 19 mm wide, 0.5 mm thick.

**2.4 CEMENT**

- .1 Thermal insulating and finishing cement:
  - .1 Hydraulic setting or air drying on mineral wool, to ASTM C449/C449M.

**2.5 VAPOUR RETARDER LAP ADHESIVE**

- .1 Water based, fire retardant type, compatible with insulation.

**2.6 VAPOUR RETARDER FINISH**

- .1 Vinyl emulsion type acrylic, compatible with insulation.

**2.7 JACKETS**

- .1 Canvas:
  - .1 220 gm/m<sup>2</sup> cotton, plain weave, treated with dilute fire retardant lagging adhesive to ASTM C921.
  - .2 Lagging adhesive: compatible with insulation.
- .2 Stainless steel:
  - .1 Type: 304.
  - .2 Thickness: 0.25 mm.
  - .3 Finish: smooth.
  - .4 Joining: longitudinal and circumferential slip joints with 50 mm laps.
  - .5 Fittings: 0.5 mm thick die-shaped fitting covers with factory-attached protective liner.
  - .6 Metal jacket banding and mechanical seals: stainless steel, 19 mm wide, 0.5 mm thick at 300 mm spacing.

**2.8 WEATHERPROOF CAULKING FOR JACKETS INSTALLED OUTDOORS**

- .1 Caulking to: Section 07 92 10 - Joint Sealing.

**Part 3 Execution**

**3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

**3.2 PRE-INSTALLATION REQUIREMENT**

- .1 Pressure testing of piping systems and adjacent equipment to be complete, witnessed and certified.
- .2 Surfaces clean, dry, free from foreign material.

**3.3 INSTALLATION**

- .1 Install in accordance with TIAC National Standards.
- .2 Apply materials in accordance with manufacturer's instructions and this specification.
- .3 Use two layers with staggered joints when required nominal wall thickness exceeds 75 mm.
- .4 Maintain uninterrupted continuity and integrity of vapour retarder jacket and finishes.
  - .1 Install hangers, supports outside vapour retarder jacket.
- .5 Supports, Hangers:
  - .1 Apply high compressive strength insulation, suitable for service, at oversized saddles and shoes where insulation saddles have not been provided.

**3.4 INSTALLATION OF ELASTOMERIC INSULATION**

- .1 Insulation to remain dry. Overlaps to manufacturer's instructions. Ensure tight joints.
- .2 Provide vapour retarder as recommended by manufacturer.

**3.5 PIPING INSULATION SCHEDULES**

- .1 Includes valves, valve bonnets, strainers, flanges and fittings unless otherwise specified.
- .2 TIAC Code: C-2 with vapour retarder jacket.
  - .1 Seals: lap seal adhesive, lagging adhesive.
  - .2 Installation: TIAC Code: 1501-C.
- .3 TIAC Code: A-2.
  - .1 Seals: lap seal adhesive, lagging adhesive.
  - .2 Installation: TIAC Code: 1501-H.

- .4 Thickness of insulation as listed in following table.
- .1 Run-outs to individual units and equipment not exceeding 4000 mm long.
- .2 Do not insulate exposed runouts to plumbing fixtures, chrome plated piping, valves, fittings.

Application	Temp°C	TIAC code	Pipe sizes (NPS) and insulation thickness (mm)					
			Run out	to 1	1/4 to 2	1/2 to 4	5 to 6	8 & over
· Domestic CWS with vapour retarder		C-2	25	25	25	25	25	25

- .5 Finishes:
- .1 Exposed indoors: canvas.
- .2 Concealed, indoors: canvas on valves, fittings. No further finish.
- .3 Outdoors: water-proof SS jacket.
- .4 Finish attachments: SS bands, at 150 mm on centre. Seals: closed.
- .5 Installation: to appropriate TIAC code CRF/1 through CPF/5.

**3.6 CLEANING**

- .1 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

**END OF SECTION**

**Part 1      General**

**1.1      SECTION INCLUDES**

.1      Materials and installation for domestic water service used in the following:

.1      Polyvinyl chloride (PVC) domestic cold water services inside building.

**1.2      REFERENCES**

.1      American National Standards Institute (ANSI)/American Society of Mechanical Engineers International (ASME).

.1      ANSI/ASME B16.15, Cast Bronze Threaded Fittings, Classes 125 and 250.

.2      ANSI/ASME B16.18, Cast Copper Alloy Solder Joint Pressure Fittings.

.3      ANSI/ASME B16.22, Wrought Copper and Copper Alloy Solder Joint Pressure Fittings.

.4      ANSI/ASME B16.24, Cast Copper Alloy Pipe Flanges and Flanged Fittings, Class 150, 300, 400, 600, 900, 1500 and 2500.

.2      American Society for Testing and Materials International, (ASTM).

.1      ASTM A307, Standard Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.

.2      ASTM B88M, Standard Specification for Seamless Copper Water Tube (Metric).

.3      ASTM F492, Standard Specification for Propylene and Polypropylene (PP) Plastic-Lined Ferrous Metal Pipe and Fittings.

.3      American Water Works Association (AWWA).

.1      AWWA C111, Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings.

.4      Canadian Standards Association (CSA International).

.1      CSA B242, Groove and Shoulder Type Mechanical Pipe Couplings.

.5      Manufacturer's Standardization Society of the Valve and Fittings Industry (MSS).

.1      MSS-SP-67, Butterfly Valves.

.2      MSS-SP-70, Cast Iron Gate Valves, Flanged and Threaded Ends.

.3      MSS-SP-71, Cast Iron Swing Check Valves, Flanged and Threaded Ends.

.4      MSS-SP-80, Bronze Gate, Globe, Angle and Check Valves.

.6      National Research Council (NRC)/Institute for Research in Construction.

.1      National Plumbing Code of Canada complete with Manitoba Amendments (MPC).

**1.3      SUBMITTALS**

.1      Submittals in accordance with Section 01 33 00 - Submittal Procedures.

.2      Submit product data for following: valves.

- .3 Provide maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

## **Part 2 Products**

### **2.1 PIPING**

- .1 Domestic cold piping within building.
  - .1 Above ground: PVC: to CAN/CSA-B181.2.
  - .2 Buried or embedded: HDPE in long lengths and with no buried joints.

### **2.2 FITTINGS**

- .1 PVC: to CAN/CSA-B181.2.

### **2.3 JOINTS**

- .1 Rubber gaskets, latex-free 1.6 mm thick: to AWWA C111.
- .2 Bolts, nuts, hex head and washers: to ASTM A307, heavy series.
- .3 Teflon tape: for threaded joints.

### **2.4 BALL VALVES**

- .1 NPS 2 and under, threaded or solvent ends:
  - .1 PVC body, PVC and ABS ball, PTFE seat, EPDM O-Ring, ABS handle.

## **Part 3 Execution**

### **3.1 INSTALLATION**

- .1 Install in accordance with MPC and local authority having jurisdiction.
- .2 Assemble piping using fittings manufactured to ANSI standards.
- .3 Install CWS piping below and away from heat sources so as to maintain temperature of cold water.
- .4 Connect to fixtures and equipment in accordance with manufacturer's written instructions unless otherwise indicated.
- .5 Buried tubing:
  - .1 Lay in well compacted washed sand in accordance with AWWA Class B bedding.
  - .2 Bend tubing without crimping or constriction. Minimize use of fittings.

### **3.2 VALVES**

- .1 Isolate equipment, fixtures and branches with ball valves.

**3.3 PRESSURE TESTS**

- .1 Conform to requirements of Section 21 05 01 - Common Work Results - Mechanical.
- .2 Test pressure: greater of 1.5 times maximum system operating pressure or 860 kPa.

**3.4 PRE-START-UP INSPECTIONS**

- .1 Systems to be complete, prior to flushing, testing and start-up.
- .2 Verify that system can be completely drained.
- .3 Ensure that pressure booster systems are operating properly.
- .4 Ensure that air chambers, expansion compensators are installed properly.

**3.5 START-UP**

- .1 Timing: Start up after:
  - .1 Pressure tests have been completed.
  - .2 Certificate of static completion has been issued.
- .2 Start-up procedures:
  - .1 Establish circulation and ensure that air is eliminated.
  - .2 Check pressurization to ensure proper operation and to prevent water hammer, flashing and/or cavitation.
- .3 Rectify start-up deficiencies.

**END OF SECTION**

**Part 1        General**

**1.1            SUMMARY**

- .1 Section Includes:
  - .1 Materials and installation for plumbing specialties and accessories.

**1.2            REFERENCES**

- .1 American Society for Testing and Materials International (ASTM).
  - .1 ASTM A126, Specification for Gray Iron Castings for Valves, Flanges and Pipe Fittings.
  - .2 ASTM B62, Specification for Composition Bronze or Ounce Metal Castings.
- .2 American Water Works Association (AWWA).
  - .1 AWWA C700, Cold Water Meters-Displacement Type, Bronze Main Case.
  - .2 AWWA C701, Cold Water Meters-Turbine Type for Customer Service.
  - .3 AWWA C702-1, Cold Water Meters-Compound Type.
- .3 Canadian Standards Association (CSA International).
  - .1 CSA-B64 Series, Backflow Preventers and Vacuum Breakers.
  - .2 CSA-B79, Floor, Area and Shower Drains, and Cleanouts for Residential Construction.
  - .3 CSA-B356, Water Pressure Reducing Valves for Domestic Water Supply Systems.
- .4 Plumbing and Drainage Institute (PDI).
  - .1 PDI-G101, Testing and Rating Procedure for Grease Interceptors with Appendix of Sizing and Installation Data.
  - .2 PDI-WH201, Water Hammer Arresters Standard.

**1.3            SUBMITTALS**

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Shop Drawings:
  - .1 Submit shop drawings to indicate materials, finishes, method of anchorage, number of anchors, dimensions, construction and assembly details.
- .3 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .4 Instructions: submit manufacturer's installation instructions.
- .5 Manufacturers' Field Reports: manufacturers' field reports specified.

- .6 Closeout submittals: submit maintenance and engineering data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals, include:
  - .1 Description of plumbing specialties and accessories, giving manufacturers name, type, model, year and capacity.
  - .2 Details of operation, servicing and maintenance.
  - .3 Recommended spare parts list.

**Part 2 Products**

**2.1 BACK FLOW PREVENTERS**

- .1 Preventers: to CSA-B64 Series, reduced pressure principle type.
- .2 Acceptable Manufacturers: Watts

**2.2 WATER METERS**

- .1 Turbine type to AWWA C701 and as per City requirements.

**Part 3 Execution**

**3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and data sheet.

**3.2 INSTALLATION**

- .1 Install in accordance with provincial codes, and local authority having jurisdiction.
- .2 Install in accordance with manufacturer's instructions and as specified.

**3.3 WATER METERS**

- .1 Install water meter provided by local water authority.
- .2 Install water meter as indicated.

**3.4 START-UP**

- .1 Timing: start-up only after:
  - .1 Pressure tests have been completed.
  - .2 Disinfection procedures have been completed.
  - .3 Certificate of static completion has been issued.
  - .4 Water treatment systems operational.

**3.5 TESTING AND ADJUSTING**

- .1 Timing:
  - .1 After start-up deficiencies rectified.
  - .2 After certificate of completion has been issued by authority having jurisdiction.
- .2 Application tolerances:
  - .1 Pressure at fixtures:  $\pm[70]$  kPa.
  - .2 Flow rate at fixtures:  $\pm 20\%$ .
- .3 Vacuum breakers, backflow preventers:
  - .1 Test tightness, accessibility for O&M of cover and of valve.
  - .2 Simulate reverse flow and back-pressure conditions to test operation of vacuum breakers, backflow preventers.
  - .3 Verify visibility of discharge from open ports.
- .4 Access doors:
  - .1 Verify size and location relative to items to be accessed.

**END OF SECTION**

**Part 1 General**

**1.1 SUMMARY**

.1 Section Includes:

- .1 Hangers and supports for mechanical piping, ducting and equipment.

**1.2 REFERENCES**

.1 American National Standards Institute/American Society of Mechanical Engineers (ANSI/ASME)

- .1 ANSI/ASME B31.1, Power Piping.

.2 American Society for Testing and Materials International (ASTM)

- .1 ASTM A125, Specification for Steel Springs, Helical, Heat-Treated.
- .2 ASTM A307, Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.
- .3 ASTM A563, Specification for Carbon and Alloy Steel Nuts.

.3 Factory Mutual (FM)

.4 Manufacturer's Standardization Society of the Valves and Fittings Industry (MSS)

- .1 MSS SP58, Pipe Hangers and Supports - Materials, Design and Manufacture.
- .2 ANSI/MSS SP69, Pipe Hangers and Supports - Selection and Application.
- .3 MSS SP89, Pipe Hangers and Supports - Fabrication and Installation Practices.

.5 Underwriter's Laboratories of Canada (ULC)

**1.3 SYSTEM DESCRIPTION**

.1 Design Requirements:

- .1 Construct pipe hanger and support to manufacturer's recommendations utilizing manufacturer's regular production components, parts and assemblies.
- .2 Base maximum load ratings on allowable stresses prescribed by ASME B31.1 or MSS SP58.
- .3 Ensure that supports, guides, anchors do not transmit excessive quantities of heat to building structure.
- .4 Design hangers and supports to support systems under conditions of operation, allow free expansion and contraction, prevent excessive stresses from being introduced into pipework or connected equipment.
- .5 Provide for vertical adjustments after erection and during commissioning. Amount of adjustment in accordance with MSS SP58.

## **1.4 SUBMITTALS**

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit shop drawings and product data for following items:
  - .1 Bases, hangers and supports.
  - .2 Connections to equipment and structure.
  - .3 Structural assemblies.
- .3 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
  - .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
  - .2 Instructions: submit manufacturer's installation instructions.
- .4 Closeout Submittals:
  - .1 Provide maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

## **Part 2 Products**

### **2.1 GENERAL**

- .1 Fabricate hangers, supports and sway braces in accordance with ANSI B31.1 and MSS SP58.
- .2 Use components for intended design purpose only. Do not use for rigging or erection purposes.

### **2.2 PIPE HANGERS**

- .1 Finishes:
  - .1 Pipe hangers and supports: galvanized after manufacture.
  - .2 Use hot dipped galvanizing process.
  - .3 Ensure steel hangers in contact with copper piping are epoxy coated.
- .2 Hanger rods: threaded rod material to MSS SP58:
  - .1 Ensure that hanger rods are subject to tensile loading only.
  - .2 Provide linkages where lateral or axial movement of pipework is anticipated.
  - .3 Do not use 22 mm or 28 mm rod.
- .3 Pipe attachments: material to MSS SP58:
  - .1 Attachments for steel piping: carbon steel galvanized.
  - .2 Attachments for copper piping: copper plated black steel.
  - .3 Use insulation shields for hot pipework.
  - .4 Oversize pipe hangers and supports.

- .4 Adjustable clevis: material to MSS SP69 UL listed, clevis bolt with nipple spacer and vertical adjustment nuts above and below clevis.
  - .1 Ensure "U" has hole in bottom for rivetting to insulation shields.
- .5 Yoke style pipe roll: carbon steel yoke, rod and nuts with cast iron roll, to MSS SP69.
- .6 U-bolts: carbon steel to MSS SP69 with two (2) nuts at each end to ASTM A563.
  - .1 Finishes for steel pipework: galvanized.
  - .2 Finishes for copper, glass, brass or aluminum pipework: galvanized, with formed portion plastic coated.
- .7 Pipe rollers: cast iron roll and roll stand with carbon steel rod to MSS SP69.

### **2.3 RISER CLAMPS**

- .1 Steel or cast iron pipe: galvanized carbon steel to MSS SP58, type 42, UL listed.
- .2 Copper pipe: carbon steel copper plated to MSS SP58, type 42.
- .3 Bolts: to ASTM A307.
- .4 Nuts: to ASTM A563.

### **2.4 INSULATION PROTECTION SHIELDS**

- .1 Insulated cold piping:
  - .1 64 kg/m<sup>3</sup> density insulation plus insulation protection shield to: MSS SP69, galvanized sheet carbon steel. Length designed for maximum 3 m span.

### **2.5 EQUIPMENT ANCHOR BOLTS AND TEMPLATES**

- .1 Provide templates to ensure accurate location of anchor bolts.

## **Part 3 Execution**

### **3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

### **3.2 INSTALLATION**

- .1 Install in accordance with:
  - .1 Manufacturer's instructions and recommendations.
- .2 Clamps on riser piping:
  - .1 Support independent of connected horizontal pipework using riser clamps and riser clamp lugs welded to riser.

- .2 Bolt-tightening torques to industry standards.
- .3 Steel pipes: install below coupling or shear lugs welded to pipe.
- .4 Cast iron pipes: install below joint.
- .3 Clevis plates:
  - .1 Attach to concrete with four (4) minimum concrete inserts, one at each corner.
- .4 Provide supplementary structural steelwork where structural bearings do not exist or where concrete inserts are not in correct locations.

**3.3 HANGER SPACING**

- .1 Plumbing piping: to Provincial Code and authority having jurisdiction.
- .2 Fire protection: to applicable fire code.
- .3 PVC piping: up to NPS 1/2: every 1.5 m.
- .4 Flexible joint roll groove pipe: in accordance with table below, but not less than one hanger at joints.
- .5 Within 300 mm of each elbow.

Maximum Pipe Size : NPS	Maximum Spacing Steel	Maximum Spacing Copper
up to 1-1/4	2.1 m	1.8 m
1-1/2	2.7 m	2.4 m
2	3.0 m	2.7 m
2-1/2	3.6 m	3.0 m
3	3.6 m	3.0 m
3-1/2	3.9 m	3.3 m
4	4.2 m	3.6 m
5	4.8 m	
6	5.1 m	
8	5.7 m	
10	6.6 m	
12	6.9 m	

- .6 Pipework greater than NPS 12: to MSS SP69.

**3.4 HANGER INSTALLATION**

- .1 Install hanger so that rod is vertical under operating conditions.
- .2 Adjust hangers to equalize load.
- .3 Support from structural members. Where structural bearing does not exist or inserts are not in suitable locations, provide supplementary structural steel members.

### **3.5 HORIZONTAL MOVEMENT**

- .1 Angularity of rod hanger resulting from horizontal movement of pipework from cold to hot position not to exceed 4 degrees from vertical.
- .2 Where horizontal pipe movement is less than 13 mm, offset pipe hanger and support so that rod hanger is vertical in the hot position.

### **3.6 FINAL ADJUSTMENT**

- .1 Adjust hangers and supports:
  - .1 Ensure that rod is vertical under operating conditions.
  - .2 Equalize loads.
- .2 Adjustable clevis:
  - .1 Tighten hanger load nut securely to ensure proper hanger performance.
  - .2 Tighten upper nut after adjustment.
- .3 C-clamps:
  - .1 Follow manufacturer's recommended written instructions and torque values when tightening C-clamps to bottom flange of beam.

### **3.7 FIELD QUALITY CONTROL**

- .1 Manufacturer's Field Services:
  - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in Part 1 - Submittals.
  - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
  - .3 Schedule site visits, to review Work, as directed in Part 1 - Quality Assurance.

**END OF SECTION**

**Part 1 General**

**1.1 SUMMARY**

- .1 TAB is used throughout this Section to describe the process, methods and requirements of testing, adjusting and balancing for HVAC.
- .2 TAB means to test, adjust and balance to perform in accordance with requirements of Contract Documents and to do other work as specified in this section.

**1.2 QUALIFICATIONS OF TAB PERSONNEL**

- .1 Submit names of personnel to perform TAB to Contract Administrator within ninety (90) days of award of Contract.
- .2 Provide documentation confirming qualifications, successful experience.
- .3 TAB: performed in accordance with the requirements of standard under which TAB Firm's qualifications are approved:
  - .1 Associated Air Balance Council, (AABC) National Standards for Total System Balance, MN-1.
  - .2 National Environmental Balancing Bureau (NEBB) TABES, Procedural Standards for Testing, Adjusting, Balancing of Environmental Systems.
  - .3 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA), HVAC TAB HVAC Systems - Testing, Adjusting and Balancing.
- .4 Recommendations and suggested practices contained in the TAB Standard: mandatory.
- .5 Use TAB Standard provisions, including checklists, and report forms to satisfy Contract requirements.
- .6 Use TAB Standard for TAB, including qualifications for TAB Firm and Specialist and calibration of TAB instruments.
- .7 Where instrument manufacturer calibration recommendations are more stringent than those listed in TAB Standard, use manufacturer's recommendations.
- .8 TAB Standard quality assurance provisions such as performance guarantees form part of this Contract.
  - .1 For systems or system components not covered in TAB Standard, use TAB procedures developed by TAB Specialist.
  - .2 Where new procedures, and requirements, are applicable to Contract requirements have been published or adopted by body responsible for TAB Standard used (AABC, NEBB, or TABB), requirements and recommendations contained in these procedures and requirements are mandatory.

**1.3 PURPOSE OF TAB**

- .1 Test to verify proper and safe operation, determine actual point of performance, evaluate qualitative and quantitative performance of equipment, systems and controls at design, average and low loads using actual or simulated loads
- .2 Adjust and regulate equipment and systems to meet specified performance requirements and to achieve specified interaction with other related systems under normal and emergency loads and operating conditions.
- .3 Balance systems and equipment to regulate flow rates to match load requirements over full operating ranges.

**1.4 EXCEPTIONS**

- .1 TAB of systems and equipment regulated by codes, standards to satisfaction of authority having jurisdiction.

**1.5 CO-ORDINATION**

- .1 Schedule time required for TAB (including repairs, re-testing) into project construction and completion schedule to ensure completion before acceptance of project.
- .2 Do TAB of each system independently and subsequently, where interlocked with other systems, in unison with those systems.

**1.6 PRE-TAB REVIEW**

- .1 Review Contract documents before project construction is started and confirm in writing to Contact Administrator adequacy of provisions for TAB and other aspects of design and installation pertinent to success of TAB.
- .2 Review specified standards and report to Contact Administrator in writing proposed procedures which vary from standard.
- .3 During construction, co-ordinate location and installation of TAB devices, equipment, accessories, measurement ports and fittings.

**1.7 START-UP**

- .1 Follow start-up procedures as recommended by equipment manufacturer unless specified otherwise.
- .2 Follow special start-up procedures specified elsewhere in Division 23.

**1.8 OPERATION OF SYSTEMS DURING TAB**

- .1 Operate systems for length of time required for TAB and as required by Contract Administrator for verification of TAB reports.

**1.9 START OF TAB**

- .1 Notify Contract Administrator seven (7) days prior to start of TAB.
  - .1 Start TAB when building is essentially completed, including:
    - .2 Installation of ceilings, doors, windows, other construction affecting TAB.
    - .3 Application of weather-stripping, sealing, and caulking.
    - .4 Pressure, leakage, other tests specified elsewhere Division 23.
    - .5 Provisions for TAB installed and operational.
  - .2 Start-up, verification for proper, normal and safe operation of mechanical and associated electrical and control systems affecting TAB including but not limited to:
    - .1 Proper thermal overload protection in place for electrical equipment.
    - .2 Air systems:
      - .1 Filters in place, clean.
      - .2 Duct systems clean.
      - .3 Ducts, air shafts, ceiling plenums are airtight to within specified tolerances.
      - .4 Correct fan rotation.
      - .5 Fire, smoke, volume control dampers installed and open.
      - .6 Coil fins combed, clean.
      - .7 Access doors, installed, closed.
      - .8 Outlets installed, volume control dampers open.
    - .3 Liquid systems:
      - .1 Flushed, filled, vented.
      - .2 Correct pump rotation.
      - .3 Strainers in place, baskets clean.
      - .4 Isolating and balancing valves installed, open.
      - .5 Calibrated balancing valves installed, at factory settings.
      - .6 Chemical treatment systems complete, operational.

**1.10 APPLICATION TOLERANCES**

- .1 Do TAB to following tolerances of design values:
  - .1 HVAC systems:  $\pm 5\%$ .

**1.11 ACCURACY TOLERANCES**

- .1 Measured values accurate to within  $\pm 2\%$  of actual values.

**1.12 INSTRUMENTS**

- .1 Prior to TAB, submit to Contract Administrator list of instruments used together with serial numbers.
- .2 Calibrate in accordance with requirements of most stringent of referenced standard for either applicable system or HVAC system.

- .3 Calibrate within three (3) months of TAB. Provide certificate of calibration to Contract Administrator.

**1.13 SUBMITTALS**

- .1 Submit, prior to commencement of TAB:
- .2 Proposed methodology and procedures for performing TAB if different from referenced standard.

**1.14 PRELIMINARY TAB REPORT**

- .1 Submit for checking and approval of Contract Administrator, prior to submission of formal TAB report, sample of rough TAB sheets. Include:
  - .1 Details of instruments used.
  - .2 Details of TAB procedures employed.
  - .3 Calculations procedures.
  - .4 Summaries.

**1.15 TAB REPORT**

- .1 Format in accordance with referenced standard.
- .2 TAB report to show results in SI units and to include:
  - .1 Project record drawings.
  - .2 System schematics.
- .3 Submit TAB Report to Contract Administrator for verification and approval, complete with index tabs.

**1.16 VERIFICATION**

- .1 Reported results subject to verification by Contract Administrator.
- .2 Provide personnel and instrumentation to verify up to 30% of reported results.
- .3 Number and location of verified results as directed by Contract Administrator.
- .4 Pay costs to repeat TAB as required to satisfaction of Contract Administrator.

**1.17 SETTINGS**

- .1 After TAB is completed to satisfaction of Contract Administrator, replace drive guards, close access doors, lock devices in set positions, ensure sensors are at required settings.
- .2 Permanently mark settings to allow restoration at any time during life of facility. Do not eradicate or cover markings.

**1.18 COMPLETION OF TAB**

- .1 TAB considered complete when final TAB Report received and approved by Contract Administrator.

**1.19 AIR SYSTEMS**

- .1 Standard: TAB to most stringent of this section or TAB standards of AABC, NEBB, SMACNA, ASHRAE.
- .2 Do TAB of systems, equipment, components, controls specified Division 23.
- .3 Qualifications: personnel performing TAB current member in good standing of AABC or NEBB qualified to standards of AABC or NEBB.
- .4 Quality assurance: perform TAB under direction of supervisor qualified to standards of AABC or NEBB.
- .5 Measurements: to include as appropriate for systems, equipment, components, controls: air velocity, static pressure, flow rate, pressure drop (or loss), temperatures (dry bulb, wet bulb, dewpoint), duct cross-sectional area, RPM, electrical power, voltage, noise, vibration.
- .6 Locations of equipment measurements: to include as appropriate:
  - .1 Inlet and outlet of dampers, filter, coil, humidifier, fan, other equipment causing changes in conditions.
  - .2 At controllers, controlled device.
- .7 Locations of systems measurements to include as appropriate: main ducts, main branch, sub-branch, run-out (or grille, register or diffuser).

**1.20 OTHER TAB REQUIREMENTS**

- .1 General requirements applicable to work specified this paragraph:
  - .1 Qualifications of TAB personnel: as for air systems specified this section.
  - .2 Quality assurance: as for air systems specified this section.

**Part 2 Products**

**2.1 NOT USED**

- .1 Not used.

**Part 3 Execution**

**3.1 NOT USED**

- .1 Not used.

**END OF SECTION**

**Part 1        General**

**1.1        REFERENCES**

- .1 American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE)
  - .1 ANSI/ASHRAE/IESNA 90.1, SI; Energy Standard for Buildings Except Low-Rise Residential Buildings.
- .2 American Society for Testing and Materials International, (ASTM)
  - .1 ASTM B209M, Specification for Aluminum and Aluminum Alloy Sheet and Plate (Metric).
  - .2 ASTM C335, Test Method for Steady State Heat Transfer Properties of Horizontal Pipe Insulation.
  - .3 ASTM C411, Test Method for Hot-Surface Performance of High-Temperature Thermal Insulation.
  - .4 ASTM C449/C449M, Standard Specification for Mineral Fiber-Hydraulic-Setting Thermal Insulating and Finishing Cement.
  - .5 ASTM C547, Specification for Mineral Fiber Pipe Insulation.
  - .6 ASTM C553, Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications.
  - .7 ASTM C612, Specification for Mineral Fiber Block and Board Thermal Insulation.
  - .8 ASTM C795, Specification for Thermal Insulation for Use with Austenitic Stainless Steel.
  - .9 ASTM C921, Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel.
- .3 Canadian General Standards Board (CGSB)
  - .1 CGSB 51-GP-52Ma, Vapour Barrier, Jacket and Facing Material for Pipe, Duct and Equipment Thermal Insulation.
- .4 Thermal Insulation Association of Canada (TIAC): National Insulation Standards (R1999).
- .5 Underwriters Laboratories of Canada (ULC)
  - .1 CAN/ULC-S102, Surface Burning Characteristics of Building Materials and Assemblies.
  - .2 CAN/ULC-S701, Thermal Insulation Polyotrene, Boards and Pipe Covering.

**1.2        DEFINITIONS**

- .1 For purposes of this section:
  - .1 "CONCEALED" - insulated mechanical services and equipment in suspended ceilings and non-accessible chases and furred-in spaces.
  - .2 "EXPOSED" - will mean "not concealed" as defined herein.

- .3 Insulation systems - insulation material, fasteners, jackets, and other accessories.
- .2 TIAC Codes:
  - .1 CRD: Code Round Ductwork,
  - .2 CRF: Code Rectangular Finish.
- 1.3 SHOP DRAWINGS**
  - .1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
  - .2 Submit for approval manufacturer's catalogue literature related to installation, fabrication for duct jointing recommendations.
- 1.4 SAMPLES**
  - .1 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
  - .2 Submit for approval: complete assembly of each type of insulation system, insulation, coating, and adhesive proposed. Mount sample on 12 mm plywood board. Affix typewritten label beneath sample indicating service.
- 1.5 MANUFACTURERS' INSTRUCTIONS**
  - .1 Submit manufacturer's installation instructions in accordance with Section 01 33 00 - Submittal Procedures.
  - .2 Installation instructions to include procedures used and installation standards achieved.
- Part 2 Products**
  - 2.1 FIRE AND SMOKE RATING**
    - .1 In accordance with CAN/ULC-S102:
      - .1 Maximum flame spread rating: 25.
      - .2 Maximum smoke developed rating: 50.
  - 2.2 INSULATION**
    - .1 Mineral fibre: as specified includes glass fibre, rock wool, slag wool.
    - .2 Thermal conductivity ("k" factor) not to exceed specified values at 24°C mean temperature when tested in accordance with ASTM C335.
    - .3 TIAC Code C-1: Rigid mineral fibre board to ASTM C612, with factory applied vapour retarder jacket to CGSB 51-GP-52Ma (as scheduled in Part 3 of this Section).

- .4 TIAC Code C-2: Mineral fibre blanket to ASTM C553 faced with factory applied vapour retarder jacket to CGSB 51-GP-52Ma (as scheduled in Part 3 of this Section).
  - .1 Mineral fibre: to ASTM C553.
  - .2 Jacket: to CGSB 51-GP-52Ma.
  - .3 Maximum "k" factor: to ASTM C553.

### **2.3 JACKETS**

- .1 Canvas:
  - .1 220 gm/m<sup>2</sup> cotton, plain weave, treated with dilute fire retardant lagging adhesive to ASTM C921.
- .2 Lagging adhesive: Compatible with insulation.

### **2.4 ACCESSORIES**

- .1 Vapour retarder lap adhesive:
  - .1 Water based, fire retardant type, compatible with insulation.
- .2 Indoor Vapour Retarder Finish:
  - .1 Vinyl emulsion type acrylic, compatible with insulation.
- .3 Insulating Cement: hydraulic setting on mineral wool, to ASTM C449.
- .4 Tape: self-adhesive, aluminum, reinforced, 50 mm wide minimum.
- .5 Contact adhesive: quick-setting
- .6 Canvas adhesive: washable.
- .7 Tie wire: 1.5 mm stainless steel.
- .8 Banding: 19 mm wide, 0.5 mm thick stainless steel.

## **Part 3 Execution**

### **3.1 PRE-INSTALLATION REQUIREMENTS**

- .1 Pressure testing of ductwork systems complete, witnessed and certified.
- .2 Surfaces clean, dry, free from foreign material.

### **3.2 INSTALLATION**

- .1 Install in accordance with TIAC National Standards.
- .2 Apply materials in accordance with manufacturer's instructions and as indicated.
- .3 Use two layers with staggered joints when required nominal thickness exceeds 75 mm.

- .4 Maintain uninterrupted continuity and integrity of vapour retarder jacket and finishes.
  - .1 Hangers, supports to be outside vapour retarder jacket.
- .5 Supports, Hangers in accordance with Section 23 05 29 - Hangers and Supports for HVAC Piping and Equipment.
  - .1 Apply high compressive strength insulation where insulation may be compressed by weight of ductwork.
- .6 Fasteners: At 300 mm on centre in horizontal and vertical directions, minimum two (2) rows each side.

### 3.3 DUCTWORK INSULATION SCHEDULE

- .1 Insulation types and thicknesses: Conform to following table:

	<b>TIAC Code</b>	<b>Vapour Retarder</b>	<b>Thickness (mm)</b>
Rectangular cold and dual temperature supply air ducts	C-1	Yes	50
Round cold and dual temperature supply air ducts	C-2	Yes	50
Exhaust duct between dampers and louvres	C-1	Yes	25

**END OF SECTION**

**Part 1            General**

**1.1                SUMMARY**

- .1    Section Includes:
  - .1    Materials and installation procedures for electric heating and cooling controls.

**1.2                SUBMITTALS**

- .1    Product Data:
  - .1    Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
- .2    Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
  - .1    Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
  - .2    Instructions: submit manufacturer's installation instructions.

**Part 2            Products**

**2.1                THERMOSTAT (LOW VOLTAGE)**

- .1    Low voltage wall thermostat:
  - .1    For use on 24 V circuit at 1.5 A capacity.
  - .2    Temperature setting range: 10 to 40 degrees Celsius.
  - .3    With sub-base.

**2.2                CONTROLLER**

- .1    The ventilation system consists of the following components:
  - .1    Supply fan SF-L60
  - .2    Outside air damper MD-L60-1
  - .3    Recirculation air damper MD-L60-2
- .2    The ventilation system shall operate as follows:
  - .1    Interlock dampers MD-L60-1 and MD-L60-2 with Motor Room light switch. The supply fan SF-L60 operates continuously during occupied and unoccupied mode.
  - .2    When the Motor Room light switch is turned ON (occupied mode), damper MD-L60-1 is fully open and damper MD-L60-2 is fully closed.
  - .3    When the Motor Room light switch is turned OFF (unoccupied mode), dampers MD-L60-1 and MD-L60-2 will be positioned to provide 75% recirculated air and 25% outside air. The position of the dampers is to be

determined during air balancing to provide the required outside air and recirculated air flows.

- .4 Controls contractor shall be responsible for specifying all control wiring and controls to meet the sequence of operation.

### **Part 3 Execution**

#### **3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

#### **3.2 INSTALLATION**

- .1 Install control devices.
- .2 On outside wall, mount thermostats on bracket or insulated pad 25 mm from exterior wall.
- .3 Install remote sensing device and capillary tube in metallic conduit. Conduit enclosing capillary tube must not touch heater or heating cable.

#### **3.3 CLEANING**

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

**END OF SECTION**

**Part 1 General**

**1.1 SUMMARY**

.1 Section Includes:

.1 Materials and installation of low-pressure metallic ductwork, joints and accessories.

**1.2 REFERENCES**

.1 American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE).

.2 American Society for Testing and Materials International, (ASTM).

.1 ASTM A480/A480M, Standard Specification for General Requirements for Flat-Rolled Stainless and Heat-Resisting Steel Plate, Sheet and Strip.

.2 ASTM A635/A635M, Standard Specification for Steel, Sheet and Strip, Heavy-Thickness Coils, Carbon, Hot Rolled.

.3 ASTM A653/A653M, Standard Specification for Steel Sheet, Zinc Coated (Galvanized) or Zinc-Iron Alloy Coated (Galvannealed) by the Hot-Dip Process.

.3 National Fire Protection Association (NFPA).

.1 NFPA 90A, Standard for the Installation of Air-Conditioning and Ventilating Systems.

.2 NFPA 90B, Standard for the Installation of Warm Air Heating and Air-Conditioning Systems.

.3 NFPA 96, Standard for Ventilation Control and Fire Protection of Commercial Cooking Operations.

.4 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA).

.1 SMACNA HVAC Duct Construction Standards - Metal and Flexible.

.2 SMACNA HVAC Air Duct Leakage Test Manual.

.3 IAQ Guideline for Occupied Buildings Under Construction.

**1.3 SUBMITTALS**

.1 Submit shop drawings and product data in accordance with Section 01 33 00 - Submittal Procedures.

**Part 2 Products**

**2.1 SEAL CLASSIFICATION**

.1 Classification as follows:

Maximum Pressure Pa	SMACNA Seal Class
---------------------	-------------------

Maximum Pressure Pa	SMACNA Seal Class
500	C
250	C
125	C
125	Unsealed

- .2 Seal classification:
  - .1 Class A: longitudinal seams, transverse joints, duct wall penetrations and connections made airtight with sealant and tape.
  - .2 Class B: longitudinal seams, transverse joints and connections made airtight with sealant tape or combination thereof.
  - .3 Class C: transverse joints and connections made air tight with gaskets, sealant, tape, or combination thereof. Longitudinal seams unsealed.
  - .4 Unsealed seams and joints.

## 2.2 SEALANT

- .1 Sealant: oil resistant, polymer type flame resistant duct sealant. Temperature range of -30°C to 93°C.

## 2.3 TAPE

- .1 Tape: polyvinyl treated, open weave fiberglass tape, 50 mm wide.

## 2.4 DUCT LEAKAGE

- .1 In accordance with SMACNA HVAC Air Duct Leakage Test Manual.

## 2.5 FITTINGS

- .1 Fabrication: to SMACNA.
- .2 Radiused elbows.
  - .1 Rectangular: standard radius. Centreline radius: 1.5 times width of duct.
  - .2 Round: five piece. Centreline radius: 1.5 times diameter.
- .3 Mitred elbows, rectangular:
  - .1 To 400 mm: with single thickness turning vanes.
  - .2 Over 400 mm: with double thickness turning vanes.
- .4 Branches:
  - .1 Rectangular main and branch: with radius on branch 1.5 times width of duct 45 degrees entry on branch.
  - .2 Round main and branch: enter main duct at 45 degrees with conical connection.
  - .3 Provide volume control damper in branch duct near connection to main duct.
  - .4 Main duct branches: with splitter damper.

- .5 Transitions:
  - .1 Diverging: 20 degrees maximum included angle.
  - .2 Converging: 30 degrees maximum included angle.
- .6 Offsets:
  - .1 Full radiused elbows.
- .7 Obstruction deflectors: maintain full cross-sectional area.
  - .1 Maximum included angles: as for transitions.

## 2.6 DUCT MATERIAL

- .1 To SMACNA. Aluminum type: 3003-H-14 or 5052-H-32
- .2 Thickness, fabrication and reinforcement: to SMACNA.
- .3 Joints: to SMACNA.

## 2.7 HANGERS AND SUPPORTS

- .1 Hangers and Supports:
  - .1 Strap hangers: of same material as duct but next sheet metal thickness heavier than duct.
  - .2 Hanger configuration: to SMACNA.
  - .3 Hangers: galvanized steel angle with galvanized steel rods to SMACNA following table:

Duct Size (mm)	Angle Size (mm)	Rod Size (mm)
up to 750	25 x 25 x 3	6
751 to 1050	40 x 40 x 3	6
1051 to 1500	40 x 40 x 3	10
1501 to 2100	50 x 50 x 3	10
2101 to 2400	50 x 50 x 5	10
2401 and over	50 x 50 x 6	10

- .4 Upper hanger attachments:
  - .1 For concrete: manufactured concrete inserts.
  - .2 For steel joist: manufactured joist clamp.
  - .3 For steel beams: manufactured beam clamps.
  - .4 For wood trusses: steel plate washer

## Part 3 Execution

### 3.1 GENERAL

- .1 Do Work in accordance with SMACNA.
- .2 Do not break continuity of insulation vapour barrier with hangers or rods.

- .3 Support risers in accordance with SMACNA.
- .4 Install proprietary manufactured flanged duct joints in accordance with manufacturer's instructions.

**3.2 HANGERS**

- .1 Strap hangers: install in accordance with SMACNA.
- .2 Angle hangers: complete with locking nuts and washers.
- .3 Hanger spacing: in accordance with SMACNA as follows:

<b>Duct Size</b>	<b>Spacing</b>
(mm)	(mm)
to 1500	3000
1501 and over	2500

**3.3 SEALING AND TAPING**

- .1 Apply sealant to outside of joint to manufacturer's recommendations.
- .2 Bed tape in sealant and recoat with minimum of one (1) coat of sealant to manufacturers recommendations.

**3.4 LEAKAGE TESTS**

- .1 In accordance with SMACNA HVAC Duct Leakage Test Manual.
- .2 Make trial leakage tests as instructed to demonstrate workmanship.
- .3 Do not install additional ductwork until trial test has been passed.
- .4 Complete test before performance insulation or concealment Work.

**END OF SECTION**

**Part 1        General**

**1.1            SUMMARY**

.1        Section Includes:

.1            Materials and installation for duct accessories including flexible connections, access doors, vanes and collars.

**1.2            REFERENCES**

.1        Sheet Metal and Air Conditioning Contractors' National Association (SMACNA).

.1            SMACNA - HVAC Duct Construction Standards - Metal and Flexible

**1.3            SUBMITTALS**

.1        Submittals in accordance with Section 01 33 00 - Submittal Procedures.

.2        Product Data:

.1            Submit manufacturer's printed product literature, specifications and data sheet. Indicate the following:

- .1            Flexible connections
- .2            Duct access doors
- .3            Turning vanes
- .4            Instrument test ports

.3        Test Reports: submit certified test reports from approved independent testing laboratories indicating compliance with specifications for specified performance characteristics and physical properties.

.1            Certification of ratings: catalogue or published ratings to be those obtained from tests carried out by manufacturer or independent testing agency signifying adherence to codes and standards.

.4        Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.

.5        Instructions: submit manufacturer's installation instructions.

.6        Manufacturer's Field Reports: manufacturer's field reports specified.

.7        Closeout submittals: submit maintenance and engineering data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

**Part 2        Products**

**2.1            GENERAL**

.1        Manufacture in accordance with SMACNA - HVAC Duct Construction Standards.

## **2.2 FLEXIBLE CONNECTIONS**

- .1 Frame: galvanized sheet metal frame with fabric clenched by means of double locked seams.
- .2 Material:
  - .1 Fire resistant, self-extinguishing, neoprene coated glass fabric, temperature rated at -40°C to 90°C, density of 1.3 kg/m<sup>2</sup>.

## **2.3 ACCESS DOORS IN DUCTS**

- .1 Non-Insulated Ducts: sandwich construction of same material as duct, one sheet metal thickness heavier, minimum 0.6 mm thick complete with sheet metal angle frame.
- .2 Insulated Ducts: sandwich construction of same material as duct, one (1) sheet metal thickness heavier, minimum 0.6 mm thick complete with sheet metal angle frame and 25 mm thick rigid glass fibre insulation.
- .3 Gaskets: foam rubber.
- .4 Hardware:
  - .1 Up to 300 x 300 mm: two (2) sash locks
  - .2 301 to 450 mm: four sash locks
  - .3 Hold open devices

## **2.4 INSTRUMENT TEST**

- .1 1.6 mm thick steel zinc plated after manufacture.
- .2 Cam lock handles with neoprene expansion plug and handle chain.
- .3 28 mm minimum inside diameter. Length to suit insulation thickness.
- .4 Neoprene mounting gasket.

## **2.5 SPIN-IN COLLARS**

- .1 Conical galvanized sheet metal spin-in collars with lockable butterfly damper.
- .2 Sheet metal thickness to co-responding round duct standards.

## **Part 3 Execution**

### **3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and data sheet.

### 3.2 INSTALLATION

- .1 Flexible Connections:
  - .1 Install in following locations:
    - .1 Inlets and outlets to supply air units and fans
    - .2 Inlets and outlets of exhaust and return air fans
    - .3 As indicated
  - .2 Length of connection: 100 mm.
  - .3 Minimum distance between metal parts when system in operation: 75 mm.
  - .4 Install in accordance with recommendations of SMACNA.
  - .5 When fan is running:
    - .1 Ducting on sides of flexible connection to be in alignment
    - .2 Ensure slack material in flexible connection
- .2 Access Doors and Viewing Panels:
  - .1 Size:
    - .1 450 x 450 mm for servicing entry
    - .2 150 x 150 mm for viewing
    - .3 As indicated
  - .2 Locations:
    - .1 Devices requiring maintenance
    - .2 Required by code
    - .3 Elsewhere as indicated
- .3 Instrument Test Ports:
  - .1 General:
    - .1 Install in accordance with recommendations of SMACNA and in accordance with manufacturer's instructions.
  - .2 Locate to permit easy manipulation of instruments.
  - .3 Install insulation port extensions as required.
  - .4 Locations:
    - .1 For traverse readings:
      - .1 Ducted inlets to roof and wall exhausters
      - .2 Inlets and outlets of other fan systems
      - .3 Main and sub-main ducts
      - .4 And as indicated
    - .2 For temperature readings:
      - .1 At outside air intakes
      - .2 In mixed air applications in locations as indicated
      - .3 At inlet and outlet of coils
      - .4 Downstream of junctions of two (2) converging air streams of different temperatures
      - .5 As indicated

- .4 Turning vanes:
  - .1 Install in accordance with recommendations of SMACNA and as indicated.

**3.3 CLEANING**

- .1 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

**END OF SECTION**

**Part 1        General**

**1.1            SUMMARY**

.1            Section Includes:

- .1            Operating dampers for mechanical forced air ventilation and air conditioning systems.

**1.2            REFERENCES**

.1            American Society for Testing and Materials International (ASTM)

- .1            ASTM A653/A653M, Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by Hot-Dip Process.

**1.3            SUBMITTALS**

.1            Product Data:

- .1            Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.

.2            Closeout Submittals

- .1            Provide maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

**Part 2        Products**

**2.1            MULTI-LEAF DAMPERS**

.1            Opposed blade type.

.2            Extruded aluminum, interlocking blades, complete with extruded vinyl seals, spring stainless steel side seals, extruded aluminum frame.

.3            Pressure fit self-lubricated bronze bearings.

.4            Linkage: plated steel tie rods, brass pivots and plated steel brackets, complete with plated steel control rod.

.5            Operators: equal to Belimo

.6            Performance:

- .1            Leakage: in closed position less than 10% of rated air flow at 1 kPa differential across damper.
- .2            Pressure drop: at full open position less than 25 Pa differential across damper at 5 m/s.

.7            Insulated aluminum dampers:

- .1 Frames: insulated with extruded polystyrene foam with RSI 0.44.
- .2 Blades: constructed from aluminum extrusions thermally broken with internal hollows insulated with polyurethane or polystyrene foam, RSI 0.44.
- .8 Acceptable Manufacturers: Greenheck, Price, Ruskin, Ventex, TAMCO

**Part 3 Execution**

**3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

**3.2 INSTALLATION**

- .1 Install where indicated.
- .2 Install in accordance with recommendations of SMACNA and manufacturer's instructions.
- .3 Seal multiple damper modules with silicon sealant.
- .4 Install access door adjacent to each damper. See Section 23 33 00 - Air Duct Accessories.
- .5 Ensure dampers are observable and accessible.

**3.3 CLEANING**

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

**END OF SECTION**

**Part 1        General**

**1.1            SUMMARY**

.1        Section Includes:

.1            Materials and installation of flexible ductwork, joints and accessories.

**1.2            REFERENCES**

.1        American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE).

.2        National Fire Protection Association (NFPA).

.1            NFPA 90A, Standard for the Installation of Air-Conditioning and Ventilating Systems.

.2            NFPA 90B, Standard for Installation of Warm Air Heating and Air-Conditioning Systems.

.3        Sheet Metal and Air-Conditioning Contractors' National Association (SMACNA).

.1            SMACNA HVAC Duct Construction Standards - Metal and Flexible.

.2            SMACNA IAQ Guideline for Occupied Buildings under Construction.

.4        Underwriters' Laboratories Inc. (UL).

.1            UL 181, Standard for Factory-Made Air Ducts and Air Connectors.

.5        Underwriters' Laboratories of Canada (ULC).

.1            CAN/ULC-S110, Fire Tests for Air Ducts.

**1.3            SUBMITTALS**

.1        Make submittals in accordance with Section 01 33 00 - Submittal Procedures.

**Part 2        Products**

**2.1            GENERAL**

.1        Factory fabricated to CAN/ULC-S110.

.2        Pressure drop coefficients listed below are based on relative sheet metal duct pressure drop coefficient of 1.00.

.3        Flame spread rating not to exceed 25. Smoke developed rating not to exceed 50.

**2.2            METALLIC - UNINSULATED**

.1        Type 1: spiral wound flexible stainless steel, as indicated.

.2        Performance:

- .1 Factory tested to 2.5 kPa without leakage.
- .2 Maximum relative pressure drop coefficient: 3.

**2.3 METALLIC - INSULATED**

- .1 Type 2: spiral wound flexible aluminum with factory applied 37 mm thick flexible glass fibre thermal insulation with vapour barrier and reinforced mylar/neoprene laminate jacket, as indicated.
- .2 Performance:
  - .1 Factory tested to 2.5 kPa without leakage.
  - .2 Maximum relative pressure drop coefficient: 3.

**Part 3 Execution**

**3.1 DUCT INSTALLATION**

- .1 Install in accordance with: SMACNA.

**END OF SECTION**

**Part 1 General**

**1.1 SUMMARY**

.1 Section Includes:

- .1 Fans, motors, accessories and hardware for commercial use.

**1.2 REFERENCES**

.1 Air Conditioning and Mechanical Contractors (AMCA)

- .1 AMCA Publication 99, Standards Handbook.
- .2 AMCA 300, Reverberant Room Method for Sound Testing of Fans.
- .3 AMCA 301, Methods for Calculating Fan Sound Ratings from Laboratory Test Data.

.2 American National Standards Institute (ANSI)/American Society of Mechanical Engineers (ASME)

- .1 ANSI/AMCA 210, Laboratory Methods of Testing Fans for Aerodynamic Performance Rating.

.3 Canadian General Standards Board (CGSB)

- .1 CAN/CGSB 1.181, Ready-Mixed Organic Zinc-Rich Coating.

**1.3 SYSTEM DESCRIPTION**

.1 Performance Requirements:

- .1 Catalogued or published ratings for manufactured items: obtained from tests carried out by manufacturer or those ordered by manufacturer from independent testing agency signifying adherence to codes and standards in force.
- .2 Capacity: flow rate, external static pressure, bhp (W), efficiency, revolutions per minute, power, model, size, sound power data and as indicated on schedule.
- .3 Fans: statically and dynamically balanced, constructed in conformity with AMCA 99.
- .4 Sound ratings: comply with AMCA 301, tested to AMCA 300.
- .5 Performance ratings: based on tests performed in accordance with ANSI/AMCA 210.

**1.4 SUBMITTALS**

.1 Product Data:

- .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.

.2 Shop Drawings:

- .1 Submit shop drawings and product data in accordance with Section 01 33 00 - Submittal Procedures.
- .3 Provide:
  - .1 Fan performance curves showing point of operation, BHP (kW) and efficiency.
  - .2 Sound rating data at point of operation.
- .4 Indicate:
  - .1 Motors, sheaves, bearings, shaft details.
  - .2 Minimum performance achievable with variable speed controllers.
- .5 Closeout Submittals:
  - .1 Provide operation and maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

## **1.5 MAINTENANCE**

- .1 Extra Materials:
  - .1 Provide maintenance materials in accordance with Section 01 78 00 - Closeout Submittals.

## **1.6 DELIVERY, STORAGE, AND HANDLING**

- .1 Packing, shipping, handling and unloading:
  - .1 Deliver, store and handle materials in accordance with manufacturer's written instructions.

## **Part 2 Products**

### **2.1 FANS GENERAL**

- .1 Motors:
  - .1 For use with variable speed controllers.
  - .2 Sizes as indicated.
- .2 Factory primed before assembly in colour standard to manufacturer.
- .3 Scroll casing drains: as indicated.
- .4 Flexible connections: to Section 23 33 00 - Air Duct Accessories.

### **2.2 IN-LINE CENTRIFUGAL FANS**

- .1 Acceptable Manufacturers: Cook, Greenheck.

**Part 3 Execution**

**3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

**3.2 FAN INSTALLATION**

- .1 Install fans as indicated, complete with resilient mountings, flexible electrical leads and flexible connections.
- .2 Access doors and access panels to be easily accessible.

**CLEANING**

- .3 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

**END OF SECTION**

**Part 1        General**

**1.1            SUMMARY**

- .1    Section Includes:
  - .1        Mechanical louvers; intakes; vents; and reinforcement and bracing for air vents, and intakes.

**1.2            REFERENCES**

- .1    American National Standards Institute (ANSI)/ National Fire Protection Association (NFPA)
  - .1        ANSI/NFPA 96, Standard for Ventilation Control and Fire Protection of Commercial Cooking Operations.
- .2    American Society for Testing and Materials International (ASTM)
  - .1        ASTM E90, Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements.
- .3    Sheet Metal and Air Conditioning Contractors' National Association (SMACNA)
- .4    Society of Automotive Engineers (SAE)

**1.3            SYSTEM DESCRIPTION**

- .1    Performance Requirements:
  - .1        Catalogued or published ratings for manufactured items: obtained from tests carried out by manufacturer or those ordered by manufacturer from independent testing agency signifying adherence to codes and standards.

**1.4            SUBMITTALS**

- .1    Product Data:
  - .1        Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
  - .2        Indicate following:
    - .1            Pressure drop.
    - .2            Face area.
    - .3            Free area.

**Part 2        Products**

**2.1            FIXED LOUVRES - ALUMINUM**

- .1    Construction: welded with exposed joints ground flush and smooth.
- .2    Material: extruded aluminum alloy 6063-T5.

- .3 Blade: minimum 3mm thick with reinforcing bosses and maximum blade length of 1500 mm.
- .4 Frame, head, sill and jamb: 100 mm deep one piece extruded aluminum, minimum 3 mm thick with approved caulking slot, integral to unit.
- .5 Mullions: at 1500mm maximum centres.
- .6 Fastenings: stainless steel SAE-194-8F with SAE-194-SFB nuts and resilient neoprene washers between aluminum and head of bolt, or between nut, ss washer and aluminum body.
- .7 Screen: 12 mm mesh, 2 mm diameter wire aluminum birdscreen on inside face of louvres in formed U-frame.
- .8 Finish: anodized. Colour: to Contract Administrator's approval.
- .9 Acceptable Manufacturers: Greenheck, Price, Ruskin, Ventex.

### **Part 3 Execution**

#### **3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

#### **3.2 INSTALLATION**

- .1 In accordance with manufacturer's and SMACNA recommendations.
- .2 Reinforce and brace as indicated.
- .3 Anchor securely into opening. Seal with caulking to ensure weather tightness.

#### **3.3 CLEANING**

- .1 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

**END OF SECTION**

**Part 1        General**

**1.1        SUMMARY**

- .1        Section Includes:
  - .1        Materials and application of electric duct heaters.

**1.2        REFERENCES**

- .1        Canadian Standards Association (CSA International).
  - .1        CSA C22.2 No. 155– Electric Duct Heaters.

**1.3        PRODUCT DATA**

- .1        Submit product data in accordance with Section 01 33 00 - Submittal Procedures.
- .2        Submit product data sheets for unit heaters. Include:
  - .1        Product characteristics
  - .2        Performance criteria
  - .3        Mounting methods
  - .4        Physical size
  - .5        kW rating, voltage, phase
  - .6        Cabinet material thicknesses
  - .7        Limitations
  - .8        Colour and finish
- .3        Submit product data sheets for unit heaters.
  - .1        Include product characteristics, performance criteria, physical size, limitations and finish.

**1.4        CLOSEOUT SUBMITTALS**

- .1        Provide operation and maintenance data for unit heaters for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

**Part 2        Products**

**2.1        DUCT HEATERS**

- .1        Duct heaters: flange type.
- .1        Elements:
  - .1        Open coil.
- .2        Staging:
  - .1        Staged heaters: balanced line current at each stage.

- .2 Each stage: uniform face distribution.
- .3 Maximum temperature at discharge: 40°C.
- .4 Controls:
  - .1 Factory mounted and wired in control box. Use terminal blocks for power and control wiring to thermostat and sail switch.
  - .2 Controls mounted in a CSA type enclosure and to include:
    - .1 Magnetic contactors;
    - .2 Pneumatic electric relays;
    - .3 Control transformers; and,
    - .4 SCR controller.
  - .3 Where controls are mounted in heater, exercise care in mounting contactors to minimize switching noise transmission through ductwork.
  - .4 High temperature cut-out and air proving switch.
- .5 Electrical:
  - .1 As indicated on Drawings.
- .6 Main isolation disconnect switch.
- .7 Acceptable Manufacturers: Greenheck, Price, Thermolec.

**Part 3 Execution**

**3.1 INSTALLATION**

- .1 Make power and control connections to CSA C22.2 No.155.

**3.2 FIELD QUALITY CONTROL**

- .1 Perform tests in accordance with Section 26 05 00 - Common Work Results - Electrical.
- .2 Test cut-out protection when air movement is obstructed.
- .3 Test fan delay switch to assure dissipation of heat after element shut down.
- .4 Test unit cut-off when fan motor overload protection has operated.
- .5 Ensure heaters and controls operate correctly.

**END OF SECTION**

**Part 1        General**

**1.1        REFERENCES**

- .1        Canadian Standards Association (CSA International)
  - .1        CSA C22.2 No.46, Electric Air-Heaters.

**1.2        PRODUCT DATA**

- .1        Submit product data in accordance with Section 01 33 00 - Submittal Procedures.
- .2        Submit product data sheets for unit heaters. Include:
  - .1        Product characteristics
  - .2        Performance criteria
  - .3        Mounting methods
  - .4        Physical size
  - .5        kW rating, voltage, phase
  - .6        Cabinet material thicknesses
  - .7        Limitations
  - .8        Colour and finish
- .3        Submit product data sheets for unit heaters.
  - .1        Include product characteristics, performance criteria, physical size, limitations and finish.

**1.3        CLOSEOUT SUBMITTALS**

- .1        Provide operation and maintenance data for unit heaters for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

**Part 2        Products**

**2.1        UNIT HEATERS**

- .1        Unit heater: to CSA C22.2 No.46, horizontal discharge complete with adjustable louvers finished to match cabinet.
- .2        Hangers: as indicated.

**2.2        MANUFACTURERS**

- .1        Acceptable Manufacturers: Ouellete, Ruffneck.

**Part 3 Execution**

**3.1 INSTALLATION**

- .1 Suspend unit heaters from ceiling or mount on wall as indicated.
- .2 Make power and control connections.

**3.2 FIELD QUALITY CONTROL**

- .1 Perform tests in accordance with Section 26 05 00 - Common Work Results - Electrical.
- .2 Test cut-out protection when air movement is obstructed.
- .3 Test fan delay switch to assure dissipation of heat after element shut down.
- .4 Test unit cut-off when fan motor overload protection has operated.
- .5 Ensure heaters and controls operate correctly.

**END OF SECTION**

**Part 1 General**

**1.1 SUMMARY**

- .1 Section Includes:
  - .1 General requirements that are common to NMS sections found in Section 26 – Electrical.

**1.2 REFERENCES**

- .1 Canadian Standards Association (CSA International)
  - .1 CSA C22.1, Canadian Electrical Code, Part 1, Safety Standard for Electrical Installations.
  - .2 CAN3-C235, Preferred Voltage Levels for AC Systems, 0 to 50,000 V.
- .2 Electrical and Electronic Manufacturer's Association of Canada (EEMAC)
  - .1 EEMAC 2Y-1, Light Gray Colour for Indoor Switch Gear.
- .3 Health Canada / Workplace Hazardous Materials Information System (WHMIS)
  - .1 Material Safety Data Sheets (MSDS).
- .4 City of Winnipeg Water and Waste Department – Electrical Design Guide, Rev 01
- .5 City of Winnipeg Water and Waste Department – Automation Design Guide, Rev 00
- .6 City of Winnipeg Water and Waste Department – Identification Standard, Rev 00

**1.3 DESIGN REQUIREMENTS**

- .1 Operating voltages: to CAN3-C235.
- .2 Motors, electric heating, control and distribution devices and equipment to operate satisfactorily at 60 Hz within normal operating limits established by above standard.
  - .1 Equipment to operate in extreme operating conditions established in above standard without damage to equipment.
- .3 Language operating requirements: provide identification nameplates for control items in English.

**1.4 SUBMITTALS**

- .1 Quality Control:
  - .1 Provide CSA certified equipment and material.
  - .2 Where CSA certified equipment and material is not available, submit such equipment and material to authority having jurisdiction for special approval before delivery to Site.
  - .3 Submit test results of installed electrical systems and instrumentation.

- .4 Permits and fees: in accordance with General Conditions of Contract.
- .5 Submit certificate of acceptance from authority having jurisdiction upon completion of Work to Contract Administrator.
- .2 Manufacturer's Field Reports: submit to Contract Administrator manufacturer's written report, within three (3) days of review, verifying compliance of Work and electrical system and instrumentation testing, as described in Part 3 - Field Quality Control.

## **1.5 QUALITY ASSURANCE**

- .1 Quality Assurance:
- .2 Qualifications: electrical Work to be carried out by qualified, licensed electricians who hold valid Master Electrical Contractor license or apprentices in accordance with authorities having jurisdiction as per the conditions of Provincial Act respecting manpower vocational training and qualification.
  - .1 Employees registered in provincial apprentices program: permitted, under direct supervision of qualified licensed electrician, to perform specific tasks.
  - .2 Permitted activities: determined based on training level attained and demonstration of ability to perform specific duties.

## **1.6 SYSTEM STARTUP**

- .1 Instruct City's personnel in operation, care and maintenance of systems, system equipment and components.
- .2 Assist City's personnel and the Contract Administrator in the start-up of equipment.
- .3 Provide these services for such period, and for as many visits as necessary to put equipment in operation, and ensure that operating personnel are conversant with aspects of its care and operation.

## **1.7 Site**

- .1 Classification of Pumping Station Areas
  - .1 Building Superstructure: Ordinary
  - .2 Dry Well: Category 1

## **Part 2 Products**

### **2.1 MATERIALS AND EQUIPMENT**

- .1 Material and equipment to be CSA certified. Where CSA certified material and equipment are not available, obtain special approval from authority having jurisdiction before delivery to Site and submit such approval as described in Part 1 - Submittals.
- .2 Factory assemble control panels and component assemblies.

**2.2 ELECTRIC MOTORS, EQUIPMENT AND CONTROLS**

- .1 Verify installation and co-ordination responsibilities related to motors, equipment and controls, as indicated.
- .2 Control wiring and conduit: in accordance with Division 29.

**2.3 WARNING SIGNS**

- .1 Warning Signs: in accordance with requirements of inspection authorities.
- .2 Lamacoid signs, minimum size 175 x 250 mm.

**2.4 WIRING TERMINATIONS**

- .1 Ensure lugs, terminals, screws used for termination of wiring are suitable for either copper or aluminum conductors.

**2.5 EQUIPMENT IDENTIFICATION**

- .1 Identify electrical equipment with nameplates as follows:
  - .1 Nameplates: lamicoid 3 mm thick plastic engraving sheet, white with black core, lettering accurately aligned and engraved into core mechanically attached with self-tapping stainless steel screws.
  - .2 Lamacoids as follows:

Application	Text Size	Text
Electrical Equipment - General	5 mm	Line 1: Identifier
Circuit Breaker - Separate	5 mm	Line 1: Identifier Line 2: Load Identifier Line 3: Load Description
Disconnect Switch - Separate	5 mm	Line 1: Identifier Line 2: Load Identifier Line 3: Load Description
Fire Alarm Devices	8 mm	Line 1: Identifier
Light Switches	3 mm	Source Panel and Circuit Number
Motor Control Centre	8 mm	Line 1: Identifier Line 2: Description Line 3: System Voltage Line 4: Fed By
Motor Starter or MCC Bucket	5 mm	Line 1: Load Identifier Line 2: Load Description
Panelboards	8mm	Line 1: Identifier Line 2: Description Line 3: System Voltage Line 4: Fed By
Receptacles	3 mm	Source Panel and Circuit Number
Switchgear	8 mm	Line 1: Identifier Line 2: Description Line 3: System Voltage Line 4: Fed By

Application	Text Size	Text
Switchgear Breaker	8 mm	Line 1: Identifier Line 2: Description Line 3: System Voltage Line 4: Fed By
Transformer - Indoor	8 mm	Line 1: Identifier Line 2: Rating, System Voltage Line 3: Fed By
Transformer – Outdoor	10 mm	Line 1: Identifier Line 2: Rating, System Voltage Line 3: Fed By

- .2 Wording on nameplates to be approved Contract Administrator prior to manufacture.

**2.6 WIRING IDENTIFICATION**

- .1 Identify wiring with permanent indelible identifying markings, coloured plastic tapes, on both ends of phase conductors of feeders and branch circuit wiring.
- .2 Maintain phase sequence and colour coding throughout.
- .3 Colour coding: to CSA C22.1.
- .4 Use colour coded wires in communication cables, matched throughout system.

**2.7 CONDUIT AND CABLE IDENTIFICATION**

- .1 Colour code conduits, boxes, and metallic sheathed cables.
- .2 Code with plastic tape or paint at points where conduit or cable enters wall, ceiling, or floor, and at 15m intervals.
- .3 Colours: 25 mm wide prime colour and 20 mm wide auxiliary colour.
- .4 Colour Codes

	Prime	Auxiliary
Power, 120/208/240 VAC	Black	
UPS Power, 120/208/240 VAC	Black	Green
Control Wiring, 120VAC	Black	Orange
Fire Alarm	Red	
Low Voltage Communication/General	Blue	
Low Voltage Control Wiring, <50 V	Blue	Orange
Intrinsically Safe	Blue	White
up to 250 V	Yellow	
up to 600 V	Yellow	Green
Other Communication Systems	Green	Blue

- .5 Cable Colour Codes

	Prime	Auxiliary
Power, 120/208/240 VAC	Black	

	<b>Prime</b>	<b>Auxiliary</b>
UPS Power, 120/208/240 VAC	Black	Green
Control Wiring, 120VAC	Black	Orange
Fire Alarm	Red	
Low Voltage Communication/General	Blue	
Low Voltage Control Wiring, <50 V	Blue	Orange
Intrinsically Safe	Blue	White
up to 600 V	Yellow	Green
Other Communication Systems	Green	Blue

**2.8 FINISHES**

- .1 Shop finish metal enclosure surfaces by application of rust resistant primer inside and outside, and at least two (2) coats of finish enamel.
  - .1 Paint outdoor electrical equipment "equipment green" finish.
  - .2 Paint indoor switchgear and distribution enclosures light gray to EEMAC 2Y-1.

**Part 3 Execution**

**3.1 INSTALLATION**

- .1 Do complete installation in accordance with CSA C22.1 except where specified otherwise.
- .2 Do overhead and underground systems in accordance with CSA C22.3 No.1 except where specified otherwise.

**3.2 NAMEPLATES AND LABELS**

- .1 Ensure manufacturer's nameplates, CSA labels and identification nameplates are visible and legible after equipment is installed.

**3.3 MOUNTING HEIGHTS**

- .1 Mounting height of equipment is from finished floor to centreline of equipment unless specified or indicated otherwise.
- .2 If mounting height of equipment is not specified or indicated, verify before proceeding with installation.
- .3 Install electrical equipment at following heights unless indicated otherwise.
  - .1 Local switches: 1400 mm.
  - .2 Wall receptacles:
    - .1 General: 300 mm.
    - .2 In mechanical rooms: 1400 mm.
  - .3 Panelboards: as required by Code or as indicated.
  - .4 Control panels: as indicated.

**3.4 CO-ORDINATION OF PROTECTIVE DEVICES**

- .1 Ensure circuit protective devices such as overcurrent trips, relays, and fuses are installed to required values and settings.

**3.5 FIELD QUALITY CONTROL**

- .1 Conduct following tests:
  - .1 Circuits originating from branch distribution panels.
  - .2 Lighting and its control.
  - .3 Insulation resistance testing:
    - .1 Megger circuits, feeders and equipment up to 350 V with a 500 V instrument.
    - .2 Megger 350-600 V circuits, feeders and equipment with a 1000 V instrument.
    - .3 Check resistance to ground before energizing.
- .2 Carry out tests in presence of Contract Administrator.
- .3 Provide instruments, meters, equipment and personnel required to conduct tests during and at conclusion of Project.

**3.6 CLEANING**

- .1 Clean and touch up surfaces of shop-painted equipment scratched or marred during shipment or installation, to match original paint.
- .2 Clean and prime exposed non-galvanized hangers, racks and fastenings to prevent rusting.

**END OF SECTION**

**Part 1        General**

**1.1            SECTION INCLUDES**

- .1        Materials and installation for wire and box connectors.

**1.2            REFERENCES**

- .1        Canadian Standards Association (CSA International)
  - .1        CAN/CSA-C22.2No.18, Outlet Boxes, Conduit Boxes, Fittings and Associated Hardware.
  - .2        CSA C22.2No.65, Wire Connectors.
- .2        Electrical and Electronic Manufacturers' Association of Canada (EEMAC)
  - .1        EEMAC 1Y-2, Bushing Stud Connectors and Aluminum Adapters (1200 Ampere Maximum Rating).
- .3        National Electrical Manufacturers Association (NEMA)

**Part 2        Products**

**2.1            MATERIALS**

- .1        Pressure type wire connectors to: CSA C22.2No.65, with current carrying parts of copper sized to fit copper conductors as required.
- .2        Fixture type splicing connectors to: CSA C22.2No.65, with current carrying parts of copper sized to fit copper conductors 10 AWG or less.
- .3        Bushing stud connectors: to EEMAC 1Y-2 to consist of:
  - .1        Connector body and stud clamp for stranded copper conductors.
  - .2        Clamp for stranded copper conductors.
  - .3        Stud clamp bolts.
  - .4        Bolts for copper conductors.
  - .5        Sized for conductors as indicated.
- .4        Clamps or connectors for armoured cable, flexible conduit, non-metallic sheathed cable as required to: CAN/CSA-C22.2No.18.

**Part 3        Execution**

**3.1            INSTALLATION**

- .1        Remove insulation carefully from ends of conductors and:
  - .1        Install mechanical pressure type connectors and tighten screws with appropriate compression tool recommended by manufacturer. Installation shall meet secureness tests in accordance with CSA C22.2No.65.
  - .2        Install fixture type connectors and tighten. Replace insulating cap.

- .3 Install bushing stud connectors in accordance with EEMAC 1Y-2.

**END OF SECTION**

**Part 1        General**

**1.1            RELATED SECTIONS**

- .1        Section 26 05 20 - Wire and Box Connectors - 0 - 1000 V.

**1.2            REFERENCES**

- .1        CSA C22.2 No.0.3, Test Methods for Electrical Wires and Cables.
- .2        CAN/CSA-C22.2 No.131, Type TECK 90 Cable.

**Part 2        Products**

**2.1            BUILDING WIRES**

- .1        Conductors: stranded for 10 AWG and larger. Minimum size: 12 AWG.
- .2        Copper conductors: size as indicated, with thermoplastic insulation type TWU or TWH rated at 600 V.

**2.2            TECK CABLE**

- .1        Cable: to CAN/CSA-C22.2 No.131.
- .2        Conductors:
  - .1        Grounding conductor: copper.
  - .2        Circuit conductors: copper, size as indicated.
- .3        Insulation:
  - .1        Chemically cross-linked thermosetting polyethylene rated type RW90, 1000 V.
- .4        Inner jacket: polyvinyl chloride material.
- .5        Armour: interlocking aluminum.
- .6        Overall covering: thermoplastic polyvinyl chloride material.
- .7        Fastenings:
  - .1        One-hole stainless steel straps to secure surface cables 50 mm and smaller. Two-hole stainless steel straps for cables larger than 50 mm.
  - .2        Channel type supports for two (2) or more cables at 900 mm centers.
  - .3        Stainless steel threaded rods: 6 mm dia. to support suspended channels.
- .8        Connectors

**2.3 CONTROL CABLES**

- .1 Type LVT: soft annealed copper conductors, sized as indicated, with thermoplastic insulation, outer covering of thermoplastic jacket.
- .2 600 V type: stranded annealed copper conductors, sizes as indicated with PVC insulation type TW, or cross-linked polyethylene type RW90 (x-link with shielding of metallized tapes over each pair of conductors and overall covering of thermoplastic jacket interlocked armour and jacket over sheath of PVC.

**Part 3 Execution**

**3.1 INSTALLATION OF TECK CABLE 0 -1000 V**

- .1 Install cables.
  - .1 Group cables wherever possible on channels.
- .2 Lay cable in cabletroughs/cable tray in accordance with Section 26 05 36.
- .3 Terminate cables in accordance with Section 26 05 20- Wire and Box Connectors - 0 - 1000 V.

**3.2 INSTALLATION OF CONTROL CABLES**

- .1 Install control cables in conduit.
- .2 Group armoured control cables wherever possible on channels.
- .3 Ground control cable shield at one end only.

**END OF SECTION**

**Part 1        General**

**1.1            RELATED SECTIONS**

- .1        Section 26 05 00 - Common Work Results - Electrical.

**1.2            REFERENCES**

- .1        American National Standards Institute (ANSI)/Institute of Electrical and Electronics Engineers (IEEE)
  - .1        ANSI/IEEE 837, Qualifying Permanent Connections Used in Substation Grounding.
- .2        Canadian Standards Association, (CSA International)

**Part 2        Products**

**2.1            EQUIPMENT**

- .1        Clamps for grounding of conductor: size as required to electrically conductive underground water pipe.
- .2        Rod electrodes: copper clad steel 19 mm dia. by 3 m long.
- .3        Grounding conductors: bare stranded copper, soft annealed, size as indicated.
- .4        Insulated grounding conductors: green, type RW90.
- .5        Ground bus: copper, size as required, complete with insulated supports, fastenings, connectors.
- .6        Non-corroding accessories necessary for grounding system, type, size, material as indicated, including but not necessarily limited to:
  - .1        Grounding and bonding bushings.
  - .2        Protective type clamps.
  - .3        Bolted type conductor connectors.
  - .4        Thermit welded type conductor connectors.
  - .5        Bonding jumpers, straps.
  - .6        Pressure wire connectors.

**Part 3        Execution**

**3.1            INSTALLATION GENERAL**

- .1        Install complete permanent, continuous grounding system including, electrodes, conductors, connectors, accessories.
- .2        Install connectors in accordance with manufacturer's instructions.

- .3 Protect exposed grounding conductors from mechanical injury.
- .4 Make buried connections, and connections to conductive water main, electrodes, using copper welding by thermit process.
- .5 Use mechanical connectors for grounding connections to equipment provided with lugs.
- .6 Soldered joints not permitted.
- .7 Install bonding wire for flexible conduit, connected at both ends to grounding bushing, solderless lug, clamp or cup washer and screw. Neatly cleat bonding wire to exterior of flexible conduit.
- .8 Install flexible ground straps for bus duct enclosure joints, where such bonding is not inherently provided with equipment.
- .9 Bond single conductor, metallic armoured cables to cabinet at supply end, and provide non-metallic entry plate at load end.
- .10 Ground secondary service pedestals.

### **3.2 ELECTRODES**

- .1 Install rod electrodes and make grounding connections.
- .2 Bond separate, multiple electrodes together.
- .3 Use size 2/0AWG copper conductors for connections to electrodes.

### **3.3 SYSTEM AND CIRCUIT GROUNDING**

- .1 Install system and circuit grounding connections to neutral of primary 600 V system, secondary 208 V system.

### **3.4 EQUIPMENT GROUNDING**

- .1 Install grounding connections to typical equipment included in, but not necessarily limited to following list. Service equipment, transformers, switchgear, duct systems, frames of motors, motor control centres, starters, control panels, building steel work, generators, elevators and escalators, distribution panels, outdoor lighting.

### **3.5 GROUNDING BUS**

- .1 Install copper grounding bus mounted on insulated supports on wall.
- .2 Ground items of electrical equipment in electrical room to ground bus with individual bare stranded copper connections sized in accordance with the Canadian Electrical Code.

**3.6 FIELD QUALITY CONTROL**

- .1 Perform tests in accordance with Section 26 05 00 - Common Work Results - Electrical.
- .2 Perform ground continuity and resistance tests using method appropriate to Site conditions and to approval of Contract Administrator.
- .3 Perform tests before energizing electrical system.

**END OF SECTION**

**Part 1        General**

**1.1        RELATED SECTIONS**

- .1        Not Used

**Part 2        Products**

**2.1        SUPPORT CHANNELS**

- .1        U shape aluminum, size 41 x 41 mm, 2.5 mm thick, surface mounted or suspended.

**Part 3        Execution**

**3.1        INSTALLATION**

- .1        Secure equipment to hollow or solid masonry, tile and plaster surfaces with lead anchors.
- .2        Secure equipment to poured concrete with expandable inserts.
- .3        Secure equipment to hollow masonry walls or suspended ceilings with toggle bolts.
- .4        Support equipment, conduit or cables using clips, spring loaded bolts, cable clamps designed as accessories to basic channel members.
- .5        Fasten exposed conduit or cables to building construction or support system using straps.
  - .1        One-hole stainless steel straps to secure surface conduits and cables 50 mm and smaller.
  - .2        Two-hole stainless steel straps for conduits and cables larger than 50 mm.
  - .3        Beam clamps to secure conduit to exposed steel work.
- .6        Suspended support systems.
  - .1        Support individual cable or conduit runs with 6 mm dia. threaded rods and spring clips.
  - .2        Support two (2) or more cables or conduits on channels supported by 6 mm dia. threaded rod hangers where direct fastening to building construction is impractical.
- .7        For surface mounting of two or more conduits use channels at 1 m on center spacing.
- .8        Provide metal brackets, frames, hangers, clamps, and related types of support structures where indicated or as required to support conduit and cable runs.

- .9 Ensure adequate support for raceways and cables dropped vertically to equipment where there is no wall support.
- .10 Do not use wire lashing or perforated strap to support or secure raceways or cables.
- .11 Do not use supports or equipment installed for other trades for conduit or cable support except with permission of other trade and approval of Contract Administrator.
- .12 Install fastenings and supports as required for each type of equipment cables and conduits, and in accordance with manufacturer's installation recommendations.

**END OF SECTION**

**Part 1        General**

**1.1            SHOP DRAWINGS AND PRODUCT DATA**

- .1        Submit shop drawings and product data for cabinets in accordance with Section 01 33 00 - Submittal Procedures.

**Part 2        Products**

**2.1            SPLITTERS**

- .1        Sheet metal enclosure, welded corners and formed hinged cover suitable for locking in closed position.
- .2        Main and branch lugs to match required size and number of incoming and outgoing conductors as indicated.
- .3        At least three (3) spare terminals on each set of lugs in splitters less than 400 A.

**2.2            JUNCTION AND PULL BOXES**

- .1        Welded steel construction with screw-on flat covers for surface mounting.
- .2        Covers with 25 mm minimum extension all around, for flush-mounted pull and junction boxes.

**2.3            CABINETS**

- .1        Type E: sheet steel, hinged door and return flange overlapping sides, handle, lock and catch, for surface mounting.
- .2        Type T: sheet steel cabinet, with hinged door, latch, lock, two (2) keys, containing sheet steel backboard for surface mounting.

**Part 3        Execution**

**3.1            SPLITTER INSTALLATION**

- .1        Install splitters and mount plumb, true and square to the building lines.
- .2        Extend splitters full length of equipment arrangement except where indicated otherwise.

**3.2            JUNCTION, PULL BOXES AND CABINETS INSTALLATION**

- .1        Install pull boxes in inconspicuous but accessible locations.
- .2        Mount cabinets with top not higher than 2 m above finished floor.
- .3        Install terminal block as indicated in Type T cabinets.

- .4 Only main junction and pull boxes are indicated. Install pull boxes so as not to exceed 30 m of conduit run between pull boxes.

**3.3 IDENTIFICATION**

- .1 Provide equipment identification in accordance with Section 26 05 00 - Common Work Results - Electrical.
- .2 Install size 2 identification labels indicating system name, voltage and phase.

**END OF SECTION**

**Part 1        General**

**1.1            REFERENCES**

- .1        CSA C22.1, Canadian Electrical Code, Part 1.

**Part 2        Products**

**2.1            OUTLET AND CONDUIT BOXES GENERAL**

- .1        Size boxes in accordance with CSA C22.1.
- .2        102 mm square or larger outlet boxes as required for special devices.
- .3        Gang boxes where wiring devices are grouped.
- .4        Blank cover plates for boxes without wiring devices.
- .5        347 V outlet boxes for 347 V switching devices.
- .6        Combination boxes with barriers where outlets for more than one (1) system are grouped.

**2.2            SHEET STEEL OUTLET BOXES**

- .1        Electro-galvanized steel single and multi gang flush device boxes for flush installation, minimum size 76 x 50 x 38 mm or as indicated. 102 mm square outlet boxes when more than one (1) conduit enters one side with extension and plaster rings as required.
- .2        Electro-galvanized steel utility boxes for outlets connected to surface-mounted EMT conduit, minimum size 102 x 54 x 48 mm.
- .3        102 mm square or octagonal outlet boxes for lighting fixture outlets.

**2.3            MASONRY BOXES**

- .1        Electro-galvanized steel masonry single and multi gang boxes for devices flush mounted in exposed block walls.

**2.4            CONCRETE BOXES**

- .1        Electro-galvanized sheet steel concrete type boxes for flush mount in concrete with matching extension and plaster rings as required.

**2.5            CONDUIT BOXES**

- .1        Cast FS or FD aluminum boxes with factory-threaded hubs and mounting feet for surface wiring of switches and receptacle.

**2.6 FITTINGS - GENERAL**

- .1 Bushing and connectors with nylon insulated throats.
- .2 Knock-out fillers to prevent entry of debris.
- .3 Conduit outlet bodies for conduit up to 32 mm and pull boxes for larger conduits.
- .4 Double locknuts and insulated bushings on sheet metal boxes.

**Part 3 Execution**

**3.1 INSTALLATION**

- .1 Support boxes independently of connecting conduits.
- .2 Fill boxes with paper, sponges or foam or similar approved material to prevent entry of debris during construction. Remove upon completion of work.
- .3 For flush installations mount outlets flush with finished wall using plaster rings to permit wall finish to come within 6 mm of opening.
- .4 Provide correct size of openings in boxes for conduit, mineral insulated and armoured cable connections. Reducing washers are not allowed.

**END OF SECTION**

**Part 1            General**

**1.1                REFERENCES**

- .1 Canadian Standards Association (CSA)
  - .1 CAN/CSA C22.2 No. 18, Outlet Boxes, Conduit Boxes, and Fittings and Associated Hardware.
  - .2 CSA C22.2 No. 45, Rigid Metal Conduit.
  - .3 CSA C22.2 No. 56, Flexible Metal Conduit and Liquid-Tight Flexible Metal Conduit.
  - .4 CSA C22.2 No. 83, Electrical Metallic Tubing.
  - .5 CSA C22.2 No. 211.2 Rigid PVC (Unplasticized) Conduit.
  - .6 CAN/CSA C22.2 No. 227.3, Flexible Nonmetallic Tubing.

**Part 2            Products**

**2.1                CONDUITS**

- .1 Rigid metal conduit: to CSA C22.2 No. 45, aluminum threaded.
- .2 Epoxy coated conduit: to CSA C22.2 No. 45, with zinc coating and corrosion resistant epoxy finish inside and outside.
- .3 Flexible metal conduit: to CSA C22.2 No. 56, liquid-tight flexible metal.

**2.2                CONDUIT FASTENINGS**

- .1 One-hole aluminum or stainless steel straps to secure surface conduits 50 mm and smaller. Two-hole aluminum or stainless steel straps for conduits larger than 50 mm.
- .2 Beam clamps to secure conduits to exposed steel work.
- .3 Channel type supports for two or more conduits at 1 m oc.
- .4 Stainless steel threaded rods, 6 mm dia., to support suspended channels.

**2.3                CONDUIT FITTINGS**

- .1 Fittings: manufactured for use with conduit specified. Coating: same as conduit.
- .2 Factory "ells" where 90° bends are required for 25 mm and larger conduits.
- .3 Watertight connectors and couplings for EMT. Set-screws are not acceptable.

**2.4                EXPANSION FITTINGS FOR RIGID CONDUIT**

- .1 Weatherproof expansion fittings with internal bonding assembly suitable for 100 mm linear expansion.

□

.2 Watertight expansion fittings with integral bonding jumper suitable for linear expansion and 19 mm deflection in all directions.

.3 Weatherproof expansion fittings for linear expansion at entry to panel.

## **2.5 FISH CORD**

.1 Polypropylene.

## **Part 3 Execution**

### **3.1 INSTALLATION**

.1 Install conduits to conserve headroom in exposed locations and cause minimum interference in spaces through which they pass.

.2 X-ray cast walls and floors before coring to confirm location of embedded items.

.3 Existing structure may contain asbestos. Confirm materials are free of asbestos before drilling or coring.

.4 Use rigid aluminum threaded conduit in all areas.

.5 Use epoxy coated conduit underground and in cast concrete.

.6 Use liquid tight flexible metal conduit for connection to motors or vibrating equipment.

.7 Minimum conduit size for lighting and power circuits: 19 mm.

.8 Bend conduit cold. Replace conduit if kinked or flattened more than 1/10<sup>th</sup> of its original diameter.

.9 Mechanically bend steel conduit over 19 mm dia.

.10 Field threads on rigid conduit must be of sufficient length to draw conduits up tight.

.11 Install fish cord in empty conduits.

.12 Remove and replace blocked conduit sections. Do not use liquids to clean out conduits.

.13 Dry conduits out before installing wire.

### **3.2 SURFACE CONDUITS**

.1 Paint walls before installation of electrical equipment including conduits.

.2 Run parallel or perpendicular to building lines.

.3 Locate conduits behind infrared or gas fired heaters with 1.5 m clearance.

- .4 Run conduits in flanged portion of structural steel.
- .5 Group conduits wherever possible on suspended or surface channels.
- .6 Do not pass conduits through structural members except as indicated.
- .7 Do not locate conduits less than 75 mm parallel to steam or hot water lines with minimum of 25 mm at crossovers.

**3.3 CONCEALED CONDUITS**

- .1 Run parallel or perpendicular to building lines.
- .2 Do not install horizontal runs in masonry walls.
- .3 Do not install conduits in terrazzo or concrete toppings.

**3.4 CONDUITS IN CAST-IN-PLACE CONCRETE**

- .1 Locate to suit reinforcing steel. Install in centre one third of slab.
- .2 Protect conduits from damage where they stub out of concrete.
- .3 Install sleeves where conduits pass through slab or wall.
- .4 Provide oversized sleeve for conduits passing through waterproof membrane, before membrane is installed. Use cold mastic between sleeve and conduit.
- .5 Do not place conduits in slabs in which slab thickness is less than four (4) times conduit diameter.
- .6 Encase conduits completely in concrete with minimum 25 mm concrete cover.
- .7 Organize conduits in slab to minimize cross-overs.

**3.5 CONDUITS IN CAST-IN-PLACE SLABS ON GRADE**

- .1 Run conduits 25 mm and larger below slab and encased in 75 mm concrete envelope. Provide 50 mm of sand over concrete envelope below floor slab.

**3.6 CONDUITS UNDERGROUND**

- .1 Slope conduits to provide drainage.
- .2 Waterproof joints (pvc excepted) with heavy coat of bituminous paint.

**END OF SECTION**

**Part 1 General**

**1.1 SECTION INCLUDES**

- .1 Switches, receptacles, wiring devices, cover plates and their installation.

**1.2 RELATED SECTIONS**

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 26 05 00 - Common Work Results - Electrical.

**1.3 REFERENCES**

- .1 Canadian Standards Association (CSA International)
  - .1 CSA-C22.2 No.42, General Use Receptacles, Attachment Plugs and Similar Devices.
  - .2 CSA-C22.2 No.42.1, Cover Plates for Flush-Mounted Wiring Devices (Bi-national standard, with UL 514D).
  - .3 CSA-C22.2 No.55, Special Use Switches.
  - .4 CSA-C22.2 No.111, General-Use Snap Switches (Bi-national standard, with UL 20, twelfth edition).

**1.4 SHOP DRAWINGS AND PRODUCT DATA**

- .1 Submit shop drawings and product data in accordance with Section 01 33 00 - Submittal Procedures.

**Part 2 Products**

**2.1 SWITCHES**

- .1 20 A, 120 V, single pole, double pole, three-way, four-way switches to: CSA-C22.2 No.55 and CSA-C22.2 No.111.
- .2 Manually-operated general purpose ac switches with following features:
  - .1 Terminal holes approved for No. 10 AWG wire
  - .2 Silver alloy contacts
  - .3 Urea or melamine moulding for parts subject to carbon tracking
  - .4 Suitable for back and side wiring
  - .5 Ivory toggle
- .3 Toggle operated locking fully rated for tungsten filament and fluorescent lamps, and up to 80% of rated capacity of motor loads.
- .4 Switches of one manufacturer throughout project.
- .5 Acceptable materials: Leviton specification grade, Hubbell specification grade.

## **2.2 RECEPTACLES**

- .1 Duplex receptacles, CSA type 5-15 R, 125 V, 15 A, U ground, to: CSA-C22.2 No.42 with following features:
  - .1 Ivory urea moulded housing
  - .2 Suitable for No. 10 AWG for back and side wiring
  - .3 Break-off links for use as split receptacles
  - .4 Eight (8) back wired entrances, four side wiring screws
  - .5 Triple wipe contacts and rivetted grounding contacts
- .2 Single receptacles CSA type 5-15 R, 125 V, 15 A, U ground with following features:
  - .1 Ivory urea moulded housing
  - .2 Suitable for No. 10 AWG for back and side wiring
  - .3 Four (4) back wired entrances, 2-side wiring screws
- .3 Other receptacles with ampacity and voltage as indicated.
- .4 Receptacles of one manufacturer throughout project.
- .5 Acceptable materials: Leviton specification grade, Hubbell specification grade.

## **2.3 COVER PLATES**

- .1 Cover plates for wiring devices to: CSA-C22.2 No.42.1.
- .2 Cover plates from one manufacturer throughout project.
- .3 Weatherproof double lift spring-loaded cast aluminum cover plates, complete with gaskets for duplex receptacles as indicated.
- .4 Weatherproof spring-loaded cast aluminum cover plates complete with gaskets for single receptacles or switches.

## **Part 3 Execution**

### **3.1 INSTALLATION**

- .1 Switches:
  - .1 Install single throw switches with handle in "UP" position when switch closed.
  - .2 Install switches in gang type outlet box when more than one (1) switch is required in one (1) location.
  - .3 Mount toggle switches at height in accordance with Section 26 05 00 - Common Work Results - Electrical.
- .2 Receptacles:
  - .1 Install receptacles in gang type outlet box when more than one receptacle is required in one location.

- .2 Mount receptacles at height in accordance with Section 26 05 00 - Common Work Results - Electrical.
- .3 Where split receptacle has one portion switched, mount vertically and switch upper portion.
- .3 Cover plates:
  - .1 Protect stainless steel cover plate finish with paper or plastic film until painting and other work is finished.
  - .2 Install suitable common cover plates where wiring devices are grouped.
  - .3 Do not use cover plates meant for flush outlet boxes on surface-mounted boxes.

**END OF SECTION**

**Part 1            General**

**1.1                SECTION INCLUDES**

- .1            Materials for moulded-case circuit breakers.

**1.2                RELATED SECTIONS**

- .1            Section 01 33 00 - Submittal Procedures.

**1.3                REFERENCES**

- .1            Canadian Standards Association (CSA International).
  - .1            CSA-C22.2 No. 5, Moulded-Case Circuit Breakers, Molded-Case Switches and Circuit-Breaker Enclosures (Tri-national standard with UL 489, tenth edition, and the second edition of NMX-J-266-ANCE).

**1.4                SUBMITTALS**

- .1            Submit product data in accordance with Section 01 33 00 - Submittal Procedures.
- .2            Include time-current characteristic curves for breakers with ampacity of 90 A and over or with interrupting capacity of 22,000 A symmetrical (rms) and over at system voltage.

**Part 2            Products**

**2.1                BREAKERS GENERAL**

- .1            Moulded-case circuit breakers: to CSA C22.2 No. 5.
- .2            Bolt-on moulded case circuit breaker: quick- make, quick-break type, for manual and automatic operation with temperature compensation for 40 degrees Celsius ambient.
- .3            Common-trip breakers: with single handle for multi-pole applications.
- .4            Magnetic instantaneous trip elements in circuit breakers to operate only when value of current reaches setting.
  - .1            Trip settings on breakers with adjustable trips to range from three (3) to eight (8) times current rating.
- .5            Circuit breakers to have minimum symmetrical rms interrupting capacity rating matching panel board or switchboard containing breaker.

**2.2                THERMAL MAGNETIC BREAKERS [DESIGN A]**

- .1            Moulded case circuit breaker to operate automatically by means of thermal and magnetic tripping devices to provide inverse time current tripping and instantaneous tripping for short circuit protection.

**2.3            MAGNETIC BREAKERS [DESIGN B]**

- .1            Moulded case circuit breaker to operate automatically by means of magnetic tripping devices to provide instantaneous tripping for short circuit protection.

**2.4            SOLID STATE TRIP BREAKERS [DESIGN D]**

- .1            Moulded case circuit breaker to operate by means of solid-state trip unit with associated current monitors and self-powered shunt trip to provide inverse time current trip under overload condition, and long time, short time, instantaneous tripping for phase and ground fault short circuit protection.

**Part 3           Execution**

**3.1            INSTALLATION**

- .1            Install circuit breakers as indicated.
- .2            Set adjustable trip settings according to coordination study.

**END OF SECTION**

**Part 1 General**

**1.1 REQUIREMENTS OF WORK**

- .1 Supply, install and commissioning a complete instrumentation and control (I&C) system for the pumping station as shown on the Drawings and as specified herein.
- .2 Component subsystems of the I&C system will include, but are not limited to, the following:
  - .1 Primary elements and transmitters;
  - .2 Final control elements;
  - .3 RTU control panels;
  - .4 Instrumentation cabling;
  - .5 Instrumentation power supplies; and,
  - .6 Conduit and cable tray.
- .3 Where packaged, stand-alone control systems are supplied by others provide cabling to connect to the required remote monitoring and/or control functions. Provide end-to-end Commissioning of all required remote monitoring and/or control functions. Assist in ensuring the correct functionality of any equipment supplied by others.
- .4 Documentation referred to in 1.1.1 to include as a minimum:
  - .1 Records of as-built information for the complete instrumentation system.
- .5 Documentation provided is formatted as follows:
  - .1 Location Drawings – indicate in plan and/or elevation views where the instrument elements are physically located. These Drawings are provided to assist the Contractor in estimating the amount of cable and ducting required.
  - .2 Standard Details – provide a reference for installation, operation and other instructions pertinent to a particular device.
  - .3 Detailed Specification – lists qualifications, quality of materials and workmanship, and supplementary information.
- .6 Definitions
  - .1 Interpret specialized terms not explicitly defined herein in accordance with ISA-S51.1, NEMA-ICS-1, ANSI/IEEE-Std-100, and The Communications Standard Dictionary, by Martin H. Weik.
- .7 References
  - .1 This Specification contains references to the following Documents. They are a part of this Section as specified and modified. In case of conflict between the requirements of this Section and those of the listed Documents, the requirements of this Section prevail.

<b>Reference</b>	<b>Title</b>
API RP550	Manual on Installation of Refinery Instruments and Control Systems, Part I--Process Instrumentation and Control Sections 1 Through 13
ASME Section VII	Rules for Construction of Pressure Vessels
ASTM B68	Seamless Copper Tube
ASTM D883	Terms Relating to Plastics
IEEE 100	Dictionary of Electrical and Electronic Terms
ISA RP7.1	Pneumatic Control Circuit Pressure Test
ISA RP12.6	Installation of Intrinsically Safe Systems for Hazardous (Classified) Locations
ISA S5.4	Instrument Loop Diagrams
ISA S18.1	Annunciator Sequences and Specifications
ISA S51.1	Process Instrumentation Terminology
NEMA 250	Enclosures for Industrial Controls and Systems
NEMA ICS 1	General Standards for Industrial Control and Systems
NEMA ICS 2	Industrial Control Devices, Controllers, and Assemblies
NFPA 70	National Electrical Code (NEC)
SAMA PMC 17-10	Bushings and Wells for Temperature Sensing Elements
UBC	Uniform Building Code
UL 1012	Power Supplies
UL 94	Tests for Flammability of Plastic Materials for Parts in Devices and Appliances Weik, Martin H. Communications Standard Dictionary, Van Nostrand Reinhold Co.

.8 Related Work:

- .1 Mechanical
- .2 Electrical

.9 Qualifications

- .1 The instrumentation Subcontractor shall be a firm normally engaged and fully competent in the type of Work described in this Section of the Specification. The firm shall have been continuously and successfully engaged in this business for at least five years.
- .2 Qualified journeyman instrument mechanics that are familiar with the devices being installed shall perform all instrument hook-ups, calibrations, and checkouts.
- .3 Qualified journeyman electricians shall perform all control wiring installation and connections.

.10 Codes, Rules, Permits and Fees

- .1 Comply with all laws, ordinances, rules, regulations, codes and orders of all authorities having jurisdiction relating to this Work.
- .2 Comply with all rules of the Electrical Safety Act of the Province, CSA Standards, the ULC and the applicable building codes, whether specifically shown on Drawings or not.
- .3 Give all required notices, submit Drawings, obtain all permits, licenses and certificates and pay all fees required for this Work.

- .4 Furnish a certificate of final inspection and approvals from an inspection authority to the Contract Administrator.
- .11 Standards of Workmanship
  - .1 Execute all Work in a manner, which will result in the completed installation presenting an acceptable appearance, to a level of quality defined in the general conditions of this Specification.
  - .2 Employ a competent supervisor and all necessary licensed tradesmen to complete the Work in the required time.
  - .3 Arrange and install products to fit properly into designated building spaces.
  - .4 Install products in accordance with the recommendations and ratings of the product manufacturers.
- .12 Contract Drawings and Specifications
  - .1 Refer to Division 1.
  - .2 Provide all items and accessories required to install City supplied equipment.
  - .3 Perform all operations as designated by the Specification according to the methods prescribed, complete with all necessary labour and incidentals.
  - .4 Treat any item or subject omitted from this Division's Specifications or Drawings, but which is mentioned or reasonably specified in other Divisions' Specifications or Drawings and pertains to the instrumentation and control system, as being integral to the overall system. Provide such specified items or subjects.
  - .5 Provide all minor items and Work not shown or specified but which are reasonably necessary to complete the Work.
  - .6 If discrepancies or omissions in the Drawings or Specifications are found, or if intent or meaning is not clear, consult the Contract Administrator for clarification before submitting bid.

## **1.2 EQUIPMENT**

- .1 Receiving, Storing, and Protection of Components during Construction
  - .1 Examine each component upon delivery to Site. Report all damage noted to the Contract Administrator prior to accepting or rejecting delivery. All instrumentation primary elements, control components, panels, etc. shall be placed in a secure, dry, heated storage building. Maintain the space temperature above 10°C and the space relative humidity below 50 percent.
  - .2 Perform a preliminary examination upon delivery to ensure that:
    - .1 All instrumentation and control components supplied for this project under this Section of the Specification comply with the requirements stated in the instrument Specification sheets.
    - .2 All instrumentation and control components supplied by others, to be connected to instrumentation and control components comply with the requirements stated in the Contract Documents.

- .3 Itemize all non-conformities noted above and forward them to the Contract Administrator.
- .4 Do not install primary elements or other sensitive equipment until construction is sufficiently completed to provide an "operating condition" environment. Notify the Contract Administrator prior to installing any equipment of this type.
- .5 Ensure that covers where required are properly installed on all equipment. Provide all covers, padding, guards, etc. as required to guard any equipment against damage.  
Return all damaged equipment to the supplier for total corrective repairs. If deemed necessary by the Contract Administrator, the damaged equipment shall be replaced with new product.

### **1.3 SITE**

- .1 Classification of Plant Areas
  - .1 Building: Ordinary
  - .2 Dry Well: Category 1

### **1.4 DOCUMENTATION**

- .1 Submittals
  - .1 Submit Shop Drawings for all products supplied by this Division.
  - .2 Shop Drawings for City supplied equipment will be provided to the Contractor.
- .2 Construction Record Drawings
  - .1 Maintain on-site a complete set of Construction Record Drawings as listed in Division 1 of this Specification.
  - .2 In addition to the requirements as stated in Division 1, record the following information on the Drawings:
    - .1 All changes, alterations or additions;
    - .2 All instrumentation cable and control tubing; and,
    - .3 All changes to the numbers and location of outlets, motors, panels and end devices that may occur during the course of the Work.
  - .3 Before requesting the Certificate of Total Performance, make any necessary final corrections to the Drawings, sign each print as a certification of accuracy and deliver all sets to the Contract Administrator for approval.

## **Part 2 Products**

### **2.1 GENERAL**

- .1 Refer to the requirements of Division 1.
- .2 Selected Products:
  - .1 Provide products and materials that are new and free from all defects.

- .2 The design has been based on the use of the first named product where multiple products have been listed.
- .3 Quality of Products
  - .1 All products provided to be CSA and ULC approved where applicable.
  - .2 If products specified are not CSA approved, obtain approval of the relevant provincial regulatory authority. Pay all applicable charges levied and make all modifications required for approval.
  - .3 Refer to Division 1 of this Specification for further information.
- .4 Uniformity of Manufacture
  - .1 Unless otherwise specifically called for in the Specification, uniformity of manufacture to be maintained for similar products throughout the Work.
- .5 Use of Products During Construction
  - .1 Any equipment used for temporary or construction purposes is to be approved by the Contract Administrator. Clean and restore to "as new" condition all equipment prior to the time of Substantial Performance.

## **2.2 INSTRUMENTATION**

- .1 General
  - .1 Instruments and installation methods to be suitable for the environmental conditions in which they are to be installed.
  - .2 Determine where injurious conditions may be expected to occur and make proper provision to protect the instruments to ensure their proper and reliable operation.

## **2.3 IDENTIFICATION**

- .1 Refer to City of Winnipeg Water and Waste Department – Identification Standard, Rev 00 for general identification requirements.
- .2 Provide 3 mm thick lamicoïd nameplates with 6 mm black lettering on white background. Identify the loop tag number (where applicable) and the device name, function, and instrument range or setpoint value on the nameplate.
- .3 Where it is not possible to attach a lamicoïd nameplate to a field instrument component, provide the component with a stainless steel metal tag firmly wired to the device and identified with the loop tag number.
- .4 Identify all wires where they terminate at the marshalling panels, junction boxes and field devices with a heat shrink sleeve with machine printed labeling.
- .5 Clearly mark all panels, pull boxes, junction boxes, etc. to indicate the nature of service.
- .6 Provide neatly typed circuit directories for panel power distribution systems to indicate loops or devices powered by the circuit and the fuse size.
- .7 Identify all exposed control conduits at all pull box locations, where the conduits enter or leave a room, and 13 m on centre throughout the room. This shall apply to conduits above removable ceilings. Use Thomas & Betts TY-RAP 5532-M labels conduit identification.

- .8 For direct current wiring use black for positive and white for negative.
- .9 For thermistor wiring to motors use red and blue coloured, insulated wire.

**Part 3 Execution**

**3.1 SITE EXAMINATION**

- .1 Refer to the requirements of Division 1.
- .2 No additional compensation will be given for extra Work due to existing conditions that a Site examination prior to Bid should have disclosed.

**3.2 COORDINATION WITH OTHER DIVISIONS**

- .1 Examine the Drawings and Specifications of all Divisions and become fully familiar the Work. Before commencing Work, obtain a ruling from the Contract Administrator on any conflicting issues between Divisions. No compensation will be made for any costs arising from conflict not identified before Work has commenced.
- .2 Coordinate the Work to be performed under this Section of the Specification with all Divisions installing equipment to ensure that there are no conflicts.
- .3 Install anchors, bolts, pipe sleeves, hanger inserts, etc. required in ample time to prevent delays to other Division's installation Work.
- .4 Lay out the Work and equipment with due regard to architectural, structural and mechanical features. Architectural and structural Drawings take precedence over electrical Drawings regarding locations of walls, doors, and equipment.
- .5 Structural members shall not be cut without prior approval of the Contract Administrator.
- .6 Examine previously constructed Work and notify the Contract Administrator of any conditions, which prejudice the proper completion of this Work.

**3.3 PRODUCT HANDLING**

- .1 Use all means necessary to protect the products included in this Division before, during and after installation, and to protect products and installed Work of all other trades.
- .2 Any damage to the products and/or installed Work shall be repaired or replaced by the Contractor at no additional cost to the City and to the approval of the Contract Administrator.
- .3 Remove advertising labels from all products installed that have such labels attached. Identification or CSA labels are not to be removed.
- .4 Remove dirt, rubbish, grease, etc. resulting from Work performed under this Division of the Contract from all surfaces.

**3.4 SEPARATION OF SERVICES**

- .1 Maintain separation between the electrical wiring system, piping, ductwork, and the instrumentation cables so that each system is isolated (except at approved

connections to such systems) to prevent galvanic corrosion. In particular, contact between dissimilar metals, such as copper and aluminum, in damp or wet locations is unacceptable.

- .2 Do not support wiring from pipes, ductwork, etc. Hangers for suspended ceilings are not to be used for the support of wiring.
- .3 Classifications of Circuits
  - .1 The circuit categorization shall of first priority follow Canadian Electrical Code with respect to separation for electrical safety and the following shall apply with respect to electro-magnetic compatibility:

Very Noisy	High voltage circuits and their associated grounding
	High current (>200 A) LV circuits.
	Harmonic-rich LV circuits
	DC circuits: un-suppressed or above 50 V
Noisy	Low current class two (2) circuits
	Medium power pulsed or radio frequency circuits
Indifferent	ELV digital status circuits
	Intrinsically safe circuits
	Telecommunications circuits
	Fire alarm and emergency lighting circuits (note that some fire alarm circuits may fall into the category of signal circuits).
Sensitive	Any other emergency, shutdown, or high integrity circuit (e.g. toxic gas alarm).
	Analogue signal circuits
Very Sensitive	Data communication circuits
	Low level voltage and current signals (e.g. from instrument sensors).

- .4 Separation of Circuits
  - .1 This Section relates to the running of cables carrying differing types of circuit in close proximity to one another and to other services. Sensitive circuits shall normally be run in overall shielded cable. Very sensitive circuits shall normally be run in individually twisted pair shielded cable.
  - .2 For cables sharing the same support/containment system, the following shall provide guidance to minimize extraneous interference:

<b>Segregation between circuits</b>	<b>Very Noisy</b>	<b>Noisy</b>	<b>Indifferent</b>	<b>Sensitive</b>	<b>Very Sensitive</b>
Very Noisy	Thermal grouping as per CE Code	150 mm	300 mm	300 mm	300 mm
Noisy	150 mm	Thermal grouping as per CE Code	150 mm	150 mm	150 mm
Indifferent	300 mm	150 mm	Separation of circuit types.	100 mm	100 mm
Sensitive	300 mm	150 mm	100 mm	Touching	50 mm
Very Sensitive	300 mm	150 mm	100 mm	50 mm	Touching

**3.5 WIRE AND CABLE**

.1 Refer Division 26.

**3.6 CONTROL WIRING COLOUR IDENTIFICATION**

.1 Colour Codes

Conductor Purpose	Colour
Power, 120/208/240 VAC Supply	Black
Power, 120/208/240 VAC Neutral	White
Power, 24 VDC Supply (+)	Blue
Power, 24 VDC Common (-, or 0VDC)	Brown
Discrete Control AC	Red
Discrete Control DC	Blue
Intrinsically Safe	IS (light) Blue
Protective Earth (PE)	Green
Signal Ground/Instrumentation Earth (IE)	Green/Yellow

**3.7 NETWORK CABLE – JACKET COLOUR**

.1 Colour Codes

Cable Purpose	Colour
Ethernet, CAT5E or CAT6	Blue
Profibus DP	Purple
Profibus PA, Non-Intrinsically Safe	Black
Profibus PA, Intrinsically Safe	Light Blue
Modbus/RTU (serial)	Grey

### **3.8 EQUIPMENT CONNECTIONS**

- .1 Prior to the connection of signal wiring to process control and instrumentation devices, check the device voltage rating and polarity for compatibility with the corresponding loop and/or schematic diagram. Where device and circuit characteristics are found to be incompatible, the connections are not to be made. Report the condition immediately to the Contract Administrator.
- .2 All control wiring diagrams illustrate typical control circuits applicable to the type of equipment specified. Control circuits may vary with different manufacturer's equipment. Verify all control circuits with the manufacturers of the equipment and make any corrections to the control wiring diagrams that may be required.

### **3.9 WIRING TO EQUIPMENT SUPPLIED BY OTHER DIVISIONS**

- .1 Equipment supplied by the City or by other Divisions, that have external or field mounted control devices, are to be installed, wired and commissioned by this Division.

### **3.10 INSTRUMENT MOUNTING STANDS**

- .1 Supply and install instrumentation mounting stands as required. Stands are to be either floor or wall mounted. The mounting stands are to be fabricated from aluminum.
- .2 Supply and install protective drip shields for any exterior stand-mounted instrumentation equipment. Drip shields are to extend 50 mm past the front and side faces of the equipment. Drip shields are to be fabricated from aluminum.

### **3.11 SEALING OF WALL AND FLOOR OPENINGS**

- .1 Seal all conduit and cable entries passing through walls of buildings, through partition walls separating electrical rooms from other areas, through fire separations, and through floors above grade.
- .2 Seal openings after all wiring entries have been completed.
- .3 Sealing material shall be fire resistant and shall not contain any compounds that could chemically affect the wiring jacket or insulating material. Cable penetrations through fire separations, if required, are to be sealed. Submit shop drawing for rated assembly prior to installation of fire stop.

### **3.12 TAGGING STANDARDS FOR DEVICES AND WIRING**

- .1 Tag all devices, wires, and I/O using the assigned loop, equipment, or device tag name. Where tag naming and numbering is not specified, the Contract Administrator will provide naming and numbering that is consistent with the plant naming conventions.

### **3.13 TESTING OF INSTRUMENTATION LOOPS**

- .1 After all devices within a loop have been connected, check the loop for correct functioning and interaction with other loops, where applicable. Provide written notice to the Contract Administrator when the loops are going to be tested so that the tests may be witnessed at the Contract Administrator's discretion.

- .2 Check the operation of final control elements such as solenoid valves, actuators, etc. by manual control before checking with automatic control.
- .3 Check and simulate all alarms and shutdown functions.
- .4 Test all tubing for leaks in compliance with ISA RP7.1. Isolate all instruments when tubing is being tested to protect against over pressure.
- .5 Perform tests and record results on the test data forms that are included in this Section. Develop additional and/or more detailed test forms as necessary to suit more complex instrumentation.
- .6 Sign and date all test reports. Submit the test reports to the Contract Administrator within five (5) Business Days of testing.
- .7 Coordinate and cooperate with City's staff while they verify the instrument loop I/O in the programmable logic controller (PLC) and on the supervisory control and data acquisition (SCADA) system.

### **3.14 CALIBRATION**

- .1 Instruments are to be factory pre-calibrated. Verify calibration after installation for all instruments installed under these Specifications. Provide a printed record of the factory calibration parameters for "smart" devices.
- .2 Prior to calibration, completely program all "smart" transmitters including entries of the appropriate range and tag number. Provide a printed record of smart device serial numbers against their assigned tag number with all programmed parameters.
- .3 Calibrate all instruments to an accuracy of 0.5 percent of full range, or to the manufacturer's stated accuracy of the instrument whenever an accuracy of 0.5 percent is not achievable.
- .4 Prior to instrument installation perform the following applicable calibration for each instrument and its associated signal conditioning equipment:
  - .1 Calibrate online analyzers with known samples.

### **3.15 COMMISSIONING**

- .1 Refer to the requirements of Division 1 for additional requirements.
- .2 Inspections
  - .1 Provide two weeks' written notice to the Contract Administrator prior to energizing any system to allow for inspection by the Contract Administrator of the following:
    - .1 Proper mounting; and,
    - .2 Proper connections.
  - .2 During Commissioning, demonstrate to the Contract Administrator proper calibration and correct operation of instruments and gauges
  - .3 Commissioning of the instrumentation and control system to include but not be limited to the following.
    - .1 Verify installation of components, wiring connections and piping connections.

- .2 Supervise wiring continuity and pipe leak tests.
- .3 Verify instrument calibration and provide written report.
- .4 Function check and adjust the instruments and control equipment under operational conditions.
- .5 Coordinate manufacturer's service personnel as required for complete system testing.
- .6 Instruct plant personnel in correct method of instruments equipment operation.
- .7 Direct plant personnel at hand-over as to final adjustment of the system for correct plant operation.
- .8 Ensure that the Manufacturer's representatives cooperate to complete the Work of this Section.
- .9 Verify signal levels and wiring connections to all instrumentation and control equipment.
- .10 Work with control system programmer to verify all field devices, wiring, calibration and operation.

**3.16**

**TEST FORMS**

<b>Form No.</b>	<b>Title</b>
.1 ITR	Instrument Test Report
.2 LCR	Loop Check Report

# LOOP CHECK REPORT

- CHECKED OUT OK
- NOT APPLICABLE
- FURTHER ACTION REQUIRED

	INSTRUMENT TAG NO.							
LOOP NO.								
SHEET NO.								
P & I DWG. NO.								
<b>INSTALLATION COMPLETE</b>								
Primary Element								
Impulse Lines								
Block and Drain Valves								
Air Supply/Filter/Reg.								
Wiring								
Tracing/Insulation/Housing								
Mounting and Location								
PLC/SCADA I/O & Status								
<b>CALIBRATED</b>								
Impulse Lines Press. Tested								
<b>LOOP CHECKED</b>								
Element To Receiver								
X Mtr. to Receiver								
X Mtr./Trans. to Receiver								
X Mtr./Trans. to Switches								
Switches to Annunciator								
Interlocking Circuit								
Controller to Valve								
Controller Action D or R								

REMARKS:

## READY FOR START-UP

DATE: \_\_\_\_\_

Installed by: \_\_\_\_\_

Checked by: \_\_\_\_\_

# INSTRUMENT TEST REPORT

SYSTEM: \_\_\_\_\_  
 SERVICE: \_\_\_\_\_ TAG NO. \_\_\_\_\_  
 LOCATION: \_\_\_\_\_  
 MAKE: \_\_\_\_\_ MODEL: \_\_\_\_\_  
 SERIAL NO.: \_\_\_\_\_ CSA: \_\_\_\_\_  
 ELEMENT: \_\_\_\_\_ RANGE: \_\_\_\_\_  
 DESIGN SETTING/RANGE: \_\_\_\_\_ CONTACT TO: \_\_\_\_\_ ON: \_\_\_\_\_  
 SIGNAL IN: \_\_\_\_\_ OUT: \_\_\_\_\_ ASSOCIATED INSTRUMENT: \_\_\_\_\_  
 INSTRUMENT CONDITION: \_\_\_\_\_ CONFORM TO SPEC: \_\_\_\_\_  
 PROJECT NO.: \_\_\_\_\_ DATA SHEET: \_\_\_\_\_

	TEST 1				TEST 2			
TEST METHOD								
	INPUT		OUTPUT		INPUT		OUTPUT	
PROCESS	INC.	DEC.	INC.	DEC.	INC.	DEC.	INC.	DEC.
TEST POINT 1								
TEST POINT 2								
TEST POINT 3								
TEST POINT 4								
TEST POINT 5								
COMMENTS								
GRAPHS								

TESTED BY: \_\_\_\_\_ CHECKED BY: \_\_\_\_\_  
 DATE: \_\_\_\_\_ DATE: \_\_\_\_\_

**END OF SECTION**

**Part 1            General**

**1.1                REFERENCES**

- .1 Canadian Standards Association (CSA International)
  - .1 CSA-C22.2 No. 214, Communications Cables (Bi-National standard with UL 444).
  - .2 CSA-C22.2 No. 232, Optical Fiber Cables.
- .2 Telecommunications Industry Association (TIA)/Electronic Industries Alliance (EIA)
  - .1 TIA/EIA-568-B.1, Commercial Building Telecommunications Cabling Standard, Part 1: General Requirements.
  - .2 TIA/EIA-568-B.2, Commercial Building Telecommunications Cabling Standard, Part 2: Balanced Twisted-Pair Cabling Components.
  - .3 TIA/EIA-568-B.3, Optical Fiber Cabling Components Standard.
  - .4 TIA/EIA-606-A, Administration Standard for the Commercial Telecommunications Infrastructure.
  - .5 TIA TSB-140, Telecommunications Systems Bulletin - Additional Guidelines for Field-Testing Length, Loss and Polarity of Optical Fiber Cabling Systems.
  - .6 TIA-598-C, Optical Fiber Cable Color Coding.

**1.2                DEFINITIONS**

- .1 Refer to TIA/EIA-598-C, Annex A for definitions of terms: optical-fiber interconnect, distribution, and breakout cables.

**1.3                PRODUCT DATA**

- .1 Submit product data in accordance with Division 26.

**1.4                RELATED WORK**

- .1 Refer to Division 26.

**1.5                INSPECTION**

- .1 Provide adequate notice to the Contract Administrator so that all cable installations can be inspected prior to energizing equipment.

**1.6                STANDARDS**

- .1 All wire and cable shall be CSA approved.

**Part 2 Products**

**2.1 TWISTED PAIR SHIELDED CABLES (TPSH)**

- .1 TPSH shall be constructed as follows:
  - .1 Two (2) copper conductors, stranded, minimum #18 AWG, PVC insulated, twisted in nominal intervals of 50 mm.
  - .2 Insulated for 600 V, 90°C.
  - .3 100 percent coverage aluminum foil or tape shield.
  - .4 Separate bare stranded copper drain wire, minimum #18 AWG.
  - .5 Overall flame retardant PVC jacket to CSA-C22.2.
  - .6 The entire cable assembly to be suitable for pulling in conduit or laying in cable tray.
  - .7 Interlocked aluminum armour and outer PVC jacket.
  - .8 Shaw Type 1751-CSA or Beldon equivalent.
- .2 Where multi-conductor TPSH cables are called for, each pair shall be individually shielded, continuous number coded, and the cable assembly shall have an overall shield and overall flame retardant PVC jacket.

**2.2 RTD AND MULTI CONDUCTOR SHIELDED CABLE**

- .1 RTD cables shall be CSA approved and shall be constructed as follows:
  - .1 Three or more copper conductors, stranded, minimum # 18 AWG.
  - .2 PVC insulated for 600 V.
  - .3 100 percent coverage aluminum foil or tape shield.
  - .4 Separate bare stranded copper drain wire.
  - .5 Interlocked aluminum armour and outer PVC jacket.
  - .6 Overall flame retardant PVC jacket to CSA-C22.2.

**2.3 TECK CABLES**

- .1 As per Division 26.

**2.4 WIRE**

- .1 As per Division 26.

**2.5 100 BASE TX CATEGORY 6 COMMUNICATION CABLE**

- .1 Category 6 cable shall be CSA approved and constructed as follows:
  - .1 Four (4) bonded pairs, solid stranded, #24 AWG.
  - .2 Interlocked aluminum armour.
  - .3 Rip cord.
  - .4 PVC inner and outer jackets.
  - .5 UL verified to Category 6.
  - .6 Insulated for 300 V.
  - .7 Shielded

**Part 3 Execution**

**3.1 ANALOG SIGNALS**

- .1 Use TPSH cable for all low level analog signals such as 4-20 mA, pulse type circuits 24 VDC and under, and other signals of a similar nature.
- .2 Use RTD cable for connections between RTDs and transmitters or control system RTD inputs.

**3.2 DIGITAL SIGNALS**

- .1 Use TPSH cable for all low level input (24 V and below) and output signals to the control system.

**3.3 INSTRUMENT POWER**

- .1 Use Teck cable or wire and conduit for power to instruments, for 120 V signals other than those mentioned above and as otherwise indicated on the Drawings. Use stranded wire and cable to supply power to instruments.

**3.4 INSTALLATION**

- .1 Install instrumentation cables in cable trays. Use a minimum of 300 mm and a maximum of 1000 mm length of liquid tight flexible conduit to connect the field sensors to the conduit.
- .2 Where instrumentation cables are installed in cable trays, provide barriers in the tray to separate instrumentation cables from power cables.
- .3 At each end of the run leave sufficient cable length for termination.
- .4 Do not make splices in any of the instrumentation cable runs.
- .5 Cable shields shall be terminated on insulated terminals and carried through to the extent of the cable.
- .6 Ground cable shields at one end only. Unless otherwise specified, ground the shields at the PLC control panel.
- .7 Protect all conductors against moisture during and after installation.

**3.5 CAT 6 INSTALLATION:**

- .1 Always follow the Manufacturer's guidelines for minimum bend radius and tension.
- .2 All installations and terminations shall be performed by personnel experienced in Cat 6 cable installation.
- .3 Perform cable testing with time domain reflectometer instrument and provide complete detailed test report. Test all runs upon completion of permanent terminations, using instrumentation acceptable to Contract Administrator. Before commencing testing, submit sample test data sheets and information with respect to test instrumentation to be used.

- .1 Test for the following:
  - .1 Continuity.
  - .2 Pair placement and polarity.
  - .3 DC resistance.
  - .4 Characteristics at highest contemplated frequency:
    - .1 Attenuation - data cable.
    - .2 Mutual Capacitance - data cable.
    - .3 Near-end crosstalk (NEXT) - data cable.
  - .5 Run length.
- .2 Category 6 using certified level III tester to: TIA/EIA-568-B.2.
- .3 Reconnect or re-install and retest as necessary to correct excessive variations.

### **3.7 FIELD QUALITY CONTROL**

- .1 Test horizontal UTP cables as specified below and correct deficiencies provide record of results as hard copy.
  - .1 Perform tests for Permanent Link on installed cables, including spares:
    - .1 Category 6 using certified level III tester to: TIA/EIA-568-B.2.
  - .2 Perform tests for Channel on 100% of cross-connected data horizontal cabling installed from each telecommunications room, including shortest and longest drops from each telecommunications room.
    - .1 Category 6 using certified level III tester to: TIA/EIA-568-B.

### **3.8 CONDUCTOR TERMINATIONS**

- .1 All equipment supplied shall be equipped with terminal blocks to accept conductor connections.
- .2 Instrumentation conductors, where terminated at equipment terminals other than clamping type terminal blocks, shall be equipped with Burndy-YAE-2 or STA-KON, self-insulated, locking type terminators, sized as required to fit conductors and screw terminals.

### **3.9 TESTING**

- .1 Test all conductors for opens, shorts, or grounds. Resistance values shall not be less than those recommended by the cable manufacturer.

### **3.10 IDENTIFICATION**

- .1 Identify all instrumentation cables.
- .2 Identify each conductor with wire numbers using a machine printed Raychem TMS heat shrink wire marker or approved equal in accordance with B7.

**END OF SECTION**