
-EXISTING GRANULAR PATHWAY TO BE SCARIFIED AND TOPPED UP-REFER TO LAYOUT PLAN EXCAVATE, REMOVE AND DISPOSE OF EXISTING TRASH RECEPTACLE EXISTING SEESAWS (2) TO REMAIN REMOVE AND DISPOSE OF -EXISTING BENCH (1) REMOVE AND DISPOSE EXISTING -PICNIC BENCH (1) EXCAVATE, REMOVE AND DISPOSE OF-EXISTING GRANULAR BASE EXCAVATE, REMOVE AND DISPOSE OF-EXISTING TIMBER EDGING EXCAVATE, REMOVE EXISTING FLAT STRUCTURE. DELIVER TO DESIGNATED REMOVE AND DISPOSE OF EXISTING 'NO VEHICLES' SIGN - EXISTING PAVERS TO REMAIN. PAVER JOINTS TO BE SPRAYED WITH HERBICIDE AND WEEDS REMOVED BY CITY. - EXCAVATE REMOVE AND DISPOSE OF EXISTING UNIT PAVERS AND BASE COURSE EXCAVATE, REMOVE AND DISPOSE — REMOVE AND DISPOSE OF EXISTING EXISTING BENCH (1) BENCH (1) EXISTING TIMBER EDGE TO REMAIN -EXISTING TREE TO REMAIN AND BE PROTECTED DURING CONSTRUCTION TO CITY OF WINNIPEG STANDARDS EXISTING SWINGS TO REMAIN -EXISTING PEA GRAVEL TO REMAIN-- EXISTING SPRING RIDERS (2) TO - EXCAVATE, REMOVE AND DISPOSE OF EXISTING SOD IN LINE WITH NEW WORK EXCAVATE, REMOVE AND DISPOSE OF EXISTING SAND BOX INCLUDING, BASE MATERIAL, TIMBER EDGE AND PLAY SAND - EXCAVATE, REMOVE AND DISPOSE OF EXISTING 'LIL' DIGGER' PLAY FEATURE EXCAVATE, REMOVE AND STOCKPILE EXISTING PEA GRAVEL TO BE REUSED IN SWING SET PLAY AREA AS REQUIRED - EXCAVATE, REMOVE AND DISPOSE OF EXISTING TIMBER EDGING - NEW TIMBER EDGE-REFER TO LAYOUT PLAN. CONFIRM NEW EDGE AT LIMIT OF NO ENCROACHMENT ZONE EXISTING TIMBER EDGE TO REMAIN-REFER TO LAYOUT DRAWING **REMOVALS PLAN** SCALE: 150

LEGEND



SCARIFY EXISTING GRANULAR PATHWAY




EXCAVATE, REMOVE AND DISPOSE OF EXISTING UNIT PAVERS AND BASE COURSES



REMOVE AND DISPOSE OF EXISTING

REMOVE AND DISPOSE OF EXISTING PEA GRAVEL AND PLAY SAND



EXISTING DECIDUOUS TREE TO REMAIN




LOCATION PLAN SCALE: NTS



REMOVALS NOTES

- 1. CONTRACTOR IS RESPONSIBLE FOR ALL EXCAVATIONS, REMOVALS, DISPOSALS, AND ROUGH GRADING AS REQUIRED TO CONSTRUCT ALL WORKS AS SHOWN ON ALL PLANS, DETAILS AND SPECIFICATIONS.
- 2. CONTRACTOR TO COORDINATE REMOVALS WITH THE CITY OF WINNIPEG. 3. LIMIT OF WORK IS APPROXIMATE. CONTRACTOR TO ENSURE THAT ALL AREAS
- DAMAGED DUE TO CONSTRUCTION ACTIVITIES EITHER WITHIN LIMIT OF WORK OR OUTSIDE ARE TO BE RESTORED AT CONTRACTOR'S OWN COST. 4. CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO
- CONTRACT ADMINISTRATOR PRIOR TO REMOVALS. 5. REFER ALSO TO WRITTEN SPECIFICATIONS.
- 6. SAWCUT EXISTING PAVEMENTS AND CURBS TO ENSURE CLEAN EDGE ON
- PAVEMENT AND CURBS TO REMAIN (NO BROKEN EDGES). 7. LOCATION OF ALL UTILITIES SHOWN FOR ILLUSTRATION ONLY. CONTRACTOR MUST CONTACT ALL UTILITIES REGARDING RULES FOR WORKING IN THE AREA OF THE UTILITIES PRIOR TO COMMENCEMENT OF ANY WORK. CONTRACTOR MUST CONFIRM LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION.
- 8. ALL EXISTING TREES, SIDEWALKS, CURBS, FENCING, SOD AND PAVING TO REMAIN TO BE PROTECTED DURING CONSTRUCTION TO CITY OF WINNIPEG STANDARDS. AREAS DAMAGED DURING CONSTRUCTION TO BE REPAIRED TO CITY OF WINNIPEG STANDARDS AT THE CONTRACTORS OWN COST.
- 9. FILL ALL HOLES AND LOW AREAS TO DESIGN SUBGRADE WITH COMPACTED FILL (SUITABLE TO SURFACE FINISH), FOR SODDED/PLANTED AREAS USE COMPACTED CLEAN EARTH FILL SUITABLE FOR PLANT GROWTH. FOR PAVED AREAS USE COMPACTED GRANULAR BASE. REFER TO SPECIFICATIONS.
- 10. ALL DIMENSIONS ARE IN METRIC UNLESS OTHERWISE NOTED.
- 11. ALL ITEMS TO BE REMOVED MUST BE DISPOSED OF LEGALLY OFFSITE.
- 12. ALL TREE AREAS TO REMAIN TO BE PROTECTED IN ACCORDANCE WITH CITY OF WINNIPEG SPECIFICATIONS.



Date	Scale	
04-12-18	AS NOTED	
Designed By	Drawn By	Checked By
AH	GL	AH



CITY OF WINNIPEG

EDWARD SHINDELMAN PLAYGROUND UPGRADES

REMOVALS PLAN

Drawing No. L1.2

Project No. 18-019