



100-2019 ADDENDUM 2

2019 DOWNTOWN STREETS – MAIN ST – HIGGINS AVE TO LOMBARD AVE – ASPHALT OVERLAY

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE TENDER

ISSUED: June 7, 2019
BY: Cory Humbert
TELEPHONE NO. 204 226 2303

THIS ADDENDUM SHALL BE INCORPORATED INTO THE TENDER AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20190115

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Tender, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 100-2019 Bid Submission with 100-2019 Addendum 2 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

- Form B(R1): Add items A.5 and A.5 i)
- Add item A.11 i)
- Revise quantity of item A.12 iv)

Page numbering on some forms may be changed as a result.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, **June 17, 2019**.

PART D – SUPPLEMENTAL CONDITIONS

Revise: D14.4 to read: The City intends to award this Contract by **July 8, 2019**.

PART E – SPECIFICATIONS

Revise: E14.1.1(a) to read: Alsip's Building Products – Endicott Clay Paver (60mm thick) – Dark Ironspot **or Alston Brick Supply Inc. – Yankee Hill Brick (60mm thick) – Dark Ironspot**

Clarification: Alston Brick Supply Inc. - Yankee Hill Brick (60mm thick) – Dark Ironspot is an approved substitute.

Add:

E16. REMOVAL OF INTERLOCKING PAVING STONES

DESCRIPTION

E16.1 This specification shall supplement CW 3110.

CONSTRUCTION METHODS

E16.2 Further to section 3.1 of CW 3110, paving stones shall be removed in such a way as to avoid damaging the concrete slab beneath the paving stones being removed, and to avoid chipping greater than 35 mm along the edges of the concrete.

MEASUREMENT AND PAYMENT

E16.3 Removal of Interlocking Paving Stones will be measured on an area basis and paid for at the Contract Unit Price per square metre for the "Items of Work" listed below. The area to be paid for will be the total number of square metres of existing paving stones removed in accordance with this specification, accepted and measured by the Contract Administrator.

Items of Work:

Pavement Removal

- i) Interlocking Paving Stones

E16.4 Disposal of material will be included in the payment for the "Items of Work" listed for pavement removal.

DRAWINGS

Replace: 100-2019_Drawing_SE-19-23-R0 with 100-2019_Addendum_2-Drawing_SE-19-23-R1

100-2019_Drawing_SE-19-30-R0 with 100-2019_Addendum_2-Drawing_SE-19-30-R1