

**Sewer Junction Information** (From Video Inspection)

(i rom video mapeonom)				
Reference MH	Distance	Size	Clock	
S-MH50004779	003.8	150	02	
-	009.2	150	10	
-	017.8	150	10	
-	020.6	150	02	
-	037.9	150	10	
-	039.3	150	01	
-	054.8	150	10	
-	058.6	150	02	
-	069.6	150	10	
-	074.4	150	02	
-	086.7	150	10	
-	090.3	150	01	
-	103.6	150	11	

**Traffic Controls** 

Regional Street Lane Closure Required: No npacted Regional Street: N/A

**General Requirements:** Residential Street Restrictions.

## WARNING

IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT, THE CONTRACTOR MUST:

1) NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION

OF EXCAVATION

2) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY

INSTALLATIONS. SEE PROVINCIAL REGULATION 140/92 FOR DETAILS



Certificate of Authorization

AECOM Canada Ltd.

No. 4671 Date: 04/04/7019

WHOLE NUMBERS INDICATE MILLIMETRES DECIMALIZED NUMBERS INDICATE METRES

0 2.5 5 10 15 20 Meters Meters

TENDER NO. 183-2019

**LOCATION APPROVED** UNDERGROUND STRUCTURES

SUPR. U/G STRUCTURES DATE COMMITTEE

NOTE: LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE. BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

ISSUED FOR CONSTRUCTION

NO. REVISIONS

19/04/01

YY/MM/DD BY

**A**ECOM

DESIGNED BY	NK	CHECKED A
DRAWN BY	ES	APPROVED BY
HOR. SCALE VERT. SCALE	1: 500 N/A	RELEASED FOR CONSTRUCTION
DATE		DATE A72



60592016-01-C-2018 Lining - C5-R0 mxd

## THE CITY OF WINNIPEG **WATER AND WASTE DEPARTMENT**

**2018 SEWER RENEWALS BY CIPP LINING CONTRACT 6** 

**CONIFER CR (W LEG)** 

1ST MH N OF CONIFER CR (S LEG) TO 2ND MH N OF CONIFER CR (S LEG)

SHEET 30 OF 49

CITY DRAWING NUMBER

12100