

1 E1.3 FORT ROUGE GARAGE BUILDING B MAIN FLOOR PLAN - ELETRICAL - NEW CONSTRUCTION

SCALE: 1/64" = 1'-0"

2 E1.3 FORT ROUGE GARAGE BUILDING B ROOF FLOOR PLAN - ELETRICAL - NEW CONSTRUCTION

SCALE: 1/64" = 1'-0"

GENERAL NOTES

A. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING EXACT LAYOUT, ROUTING, ETC. VERIFY EXISTING SERVICES ON SITE.

B. CONTRACTOR SHALL ENSURE COORDINATION BETWEEN ALL TRADES AND CONSULTANTS ON AND OFF SITE, AS REQUIRED FOR INSTALLATION OF ELECTRICAL EQUIPMENT.

C. SEAL ALL ROOF PENETRATIONS AS REQUIRED.

D. PROVIDE LIQUID TIGHT CONNECTORS ON ALL OUTDOOR CONDUITS.

E. FIRE STOP ALL PENETRATION THROUGH RATED WALLS.

KEY NOTES (#)

1. DAVIT HOIST PROVIDED AND INSTALLED BY GENERAL CONTRACTOR. HOIST IS C/W POWER CORD AND PLUG. BASIS OF DESIGN IS PRO-BEL ROOF MOUNTED MATERIALS WINCH HOIST WITH 2000-3000LB CAPACITY. REFER TO ELECTRICAL SPECIFICATION FOR HOIST ELECTRICAL REQUIREMENTS. IF DIFFERENT HOIST IS PROVIDED, NOTIFY CONTRACT ADMINISTRATOR, AS ELECTRICAL REQUIREMENTS MAY CHANGE.

2. PROVIDE PEDESTAL MOUNTED CLASS A GFCI 5-20R RECEPTACLE ON ROOF TOP. MINIMUM 750mm (30") ABOVE FINISHED ROOF. LOCATE RECEPTACLE WITHIN REACH OF DAVIT HOIST POWER CORD. COORDINATE LOCATION WITH CONTRACT ADMINISTRATOR AND GENERAL CONTRACTOR. REFER TO ELECTRICAL SPECIFICATION FOR PEDESTAL MODEL NUMBER. REFER TO STRUCTURAL DRAWING S4.1 DETAILS A OR B FOR REQUIRED ROOFING REPAIR.

3. PROVIDE NEW 20A-1P BREAKER IN PANEL AND CONNECT NEW ROOF TOP RECEPTACLE. WIRE WITH 2#6 AWG MINIMUM.

The General Contractor shall check & verify all dimensions and report any errors or omissions to the designers.

No.	Date	Issue/Revision	By
A	2019-05-06	ISSUED FOR CONSTRUCTION	MZ

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
SMS Engineering Ltd.
No. 166

PROVINCE OF MANITOBA
May 06, 2019
M. ZUHAIR
Member
36873
REGISTERED PROFESSIONAL ENGINEER

Consultant

770 Bradford Street
Winnipeg, Canada
T 204 775 0291
SMSeng.com
19-086-01

SMS ENGINEERING

CITY OF WINNIPEG BID OPPORTUNITY 236-2019

300-275 Carlton Street
Winnipeg, Manitoba R3C 5R6
T 204. 943. 7501
F 204. 943. 7507

Crosier Kilgour & Partners Ltd.
CONSULTING STRUCTURAL ENGINEERS

Project
WINNIPEG TRANSIT
ROOF FALL ARREST MEASURES

FORT ROUGE GARAGE - BUILDING 'B'
421 OSBORNE STREET
WINNIPEG, MANITOBA

Sheet Title
FORT ROUGE GARAGE - BUILDING B
MAIN FLOOR AND ROOF PLAN -
ELECTRICAL - NEW CONSTRUCTION

File	Date
2018-0794	2019-05-01
Design: MZ	Drawn: WPD

Revision: A

Sheet No.: E1.3