



LEGEND

- 1 Remove Existing Swing Bays and Timbers (BY OTHERS)
- 2 Remove Existing Play Equipment and Timbers (BY OTHERS)
- 3 Remove Existing Site Furniture Within Work Area (BY OTHERS)
- 4 Remove Existing Sand Play Surface, Pavers and Pathways Designated for Resurfacing. Path Excavation Depth Varies Based on Designated Pathway Type (Refer To Materials Plan) (170 CM)
- 5 Existing Boulder with Plaque - Protect in Place
- 6 Existing Bollards to Remain
- 7 All Existing Trees Within Work Area to be Protected with Strapping

*Dotted orange line indicates extents of proposed design



CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.



THE CITY OF WINNIPEG
 Planning, Property and Development Department
 Planning and Land Use Division
 Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)

DESIGNED BY	CHECKED BY	MANAGER, PARK AND OPEN SPACES	DATE
DRAWN BY IM	APPROVED BY		
HORIZ. SCALE		MANAGER, PLANNING AND LAND USE DIVISION	DATE
VERT. SCALE			
DATE	April 2020		

DRAWING TITLE
**Morley R. Kare Park
 Playground Redevelopment
 Existing Conditions and Removals**

SITE ADDRESS 115 North Meadow Road

DRAWING NO.
M.93-B1

BID OPPORTUNITY NO.
 348-2020