



# 476-2020 ADDENDUM 1

Van Walleggem Park Pathway Improvements

## **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE REQUEST FOR PROPOSAL**

ISSUED: July 29,2020  
BY: **Ian Macdonald**  
TELEPHONE NO. 204 – 451-3069

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE REQUEST FOR PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS**

Template Version: Ar20160708

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Request for Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Proposal may render your Proposal non-responsive.**

## **PART A – PROPOSAL SUBMISSION (FORM B PRICES)**

Replace: 476-2020\_eBid\_FormB with 476-2020\_eBid\_FormB(R1)\_Addendum 1. The following is a summary of changes incorporated in the replacement Proposal Submission

Form B(R1): Add Item No. 8.

## **PART E – SPECIFICATIONS**

Revise: E1.4 to read:

E1.4 The following are applicable to the Work:

<u>Drawing No.</u>	<u>Drawing Name/Title</u>
V.7-I-R0	Existing Conditions & Removals
<b>V.7-J-R1</b>	<b>Grading Plan</b>
<b>V.7-K-R1</b>	<b>Layout Plan</b>
<b>V.7-L-R1</b>	<b>Details</b>
SCD-121A	Tache Bench – Composite w/Arms
SCD-646-R1	Park Path Crushed Limestone
SD-243-R2	Sodding Details

Add:

### **E18. CAST-IN-PLACE CONCRETE PAVEMENT WITH TACTILE WARNING TILE**

E18.1 Description

E18.1.1 The specification shall supplement the current version of CW 3325, CW 3235 and CW 3310.

E18.1.2 The Contractor shall furnish all labour, materials, equipment and services necessary to complete the Work according to the drawings and specifications.

E18.2 Materials

- E18.2.1 All material shall conform to current CW 3325, CW 3235 and CW 3310 and all other applicable current City of Winnipeg Standard Construction Specifications, whether listed herein or not.
- E18.3 Crushed Limestone Base Material
- E18.3.1 Description
- (a) Crushed limestone base material shall be supplied and installed in accordance with CW 3110 and as per the Drawings.
  - (b) Base course shall be Granular A as per current CW 3110, the Drawings, and this Specification.
- E18.4 Geotextile
- E18.4.1 Description
- (a) Geotextile shall be *Combigrid 30/30 Q1 151 GRK 4C*, which is a non-woven geotextile/geogrid combination or approved substitute in accordance with B7.
    - Supplier Brock White, 879 Keewatin St., Winnipeg
- E18.5 Tactile Warning Tile
- E18.5.1 Description
- (a) ADA Solutions Paver 24"x60" Yellow or Substitute as per B7.
    - Supplier Brock White, 879 Keewatin St., Winnipeg
    - Product No. 0403054 MFG #: 2460IDPAV2
- E18.6 Supply of Materials and Equipment
- E18.6.1 The Contractor shall supply all materials and use equipment in accordance with the current version of CW 3325.
- E18.7 Construction Methods
- E18.7.1 No concrete work shall commence until the excavation has been completed in accordance with the current version of CW 3110 and the drawings has been approved by the Contract Administrator.
- E18.7.2 Sub-base compaction shall be in accordance with the current version of CW 3110.
- E18.7.3 Combigrid geotextile shall be installed as per Manufacturer's written instruction.
- E18.7.4 Base Course to be installed to a depth of 125 mm in accordance with the current version of CW 3110 and the drawings.
- E18.7.5 Concrete pavement shall be installed as shown on drawings in accordance with the current version of CW 3310.
- E18.7.6 Concrete Placement shall be installed to a depth of 100 mm thickness in accordance with the current version of CW 3310, Section 9.4.
- E18.7.7 Tactile Warning Tile shall be installed as per Manufacturer's written instruction and City of Winnipeg Universal Design Standard.
- E18.8 Method of Measurement and Basis of Payment
- E18.8.1 Method of Measurement shall be as follows:
- (a) CIP concrete pavement shall be measured on a square meter basis for:
    - (i) "Supply and Install Cast-In-Place Concrete Pavement with Tactile Warning Tiles" on Form B: Prices.
- E18.9 Basis of Payment shall be as follows:
- E18.9.1 "Supply and Install Cast-In-Place Concrete Pavement with Tactile Warning Tiles" will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B:

Prices. This price shall be full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.

## **DRAWINGS**

Replace: 476-2020\_Drawing\_V.7-J-R0 with 476-2020\_Drawing\_V.7-J-R1 \_Addendum\_1

Replace: 476-2020\_Drawing\_V.7-K-R0 with 476-2020\_Drawing\_V.7-K-R1 \_Addendum\_1

Replace: 476-2020\_Drawing\_V.7-L-R0 with 476-2020\_Drawing\_V.7-L-R1 \_Addendum\_1