



367-2021 ADDENDUM 5

WEATHER PROTECTED WALKWAY SYSTEM ACCESSIBILITY UPGRADES – 251 DONALD STREET

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: April 1, 2022
BY: Lou Chubenko
TELEPHONE NO. 204 470-7881

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

PART E – SPECIFICATIONS

DRAWINGS

Replace: 367-2021_Drawing_A2.0-R0 with 367-2021_Addendum_5-Drawing_A2.0-R1

367-2021_Drawing_E2.0-R1 with 367-2021_Addendum_5-Drawing_E2.0-R1

QUESTIONS AND ANSWERS

Q1: We have discrepancy in the scope of work for doors D202a, D202b and D203b – Drawing E2.0: deems no card readers; Drawing A2.0: deems two (2) card readers and hardware sets (Section 08 71 00 Set 3.0): deems one (1) card reader. Please clarify. If card readers in are in fact required, a specification for card readers will be required.

A1: Provide card readers for the following doors, as per 367-2021_Addendum_5-Drawing_A2.0-R1 and 367-2021_Addendum_5-Drawing_E2.0-R1:

- 1 - Card Reader for doors D202a (single door) and D202b (double door). The card reader will operate the three doors.
2. 1 - Card Reader for D203b (double door). The existing card reader to be removed, relocated and re-installed, will operate D203b only. No card reader required for door D203a.

Card readers are required, refer to Answer 3 below.

Q2: There is some ambiguity regarding what is required at Doors D202a, D202b for the pole mounted/full height bollard mounted components versus wall mounted (refer to Drawing A2.0 and Hardware Set 3).

A2: Refer to 367-2021_Addendum_5-Drawing_A2.0-R1 and 367-2021_Addendum_5-Drawing_E2.0-R1. No changes to hardware specification.

Q3: The hardware sets call up “Card Readers” to be by Security/Electrical, so we need to clarify who is supplying these items?

A3: New card readers shall be supplied and installed by Prime Contractor. Existing card readers shall be removed and re-installed by the Prime Contractor. Prime Contractor to coordinate with the City of Winnipeg Building Systems Services for system interconnection and programming. Acceptable Product: HID multi CLASS SE® RP40.