



# 737-2021 ADDENDUM 4

## KEEWATIN STREET NORTHBOUND REHABILITATION – INKSTER BOULEVARD TO ADSUM DRIVE

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID/PROPOSAL**

ISSUED: Jan 10, 2022  
BY: Craig Rowbotham  
TELEPHONE NO. 204 318-2051

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID/PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

### **FORM B: PRICES**

Replace: 737-2021 Addendum 1 - Form B(R1): Prices with 737-2021 Addendum 4 - Form B(R2): Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Form B(R2): Concrete pay items updated based on Addendum 4 – E23 and Addendum 4 - Appendix C.

Page numbering on some forms may be changed as a result.

### **PART D – SUPPLEMENTAL CONDITIONS**

Replace: Section D12 in its entirety with the following:

#### D12. INSURANCE

D12.1 The Contractor shall provide and maintain the following insurance coverage:

- (a) commercial general liability insurance, in the amount of at least two million dollars (\$2,000,000.00) inclusive, with The City and Manitoba and its Ministers, officers, employees and agents are added as additional insureds, with a cross-liability clause, such liability policy to also contain contractual liability, unlicensed motor vehicle liability, non-owned automobile liability, broad form property damage cover and products and completed operations, to remain in place at all times during the performance of the Work and throughout the warranty period;
- (b) automobile liability insurance covering all motor vehicles, owned and operated and used or to be used by the Contractor directly or indirectly in the performance of the Work. The limit of liability shall not be less than \$5,000,000 inclusive for loss or damage including personal injuries and death resulting from any one accident or occurrence;
- (c) an all risks Installation Floater carrying adequate limits to cover all machinery, equipment, supplies and/or materials intended to enter into and form part of any installation.

D12.2 Deductibles shall be borne by the Contractor.

D12.3 All policies shall be taken out with insurers duly licensed in the Province of Manitoba.

- D12.4 All Subcontractors performing Work on the Project shall provide the Contractor with evidence of insurance as outlined in D10.1 (a) and (b) above and be registered with Workers Compensation Board of Manitoba and maintain insurance and workers compensation coverage throughout the performance of the Work. The Contractor shall provide the Contract Administrator with evidence of same prior to the commencement of any Work.
- D12.5 The Contractor shall provide the City Solicitor with a certificate(s) of insurance, in a form satisfactory to the City Solicitor, at least two (2) Business Days prior to the commencement of any Work but in no event later than the date specified in the C4.1 for the return of the executed Contract Documents, as applicable.
- D12.6 The Contractor shall not cancel, materially alter, or cause each policy to lapse without providing at least thirty (30) Calendar Days prior written notice to the Contract Administrator.

Page numbering on some forms may be changed as a result.

## **PART E – SPECIFICATIONS**

Replace: Section E5 in its entirety with the following:

### **E5. TRAFFIC CONTROL**

E5.1 Further to clauses 3.6, 3.7 and 3.8 of CW 1130:

- (a) Where directed by the Contract Administrator, the Contractor shall construct and maintain temporary asphalt ramps to alleviate vertical pavement obstructions such as manholes and planing drop-offs to the satisfaction of the Contract Administrator. Payment shall be in accordance with CW3410.
- (b) In accordance with the Manual of Temporary Traffic Control on City Streets (MTTC), the Contractor ("Construction Agency" in the manual) shall be responsible for supplying, placing, maintaining and removing the appropriate temporary traffic control devices as specified by the MTTC, the Contract Drawings, Staging Plans, and Traffic Management Plans or by the Traffic Management Branch of the City of Winnipeg Public Works Department. The Contractor shall bear all costs associated with the supply, placement and maintenance of temporary traffic control devices by their own forces or subcontractor.
- (c) In addition, the contractor shall be responsible for removing, placing, and maintaining all regulatory signing including but not limited to:
  - (i) Parking restrictions,
  - (ii) Stopping restrictions,
  - (iii) Turn restrictions,
  - (iv) Diamond lane removal,
  - (v) Full or directional closures on a Regional Street,
  - (vi) Traffic routed across a median,
  - (vii) Full or directional closure of a non-regional street where there is a requirement for regulatory signs (turn restrictions, bus stop relocations, etc.) to implement the closure.
- (d) The Contractor shall remove and stockpile any regulatory signage not required during construction such as but not limited to parking restrictions, turn restrictions and loading restrictions.

E5.2 Further to E5.1(c) the Contractor shall make arrangements with the Traffic Services Branch of the City of Winnipeg to supply regulatory signs as required.

E5.3 Upon request from the Contract Administrator, the Contractor shall provide records demonstrating that the site has been maintained.

- E5.4 Further to E5.1(c) and E5.1(d) the Contractor shall make arrangements with the Traffic Services Branch of the City of Winnipeg to reinstall the permanent regulatory signs after the contract work is complete. At this time the contractor shall make arrangements to drop off the stockpiled materials to Traffic Services at 495 Archibald Street.
- E5.5 Any changes to the approved traffic management plan must be submitted to the Contract Administrator a minimum of 5 Working Days prior to the required change for approval.
- E5.6 If the Contract Administrator determines that the Contractor is not performing Traffic Control in accordance with this specification, Traffic Services may be engaged to perform the Traffic Control and the Contractor shall bear the costs associated by the Traffic Services Branch of the City of Winnipeg in connection with the works undertaken by the Contractor.

Revise: E13.5 to read:

E13.5 Pavement Repair Fabric

E13.5.1 The supply and installation of the pavement repair fabric will be measured on an area basis and paid for at the Contract Unit Price per square metre for "Items of Work" listed here below. The area to be paid for will be the total number of square metres of pavement repair fabric supplied and installed in accordance with this specification, accepted and measured by the Contract Administrator.

E13.5.2 Items of Work:

- (a) Supply and Installation of Pavement Repair Fabric
  - (i) Type A
  - (ii) Type B

Revise: E15.4.2 to read:

E15.4.2 Items of Work:

- (a) Monolithic Curb and 100 mm Sidewalk with Block Outs\*
  - \* - reveal height, curb type, concrete type

Revise: E18.6.2 (b) to read:

E18.6.2 Items of Work:

- (b) Concrete Curb Installation
  - (i) Type 2 Retaining Barrier Curb (180 reveal above sidewalk)

Add: Section E22 as follows:

E22. WORK PRACTICES ON ASBESTOS-CEMENT PIPE

E22.1 Further to C6.28 (d), the Contractor's attention is directed to the possible health dangers associated with working with asbestos-cement pipe and all work associated with the existing AC water mains shall conform to the following publications:

- (a) "Work Practices for Asbestos-Cement Pipe", AWWA No. M16, published by the American Water Works Association.
- (b) "Recommended Work Practices for AC Pipe", 1977, published by the AC Pipe Producers Association.

Add: Section E23 as follows:

E23. CONCRETE CONSTITUENT MATERIALS, MIX DESIGN REQUIREMENTS, AND HOT AND COLD WEATHER CONCRETING

E23.1 The specification contained in Appendix "C" – 'Concrete Constituent Materials, Mix Design Requirements, and Hot and Cold Weather Concreting' shall apply to the Work.

Page numbering on some forms may be changed as a result.

## **APPENDICES**

Add: Addendum 4 - Appendix "C" - Concrete Constituent Materials, Mix Design Requirements, and Hot and Cold Weather Concreting