

## 327-2022B ADDENDUM 1

### NEWTON FORCE MAIN RED RIVER CROSSING BY HORIZONTAL DIRECTIONAL DRILLING

#### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE  
BID/PROPOSAL**

ISSUED: November 2<sup>nd</sup>, 2022  
BY: Ray Offman, P.Eng.  
TELEPHONE NO. 204 896-1209

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID/PROPOSAL AND SHALL FORM  
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

---

#### **PART B – BIDDING PROCEDURES**

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, **November 10<sup>th</sup>, 2022.**

#### **PART E – SPECIFICATIONS**

Delete: E8.10(b)

#### **QUESTIONS AND ANSWERS**

- Q1: Will freezing temperature pressure testing be allowed if the working ends are hoarded and heated during the entire duration of the pressure test?
- A1: If exposed ends are heated, hoarded, and maintained above 5 degrees it is acceptable. Ends must be protected from freezing until backfilled or until temperature stays above freezing.
- Q2: What is to be considered an approved anchor system for the directional drill? There are several methods to anchoring but we are not familiar with any having official industry approval.
- A2: Means and methods for the Contractor anchoring the rig shall be at the discretion of the Contractor based on their rig and site setup. Anchor shall be suitable to complete drilling activities based on the site conditions.
- Q3: Is there a specification outlined for conductor tracer cable to be pulled with the 500mm underneath the river portion?
- A3: No tracer cable has been specified for this crossing.