

APPENDIX A - TABLE E13.1: SITE SPECIFIC DESIGN CONDITIONS AND REPAIR REQUIREMENTS PRIOR TO PERFORMING SEWER LINING

Community Row (Asset No. MA60000904) Land Drainage Sewer	CB at Roblin Blvd (CL) (CB60000628) to MH at N PL Roblin Blvd (MH70050653)
Drawng Number	13108
Size / Shape	525 circular
Material Type	corrugated steel
Total Length	15.08m
Maximum Sewer Depth to Invert	2.1m
Design Condition	Fully Deteriorated Ovality 2%
Site Specific Repairs	
Location	Action Required
Distance From CB60000628 (m)	
	No preparation works identified outside of sewer cleaning

Roblin Boulevard (Asset No. MA60003333) Land Drainage Sewer	5th MH W of Buckingham Rd (MH60002439) to curb inlet E of Dieppe
Drawng Number	13109
Size / Shape	450mm circular
Material Type	concrete
Total Length	29.54m
Maximum Sewer Depth to Invert	1.07m
Design Condition	Fully Deteriorated Ovality 6%
Site Specific Repairs	
Location	Action Required
Distance From MH60002439 (m)	
	No preparation works identified outside of sewer cleaning

Easement (E of Le Maire St) (Asset No. MA60023161) Land Drainage Sewer	MH at Houde Dr (S Leg) (MH60019419) to 1st MH S of Houde Dr (MH60019413)
Drawng Number	13110
Size / Shape	300mm circular
Material Type	concrete
Total Length	40.54m
Maximum Sewer Depth to Invert	2.8m
Design Condition	Fully Deteriorated Ovality 2%
Site Specific Repairs	
Location	Action Required
Distance From MH60019419 (m)	
1	CAUTION: Displaced joint
13.1	Remove encrustation from pipe joint @ 5:00
15.6	Remove encrustation from pipe joint @ 7:00
24.1	Remove encrustation from pipe joint @ 4:00 to 8:00
26.6	Remove encrustation from pipe joint @ 4:00 to 8:00
27.8	Remove encrustation from pipe joint @ 5:00
29	Remove encrustation from pipe joint @ 7:00
30.3	Remove encrustation from pipe joint @ 5:00
32.7	Remove encrustation from pipe joint @ 4:00 to 8:00
33.9	Remove encrustation from pipe joint @ 4:00 to 8:00
36.4	Remove encrustation from pipe joint @ 4:00 to 8:00
37.6	Remove encrustation from pipe joint @ 4:00 to 8:00
39.9	Remove encrustation from pipe wall @ 6:00

Lane (E of Houde Dr (W Leg)) (Asset No. MA60022941) Land Drainage Sewer	1st MH S of Ducharme Av (MH60019247) to Mh at Ducharme Av (MH60019243)
Drawng Number	13111
Size / Shape	300mm circular
Material Type	concrete
Total Length	42.14m
Maximum Sewer Depth to Invert	2.99m
Design Condition	Fully Deteriorated Ovality 2%
Site Specific Repairs	
Location	Action Required
Distance From MH60019247 (m)	
2.7	Remove encrustation from pipe joint @ 9:00
4	Remove encrustation from pipe joint @ 9:00
12.4	Remove encrustation from pipe joint @ 6:00
16.1	Remove encrustation from pipe joint @ 3:00 to 9:00
18.5	Remove encrustation from pipe joint @ 3:00 to 9:00
19.8	Remove encrustation from pipe joint @ 3:00 to 9:00
21	Remove encrustation from pipe joint @ 3:00 to 9:00
21.0 to 41.5	Remove encrustation from pipe wall @ 6:00

Pembina Highway (Asset No. MA60022371) Land Drainage Sewer	
1st MH S of Ducharme Ave (MH60018775) to MH at Ducharme Ave (N PL) (MH60018774)	
Drawng Number	13112
Size / Shape	450mm circular
Material Type	concrete
Total Length	63.7m
Maximum Sewer Depth to Invert	2.1m
Design Condition	Fully Deteriorated Ovality 2%
Site Specific Repairs	
Location	Action Required
Distance From MH60018775 (m)	
17.2 to 18.9	Remove encrustation from pipe wall @ 5:00
46.3	Remove broken piece of pipe from joint at 7:00

Campeau Street (Asset No. MA60023315) Land Drainage Sewer	
1st MH S of Therese Av (MH70074115) to 2nd MH S of Therese Av (MH60019521)	
Drawng Number	13113
Size / Shape	250mm circular
Material Type	concrete
Total Length	105.42m
Maximum Sewer Depth to Invert	2.24m
Design Condition	Fully Deteriorated Ovality 5%
Site Specific Repairs	
Location	Action Required
Distance From MH70074115 (m)	
0.7	CAUTION: Displaced Joint
1.9	CAUTION: Displaced Joint
13.2	Remove encrustation from pipe joint @ 6:00
24.9	Remove encrustation from pipe joint @ 6:00
25.7	Remove encrustation from pipe joint @ 6:00
28.1	Remove encrustation from pipe joint @ 6:00
28.9	Remove encrustation from pipe joint @ 6:00
29.6	Remove encrustation from pipe joint @ 6:00
33.6	Remove encrustation from pipe joint @ 6:00
37.2	Note: material change to PVC and diameter change
38.9	Note: material change to concrete and diameter change
43.0 to 46.0	EPR from 43.0 to 46.0
53.8	Remove encrustation from pipe joint @ 5:00 to 7:00
55.4	Remove encrustation from pipe joint @ 5:00 to 7:00
58.5	Remove encrustation from pipe joint @ 4:00 to 8:00
60.1	Remove encrustation from pipe joint @ 6:00
60.9	Remove encrustation from pipe joint @ 7:00
61.6	Remove encrustation from pipe joint @ 6:00
62.4	Remove encrustation from pipe joint @ 4:00 to 8:00
63.2	Remove encrustation from pipe joint @ 5:00 to 7:00
64.8	Remove encrustation from pipe joint @ 6:00
66.3	Remove encrustation from pipe joint @ 6:00
67.2	Remove encrustation from pipe joint @ 6:00
67.9	Remove encrustation from pipe joint @ 6:00
68.7	Remove encrustation from pipe joint @ 6:00
69.5	Remove encrustation from pipe joint @ 6:00
71.8	Remove encrustation from pipe joint @ 6:00
72.6	Remove encrustation from pipe joint @ 6:00
74.9	Remove encrustation from pipe joint @ 6:00
76.5	Remove encrustation from pipe joint @ 6:00
77.3	Remove encrustation from pipe joint @ 4:00 to 7:00
78.1	Remove encrustation from pipe joint @ 6:00
78.8	Remove encrustation from pipe joint @ 6:00
80.3	Remove encrustation from pipe joint @ 6:00
82	Remove encrustation from pipe joint @ 6:00
83.5	Note: material change to PVC
85.2	Note: material change to concrete
85.6	Remove encrustation from pipe joint @ 6:00

Campeau Street (Asset No. MA70148673) Land Drainage Sewer	
1st MH N of St Therese Av (MH60019520) to 1st MH S of St Therese Ave (MH700747115)	
Drawng Number	13113
Size / Shape	250mm circular
Material Type	concrete
Total Length	27.09m
Maximum Sewer Depth to Invert	2.24m
Design Condition	Fully Deteriorated Ovality 5%
Site Specific Repairs	
Location	Action Required
Distance From MH60019520 (m)	
5.2 to 6.2	Remove rebar from pipe invert

6	Remove encrustation from pipe joint @ 6:00
7.6	Remove encrustation from pipe joint @ 6:00
10.8	Remove encrustation from pipe joint @ 3:00
20.1	Remove encrustation from pipe joint @ 6:00

La Grave Street (Asset No. MA60022547) Land Drainage Sewer	MH at Lord Ave (MH60018919) to 1st MH N of Lord Ave (MH60018915)
Drawng Number	13114
Size / Shape	300mm circular
Material Type	concrete
Total Length	77.27m
Maximum Sewer Depth to Invert	2.07m
Design Condition	Fully Deteriorated Ovality 2%
Site Specific Repairs	
Location	Action Required
Distance From MH60018919 (m)	
17.6	Remove encrustation from pipe wall @ 6:00
23.9	Remove encrustation from pipe wall @ 5:00
24.8	Remove encrustation from pipe wall @ 5:00
25.6 to 77.5	Remove roots from pipe joints
26.3	Remove encrustation from pipe wall @ 5:00
31.2	Remove encrustation from pipe wall @ 5:00

Lord Avenue (Asset No. MA60022532) Land Drainage Sewer	1st MH S of Lemay Ave (MH60018905) to 2nd MH S of Lemay Ave (MH70023738)
Drawng Number	13115
Size / Shape	300mm circular
Material Type	concrete
Total Length	78.55m
Maximum Sewer Depth to Invert	3.23m
Design Condition	Fully Deteriorated Ovality 3%
Site Specific Repairs	
Location	Action Required
Distance From MH60018905 (m)	
0.0 to 79.1	Remove roots from pipe joints
61.1 to 71.9	EPR 61.1 to 71.9
75.1	Note: material change to PVC

Chevrier Boulevard (Asset No. MA60018009) Land Drainage Sewer	1st MH E of French St (MH60015679) to 1st MH W of French St (MH60015590)
Drawng Number	13116
Size / Shape	375mm circular
Material Type	concrete
Total Length	84.62m
Maximum Sewer Depth to Invert	3.11m
Design Condition	Fully Deteriorated Ovality 2%
Site Specific Repairs	
Location	Action Required
Distance From MH60015679 (m)	
5.1 to 10.6	CUTION: Infiltration
18.6	Remove encrustation from pipe wall @ 2:00
18.6	Remove Roots frpm pipe joint
24.4	Remove encrustation from pipe joint @ 1:00 to 4:00
26.3	Remove encrustation below service @ 1:00
38.1	Remove intruding service @ 9:00
53.9 to unknown	EPR 53.9 to limits of collapse (to be determined)

Marshall Crescent (E Leg) (Asset No. MA60017030) Land Drainage Sewer	1st MH N of Maybank Dr (MH60014824) to MH at Maybank Dr (MH60014666)
Drawng Number	13117
Size / Shape	450mm circular
Material Type	concrete / clay
Total Length	71.9m
Maximum Sewer Depth to Invert	2.73m
Design Condition	Fully Deteriorated Ovality 2%
Site Specific Repairs	
Location	Action Required
Distance From MH (m)	
0.0 to 55.0	Remove roots from pipe joints and walls
8.5	Note: material change to clay
71	Remove encrustation from pipe wall @ 5:00

Waller Avenue (Asset No. MA60017196) Land Drainage Sewer	1st MH W of Marshall Cr (MH60014814) to 2nd MH W of Marshall Cr (MH60014826)
Drawng Number	13118
Size / Shape	300mm circular
Material Type	concrete
Total Length	85.08m
Maximum Sewer Depth to Invert	2.9m
Design Condition	Fully Deteriorated Ovality 2%
Site Specific Repairs	
Location	Action Required
Distance From MH60014814 (m)	
1	Remove encrustation from pipe wall @ 5:00
5.2	Remove encrustation below service @ 10:00
5.6 to 5.9	Remove encrustation from pipe wall @ 6:00 to 9:00
6.9	Remove roots from pipe joint
21.3 to 85.1	Remove roots from pipe joints
22.1 to 22.3	Remove encrustation from pipe wall @ 4:00
41.7	Remove encrustation from pipe wall @ 5:00
44	Remove encrustation from pipe wall @ 5:00
44.8	Remove encrustation from pipe joint @ 4:00
46.5	Remove encrustation from pipe wall @ 7:00
54.3	Remove encrustation from pipe joint @ 7:00 to 12:00
67.6	Remove encrustation from pipe joint @ 8:00
84.6	Remove encrustation from pipe joint @ 8:00

Dowker Avenue (Asset No. MA60017467) Land Drainage Sewer	1st MH E of Kenneth St (MH60015083) to 2nd MH E of Kenneth St (MH60015098)
Drawng Number	13119
Size / Shape	375mm circular
Material Type	concrete
Total Length	27.47m
Maximum Sewer Depth to Invert	2.33m
Design Condition	Fully Deteriorated Ovality 7%
Site Specific Repairs	
Location	Action Required
Distance From MH60015083 (m)	
0.9 to 27.0	Remove roots from pipe joints
24.5	Note: material change to PVC

Holly Avenue (Asset No. MA60017546) Land Drainage Sewer	Mh at McDougal St (MH60015167) to MH at Oriole St (MH60015174)
Drawng Number	13120
Size / Shape	375mm circular
Material Type	concrete
Total Length	74.91m
Maximum Sewer Depth to Invert	3.07m
Design Condition	Fully Deteriorated Ovality 2%
Site Specific Repairs	
Location	Action Required
Distance From MH60015167 (m)	
0.0 to 75.1	Remove roots from pipe joints
23.2	Remove encrustation from pipe joint @ 7:00
61.7 to 63.3	EPR from 61.7 to 63.3

South Drive (Asset No. MA60017742) Land Drainage Sewer	1st MH S of Pointe Rd (MH60015373) to 2nd MH S of Pointe Rd (MH60015363)
Drawng Number	13121
Size / Shape	300mm circular
Material Type	concrete
Total Length	91.97m
Maximum Sewer Depth to Invert	2.47m
Design Condition	Fully Deteriorated Ovality 6%
Site Specific Repairs	
Location	Action Required
Distance From MH60015373 (m)	
0.0 to 0.5	Remove encrustation from pipe wall @ 6:00
6.9	Note: material change to PVC
7.8	Note: material change to concrete
35.5	Note: material change to PVC
47.3	Note: material change to concrete
70.5 to 76.4	Remove roots from pipe joints
77.1	Note: material change to PVC, CAUTION: displaced joint
78.6	Note: material change to concrete
78.6 to 80.2	Remove roots from pipe joints
91.4	CAUTION: displaced joint

Wildwood C PK (N Leg) (Asset No. MA60013403) Wastewater Sewer	MH at Wildwood C PK (MH60011532) to 1st MH E of Wildwood C PK (MH60011530)
Drawng Number	13122
Size / Shape	200mm circular
Material Type	clay
Total Length	72.15m
Maximum Sewer Depth to Invert	2.93m
Design Condition	Fully Deteriorated Ovality 2%
Site Specific Repairs	
Location	Action Required
Distance From MH60011532 (m)	
2.7	Remove roots from pipe joint @ 9:00
3.6	Remove roots from connection @ 9:00
4.0 to 4.8	Remove grease from pipe wall at 11:00 to 1:00
4	Remove roots from pipe joint @ 2:00
4.8	Remove roots from pipe joint @ 9:00
6.3	Remove roots from pipe joint @ 3:00
7	Remove roots from pipe joint @ 10:00
7.8	Remove roots from pipe joint
9.4	Remove roots from pipe joint @ 3:00 and 9:00
10.2	Remove roots from pipe joint @ 3:00 and 9:00
11	Remove roots from pipe joint @ 3:00 and 9:00
12.3	Remove roots from pipe joint @ 3:00
13.7	Remove roots from pipe joint @ 3:00
18.5	Remove roots from pipe joint @ 3:00
31.7 to 32.3	Remove encrustation from pipe wall @ 1:00 to 4:00
60.7	Remove roots from pipe joint @ 3:00
62.3	Remove roots from pipe joint @ 3:00
62.5	Remove roots from connection @ 9:00
63.2	Remove roots from connection @ 1:00
63.6	Remove roots from pipe joint @ 10:00
64.4 to 66.6	EPR 64.4 to 66.6 including 2 service connections
69	Remove roots from pipe joint @ 9:00
70.5	Remove roots from pipe joint @ 3:00
71.3	Remove roots from pipe joint @ 3:00 and 9:00
71.7	Remove roots from pipe joint @ 9:00

Hector Bay (Asset No. MA60011305) Combined Sewer	MH at Hector Bay (S Leg) (MH60009568) to MH N of Hector Bay (S Leg) (MH60009684)
Drawng Number	13123
Size / Shape	300mm circular
Material Type	clay
Total Length	58.71m
Maximum Sewer Depth to Invert	3.55m
Design Condition	Fully Deteriorated Ovality 2%
Site Specific Repairs	
Location	Action Required
Distance From MH60009568 (m)	
4.7	Remove encrustation from pipe wall @ 6:00
23.8	Remove encrustation below service @ 2:00
31.3	Remove encrustation below service @ 10:00
39.9	Remove encrustation below service @ 2:00
50.2	Remove encrustation from pipe joint @ 7:00
55.7	Remove encrustation below service @ 2:00

Hector Bay (Asset No. MA60011428) Combined Sewer	1st MH N of Hector Bay (S Leg) (MH60009684) to Tee at Hector Ave
Drawng Number	13123
Size / Shape	300mm circular
Material Type	clay
Total Length	58.73m
Maximum Sewer Depth to Invert	5.3m
Design Condition	Fully Deteriorated Ovality 7%
Site Specific Repairs	
Location	Action Required
Distance From MH60009684 (m)	
1.6	Remove encrustation from pipe joint @ 6:00
2.9	Remove encrustation below service @ 10:00
5.3	Remove encrustation from pipe joint @ 6:00
14.9	Remove encrustation from pipe joint @ 8:00
15	Remove encrustation below service @ 2:00
21.6	Remove encrustation from pipe joint @ 5:00
26.2	Remove encrustation from pipe joint @ 5:00
31.1	Remove encrustation from pipe joint @ 7:00
32	Remove roots from pipe joint
32.9	Remove intruding service @ 11:00

44	Survey abandoned due to camera under water
----	--

Morley Avenue (Asset No. MA60008749) Combined Sewer	1st MH W of Osborne St (MH60007780) to MH at Osborne St (MH60007197)
Drawng Number	13124
Size / Shape	450mm circular
Material Type	clay
Total Length	96.71m
Maximum Sewer Depth to Invert	5.32m
Design Condition	Fully Deteriorated Ovality 4%
Site Specific Repairs	
Location	Action Required
Distance From MH60007780 (m)	
2.7	Note: material change to PVC
3.1	Remove intruding service @ 12:00
3.9	Remove intruding service @ 12:00
4.3	Note: material change to clay
4.9 to 7.1	Remove grease from pipe wall at 5:00
7.1	EPR from 6.7 to 7.3 including 1 service connection
31.2	Remove encrustation from pipe wall @ 7:00 to 10:00

Champlain Street (Asset No. MA50010759) Combined Sewer	1st MH N of St. Mary's Road (MH50008732) to MH at Caton St (MH50003650)
Drawng Number	13125
Size / Shape	300mm circular
Material Type	concrete
Total Length	95.45m
Maximum Sewer Depth to Invert	4.29m
Design Condition	Fully Deteriorated Ovality 4%
Site Specific Repairs	
Location	Action Required
Distance From MH50008732 (m)	
2.1	Remove encrustation from pipe joint @ 6:00
3	Remove intruding service @ 2:00
3.4	Remove roots from pipe joint
5.8	Remove encrustation from pipe joint @ 7:00
18.1	Remove encrustation from pipe joint @ 3:00
18.9	Remove encrustation from pipe joint @ 9:00
19.6	Remove encrustation from pipe joint @ 9:00 to 3:00
20.4	Remove encrustation from pipe joint @ 1:00 to 11:00
20.9	Remove encrustation from pipe wall @ 2:00
21.2	Remove encrustation from pipe joint @ 9:00 and 3:00
22.2	Remove encrustation from pipe joint @ 10:00
23	Remove encrustation from pipe joint @ 9:00
25	Remove encrustation from pipe joint @ 9:00
25.6 to 28.9	Remove grease from pipe wall @ 12:00 to 4:00
29.7	Remove encrustation from pipe joint @ 3:00
30.5	Remove encrustation from pipe joint @ 3:00
31.3	Remove encrustation from pipe joint @ 10:00
31.3 to 36.2	Remove encrustation from pipe wall
36.5 to 40.4	Remove grease from pipe wall @ 12:00 to 4:00
40.4	Remove encrustation at service @ 2:00
41.2 to 43.1	Remove encrustation from pipe wall
44.2 to 45.8	Remove encrustation from pipe wall
71.3	Remove encrustation from pipe wall @ 8:00
72	Remove encrustation from pipe joint @ 9:00
72.7	Remove encrustation from pipe wall @ 9:00
73.6	Remove encrustation from pipe joint @ 8:00
74.4	Remove encrustation from pipe joint @ 1:00 to 11:00
84.4	Remove encrustation from pipe joint @ 8:00
86.6	Remove encrustation from pipe joint @ 9:00
93.5	Remove encrustation from pipe joint @ 5:00

Champlain Street (Asset No. MA50010752) Combined Sewer	MH at Niverville Ave (MH50008725) to 1st MH S of Niverville Ave (MH50008726)
Drawng Number	13126
Size / Shape	300mm circular
Material Type	concrete
Total Length	88.03m
Maximum Sewer Depth to Invert	3.90m
Design Condition	Fully Deteriorated Ovality 2%
Site Specific Repairs	
Location	Action Required
Distance From MH50008725 (m)	
2	Remove encrustation from pipe joint @ 4:00 to 7:00
2.7	Remove encrustation from pipe joint @ 4:00 to 7:00
3.5	Remove encrustation from pipe joint @ 4:00 to 7:00

4.2	Remove encrustation from pipe joint @ 4:00 to 7:00
5.1	Remove encrustation from pipe joint @ 4:00 to 7:00
5.8	Remove encrustation from pipe joint @ 4:00 to 7:00
8.1	Remove encrustation from pipe joint @ 4:00 to 7:00
11	Remove encrustation at service @ 10:00
12.7	Remove encrustation from pipe joint @ 5:00 to 7:00
13.5	Remove encrustation from pipe joint @ 5:00 to 7:00
18.8	Remove encrustation from pipe joint @ 6:00
22	Remove encrustation from pipe joint @ 6:00
22.6	Remove encrustation from pipe joint @ 6:00
24.3	Remove encrustation from pipe joint @ 6:00
25.1	Remove encrustation from pipe joint @ 6:00
25.9	Remove encrustation from pipe joint @ 6:00
27.3	Remove encrustation from pipe joint @ 6:00
28.2	Remove encrustation from pipe joint @ 6:00
29	Remove encrustation from pipe joint @ 6:00
29.7	Remove encrustation from pipe joint @ 6:00
31.3	Remove encrustation from pipe joint @ 5:00 to 7:00
32	Remove encrustation from pipe joint @ 6:00
32.8	Remove encrustation from pipe joint @ 6:00
33.5	Remove encrustation from pipe joint @ 6:00
34.4	Remove encrustation from pipe joint @ 5:00
35.2	Remove encrustation from pipe joint @ 5:00 to 9:00
35.9	Remove encrustation from pipe joint @ 5:00 to 9:00
37.5	Remove encrustation from pipe joint @ 6:00
38.9	Remove encrustation from pipe joint @ 6:00
39.8	Remove encrustation from pipe joint @ 6:00
41.3	Remove encrustation from pipe joint @ 6:00
42.7	Remove intruding service @ 10:00
45.5	Remove encrustation at service @ 10:00
46.6	Remove encrustation from pipe joint @ 6:00
50.6	Remove encrustation from pipe joint @ 6:00
52.1	Remove encrustation from pipe joint @ 6:00
52.9	Remove encrustation from pipe joint @ 6:00
53.7	Remove encrustation from pipe joint @ 6:00
54.5	Remove encrustation from pipe joint @ 6:00
55.2	Remove encrustation from pipe joint @ 6:00
56.8	Remove encrustation from pipe joint @ 6:00
58.3	Remove encrustation from pipe joint @ 6:00
59.9	Remove encrustation from pipe joint @ 6:00
60.7	Remove encrustation from pipe joint @ 6:00
62.2	Remove encrustation from pipe joint @ 6:00
63	Remove encrustation from pipe joint @ 6:00
63.7	Remove encrustation from pipe joint @ 6:00
64.5	Remove encrustation from pipe joint @ 9:00
65.3	Remove encrustation from pipe joint @ 6:00
66.1	Remove encrustation from pipe joint @ 6:00
66.8	Remove encrustation from pipe joint @ 6:00
67.6	Remove encrustation from pipe joint @ 6:00 and 9:00
68.4	Remove encrustation from pipe joint @ 6:00
69.2	Remove encrustation from pipe joint @ 6:00
70.7	Remove intruding service @ 10:00
71.5	Remove encrustation from pipe joint @ 5:00
72.2	Remove encrustation from pipe joint @ 6:00
73	Remove encrustation from pipe joint @ 6:00
74.5	Remove encrustation from pipe joint @ 6:00
76.1	Remove encrustation from pipe joint @ 6:00
76.9	Remove encrustation from pipe joint @ 6:00
77.7	Remove encrustation from pipe joint @ 6:00
78.4	Remove encrustation from pipe joint @ 6:00
79.2	Remove encrustation from pipe joint @ 6:00
80	Remove encrustation from pipe joint @ 6:00
81.6	Remove encrustation from pipe joint @ 6:00
83.2	Remove encrustation from pipe joint @ 6:00
86.2 to 87.7	EPR 86.2 to 87.7

St. Catherine Street (Asset No. MA50002583) Wastewater Sewer	1st MH W of Archibald St (MH50002182) to MH at Archibald Street (MH50002183)
Drawng Number	13127
Size / Shape	300mm circular
Material Type	Clay
Total Length	97.38m
Maximum Sewer Depth to Invert	4.84m
Design Condition	Fully Deteriorated Ovality 5%
Site Specific Repairs	
Location	Action Required
Distance From MH 50002182(m)	
18.6	Remove intruding service @ 10:00
29.5	Remove intruding service @ 10:00
41.6	EPR from 41.2 to 42.2 including 1 service connection
45.4	Remove encrustation from pipe joint @ 9:00

46.9	Remove encrustation from pipe joint @ 9:00
51.7	Remove encrustation from pipe joint @ 7:00
56.5	Remove intruding service @ 10:00
66.5	Remove intruding service @ 10:00
97.1	Remove encrustation from pipe wall @ 9:00

Dawson Road (Asset No. MA70150054) Wastewater Sewer	2nd MH E of Dawson Rd (MH70074901) to 1st MH E of Dawson Rd (MH70036164)
Drawng Number	13128
Size / Shape	200mm circular
Material Type	concrete
Total Length	12.47m
Maximum Sewer Depth to Invert	3.6m
Design Condition	Fully Deteriorated Ovality 4%
Site Specific Repairs	
Location	Action Required
Distance From MH70074901 (m)	
11.1	Note: material change to PVC

Dugald Road (Asset No. MA70149383) Wastewater Sewer	3rd MH E of Dawson Rd (MH70074502) to 2nd MH E of Dawson Rd (MH70074901)
Drawng Number	13128
Size / Shape	200mm circular
Material Type	concrete
Total Length	132.67m
Maximum Sewer Depth to Invert	3.23m
Design Condition	Fully Deteriorated Ovality 4%
Site Specific Repairs	
Location	Action Required
Distance From MH70074502 (m)	
0.6	Remove encrustation from pipe joint @ 5:00 to 7:00
0.6	remove roots from pipe joint
4.4 to 5.0	Remove encrustation from pipe wall
5.7	Remove encrustation from pipe joint @ 1:00 to 5:00
6.5	Remove encrustation from pipe joint @ 5:00 to 7:00
10.4	Remove encrustation from pipe joint @ 2:00
12.1	Remove encrustation from pipe wall
15.9	Remove encrustation from pipe joint
28.4	Remove encrustation from pipe joint @ 3:00
29.9	Remove encrustation from pipe joint
38.6	Remove intruding service @ 3:00
29.2	Remove encrustation from pipe wall @ 2:00
42.1	Remove encrustation from pipe wall @ 9:00
42.4	Remove encrustation from pipe joint @ 8:00 to 5:00
43.6	Remove encrustation from pipe joint @ 8:00 to 5:00
44.4	Remove encrustation from pipe joint @ 8:00 to 5:00
44.7	Remove encrustation from pipe joint @ 8:00 to 5:00
45.5	Remove encrustation from pipe joint @ 8:00 to 5:00
46.3	Remove encrustation from pipe joint @ 8:00 to 5:00
47.1	Remove encrustation from pipe joint @ 8:00 to 5:00
47.8	Remove encrustation from pipe joint @ 7:00 to 5:00
49.4	Remove encrustation from pipe joint @ 7:00 to 5:00
50.2	Remove encrustation from pipe joint @ 7:00 to 5:00
51	Remove encrustation from pipe joint @ 7:00 to 5:00
51.8	Remove encrustation from pipe joint @ 7:00 to 5:00
52.5	Remove encrustation from pipe joint @ 7:00 to 5:00
53.3	Remove encrustation from pipe joint @ 7:00 to 5:00
54.1	Remove encrustation from pipe joint @ 7:00 to 5:00
54.1 to 56.7	Remove encrustation from pipe wall
60.3	Remove encrustation from pipe joint @ 7:00
66.8	Remove intruding service @ 3:00
68.9	remove roots from pipe joint @ 3:00
71.5	remove roots from service @ 3:00
89.1	Remove encrustation from pipe joint @ 7:00 to 5:00
93.8	Remove encrustation from pipe wall @ 6:00
94.6	Remove encrustation from pipe joint @ 10:00 and 3:00
95.5	Remove encrustation from pipe wall @ 3:00
96.2	Remove encrustation from pipe joint @ 3:00
105.8	Remove encrustation from pipe wall
106.3	remove roots from pipe joint
109.3	Remove encrustation at service @ 3:00
109.5	Remove encrustation from pipe joint @ 7:00 to 4:00
114.9	Remove encrustation from pipe joint @ 7:00 to 4:00
115.6	Remove encrustation from pipe joint @ 7:00 to 4:00
115.9	Remove encrustation at service @ 3:00
116.1	Remove encrustation from pipe wall @ 7:00 to 5:00
116.4	Remove encrustation from pipe joint @ 6:00
118.0 to 118.9	Remove encrustation from pipe wall
119.6	Remove encrustation from pipe joint

123.5	Remove encrustation from pipe joint @ 6:00
129.4 to 130.7	Remove encrustation from pipe wall

Plinquet Street (Asset No. MA50009970) Combined Sewer	1st MH W of Archibald St (MH50008192) to MH at Archibald St (MH50008193)
Drawng Number	13129
Size / Shape	300mm Circular
Material Type	Concrete
Total Length	96.14m
Maximum Sewer Depth to Invert	4.12m
Design Condition	Fully Deteriorated Ovality 5%
Site Specific Repairs	
Location	Action Required
Distance From MH50008192 (m)	
0.0 to 6.6	Remove encrustation from pipe wall
7.5	Remove encrustation from pipe wall @ 5:00
8.9 to 9.6	Remove encrustation from pipe wall
10.5	Remove encrustation from pipe joint @ 5:00
11.5	Remove encrustation from pipe joint @ 5:00
11.6	Remove encrustation from pipe wall @ 12:00
16	Remove intruding service @ 2:00
18.6	Note: material change to CIPP
21.5	Note: material change to concrete
21.5 to 21.7	Remove encrustation from pipe wall @ 12:00
24	Remove encrustation from pipe joint @ 9:00
24.3 to 24.7	Remove encrustation from pipe wall
26.3	Remove encrustation from pipe joint @ 4:00
28.2	Remove encrustation from pipe joint @ 4:00
29.6	Remove encrustation from pipe wall @ 5:00
30.7	Remove encrustation from pipe joint @ 4:00
33.2	Remove intruding service @ 11:00
35.4	Remove intruding service @ 2:00
38.5	Remove encrustation from pipe joint @ 8:00
40.4	Remove encrustation from pipe joint @ 4:00
44.2	Remove encrustation from pipe joint @ 4:00
47	Remove encrustation from pipe joint @ 4:00 and 8:00
47.9	Remove encrustation from pipe joint @ 4:00
48.8	Remove encrustation from pipe joint @ 4:00 and 8:00
50.8	Remove encrustation at service at 10:00
53.6 to 53.8	Remove encrustation from pipe wall @ 2:00 to 6:00
55.4	Remove encrustation from pipe joint @ 9:00
61.9	Remove encrustation from pipe joint @ 9:00
62.5	Remove encrustation from pipe joint @ 9:00
63.3	Remove intruding service @ 10:00
63.5	Remove encrustation from pipe joint
64.4	Remove encrustation from pipe joint @ 8:00
65.3	Remove encrustation from pipe joint @ 4:00
66	Remove intruding service @ 2:00
67.2	Remove encrustation from pipe joint @ 9:00
69.7 to 71.1	Remove encrustation from pipe wall
72.2	Remove encrustation from pipe joint @ 10:00
74	Remove intruding service @ 10:00
75.2 to 75.8	Remove encrustation from pipe wall
76.5	Remove encrustation from pipe joint @ 4:00
78.6 to 81.3	Remove encrustation from pipe wall
82.6 to 83.5	Remove encrustation from pipe wall
88.1 to 91.5	Remove encrustation from pipe wall
91.6	Note: material change to PVC

Archibald Street (Asset No. MA70039101) Combined Sewer	MH at Rue Dumoulin (MH50008099) to MH at Rue Notre Dame (MH50008084)
Drawng Number	13130
Size / Shape	450mm circular
Material Type	clay
Total Length	100.87m
Maximum Sewer Depth to Invert	5.45m
Design Condition	Fully Deteriorated Ovality 7%
Site Specific Repairs	
Location	Action Required
Distance From MH50008099 (m)	
7.6	Note: material change to PVC
14.7	Note: material change to clay
15.4	Remove encrustation from pipe joint @ 5:00
25.1	Remove intruding service @ 11:00
32.1	Remove encrustation below service at 2:00
40.4	Remove encrustation below service at 10:00
47.1	Remove encrustation below service at 10:00
53.8	Note: material change to PVC
75.2	Note: material change to clay

75.2	Remove encrustation from pipe joint @ 9:00
75.2 to 75.9	Remove encrustation from pipe wall
81	Remove encrustation below service at 10:00
99.6	Remove encrustation from pipe joint @ 9:00 to 5:00
100.3	Remove encrustation from pipe joint @ 9:00 to 5:00

Mission Street (Asset No. MA50009818) Combined Sewer	MH at Archibald St (W of CL) (MH50008080) to MH at Archibald St (MH50008081)
Drawng Number	13131
Size / Shape	375mm circular
Material Type	cmp / concrete
Total Length	2.31m
Maximum Sewer Depth to Invert	6.22m
Design Condition	Fully Deteriorated Ovality 4%
Site Specific Repairs	
Location	Action Required
Distance From MH50008080 (m)	
1.5	Note: material change to concrete
1.5	Remove encrustation from pipe joint

Washington Avenue (Asset No. MA40003423) Combined Sewer	MH at Watt St (MH40003115) to MH at Watt St (E of CL) (MH40003116)
Drawng Number	13132
Size / Shape	450mm circular
Material Type	clay
Total Length	8.04m
Maximum Sewer Depth to Invert	6.14m
Design Condition	Fully Deteriorated Ovality 6%
Site Specific Repairs	
Location	Action Required
Distance From MH (m)	
7.2	Remove encrustation from pipe wall @ MH

Leighton Avenue (Asset No. MA40006756) Combined Sewer	MH at Henderson Hwy (MH40006256) to 1st MH W of Henderson Hwy (MH40006179)
Drawng Number	13133
Size / Shape	375mm circular
Material Type	clay
Total Length	96.21m
Maximum Sewer Depth to Invert	4.96m
Design Condition	Fully Deteriorated Ovality 4%
Site Specific Repairs	
Location	Action Required
Distance From MH40006256 (m)	
6.9	Remove encrustation from pipe joint @ 10:00
12	Remove encrustation at service @ 2:00
12.6	Remove encrustation at service @ 2:00
19	Remove encrustation at service @ 12:00
31	Remove encrustation from pipe joint @ 8:00
51.9	Remove encrustation from pipe joint @ 7:00 to 10:00
53.3 to 53.8	Remove encrustation from pipe wall
53.8	Remove intruding service @ 10:00
53.8	Remove intruding service @ 2:00
54.4	Remove encrustation from pipe joint @ 1:00 to 5:00
55.1	Remove encrustation from pipe joint @ 7:00 to 10:00
56	Remove encrustation from pipe joint @ 2:00 to 5:00
62.4	Remove encrustation at service @ 2:00
63	Remove encrustation at service @ 10:00
64.4	Remove encrustation from pipe joint @ 9:00
67.4	Remove encrustation from pipe joint @ 5:00 to 7:00

Henderson Highway (Asset No. MA70024905) Combined Sewer	MH at Mossdale Av (MH40006242) to MH at Leighton Av (MH40006256)
Drawng Number	13134
Size / Shape	300mm circular
Material Type	clay
Total Length	78.05m
Maximum Sewer Depth to Invert	4.39m
Design Condition	Fully Deteriorated Ovality 5%
Site Specific Repairs	
Location	Action Required
Distance From MH40006242 (m)	
9.3	Remove encrustation from pipe joint @ 3:00
10	Note: material change to CIPP

10.2 to 11.0	Remove grease from pipe wall at 9:00 and 3:00
10.4	Remove encrustation from pipe wall @ 9:00 to 12:00
12	Note: material change to clay
17.5	Remove encrustation from pipe joint @ 3:00
18.6 to 19.6	Remove encrustation from pipe wall @ 8:00 to 5:00
22.5	Remove intruding service @ 2:00
24	Remove encrustation from pipe joint @ 3:00
24.8	Remove solid debris at 6:00
26.8	Remove encrustation from pipe joint @ 3:00
28.8	Remove encrustation from pipe joint @ 9:00
40	Remove encrustation from pipe joint @ 3:00
41.8 to 43.6	Remove grease from pipe wall @ 10:00
42.7	Remove encrustation from pipe joint @ 9:00 and 3:00
44.6	Remove encrustation from pipe joint @ 9:00 and 3:00
45.0 to 49.0	Remove encrustation from pipe joint @ 9:00 and 3:00
49.3	Remove encrustation from pipe joint @ 9:00
51	Remove encrustation from pipe joint @ 9:00
55	Remove intruding service @ 2:00
63.1	Remove encrustation from pipe joint @ 3:00
73.2	Remove encrustation from pipe joint @ 5:00
75.1	Remove encrustation from pipe joint @ 5:00 and 7:00

Edkar Crescent (W Leg) (Asset No. MA40000070) Wastewater Sewer	1st MH N of Edkar Cr (S Leg) (MH40000047) to MH at Mcivor Av (MH40000113)
Drawng Number	13135
Size / Shape	250mm circular
Material Type	concrete
Total Length	84.65m
Maximum Sewer Depth to Invert	3.98m
Design Condition	Fully Deteriorated Ovality 4%
Site Specific Repairs	
Location	Action Required
Distance From MH40000047 (m)	
11.4 to 16.7	Remove grease from pipe wall @ 9:00 to 3:00
20.7	Remove encrustation from pipe wall @ 10:00
21.1 to 22.9	Remove grease from pipe wall @ 12:00
24.6	Remove encrustation from pipe joint @ 10:00 to 3:00
28.3	Remove encrustation from pipe wall @ 9:00 to 3:00
31.9	Remove encrustation from pipe wall @ 2:00
84.2	Remove encrustation from pipe wall @ 8:00 to 5:00

Cormorant Bay (Asset No. MA50001952) Wastewater Sewer	MH at Cormorant (S Leg) (MH50001704) to 1st MH N of Cormorant (S Leg) (MH50001705)
Drawng Number	13136
Size / Shape	250mm circular
Material Type	concrete
Total Length	91.30m
Maximum Sewer Depth to Invert	2.86m
Design Condition	Fully Deteriorated Ovality 2%
Site Specific Repairs	
Location	Action Required
Distance From MH50001704 (m)	
2.4	Remove encrustation from pipe joint @ 7:00 to 3:00
3.2	Remove encrustation at service @ 3:00
5.5	Remove encrustation at service @ 3:00
6.6	Remove encrustation from pipe joint @ 7:00 to 5:00
20.4	Remove encrustation at service @ 3:00
20.8 to 21.4	Remove grease from pipe wall @ 9:00 to 3:00
21.4	Remove encrustation at service @ 3:00
26.8	Remove encrustation from pipe joint @ 3:00 to 7:00
28.1	Remove encrustation from pipe joint @ 3:00 to 9:00
32.9	Remove encrustation from pipe joint @ 1:00 to 7:00
34.2	Remove encrustation from pipe joint @ 7:00 to 5:00
35.1	Remove encrustation from pipe wall @ 1:00
39	Remove encrustation from pipe joint @ 8:00 to 3:00
39.8	Remove intruding service @ 9:00
44	Remove encrustation from pipe joint @ 9:00
46.3	Remove encrustation from pipe joint @ 9:00
55	Remove encrustation from pipe joint @ 7:00
56.7	Remove encrustation at service @ 9:00
57	Remove encrustation at service @ 3:00
67.2	Remove encrustation from pipe joint @ 4:00 to 7:00
72.1	Remove encrustation from pipe joint @ 1:00 to 11:00

Marwood Crescent (S Leg) (Asset No. MA50001465) Land Drainage Sewer	1st MH W of Edgemont Dr (MH50001271) to MH at Edgemont Dr (MH50001272)
Drawng Number	13137

Size / Shape	375mm circular
Material Type	concrete
Total Length	68.57m
Maximum Sewer Depth to Invert	1.72m
Design Condition	Fully Deteriorated Ovality 2%
Site Specific Repairs	
Location	Action Required
Distance From MH50001271 (m)	
	No preparation works identified outside of sewer cleaning

Leola Street (Asset No. MA40009006) Wastewater Sewer	MH at Regent Ave E (MH40008194) to MH at Victoria Ave E (MH40008200)
Drawng Number	13138
Size / Shape	200mm circular
Material Type	Clay
Total Length	90.91m
Maximum Sewer Depth to Invert	2.71m
Design Condition	Fully Deteriorated Ovality 2%
Site Specific Repairs	
Location	Action Required
Distance From MH (m)	
7.5	Note: material change to concrete
9.4	Note: material change to clay
11.5	Remove intruding service @ 2:00
17.1	Remove encrustation below service at 10:00
32.2	Remove encrustation from pipe joint @ 4:00
33.3	Remove encrustation from pipe wall @ 4:00
84.3	Note: material change to PVC
86.3	Note: material change to clay
88.2	Remove intruding service @ 10:00