

ASSET NUMBER	STREET NAME	LOCATION DESCRIPTION	FLOW TYPE	WORK NAME TYPE	EST COST	COMMENTS	DIAMETER	LENGTH
S-MA70039101	ARCHIBALD ST	MH AT RUE DUMOULIN TO MH AT RUE NOTRE DAME	CS	FULL SEGMENT LINER	\$42,875		450	100.91
S-MA60023315	CAMPEAU ST	1ST MH N OF ST THERESE AV TO 1ST MH S OF ST THERESE AV	LDS	FULL SEGMENT LINER	\$13,400	H, BSV, FM, FC, CL, SRI	300	27.20
S-MA70148673	CAMPEAU ST	1ST MH S OF ST THERESE AV TO 2ND MH S OF ST THERESE AV	LDS	AUGMENTED FS LINER	\$48,260	HSV, BVV, BSV, B, FM, FC, FL, CM, CL, CC, SRI, SSS, MSC (200mm PVC for 1.7m). EPRs @ 0-3m and 43.3-46.3m	300	105.60
S-MA50010752	CHAMPLAIN ST	MH AT NIVERVILLE AV TO 1ST MH S OF NIVERVILLE AV	CS	AUGMENTED FS LINER	\$42,600	EPR 85.4-87.4	300	87.90
S-MA50010759	CHAMPLAIN ST	1ST MH N OF ST MARYS RD TO MH AT CATON ST	CS	AUGMENTED FS LINER	\$47,340	FL THROUGHOUT; SOME D10% - IMAGES AVAILABLE;BSV, FM, FC, CC, CL, SAM, SAP	300	95.90
S-MA60018009	CHEVRIER BV(NPL)	1ST MH E OF FRENCH ST TO 1ST MH W OF FRENCH ST	LDS	AUGMENTED FS LINER	\$53,795	EPR 55.3-57.3 - urgent	375	84.40
S-MA60000904	COMMUNITY ROW	CB AT ROBLIN BV (CL)-MH AT ROBLIN BV (NPL)	LDS	FULL SEGMENT LINER	\$14,000	INVERT STARTING TO RUST -- NEW PAVEMENT IN 2020 NEED TO DO CIPP LINER BEFORE CONDITION WORSENS	525	15.20
S-MA50001952	CORMORANT BY E LEG	MH AT CORMORANT BY S LEG TO 1ST MH N OF CORMORAN	WWS	FULL SEGMENT LINER	\$32,600	PWD STREET WORK IN 2021	250	91.31
S-MA70150054	DAWSON RD(NPL)	2ND E OF DAWSON RD TO 1ST MH E OF DAWSON RD	WWS	FULL SEGMENT LINER	\$9,225	BAD SPALLING THROUGHOUT	200	12.41
S-MA60017467	DOWKER AV	1ST MH E OF KENNETH ST TO 2ND MH E OF KENNETH ST	LDS	FULL SEGMENT LINER	\$14,100	ORIGINAL EPR WAS DONE IN THE WRONG LOCATION UNDER PWD PROJECT. RECENT VIDEO SHOWS THAT PIPE IS LINEABLE. SHOULD TRY TO CIPP LINE	375	27.11
S-MA70149383	DUGALD RD(NPL)()	3RD MH E OF DAWSON RD TO 2ND MH W OF DAWSON RD	WWS	FULL SEGMENT LINER	\$48,550		200	133.21
S-MA60023161	EASEMENT(E OF LE MAIRE ST)	MH AT HOUDE DR (S.LEG) TO 1ST MH S OF HOUDE DR	LDS	AUGMENTED FS LINER	\$33,200	EPR from 0-7.1m	300	40.30
S-MA40000070	EDKAR CR (W.LEG)	1ST MH N OF EDKAR CR (S.LEG) TO MH AT MCIVOR AV	WWS	FULL SEGMENT LINER	\$32,625	PWD street renewal in 2021 - Need to CIPP line before defects become worse or a dig required	250	85.01
S-MA60011305	HECTOR BY W WLEG	MH @ HECTOR BY S SLEG-1ST MH N HECTOR BY W SLEG	CS	FULL SEGMENT LINER	\$22,700	FL X 2 (03, 09), D 5%, B, FL X4, D 10% - images available	300	58.51
S-MA60011428	HECTOR BY W WLEG	1ST MH N HECTOR BY W SLEG-TEE @ HECTOR AV	CS	FULL SEGMENT LINER	\$22,400	FC, FL X 3, D - 5% - images available	300	57.81
S-MA70024905	HENDERSON HW	MH AT LEIGHTON AV TO MH AT MOSSDALE AV	CS	FULL SEGMENT LINER	\$33,350	APPROX 10% DEFORMATION AT 33 M AND NEW PAVEMENT IN 2021 SHOULD LINE AS SOON AS POSSIBLE BEFORE EPR IS REQUIRED	300	76.94
S-MA60017546	HOLLY AV	MH AT MCDOUGALL ST TO MH AT ORIOLE ST	LDS	AUGMENTED FS LINER	\$47,800	EPR 61.4-63.5m, stabilization from 74.5-75	375	75.10
S-MA60022547	LA GRAVE ST	MH AT LORD AV TO 1ST MH N OF LORD AV	LDS	FULL SEGMENT LINER	\$28,400	BSV, B, DR 20%, FM, FC, FL, CC, CL, SRI, SSS	300	77.50
S-MA60022941	LANE (E OF HOUDE DR (W.LEG))	1ST MH S OF DUCHARME AV TO MH AT DUCHARME AV	LDS	FULL SEGMENT LINER	\$18,975	H, B, FM, CM, CC, CL, SRI, SSS	300	42.10
S-MA40006756	LEIGHTON AVE	1ST MH W LEIGHTON AVE TO MH AT HENDERSON HWY	CS	FULL SEGMENT LINER	\$38,250	4 POINT FRACTURES AND DEFORMATION IN FIRST 20 M OF SEWER. PARTIALLY UNDER NEW PAVENMENT ON HENDERSON HWY IN 2021	375	94.71
S-MA40009006	LEOLA ST	MH @ REGENT AV E - MH @ VICTORIA AV E	WWS	FULL SEGMENT LINER	\$34,575		200	91.11
S-MA60022532	LORD AV	1ST MH S OF LEMAY AV TO 2ND MH S OF LEMAY AV	LDS	FULL SEGMENT LINER	\$23,600	FM, FC, FL, CC, CL	300	79.10
S-MA60017030	MARSHALL CR (E.LEG)	1ST MH N OF MAYBANK DR TO MH AT MAYBANK DR	LDS	FULL SEGMENT LINER	\$32,375	; B, FM, CC, CL, SRI	450	72.10
S-MA50001465	MARWOOD CR (S.LEG)	1ST MH N OF EDGEMONT DR (E.LEG) - MH AT EDGEMONT DR (E.)	LDS	FULL SEGMENT LINER	\$25,700	FM -- PWD STREET RENEWAL IN 2021	375	68.51
S-MA50009818	MISSION ST	MH@ ARCHIBLAD ST (WOFCL) TO MH@ ARCHIBALD ST(CL)	CS	FULL SEGMENT LINER	\$6,050		375	2.51
S-MA60008749	MORLEY AV	1ST MH W OF OSBORNE ST TO MH AT OSBORNE ST	CS	AUGMENTED FS LINER	\$71,725	EPR at 6.7-7.3m for defective service	450	96.81
S-MA60022371	PEMBINA HWY	1ST MH S OF DUCHARME AV TO MH AT DUCHARME AV(NPL)	LDS	FULL SEGMENT LINER	\$32,200		450	63.60
S-MA50009970	PLINQUET ST	1ST MH W OF ARCHIBALD ST-MH@ARCHIBALD ST	CS	FULL SEGMENT LINER	\$38,950	FM, SS	300	96.01
S-MA60003333	ROBLIN BV	5TH MH W OF BUCKINGHAM RD TO CURB INLET (WBOUND) E OF DIEPPE	LDS	FULL SEGMENT LINER	\$17,750	ROAD WORK IN 2020	450	29.51
S-MA60017742	SOUTH DR	1ST MH S OF POINT RD TO 2ND MH S OF POINT RD	LDS	FULL SEGMENT LINER	\$34,900		300	91.80
S-MA50002583	ST.CATHERINE ST	1ST MH W OF ARCHIBALD ST TO MH AT ARCHIBALD ST	WWS	AUGMENTED FS LINER	\$55,000	EPR at 41.4-42.2m	300	97.11
S-MA60017196	WALLER AV	1ST MH W OF MARSHALL CR (E.LEG) TO 2ND MH W OF MARSHALL CR (E.LEG)	LDS	FULL SEGMENT LINER	\$30,800	HSV, BSV, B, FM, CM, CC, CL, SRI, SSS, IRJ	300	85.10
S-MA40003423	WASHINGTON AV (CL TO N OF CL)	MH AT WATT ST(EPL) TO MH AT WATT ST (E OF CL)	CS	FULL SEGMENT LINER	\$8,400	ROAD WORK IN 2020. NEED TO ADDRESS WITH TRENCHLESS ASAP BEFORE DEFECT WORSENS AND A DIG IS REQUIRED. SRS THROUGH TOP OF SEWER	450	8.11
S-MA60013403	WILDWOOD C PK N LEG	MH AT WILDWOOD C PK W LEG TO 1ST MH E OF WILDWOOD	WWS	AUGMENTED FS LINER	\$44,060	EPR 65.0-66.6M, FM, SSL, B, FM, CXI	200	67.59
					<b>\$1,100,530</b>			