

ASSET NUMBER	STREET NAME	LOCATION DESCRIPTION	FLOW TYPE	WORK TYPE NAME	EST COST	COMMENTS	HEIGHT (mm)	WIDTH (mm)	LENGTH (m)
S-MA20011126	PORTAGE AV	MH @ DOMINION ST CL - MH @ DOMINION ST EPL	CS	FULL SEGMENT LINER	\$24,300		900	900	7.7
S-MA20015190	PORTAGE AV	MH AT BANNING ST TO TIE-IN AT LIPTON ST	CS	FULL SEGMENT LINER	\$129,600		900	900	86.3
S-MA20011101	PORTAGE AV.	MH AT SPRAGUE ST. TO MH AT MINTO ST.	CS	FULL SEGMENT LINER	\$56,300	H, SAM	750	750	42.6
S-MA20011106	PORTAGE AV.	MH AT MINTO ST. TO MH AT GREENWOOD PL.	CS	FULL SEGMENT LINER	\$77,200	H, SAM, SAP	750	750	61.1
S-MA20011111	PORTAGE AV.	1ST MH E.OF WALL ST. TO MH AT BASSWOOD ST.	CS	FULL SEGMENT LINER	\$49,700	HSV, SAM, SAP	750	750	36.1
S-MA20011114	PORTAGE AV.	MH AT GOULDING ST. TO MH AT SPRAGUE ST.	CS	FULL SEGMENT LINER	\$76,100	SAM, SAP	750	750	60.7
S-MA20011107	PORTAGE AV.	MH AT GREENWOOD PL. TO MH AT DOMINION ST.	CS	FULL SEGMENT LINER	\$139,050	H, HSV, SAM, SAP, CC	900	900	92.3
S-MA20011143	PORTAGE AV.	MH AT GARFIELD ST.S. TO MH AT SHERBURN ST.,	CS	FULL SEGMENT LINER	\$128,250	H, SAP, SAM, SSS	900	900	84.5
S-MA20015185	PORTAGE AV.	MH AT LENORE ST. TO MH AT RUBY ST.(E.OF CL)	CS	FULL SEGMENT LINER	\$124,200	H, SAM THROUGH OUT	900	900	81.5
S-MA20015246	PORTAGE AV.	MH AT BURNELL ST TO MH AT LENORE ST.	CS	FULL SEGMENT LINER	\$64,800	HSV, SAM	900	900	37.2
S-MA20017639	PORTAGE AV.	MH AT SHERBURN TO TIE-IN	CS	FULL SEGMENT LINER	\$126,900	HSV, SAM, SAP, FL	900	900	84.0
S-MA20009421	ST MATTHEWS AV	MH AT WALL ST CL TO MH AT WALL ST W OF CL	CS	FULL SEGMENT LINER	\$10,700	WE ARE LINING UPSTREAM SECTION AND DOWNSTREAM SECTION WAS PREVIOUSLY LINED	600	600	4.2
S-MA20009104	ST MATTHEWS AV	MH AT ASHBURN ST(CL)TO MH AT VALOUR RD	CS	FULL SEGMENT LINER	\$85,000		750	750	75.3
S-MA20009784	ST MATTHEWS AV	MH AT STRATHCONA ST TO MH AT ASHBURN ST(W.PL)	CS	FULL SEGMENT LINER	\$91,000		750	750	81.3
S-MA20009103	ST MATTHEWS AV	MH AT VALOUR RD TO MH AT SPRUCE ST	CS	FULL SEGMENT LINER	\$114,900		900	900	77.8
S-MA20009129	ST MATTHEWS AV	MH AT SPRUCE ST TO MH AT TELFER ST N	CS	FULL SEGMENT LINER	\$73,300		900	900	45.8
S-MA20009132	ST MATTHEWS AV	MH AT TELFER ST TO TIE IN AT CLIFTON	CS	FULL SEGMENT LINER	\$119,100		900	900	87.2
S-MA20009430	ST MATTHEWS AV (CL)	MH AT GOULDING ST TO MH AT WALL ST(CL)	CS	FULL SEGMENT LINER	\$64,900	Severe surface wear throughout pipe, missing bottom of pipe most of the way	600	600	82.0
S-MA20017074	ST.MATTHEWS AV.	MH AT SHERBURN AV.(S.OF CL) TO MH AT SHERBURN AV.(CL)	CS	FULL SEGMENT LINER	\$92,000	HSV, SAM	750	750	80.1
S-MA20017810	WELLINGTON AV	MH @ LIPTON ST (WPL) TO MH @ LIPTON ST (CL)	CS	FULL SEGMENT LINER	\$23,900	SSM, SOME SSL - IMAGES AVAILABLE	900	900	6.3
					<b>\$1,671,200</b>				