



104-2023 ADDENDUM 2

CONSTRUCTION OF TRUNK AND LDS SEPARATION – COCKBURN & CALROSSIE SEWER RELIEF (CONTRACT 9A)

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
TENDER**

ISSUED: March 24, 2023
BY: John Minkevich
TELEPHONE NO. 204 896-1209

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE TENDER AND SHALL FORM A PART
OF THE CONTRACT DOCUMENTS**

Template Version: A20190115

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Tender, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

FORM B

Replace: 104-2023 eForm_B-Prices.xlsx with 104-2023 Addendum 2 eForm_B-Prices.xlsx. The following is a summary of changes incorporated in the replacement eForm_B-Prices:

- Revised Pay Item A.1 c) i), “Approximate Quantity” to 84.0.
- Revised Pay Items A.11 a) i), A.11 b) i) and A.11 c) i) to read “Trenchless installation, Class B Type 2 bedding, Class 1 Backfill”.

PART E – SPECIFICATIONS

Revise: E13.7. (e) to read:

- (i) Cement Stabilized Fill (CLSM) shall be in accordance with CW 2030 and Table CW 2160.1 unless otherwise indicated on the Drawings. Further to Table CW2160.1 the maximum compressive strength at 28 days to be no more than **2.5 MPa**.
 - (i) The Contractor shall install fill in lifts and provide sufficient supports to resist uplift of piping or structures due to backfilling.
- (ii) Excavations made within the path of the new sewer Works prior to Trenchless Sewer Construction operations shall be backfilled with CLSM.