



FINISHES:

PLAM-1: HPL PLASTIC LAMINATE
 MANUFACTURER: FORMICA
 PRODUCT: HPL LAMINATE-VERTICAL INSTALL;
 COLOR: AGED ASH # 8844-WR
 GRAIN DIRECTION: HORIZONTAL INSTALL
 LOCATION: REFERENCE DESK FRONT CURVED FACE,
 DRAWERS, ADJUSTABLE SHELVES AND BODY GABLE
 CONSTRUCTION
 DESK BODY CONSTRUCTION: 3/4" THICK REGULAR GRADE
 PLYWOOD

CPT-1: CARPET TILE (INSTALL ONLY - PRODUCT ON SITE)
 SHAW CONTRACT
 STYLE: REPARTEE 59387
 COLOR: EVENING SATIRE 87505
 SIZE: 24"X24" (61 cm x 61 cm)
 INSTALLATION: QUARTER TURN, LOW-VOC ADHESIVE
 NOTE: PRODUCT ON SITE FOR REPAIRS ONLY AS REQUIRED

RF-1: RUBBER FLOORING (SUPPLY & INSTALL)
 ROPPE
 STYLE: RECOIL FITNESS FLOORING
 COLOUR: SUNFLOWER 603
 SIZE: 36"X36" (914.4 mm x 914.4 mm)
 GAUGE: 1/4"
 EDGE: SQUARE EDGE PROFILE
 10% CHIP CONTENT
 INSTALLATION: GLUE-DOWN, LOW-VOC ADHESIVE
 INSTALL PATTERN: ASHLAR

SSC-1 : SOLID SURFACE COUNTERTOP
 MANUFACTURER: CORIAN
 COLOR: LAVA ROCK
 THICKNESS: 1/2" THICK (12.7mm)
 SHEEN: MATTE FINISH-POLISHED
 EDGE PROFILE: EASED EDGE
 LOCATION: REFERENCE DESK COUNTERTOPS
 REFER TO DRAWINGS

S.S-1: STAINLESS STEEL TOE BASE
 18 GAUGE S.S TYPE 304 #4 POLISHED
 LOCATION: CABINET BASE AS INDICATED ON
 DRAWINGS.

TB-1: TACKBOARD
 MANUFACTURER: FORBO FLOORING SYSTEMS
 COLOR: TO BE SELECTED BY CITY OF WINNIPEG
 LOCATION: CURVED FRONT ON DESK AS INDICATED

TR-1: TRANSITION STRIP
 MANUFACTURER: TARKETT-WHEELED TRAFFIC TRANSITION
 COLOR: 40 BLACK
 PROFILE: TO SUIT FLOORING PRODUCTS. SITE CONFIRM
 WITH CITY OF WINNIPEG CONTRACT ADMINISTRATOR.
 LOCATION: REFER TO DRAWINGS AS INDICATED

MILLWORK HARDWARE SPECIFICATIONS:

DRAWER SLIDES:
 MODEL: BLUM MOVENTO 760H-40KG
 EXTENSION SLOW CLOSE SLIDE TO MATCH
 CABINET SIZE;
 INSTALL TYPE: CONCEALED UNDERMOUNT

DRAWER/ DOOR HANDLES:
 MODEL: HAFELE # 117.05.610 VERANDA
 COLLECTION
 SIZE: 192 mm (7 INCHES)
 FINISH: 304 STAINLESS STEEL

DOOR HINGES:
 MODEL: BLUM CLIPTOP BLUMOTION
 SOFT CLOSE HINGE 110 DEGREE
 PRODUCT: KNOCK IN # 71 B 3580
 FINISH: NICKEL PLATED FINISH

DRAWER/ DOOR LOCKS: (AS REQUIRED)
 HAFELE CYLINDER MODULE
 MODEL: 235.08.358

SHELF SUPPORTS: (TO SUIT CABINET)
 HAFELE 255 SERIES PILASTER
 STANDARDS: KV; 3/8" X 3/16" 23 GA
 MODEL: 255 AL 18

- REFER TO N.M.S SECTIONS : 06 02 00
 ROUGH CARPENTRY; 06 04 00
 ARCHITECTURAL WOODWORK AND 12 36 61
 SOLID SURFACING FOR STANDARD OF
 CONSTRUCTION FOR ALL MILLWORK.
 MILLWORK CONTRACTOR TO HAVE
 MINIMUM 5-7 YEARS OF EXPERIENCE.
- SHOP DRAWINGS AND SAMPLES TO BE
 SUBMITTED TO CONTRACT
 ADMINISTRATOR FOR APPROVAL PRIOR TO
 CONSTRUCTION.
- SITE MEASUREMENTS REQUIRED PRIOR
 TO CONSTRUCTION.
- CONFIRM ALL GROMMET LOCATIONS
 PRIOR TO CUTTING. GROMMET COLOR-
 GREY OR BLACK FOR SOLID SURFACE
 COUNTERTOPS.
- ALL MILLWORK CONSTRUCTION IS TO BE
 3/4" THICK REGULAR GRADE PLYWOOD
 WITH PLAM-1 FINISH.

GENERAL NOTES

- THESE DRAWINGS SHALL NOT BE SCALED.
- THE CONTRACTOR SHALL VISIT THE SITE AND SATISFY ONESELF
 ALL DIMENSIONS, DATUM AND DETAILED INFORMATION SHOWN ARE
 CORRECT.
- THE CONTRACTOR IS TO REVIEW AND COORDINATE ALL
 ARCHITECTURAL, MECHANICAL, ELECTRICAL AND
 STRUCTURAL DRAWINGS FOR ADDITIONAL OPENINGS THROUGH
 FLOORS, WALLS, AND CEILINGS FOR DUCT, PIPE & ELECTRICAL
 RISERS AND ALL OPENINGS NOT SHOWN ON DRAWINGS.
- ALL OPENINGS THROUGH FIRE ASSEMBLIES ARE TO BE FIRE
 STOPPED AND SEALED WITH ULC APPROVED FIRE STOPPING TO
 MAINTAIN THE INTEGRITY OF THE FIRE SEPARATION, AND PROVIDE
 A SMOKE-TIGHT BARRIER.
- ALL PRODUCTS AND MATERIALS TO BE USED AND INSTALLED
 SHALL CONFORM WITH MANUFACTURER'S SPECIFICATIONS &
 APPLICABLE CODES.
- THE CONTRACTOR SHALL BE RESPONSIBLE TO PATCH AND
 MAKE GOOD ALL EXISTING CONSTRUCTION AFFECTED BY THE
 REMOVAL OF ALL ITEMS FORMING THE PART OF THE
 RENOVATION WORK.
- WHERE NEW FLOORING AND BASE IS TO BE INSTALLED IN
 EXISTING AREAS (REFER TO FLOOR PLAN AND ROOM SCHEDULE)
 THE EXISTING FLOORING SURFACE AND BASE MUST BE REMOVED,
 UNLESS OTHERWISE NOTED. ALL FLOOR SURFACES SHALL BE
 PREPARED IN ACCORDANCE TO MANUFACTURER'S
 RECOMMENDATIONS FOR INSTALLATION OF NEW FLOOR.
- WHERE PAINTING OF EXISTING WALLS IS INDICATED ON THE
 ROOM SCHEDULE, THESE WALLS MUST BE CLEANED OF ANY
 EXISTING WALL COVERING, PATCHED & PREPARED TO ACCEPT
 NEW MATERIAL, UNLESS OTHERWISE NOTED.

ASBESTOS

ASBESTOS MAYBE PRESENT BEHIND WALLS,
 CEILING SPACES & FLOORS.
 IF ASBESTOS OR ANY HAZARDOUS MATERIAL
 IS FOUND, STOP WORK IMMEDIATELY AND
 CONTACT CITY OF WINNIPEG CENTRAL
 CONTROLS @ 204 986-2351.

No.	REVISION/DESCRIPTION	BY	DATE
0	CONSTRUCTION	KJN	01-10 2024

SEAL

TENDER # 1080-2023			
DRAWN	CHECKED	DESIGNED	APPROVED
DATE: 2024.01.10	USER	APPROVAL	

THE CITY OF WINNIPEG
 ASSETS & PROJECT MANAGEMENT
 DEPARTMENT
 MUNICIPAL ACCOMMODATIONS DIVISION
 3-65 GARRY STREET, R3C 4K4

PROJECT
MILLENIUM LIBRARY
 PARTIAL MAIN FLOOR PLAN

251 DONALD STREET
 SHEET TITLE
NEW READER SERVICES DESK
 NEW FLOORING PLAN

SCALE	PROJECT No:	SHEET No:
AS SHOWN	2023-057	A2

1 NEW FLOORING PLAN
 SCALE: 3/8" = 1'-0"