

274-2023 ADDENDUM 2

BILLY MCCANN MEMORIAL PARK PLAYGROUND REDEVELOPMENT

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: November 27, 2023
BY: Ian Macdonald
TELEPHONE NO. 204 451-3069

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

PART E – SPECIFICATIONS

- Add: E13.8.1 (b) If required by the Contract Administrator, no measurement will be made for material testing as these items are incidental to the Work herein.
- Add: E13.8.2 (b) If required by the Contract Administrator, no payment will be made for material testing as this item incidental to the Work herein.
- Revise: E14.5.1 (b) to read: No measurement will be made for **materials testing**, excavation, non-woven geotextile/geogrid combination, granular base material, bedding or filler sand, as these items are incidental to the Work herein.
- Revise: E14.5.2 (b) to read: No payment will be made for **materials testing**, excavation, non-woven geotextile/geogrid combination, granular base material, bedding or filler sand, as these items are incidental to the Work herein.
- Revise: E23.4.2 (b) to read: All concrete footings for play equipment and swing sets shall be in accordance with Manufacturer's specifications **and be minimum 24" deep**. Proponents are to include drawings showing Manufacturer's Footing Specification in their Bid Submission.
- Revise: E23.4.2 (d) to read: **The full depth the footing must be below subgrade**. If required for specified embedment of post in the footing, footing shall extend in sonotube through the granular drainage layer. Footing must not extend into the wood fibre safety surface.
- Add: E23.5.1 (b) If required by the Contract Administrator, no measurement will be made for material testing as this item is incidental to the Work herein.
- Add: E23.5.2 (b) If required by the Contract Administrator, no payment will be made for material testing as this item is incidental to the Work herein.