

## **APPENDIX 'A' - GEOTECHNICAL REPORT**

### **PAVEMENT CORES FOR:**

Bronx Avenue from Henderson Highway to Roch Street – Concrete Pavement Rehabilitation  
Helmsdale Avenue from Henderson Highway to Brazier Street – Concrete Pavement Rehabilitation  
Hazel Dell Avenue from Henderson Highway to Brazier Street – Concrete Pavement Rehabilitation  
Linden Avenue from Henderson Highway to Roch Street – Concrete Pavement Rehabilitation  
Oakview Avenue from Henderson Highway to Brazier Street – Concrete Pavement Rehabilitation  
Raleigh Street from Gilmore Avenue to Glenway Avenue – Asphalt Pavement Resurfacing

The geotechnical report is provided to aid in the Contractor's evaluation of the existing pavement structure and/or soil conditions. The information presented is considered accurate at the locations shown on the Drawings and at the time of drilling. However, variations in pavement structure and/or soil conditions may exist between test holes and fluctuations in groundwater levels can be expected seasonally and may occur as a result of construction activities. The nature and extent of variations may not become evident until construction commences.



Stantec Consulting Ltd.  
199 Henlow Bay  
Winnipeg MB R3Y 1G4

January 31, 2023

Project/File: 123316298

**Erik Hansen**

City of Winnipeg  
1155 Pacific Avenue  
Winnipeg, MB R3B 1B9

Good day Erik,

**Reference: 2023 Local Street Renewals Program – Bronx Avenue and Various Locations**

Stantec Consulting Ltd. (Stantec) was retained to undertake a factual geotechnical investigation for the 2023 Local Street Renewals Program (Bronx Avenue and Various Locations) located in Winnipeg, MB. Use of this report is subject to the Statement of General Conditions provided in **Appendix A**.

The subsurface coring and drilling sampling program was conducted from January 6 to January 13, 2023. Pavement coring was performed by Stantec geotechnical personnel, and drilling services were provided by Maple Leaf Drilling Ltd. under Stantec's supervision. The borehole locations are shown on the attached Borehole Location Plan provided in **Appendix B**. The pavement cores were sampled with a 150 or 100 mm bit and boreholes were drilled with 125 mm solid stem augers. Geotechnical drilling boreholes were terminated at a depth of 1.0 m below pavement, and soil samples were obtained directly from the auger flights at 0.3 m intervals. Upon completion of drilling, the testholes were examined for evidence of sloughing and groundwater seepage. The soil classification used in the borehole records is as per ASTM D2487 – *Standard Practice for Classification of Soils for Engineering Purposes*. The borehole records are provided in **Appendix C** and core photographs are provided in **Appendix D**.

The following laboratory tests were conducted on select soil samples:

- ASTM D2216 - *Laboratory Determination of Water (Moisture) Content of Soil by Mass*
- ASTM D4318 - *Liquid Limit, Plastic Limit, and Plasticity Index of Soils*
- ASTM D7928 - *Particle-Size Distribution of Fine-Grained Soils Using The Sedimentation Analysis*
- CSA A23.2-14C – *Obtaining and testing drilled cores for compressive strength testing*

The concrete compressive strength tests were conducted under wet conditions. The moisture content results are shown on the borehole records, and the laboratory test reports are provided in **Appendix E**.

We appreciate the opportunity to assist you on this project. Please contact the undersigned if you have any questions regarding this report.

Reference: 2023 Local Street Renewals Program – Bronx Avenue and Various Locations

Regards,

**STANTEC CONSULTING LTD.**



**Guillaume Beauce** P.Eng.  
Field Supervisor, Materials Testing Services  
Phone: 204-928-7618  
Mobile: 204-898-8290  
guillaume.beauce@stantec.com



**Jason Thompson** C.E.T.  
Manager, Materials Testing Services  
Phone: 204-928-4004  
Mobile: 204-981-8445  
jason.thompson@stantec.com

Attachment: Appendix A – Statement of General Conditions  
Appendix B – Borehole Location Plan  
Appendix C – Borehole Records  
Appendix D – Core Photographs  
Appendix E – Laboratory Test Reports

# **APPENDIX A**

## **Statement of General Conditions**

## STATEMENT OF GENERAL CONDITIONS

**USE OF THIS REPORT:** This report has been prepared for the sole benefit of the Client or its agent and may not be used by any third party without the express written consent of Stantec and the Client. Any use which a third party makes of this report is the responsibility of such third party.

**BASIS OF THE REPORT:** The information, opinions, and/or recommendations made in this report are in accordance with Stantec's present understanding of the site-specific project as described by the Client. The applicability of these is restricted to the site conditions encountered at the time of the investigation or study. If the proposed site-specific project differs or is modified from what is described in this report or if the site conditions are altered, this report is no longer valid unless Stantec is requested by the Client to review and revise the report to reflect the differing or modified project specifics and/or the altered site conditions.

**STANDARD OF CARE:** Preparation of this report, and all associated work, was carried out in accordance with the normally accepted standard of care in the state or province of execution for the specific professional service provided to the Client. No other warranty is made.

**INTERPRETATION OF SITE CONDITIONS:** Soil, rock, or other material descriptions, and statements regarding their condition, made in this report are based on site conditions encountered by Stantec at the time of the work and at the specific testing and/or sampling locations. Classifications and statements of condition have been made in accordance with normally accepted practices which are judgmental in nature; no specific description should be considered exact, but rather reflective of the anticipated material behavior. Extrapolation of in situ conditions can only be made to some limited extent beyond the sampling or test points. The extent depends on variability of the soil, rock, and groundwater conditions as influenced by geological processes, construction activity, and site use.

**VARYING OR UNEXPECTED CONDITIONS:** Should any site or subsurface conditions be encountered that are different from those described in this report or encountered at the test locations, Stantec must be notified immediately to assess if the varying or unexpected conditions are substantial and if reassessments of the report conclusions or recommendations are required. Stantec will not be responsible to any party for damages incurred as a result of failing to notify Stantec that differing site or sub-surface conditions are present upon becoming aware of such conditions.



**PLANNING, DESIGN, OR CONSTRUCTION:** Development or design plans and specifications should be reviewed by Stantec, sufficiently ahead of initiating the next project stage (property acquisition, tender, construction, etc.), to confirm that this report completely addresses the elaborated project specifics and that the contents of this report have been properly interpreted. Specialty quality assurance services (field observations and testing) during construction are a necessary part of the evaluation of sub-subsurface conditions and site preparation works. Site work relating to the recommendations included in this report should only be carried out in the presence of a qualified geotechnical engineer; Stantec cannot be responsible for site work carried out without being present.



# **APPENDIX B**

## **Borehole Location Plan**

\\CA0194-PPFSS01\WorkGroup\123316298\field\_data\drawings\16298\_BHLP.dwg BRONX  
 2023/01/25 11:04 AM By: Boughton, Lee



NOTE: -DRILL PAVEMENT CORE ONLY EACH TEST HOLE LOCATION  
 -MAJOR REHABILITATION

EXACT LOCATIONS OF TEST HOLES TO BE MARKED IN FIELD BY CONTRACT ADMINISTRATOR.

TESTHOLE 

DATE: 17/05/2021	DRAWING NO.: 1
DRAWN BY: M.A.D.	SCALE: N.T.S.

2023 LOCAL STREET RENEWAL PROGRAM  
 CORING DRAWING  
 BRONX AVE : FROM HENDERSON HW TO ROCH ST

ORIGINAL SHEET - ISO 11x17 - v17.05

2023-01-24  
 123316298



Stantec Consulting Ltd.  
 Suite 500, 311 Portage Avenue  
 Winnipeg MB Canada R3B 2B9  
 Tel. 204.489.5900 Fax. 204.453.9012  
 www.stantec.com

Legend

 APPROXIMATE BOREHOLE LOCATION

Scale


Client/Project  
 CITY OF WINNIPEG  
 2023 LOCAL STREET RENEWALS PROGRAM  
 WINNIPEG, MB

Figure No.  
 BRONX

Title

BOREHOLE LOCATION PLAN

\\CA0194-PPFSS01\WorkGroup\1233\active\123316298\field\_data\drawings\16298\_BHLP.dwg HELMSDALE  
2023/01/31 11:21 AM By: Boughton, Lee



NOTE: -DRILL PAVEMENT CORE ONLY EACH TEST HOLE LOCATION  
-MAJOR REHABILITATION

EXACT LOCATIONS OF TEST HOLES TO BE MARKED IN FIELD BY CONTRACT ADMINISTRATOR.

TESTHOLE

DATE:	DRAWING NO.:
17/05/2021	1
DRAWN BY:	SCALE:
M.A.D.	N.T.S.

2023 LOCAL STREET RENEWAL PROGRAM

CORING DRAWING  
HELMSDALE AVE : FROM HENDERSON HW TO BRAZIER ST

ORIGINAL SHEET - ISO 11x17 - v17.05

2023-01-25  
123316298



Stantec Consulting Ltd.  
Suite 500, 311 Portage Avenue  
Winnipeg MB Canada R3B 2B9  
Tel. 204.489.5900 Fax. 204.453.9012  
www.stantec.com

Legend


APPROXIMATE BOREHOLE LOCATION

Scale

Client/Project  
CITY OF WINNIPEG  
2023 LOCAL STREET RENEWALS PROGRAM  
WINNIPEG, MB  
Figure No.  
HELMSDALE  
Title

BOREHOLE LOCATION PLAN

\\CA0194-PPFSS01\WorkGroup\1233\active\123316298\field\_data\drawings\16298\_BHLP.dwg OAKVIEW  
2023/01/25 11:06 AM By: Boughton, Lee



NOTE: -DRILL PAVEMENT CORE ONLY EACH TEST HOLE LOCATION  
-MINOR REHABILITATION

EXACT LOCATIONS OF TEST HOLES TO BE MARKED IN FIELD BY CONTRACT ADMINISTRATOR.	TESTHOLE	DATE:	DRAWING NO.:	2023 LOCAL STREET RENEWAL PROGRAM
		17/05/2021	1	
		DRAWN BY:	SCALE:	2023 LOCAL STREET RENEWALS PROGRAM WINNIPEG, MB
		M.A.D.	N.T.S.	OAKVIEW AVE : FROM HENDERSON HW TO BRAZIER ST

ORIGINAL SHEET - ISO 11x17 - v17.05

2023-01-24  
123316298



Stantec Consulting Ltd.  
Suite 500, 311 Portage Avenue  
Winnipeg MB Canada R3B 2B9  
Tel. 204.489.5900 Fax. 204.453.9012  
www.stantec.com

Legend

APPROXIMATE BOREHOLE LOCATION


Scale

Client/Project  
CITY OF WINNIPEG  
2023 LOCAL STREET RENEWALS PROGRAM  
WINNIPEG, MB

Figure No.  
OAKVIEW

Title  
BOREHOLE LOCATION PLAN

\\CA0194-PPFSS01\Work\Group\1233\active\123316298\field\_data\drawings\16298\_BHLP.dwg HAZEL DELL  
2023/01/31 11:22 AM By: Boughton, Lee



NOTE: -DRILL PAVEMENT CORE ONLY EACH TEST HOLE LOCATION  
-MINOR REHABILITATION

EXACT LOCATIONS OF TEST HOLES TO BE MARKED IN FIELD BY CONTRACT ADMINISTRATOR.

TESTHOLE 

DATE: 17/05/2021	DRAWING NO.: 1
DRAWN BY: M.A.D.	SCALE: N.T.S.

2023 LOCAL STREET RENEWAL PROGRAM

CORING DRAWING  
HAZEL DELL AVE : FROM HENDERSON HW TO BRAZIER ST

ORIGINAL SHEET - ISO 11x17 - v17.05

2023-01-25  
123316298



Stantec Consulting Ltd.  
Suite 500, 311 Portage Avenue  
Winnipeg MB Canada R3B 2B9  
Tel. 204.489.5900 Fax. 204.453.9012  
www.stantec.com

Legend



 APPROXIMATE BOREHOLE LOCATION

Scale

Client/Project  
CITY OF WINNIPEG  
2023 LOCAL STREET RENEWALS PROGRAM  
WINNIPEG, MB  
Figure No.  
HAZEL DELL  
Title

BOREHOLE LOCATION PLAN

\\CA0194-PPF501\Work\Group\12331\active\12331\2298\field\_data\drawings\16298\_BHLP.dwg LINDEN  
2023/01/25 11:06 AM By: Boughton, Lee



NOTE: -DRILL PAVEMENT CORE ONLY EACH TEST HOLE LOCATION  
-MINOR REHABILITATION

EXACT LOCATIONS OF TEST HOLES TO BE MARKED IN FIELD BY CONTRACT ADMINISTRATOR.	TESTHOLE	DATE:	DRAWING NO.:	2023 LOCAL STREET RENEWAL PROGRAM
		17/05/2021	1	
		DRAWN BY:	SCALE:	CORING DRAWING
		M.A.D.	N.T.S.	LINDEN AVE : FROM HENDERSON HW TO ROCH ST

ORIGINAL SHEET - ISO 11x17 - v17.05

2023-01-24  
123316298



Stantec Consulting Ltd.  
Suite 500, 311 Portage Avenue  
Winnipeg MB Canada R3B 2B9  
Tel. 204.489.5900 Fax. 204.453.9012  
www.stantec.com

Legend

APPROXIMATE BOREHOLE LOCATION

Scale


Client/Project  
CITY OF WINNIPEG  
2023 LOCAL STREET RENEWALS PROGRAM  
WINNIPEG, MB

Figure No.  
LINDEN

Title

BOREHOLE LOCATION PLAN

\\CA0194-PPFSS01\Work\Group\1233\active\123316298\field\_data\drawings\16298\_BHLP.dwg RALEIGH 1  
2023/01/25 11:03 AM By: Boughton, Lee



ORIGINAL SHEET - ISO 11x17 - v17.05

2023-01-24  
123316298



Stantec Consulting Ltd.  
Suite 500, 311 Portage Avenue  
Winnipeg MB Canada R3B 2B9  
Tel. 204.489.5900 Fax. 204.453.9012  
www.stantec.com

Legend


APPROXIMATE BOREHOLE LOCATION

Scale

Client/Project  
CITY OF WINNIPEG  
2023 LOCAL STREET RENEWALS PROGRAM  
WINNIPEG, MB  
Figure No.  
RALEIGH (1 OF 2)  
Title

BOREHOLE LOCATION PLAN

\\CA0194-PPF501\Work\Group\1233\active\123316298\field\_data\drawings\16298\_BHLP.dwg RALEIGH 2  
2023/01/25 11:03 AM By: Boughton, Lee



NOTE: -GEOTECHNICAL TESTHOLES 1m DEPTH  
-AC RESURFACE

EXACT LOCATIONS OF TEST HOLES TO BE MARKED IN FIELD BY CONTRACT ADMINISTRATOR.

TESTHOLE



DATE: 17/05/2021	DRAWING NO.: 2
DRAWN BY: M.A.D.	SCALE: N.T.S.

2023 LOCAL STREET RENEWAL PROGRAM  
CORING DRAWING  
RALEIGH ST : FROM GILMORE ST TO GLENWAY ST

ORIGINAL SHEET - ISO 11x17 - v17.05

2023-01-24  
123316298



Stantec Consulting Ltd.  
Suite 500, 311 Portage Avenue  
Winnipeg MB Canada R3B 2B9  
Tel. 204.489.5900 Fax. 204.453.9012  
www.stantec.com

Legend

 APPROXIMATE BOREHOLE LOCATION

Scale

Client/Project  
CITY OF WINNIPEG  
2023 LOCAL STREET RENEWALS PROGRAM  
WINNIPEG, MB  
Figure No.  
RALEIGH (2 OF 2)  
Title

BOREHOLE LOCATION PLAN

# **APPENDIX C**

## **Borehole Records**

## SYMBOLS AND TERMS USED ON BOREHOLE AND TEST PIT RECORDS

### SOIL DESCRIPTION

#### Terminology describing common soil genesis:

<i>Rootmat</i>	- vegetation, roots and moss with organic matter and topsoil typically forming a mattress at the ground surface
<i>Topsoil</i>	- mixture of soil and humus capable of supporting vegetative growth
<i>Peat</i>	- mixture of visible and invisible fragments of decayed organic matter
<i>Till</i>	- unstratified glacial deposit which may range from clay to boulders
<i>Fill</i>	- material below the surface identified as placed by humans (excluding buried services)

#### Terminology describing soil structure:

<i>Desiccated</i>	- having visible signs of weathering by oxidization of clay minerals, shrinkage cracks, etc.
<i>Fissured</i>	- having cracks, and hence a blocky structure
<i>Varved</i>	- composed of regular alternating layers of silt and clay
<i>Stratified</i>	- composed of alternating successions of different soil types, e.g. silt and sand
<i>Layer</i>	- > 75 mm in thickness
<i>Seam</i>	- 2 mm to 75 mm in thickness
<i>Parting</i>	- < 2 mm in thickness

#### Terminology describing soil types:

The classification of soil types are made on the basis of grain size and plasticity in accordance with the Unified Soil Classification System (USCS) (ASTM D 2487 or D 2488) which excludes particles larger than 75 mm. For particles larger than 75 mm, and for defining percent clay fraction in hydrometer results, definitions proposed by Canadian Foundation Engineering Manual, 4<sup>th</sup> Edition are used. The USCS provides a group symbol (e.g. SM) and group name (e.g. silty sand) for identification.

#### Terminology describing cobbles, boulders, and non-matrix materials (organic matter or debris):

Terminology describing materials outside the USCS, (e.g. particles larger than 75 mm, visible organic matter, and construction debris) is based upon the proportion of these materials present:

<i>Trace, or occasional</i>	Less than 10%
<i>Some</i>	10-20%
<i>Frequent</i>	> 20%

#### Terminology describing compactness of cohesionless soils:

The standard terminology to describe cohesionless soils includes compactness (formerly "relative density"), as determined by the Standard Penetration Test (SPT) N-Value - also known as N-Index. The SPT N-Value is described further on page 3. A relationship between compactness condition and N-Value is shown in the following table.

Compactness Condition	SPT N-Value
<i>Very Loose</i>	<4
<i>Loose</i>	4-10
<i>Compact</i>	10-30
<i>Dense</i>	30-50
<i>Very Dense</i>	>50


#### Terminology describing consistency of cohesive soils:

The standard terminology to describe cohesive soils includes the consistency, which is based on undrained shear strength as measured by *in situ* vane tests, penetrometer tests, or unconfined compression tests. Consistency may be crudely estimated from SPT N-Value based on the correlation shown in the following table (Terzaghi and Peck, 1967). The correlation to SPT N-Value is used with caution as it is only very approximate.

Consistency	Undrained Shear Strength		Approximate SPT N-Value
	kips/sq.ft.	kPa	
<i>Very Soft</i>	<0.25	<12.5	<2
<i>Soft</i>	0.25 - 0.5	12.5 - 25	2-4
<i>Firm</i>	0.5 - 1.0	25 - 50	4-8
<i>Stiff</i>	1.0 - 2.0	50 - 100	8-15
<i>Very Stiff</i>	2.0 - 4.0	100 - 200	15-30
<i>Hard</i>	>4.0	>200	>30

## STRATA PLOT

Strata plots symbolize the soil or bedrock description. They are combinations of the following basic symbols. The dimensions within the strata symbols are not indicative of the particle size, layer thickness, etc.



## SAMPLE TYPE

SS	Split spoon sample (obtained by performing the Standard Penetration Test)
ST	Shelby tube or thin wall tube
DP	Direct-Push sample (small diameter tube sampler hydraulically advanced)
PS	Piston sample
BS	Bulk sample
HQ, NQ, BQ, etc.	Rock core samples obtained with the use of standard size diamond coring bits.

## WATER LEVEL MEASUREMENT



## RECOVERY

For soil samples, the recovery is recorded as the length of the soil sample recovered. For rock core, recovery is defined as the total cumulative length of all core recovered in the core barrel divided by the length drilled and is recorded as a percentage on a per run basis.

## N-VALUE

Numbers in this column are the field results of the Standard Penetration Test: the number of blows of a 140 pound (63.5 kg) hammer falling 30 inches (760 mm), required to drive a 2 inch (50.8 mm) O.D. split spoon sampler one foot (300 mm) into the soil. In accordance with ASTM D1586, the N-Value equals the sum of the number of blows (N) required to drive the sampler over the interval of 6 to 18 in. (150 to 450 mm). However, when a 24 in. (610 mm) sampler is used, the number of blows (N) required to drive the sampler over the interval of 12 to 24 in. (300 to 610 mm) may be reported if this value is lower. For split spoon samples where insufficient penetration was achieved and N-Values cannot be presented, the number of blows are reported over sampler penetration in millimetres (e.g. 50/75). Some design methods make use of N-values corrected for various factors such as overburden pressure, energy ratio, borehole diameter, etc. No corrections have been applied to the N-values presented on the log.

## DYNAMIC CONE PENETRATION TEST (DCPT)

Dynamic cone penetration tests are performed using a standard 60 degree apex cone connected to 'A' size drill rods with the same standard fall height and weight as the Standard Penetration Test. The DCPT value is the number of blows of the hammer required to drive the cone one foot (300 mm) into the soil. The DCPT is used as a probe to assess soil variability.

## OTHER TESTS

S	Sieve analysis
H	Hydrometer analysis
k	Laboratory permeability
$\gamma$	Unit weight
$G_s$	Specific gravity of soil particles
CD	Consolidated drained triaxial
CU	Consolidated undrained triaxial with pore pressure measurements
UU	Unconsolidated undrained triaxial
DS	Direct Shear
C	Consolidation
$Q_u$	Unconfined compression
$I_p$	Point Load Index ( $I_p$ on Borehole Record equals $I_p(50)$ in which the index is corrected to a reference diameter of 50 mm)

	Single packer permeability test; test interval from depth shown to bottom of borehole
	Double packer permeability test; test interval as indicated
	Falling head permeability test using casing
	Falling head permeability test using well point or piezometer



# BOREHOLE RECORD

BH23-18

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Bronx Ave, Winnipeg, MB  
 DATE BORED: January 12, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)	
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE			
								50 kPa	100 kPa	150 kPa	200 kPa				
								WATER CONTENT & ATTERBERG LIMITS							
								SPT (N-value) BLOWS/0.3m							
								Water Content (%) and Blow Count							
								10	20	30	40	50	60	70	80
0		CONCRETE: 195 mm													
		End of Borehole													

Printed Jan 31 2023 11:1:29 STANTEC GEO 201 6 123316298\_STREET.RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23

- BACKFILL SYMBOL
- ASPHALT
- GROUT
- CONCRETE
- BENTONITE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Stantec  
 Drilling Method: Coring  
 Completion Depth: 0.195 m

Logged By: LB  
 Reviewed By: GB  
 Page 1 of 1



# BOREHOLE RECORD

BH23-19

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Bronx Ave, Winnipeg, MB  
 DATE BORED: January 12, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)	
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE			
								50 kPa	100 kPa	150 kPa	200 kPa				
								WATER CONTENT & ATTERBERG LIMITS							
								SPT (N-value) BLOWS/0.3m							
								Water Content (%) and Blow Count							
								10	20	30	40	50	60	70	80
0		CONCRETE: 155 mm													
		End of Borehole													

Printed Jan 31 2023 11:1:30 STANTEC GEO 201 6 123316298\_STREET.RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23

- BACKFILL SYMBOL ASPHALT
- GROUT
- CONCRETE
- BENTONITE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Stantec  
 Drilling Method: Coring  
 Completion Depth: 0.155 m

Logged By: LB  
 Reviewed By: GB  
 Page 1 of 1



# BOREHOLE RECORD

BH23-20

CLIENT: City of Winnipeg

PROJECT NO.: 123316298

PROJECT: 2023 Local Street Renewals Program

BH ELEVATION: N/A

LOCATION: Bronx Ave, Winnipeg, MB

DATUM: N/A

DATE BORED: January 12, 2023

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)	
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE			
								50 kPa	100 kPa	150 kPa	200 kPa				
								WATER CONTENT & ATTERBERG LIMITS							
								SPT (N-value) BLOWS/0.3m							
								Water Content (%) and Blow Count							
								10	20	30	40	50	60	70	80
0		CONCRETE: 135 mm													
		End of Borehole													

Printed Jan 31 2023 11:1:30 STANTEC GEO 201 6 123316298\_STREET.RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23

- BACKFILL SYMBOL
- ASPHALT
- GROUT
- CONCRETE
- BENTONITE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Stantec  
 Drilling Method: Coring  
 Completion Depth: 0.135 m

Logged By: LB  
 Reviewed By: GB  
 Page 1 of 1



# BOREHOLE RECORD


BH23-21

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Bronx Ave, Winnipeg, MB  
 DATE BORED: January 12, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE		
0		CONCRETE: 147 mm												
		End of Borehole												



Printed Jan 31 2023 11:1:31 STANTEC GEO 201 6 123316298\_STREET.RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23

- BACKFILL SYMBOL ASPHALT
- GROUT
- CONCRETE
- BENTONITE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Stantec  
 Drilling Method: Coring  
 Completion Depth: 0.147 m

Logged By: LB  
 Reviewed By: GB  
 Page 1 of 1



# BOREHOLE RECORD

BH23-22

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Hemdale Ave, Winnipeg, MB  
 DATE BORED: January 12, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)	
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE			
								50 kPa	100 kPa	150 kPa	200 kPa				
								WATER CONTENT & ATTERBERG LIMITS							
								SPT (N-value) BLOWS/0.3m							
								Water Content (%) and Blow Count							
								10	20	30	40	50	60	70	80
0		CONCRETE: 155 mm													
		End of Borehole													

Printed Jan 31 2023 11:1:31 STANTEC GEO 2016 123316298\_STREET.RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23

- BACKFILL SYMBOL
- 
- 
- 
- 
- 
- 

Drilling Contractor: Stantec  
 Drilling Method: Coring  
 Completion Depth: 0.155 m

Logged By: LB  
 Reviewed By: GB  
 Page 1 of 1



# BOREHOLE RECORD

BH23-23

CLIENT: City of Winnipeg

PROJECT NO.: 123316298

PROJECT: 2023 Local Street Renewals Program

BH ELEVATION: N/A

LOCATION: Hemsdale Ave, Winnipeg, MB

DATUM: N/A

DATE BORED: January 12, 2023

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)	
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE			
								50 kPa	100 kPa	150 kPa	200 kPa				
								WATER CONTENT & ATTERBERG LIMITS							
								SPT (N-value) BLOWS/0.3m							
								Water Content (%) and Blow Count							
								10	20	30	40	50	60	70	80
0		CONCRETE: 160 mm													
		End of Borehole													

Printed Jan 31 2023 11:1:32 STANTEC GEO 2016 123316298\_STREET.RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23

- BACKFILL SYMBOL BENTONITE
- ASPHALT
- GROUT
- CONCRETE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Stantec  
 Drilling Method: Coring  
 Completion Depth: 0.16 m

Logged By: LB  
 Reviewed By: GB  
 Page 1 of 1



# BOREHOLE RECORD

**BH23-24**

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Oakview Ave, Winnipeg, MB  
 DATE BORED: January 12, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE		
0		CONCRETE: 185 mm												
		End of Borehole												

- BACKFILL SYMBOL
- ASPHALT
- GROUT
- CONCRETE
- BENTONITE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Stantec  
 Drilling Method: Coring  
 Completion Depth: 0.185 m

Logged By: LB  
 Reviewed By: GB  
 Page 1 of 1



# BOREHOLE RECORD

BH23-25

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Oakview Ave, Winnipeg, MB  
 DATE BORED: January 12, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)	
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE			
								50 kPa	100 kPa	150 kPa	200 kPa				
								WATER CONTENT & ATTERBERG LIMITS							
								SPT (N-value) BLOWS/0.3m							
								Water Content (%) and Blow Count							
								10	20	30	40	50	60	70	80
0		CONCRETE: 155 mm													
		End of Borehole													

Printed Jan 31 2023 11:33 STANTEC GEO 2016 123316298\_STREET.RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23

- BACKFILL SYMBOL ASPHALT
- GROUT
- CONCRETE
- BENTONITE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Stantec  
 Drilling Method: Coring  
 Completion Depth: 0.155 m

Logged By: LB  
 Reviewed By: GB  
 Page 1 of 1



# BOREHOLE RECORD

BH23-26

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Hazel Dell Ave, Winnipeg, MB  
 DATE BORED: January 13, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)	
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE			
								50 kPa	100 kPa	150 kPa	200 kPa				
								WATER CONTENT & ATTERBERG LIMITS							
								SPT (N-value) BLOWS/0.3m							
								Water Content (%) and Blow Count							
								10	20	30	40	50	60	70	80
0		CONCRETE: 160 mm													
		End of Borehole													

Printed Jan 31 2023 11:1:34 STANTEC GEO 201 6 123316298\_STREET.RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23

- BACKFILL SYMBOL ASPHALT
- GROUT
- CONCRETE
- BENTONITE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Stantec  
 Drilling Method: Coring  
 Completion Depth: 0.16 m

Logged By: LB  
 Reviewed By: GB  
 Page 1 of 1



# BOREHOLE RECORD

BH23-27

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Hazel Dell Ave, Winnipeg, MB  
 DATE BORED: January 13, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE		
0		CONCRETE: 150 mm												
		End of Borehole												

UNDRAINED SHEAR STRENGTH, Cu (kPa)

LABORATORY TEST ▲ FIELD VANE TEST ◆  
 POCKET PEN. ★ POCKET SHEAR VANE ◻  
 50 kPa 100 kPa 150 kPa 200 kPa

WATER CONTENT & ATTERBERG LIMITS  $W_p$   $W$   $W_L$   
 SPT (N-value) BLOWS/0.3m ●

Water Content (%) and Blow Count  
 10 20 30 40 50 60 70 80

Printed Jan 31 2023 11:1:34 STANTEC GEO 2016 123316298\_STREET.RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23

- BACKFILL SYMBOL
- ASPHALT
- GROUT
- CONCRETE
- BENTONITE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Stantec  
 Drilling Method: Coring  
 Completion Depth: 0.15 m

Logged By: LB  
 Reviewed By: GB  
 Page 1 of 1



# BOREHOLE RECORD

BH23-28

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Linden Ave, Winnipeg, MB  
 DATE BORED: January 13, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE		
0		CONCRETE: 147 mm												
		End of Borehole												

- BACKFILL SYMBOL ASPHALT
- GROUT
- CONCRETE
- BENTONITE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Stantec  
 Drilling Method: Coring  
 Completion Depth: 0.147 m

Logged By: LB  
 Reviewed By: GB  
 Page 1 of 1



# BOREHOLE RECORD

BH23-29

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Linden Ave, Winnipeg, MB  
 DATE BORED: January 13, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE		
0		CONCRETE: 140 mm												
		End of Borehole												

- BACKFILL SYMBOL
- ASPHALT
- GROUT
- CONCRETE
- BENTONITE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Stantec  
 Drilling Method: Coring  
 Completion Depth: 0.14 m

Logged By: LB  
 Reviewed By: GB  
 Page 1 of 1

Printed Jan 31 2023 11:35 STANTEC GEO 2016 123316298\_STREET.RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23



# BOREHOLE RECORD

BH23-30

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Linden Ave, Winnipeg, MB  
 DATE BORED: January 13, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE		
0		CONCRETE: 150 mm												
		End of Borehole												

- BACKFILL SYMBOL
- ASPHALT
- GROUT
- CONCRETE
- BENTONITE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Stantec  
 Drilling Method: Coring  
 Completion Depth: 0.15 m

Logged By: LB  
 Reviewed By: GB  
 Page 1 of 1



# BOREHOLE RECORD

BH23-31

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Linden Ave, Winnipeg, MB  
 DATE BORED: January 13, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE		
0		CONCRETE: 150 mm												
		End of Borehole												

- BACKFILL SYMBOL
- ASPHALT
- GROUT
- CONCRETE
- BENTONITE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Stantec  
 Drilling Method: Coring  
 Completion Depth: 0.15 m

Logged By: LB  
 Reviewed By: GB  
 Page 1 of 1

Printed Jan 31 2023 11:37 STANTEC GEO 2016 123316298\_STREET.RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23



# BOREHOLE RECORD

BH23-57

CLIENT: City of Winnipeg

PROJECT NO.: 123316298

PROJECT: 2023 Local Street Renewals Program

BH ELEVATION: N/A

LOCATION: Raleigh St, Winnipeg, MB

DATUM: N/A

DATE BORED: January 6, 2023 to January 11, 2023

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE		
0		ASPHALT: 150 mm												
		Granular FILL		AS										
		Black, moist, fat CLAY FILL (CH)		AS										
				AS										
				AS										
1				AS										
		<b>End of Borehole</b> <ul style="list-style-type: none"> <li>The soil was frozen to a depth of 0.9 m.</li> <li>No groundwater seepage or soil sloughing was observed upon completion of drilling.</li> <li>Borehole stopped at a depth of 1.2 m.</li> </ul>												

BACKFILL SYMBOL   ASPHALT   GROUT   CONCRETE  
 BENTONITE   DRILL CUTTINGS   SAND   SLOUGH

Drilling Contractor: Maple Leaf Drilling Ltd.   Logged By: LB  
Drilling Method: 125 mm SSA   Reviewed By: GB  
Completion Depth: 1.2 m   Page 1 of 1

Printed Jan 31 2023 11:1:55 STANTEC GEO 201 6 123316298\_STREET\_RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23



# BOREHOLE RECORD

**BH23-58**

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Raleigh St, Winnipeg, MB  
 DATE BORED: January 6, 2023 to January 16, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE		
0		ASPHALT: 190 mm												
		Granular FILL		AS										
		Black, moist, fat CLAY FILL (CH), trace organics		AS										
				AS										
				AS										
1				AS										
		<b>End of Borehole</b> <ul style="list-style-type: none"> <li>The soil was frozen to a depth of 0.9 m.</li> <li>No groundwater seepage or soil sloughing was observed upon completion of drilling.</li> <li>Borehole stopped at a depth of 1.2 m.</li> </ul>												

- BACKFILL SYMBOL
- ASPHALT
- GROUT
- CONCRETE
- BENTONITE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Maple Leaf Drilling Ltd.      Logged By: LB  
 Drilling Method: 125 mm SSA      Reviewed By: GB  
 Completion Depth: 1.2 m      Page 1 of 1

Printed Jan 31 2023 11:1:56 STANTEC GEO 2016 123316298\_STREET\_RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Raleigh St, Winnipeg, MB  
 DATE BORED: January 6, 2023 to January 11, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE		
0		ASPHALT: 140 mm												
		Granular FILL		AS										
		Black, moist, fat CLAY FILL (CH), trace organics		AS										
				AS				Sieve/Hydro at 0.8 m G S M C 0% 1% 32% 67%						
		Grey, moist, silty CLAY (CL-ML)		AS										
1				AS										
		<b>End of Borehole</b> • The soil was frozen to a depth of 0.9 m. • No groundwater seepage or soil sloughing was observed upon completion of drilling. • Borehole stopped at a depth of 1.2 m.												

BACKFILL SYMBOL: ASPHALT, GROUT, CONCRETE  
 BENTONITE, DRILL CUTTINGS, SAND, SLOUGH

Drilling Contractor: Maple Leaf Drilling Ltd. | Logged By: LB  
 Drilling Method: 125 mm SSA | Reviewed By: GB  
 Completion Depth: 1.2 m | Page 1 of 1

Printed Jan 31 2023 11:1:56 STANTEC GEO 201 6 123316298\_STREET\_RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23



CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Raleigh St, Winnipeg, MB  
 DATE BORED: January 12, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE		
0		ASPHALT: 165 mm												
		Granular FILL												
		Black, moist, fat CLAY FILL (CH), trace organics												
		Grey, moist, silty CLAY (CL-ML)												
		<b>End of Borehole</b> • The soil was frozen to a depth of 0.9 m. • No groundwater seepage or soil sloughing was observed upon completion of drilling. • Borehole stopped at a depth of 1.2 m.												

BACKFILL SYMBOL: ASPHALT, GROUT, CONCRETE  
 BENTONITE, DRILL CUTTINGS, SAND, SLOUGH

Drilling Contractor: Maple Leaf Drilling Ltd. | Logged By: LB  
 Drilling Method: 125 mm SSA | Reviewed By: GB  
 Completion Depth: 1.2 m | Page 1 of 1

Printed Jan 31 2023 11:1:58 STANTEC GEO 201 6 123316298\_STREET\_RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23



# BOREHOLE RECORD

**BH23-62**

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Raleigh St, Winnipeg, MB  
 DATE BORED: January 12, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE		
0		ASPHALT: 190 mm												
		Granular FILL		AS										
		Black, moist, fat CLAY FILL (CH), trace organics		AS										
				AS										
1				AS										
		<b>End of Borehole</b> • The soil was frozen to a depth of 0.9 m. • No groundwater seepage or soil sloughing was observed upon completion of drilling. • Borehole stopped at a depth of 1.2 m.												

- BACKFILL SYMBOL
- ASPHALT
- GROUT
- CONCRETE
- BENTONITE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Maple Leaf Drilling Ltd.      Logged By: LB  
 Drilling Method: 125 mm SSA      Reviewed By: GB  
 Completion Depth: 1.2 m      Page 1 of 1

Printed Jan 31 2023 11:1:59 STANTEC GEO 201 6 123316298\_STREET\_RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23



# BOREHOLE RECORD

BH23-63

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Raleigh St, Winnipeg, MB  
 DATE BORED: January 12, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE		
0		ASPHALT: 171 mm												
		Granular FILL		AS										
		Black, moist, fat CLAY FILL (CH), trace organics		AS										
				AS				Sieve/Hydro at 0.8 m G 0% S 3% M 24% C 74%						
1				AS										
		<b>End of Borehole</b> <ul style="list-style-type: none"> <li>The soil was frozen to a depth of 0.9 m.</li> <li>No groundwater seepage or soil sloughing was observed upon completion of drilling.</li> <li>Borehole stopped at a depth of 1.2 m.</li> </ul>												

Printed Jan 31 2023 11:1:59 STANTEC GEO 201 6 123316298\_STREET\_RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23

- BENTONITE
- ASPHALT
- GROUT
- CONCRETE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Maple Leaf Drilling Ltd.      Logged By: LB  
 Drilling Method: 125 mm SSA      Reviewed By: GB  
 Completion Depth: 1.2 m      Page 1 of 1

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Raleigh St, Winnipeg, MB  
 DATE BORED: January 12, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE		
0		ASPHALT: 159 mm												
		Granular FILL		AS										
		Black, moist, fat CLAY FILL (CH), trace organics		AS										
				AS										
				AS										
1				AS										
		<b>End of Borehole</b> • The soil was frozen to a depth of 0.9 m. • No groundwater seepage or soil sloughing was observed upon completion of drilling. • Borehole stopped at a depth of 1.2 m.												

BACKFILL SYMBOL: ASPHALT, GROUT, CONCRETE, BENTONITE, DRILL CUTTINGS, SAND, SLOUGH

Drilling Contractor: Maple Leaf Drilling Ltd. | Logged By: LB  
 Drilling Method: 125 mm SSA | Reviewed By: GB  
 Completion Depth: 1.2 m | Page 1 of 1



# BOREHOLE RECORD

**BH23-65**

CLIENT: City of Winnipeg  
 PROJECT: 2023 Local Street Renewals Program  
 LOCATION: Raleigh St, Winnipeg, MB  
 DATE BORED: January 12, 2023

PROJECT NO.: 123316298  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (USCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL / MONITOR WELL / PIEZOMETER	ELEVATION (m)
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		LABORATORY TEST	FIELD VANE TEST	POCKET PEN.	POCKET SHEAR VANE		
0		ASPHALT: 171 mm												
		Granular FILL		AS										
		Black, moist, fat CLAY FILL (CH), trace organics		AS										
				AS										
				AS										
1				AS										
		<b>End of Borehole</b> <ul style="list-style-type: none"> <li>The soil was frozen to a depth of 0.9 m.</li> <li>No groundwater seepage or soil sloughing was observed upon completion of drilling.</li> <li>Borehole stopped at a depth of 1.2 m.</li> </ul>												

- BACKFILL SYMBOL
- ASPHALT
- GROUT
- CONCRETE
- BENTONITE
- DRILL CUTTINGS
- SAND
- SLOUGH

Drilling Contractor: Maple Leaf Drilling Ltd.      Logged By: LB  
 Drilling Method: 125 mm SSA      Reviewed By: GB  
 Completion Depth: 1.2 m      Page 1 of 1

Printed Jan 31 2023 11:21 STANTEC GEO 201 6 123316298\_STREET\_RENEWALS.2023.GPJ GINT\_1233\_SOIL\_2018\_DATA\_TEMP\_REV2.GDT 1/31/23

# **APPENDIX D**

## **Core Photographs**



Figure 1 – Core No. 18 (Bronx Ave)



Figure 2 – Core No. 19 (Bronx Ave)



Figure 3 – Core No. 20 (Bronx Ave)



Figure 4 – Core No. 21 (Bronx Ave)



Figure 5 – Core No. 22 (Hemdale)



Figure 6 – Core No. 23 (Hemdale)



Figure 7 – Core No. 24 (Oakview Ave)



Figure 8 – Core No. 25 (Oakview Ave)



Figure 9 – Core 26 (Hazel Dell Ave)



Figure 10 – Core 27 (Hazel Dell Ave)



Figure 11 – Core 28 (Linden Ave)



Figure 12 – Core 29 (Linden Ave)



Figure 13 – Core 30 (Linden Ave)



Figure 14 – Core 31 (Linden Ave)



Figure 15 – Core 57 (Raleigh St)



Figure 16 – Core 58 (Raleigh St)



Figure 17 – Core 59 (Raleigh St)



Figure 18 – Core 60 (Raleigh St)



Figure 19 – Core 61 (Raleigh St)



Figure 20 – Core 62 (Raleigh St)



Figure 21 – Core 63 (Raleigh St)



Figure 22 – Core 64 (Raleigh St)



Figure 23 – Core 65 (Raleigh St)

# **APPENDIX E**

## **Laboratory Test Reports**



**Stantec Consulting Ltd.**  
 199 Henlow Bay, Winnipeg, MB R3Y 1G4  
 Tel: (204) 488-6999



## ASTM D4318 - LIQUID LIMIT, PLASTIC LIMIT AND PLASTICITY INDEX OF SOILS (LL METHOD B - ONE-POINT)

TO City of Winnipeg, Public Works Department  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 3P1

PROJECT 2023 Local Streets Renewals Program

PROJECT NO. 123316298

ATTN: Erik Hansen

REPORT NO. 1

DATE SAMPLED: 2023.Jan.17

DATE RECEIVED: 2023.Jan.17

DATE TESTED: 2023.Jan.27

SAMPLED BY: Stantec Consulting Ltd.

SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Larry Presado

SAMPLE ID: BH23-59, 2.8' (Raleigh St)


**LIQUID LIMIT**

TRIAL	1	2
BLOWS	25	25
MC (%)	87	87
Corr. MC (%)	87	87

**PLASTIC LIMIT**

TRIAL	1	2
MC (%)	21	21

LIQUID LIMIT, LL 87  
 PLASTIC LIMIT, PL 21  
 PLASTICITY INDEX, PI 66  
 AS REC'D MC (%) 30.2



COMMENTS:

REPORT DATE 2023.Jan.30

REVIEWED BY *Guillaume Beauce*  
 Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

Reporting of these test results constitutes a testing service only. Engineering interpretation or evaluation of the test results is provided on written request. The data presented is for sole use of client stipulated above. Stantec is not responsible, nor can be held liable, for the use of this report by any other party, with or without the knowledge of Stantec.



**Stantec Consulting Ltd.**  
 199 Henlow Bay, Winnipeg, MB R3Y 1G4  
 Tel: (204) 488-6999



## ASTM D4318 - LIQUID LIMIT, PLASTIC LIMIT AND PLASTICITY INDEX OF SOILS (LL METHOD B - ONE-POINT)

TO City of Winnipeg, Public Works Department  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 3P1

PROJECT 2023 Local Streets Renewals Program

PROJECT NO. 123316298

ATTN: Erik Hansen

REPORT NO. 2

DATE SAMPLED: 2023.Jan.17

DATE RECEIVED: 2023.Jan.17

DATE TESTED: 2023.Jan.26

SAMPLED BY: Stantec Consulting Ltd.

SUBMITTED BY: Stantec Consulting Ltd.


TESTED BY: Blair Dawson

SAMPLE ID: BH23-63, 2.9' (Raleigh St)

	LIQUID LIMIT	
TRIAL	1	2
BLOWS	25	27
MC (%)	87	87
Corr. MC (%)	87	88

	PLASTIC LIMIT	
TRIAL	1	2
MC (%)	28	28

LIQUID LIMIT, LL	87
PLASTIC LIMIT, PL	28
PLASTICITY INDEX, PI	59
AS REC'D MC (%)	36.1



COMMENTS:

REPORT DATE 2023.Jan.30

  
 REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

Reporting of these test results constitutes a testing service only. Engineering interpretation or evaluation of the test results is provided on written request. The data presented is for sole use of client stipulated above. Stantec is not responsible, nor can be held liable, for the use of this report by any other party, with or without the knowledge of Stantec.



**Stantec Consulting Ltd.**  
 199 Henlow Bay, Winnipeg, MB R3Y 1G4  
 Tel: (204) 488-6999



## ASTM D7928 - PARTICLE-SIZE DISTRIBUTION OF FINE-GRAINED SOILS USING THE SEDIMENTATION ANALYSIS

TO City of Winnipeg, Public Works Department  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 3P1

PROJECT 2023 Local Streets Renewals Program

PROJECT NO. 123316298

ATTN: Erik Hansen

REPORT NO. 1

DATE SAMPLED: 2023.Jan.17


DATE RECEIVED 2023.Jan.17

DATE TESTED: 2023.Jan.23

SAMPLED BY: Stantec Consulting Ltd.

SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Donald Eliazar



SIEVE SIZE (mm)	% PASSING
50.0	100.0
40.0	100.0
25.0	100.0
20.0	100.0
16.0	100.0
12.5	100.0
9.5	100.0
4.75	100.0
2.36	100.0
2.00	100.0
1.18	99.8
0.600	99.6
0.300	99.3
0.150	99.0
0.075	98.9
0.005	78.4
0.002	66.9
0.001	58.0

Gravel	Sand			Silt	Clay	Colloids
	Coarse	Medium	Fine			
0.0	0.0	0.4	0.7	32.0	66.9	58.0

**COMMENTS:**

Material tested was identified as BH23-59, 2.8' (Raleigh St).

REPORT DATE 2023.Jan.30

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

Reporting of these test results constitutes a testing service only. Engineering interpretation or evaluation of the test results is provided on written request. The data presented is for sole use of client stipulated above. Stantec is not responsible, nor can be held liable, for the use of this report by any other party, with or without the knowledge of Stantec.



**Stantec Consulting Ltd.**  
 199 Henlow Bay, Winnipeg, MB R3Y 1G4  
 Tel: (204) 488-6999



## ASTM D7928 - PARTICLE-SIZE DISTRIBUTION OF FINE-GRAINED SOILS USING THE SEDIMENTATION ANALYSIS

TO City of Winnipeg, Public Works Department  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 3P1

PROJECT 2023 Local Streets Renewals Program

PROJECT NO. 123316298

ATTN: Erik Hansen

REPORT NO. 2

DATE SAMPLED: 2023.Jan.17


DATE RECEIVED 2023.Jan.17

DATE TESTED: 2023.Jan.23

SAMPLED BY: Stantec Consulting Ltd.

SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Donald Eliazar



**Table 1 - Compressive Strength Test Data**

Test No.	Core Identification	Diameter (mm)	Length (mm)	L/D Ratio	Correction Factor	Peak Load (kN)	Compressive Strength (MPa)	
							Measured	Corrected
1	BH-23-19	100	168	1.68	0.974	435.73	53.8	52.4
2	BH-23-23	100	172	1.72	0.978	334.62	41.3	40.4
3	BH-23-24	100	192	1.92	0.994	482.12	59.5	59.1
4	BH-23-26	100	169	1.69	0.975	505.25	62.3	60.8
5	BH-23-30	100	158	1.58	0.966	524.69	64.7	62.5