

**APPENDIX 'A'**  
**GEOTECHNICAL REPORT**



Stantec Consulting Ltd.  
199 Henlow Bay  
Winnipeg MB R3Y 1G4

February 26, 2024

Project/File: 123316892

**Caleb Olfert**

Dillon Consulting Ltd.  
1558 Willson Place  
Winnipeg, MB R3T 0Y4

Good day Caleb,

**Reference: 24-R-06 Geotechnical Investigation**

Stantec Consulting Ltd. (Stantec) was retained to undertake a factual geotechnical investigation for the Local Streets Package 24-R-06 in Winnipeg, Manitoba. Use of this report is subject to the Statement of General Conditions provided in **Appendix A**.

The subsurface coring and drilling sampling program was conducted from January 10, 2024, to January 25, 2024. Pavement coring was performed by our geotechnical field personnel, and drilling services were provided by Maple Leaf Drilling under the supervision of our personnel. The borehole locations are shown on the attached Borehole Location Plan provided in **Appendix B**. When subsurface drilling was required, the pavement cores were sampled with a 150 mm bit and boreholes were drilled with 125 mm solid stem augers. Geotechnical drilling boreholes were terminated at a depth of 2.0 m below the pavement, which resulted in borehole depths ranging from 2.07 m to 2.22 m below the surface. Soil samples were obtained directly from the auger flights at depths of 0.6 m, 0.9 m, 1.2 m, 1.6 m, and 2.0 m from the bottom of the existing pavement. Upon completion of drilling, the testholes were examined for evidence of sloughing and groundwater seepage. The borehole records are provided in **Appendix C**. The soil classification used in the borehole records is as per ASTM D2487 – *Standard Practice for Classification of Soils for Engineering Purposes (Unified Soil Classification System)*. Core photographs are provided in **Appendix D**.

Reference: 24-R-06 Geotechnical Investigation

## EXISTING PAVEMENT THICKNESS

The existing pavement thickness is provided in the following table:

**Table 1 – Existing Pavement Thickness**

Street	Core ID	Asphalt Thickness (mm)	Concrete Thickness (mm)	Total Pavement Thickness (mm)
Lilian Ave	BH-11	110	0	110
Lilian Ave	BH-12	75	100	175
Lilian Ave	BH-13	0	220	220
Champlain St	BH-14	20	150	170
Champlain St	BH-15	0	155	155
Champlain St	BH-16	0	160	160
Champlain St	BH-17	0	165	165
Dumoulin St	BH-18	0	180	180
Dumoulin St	BH-19	0	150	150
Dumoulin St	BH-20	0	170	170
Dumoulin St	BH-21	0	180	180
Dumoulin St	BH-22	0	175	175

Reference: 24-R-06 Geotechnical Investigation

Street	Core ID	Asphalt Thickness (mm)	Concrete Thickness (mm)	Total Pavement Thickness (mm)
[REDACTED]				
Baywater PI	BH-32	0	180	180
Baywater PI	BH-33	0	200	200
Courtwood PI	BH-34	0	160	160
Courtwood PI	BH-35	0	100	100
[REDACTED]				

## LABORATORY TESTING

The following laboratory tests were conducted on select soil samples:

- ASTM D2216 - *Laboratory Determination of Water (Moisture) Content of Soil by Mass*
- ASTM D4318 - *Liquid Limit, Plastic Limit, and Plasticity Index of Soils*
- ASTM D7928 - *Particle-Size Distribution of Fine-Grained Soils Using The Sedimentation Analysis*
- ASTM D698 - *Laboratory Compaction Characteristics of Soil Using Standard Effort*
- ASTM D1883 - *California Bearing Ratio (CBR) of Laboratory-Compacted Soils*
- CSA A23.2-14C – *Obtaining and testing drilled cores for compressive strength testing*

The CBR tests were performed at 95% maximum dry density under soaked conditions. Prior to testing the concrete core samples for compressive strength, the cores were conditioned in water at room temperature for 48 hours. The moisture content results are shown on the borehole records, and the laboratory test reports are provided in **Appendix E**.

Reference: 24-R-06 Geotechnical Investigation

## CLOSURE

We appreciate the opportunity to assist you on this project. Please contact the undersigned if you have any questions regarding this report.

Regards,

**STANTEC CONSULTING LTD.**



**Guillaume Beauce** P.Eng.  
Geotechnical Engineer, Materials Testing Services  
Phone: 204-928-7618  
Mobile: 204-898-8290  
guillaume.beauce@stantec.com



**Jason Thompson** C.E.T.  
Manager, Materials Testing Services  
Phone: 204-928-4004  
Mobile: 204-981-8445  
jason.thompson@stantec.com

Attachment: Appendix A – Statement of General Conditions  
Appendix B – Borehole Location Plan  
Appendix C – Borehole Records  
Appendix D – Core Photographs  
Appendix E – Laboratory Test Reports

- Atterberg Limits Test Reports
- Particle-Size Analysis Reports
- Standard Proctor Test Reports
- CBR Test Reports
- Concrete Core Compressive Strength Test Results

# **APPENDIX A**

## **Statement of General Conditions**

## STATEMENT OF GENERAL CONDITIONS

**USE OF THIS REPORT:** This report has been prepared for the sole benefit of the Client or its agent and may not be used by any third party without the express written consent of Stantec and the Client. Any use which a third party makes of this report is the responsibility of such third party.

**BASIS OF THE REPORT:** The information, opinions, and/or recommendations made in this report are in accordance with Stantec's present understanding of the site-specific project as described by the Client. The applicability of these is restricted to the site conditions encountered at the time of the investigation or study. If the proposed site-specific project differs or is modified from what is described in this report or if the site conditions are altered, this report is no longer valid unless Stantec is requested by the Client to review and revise the report to reflect the differing or modified project specifics and/or the altered site conditions.

**STANDARD OF CARE:** Preparation of this report, and all associated work, was carried out in accordance with the normally accepted standard of care in the state or province of execution for the specific professional service provided to the Client. No other warranty is made.

**INTERPRETATION OF SITE CONDITIONS:** Soil, rock, or other material descriptions, and statements regarding their condition, made in this report are based on site conditions encountered by Stantec at the time of the work and at the specific testing and/or sampling locations. Classifications and statements of condition have been made in accordance with normally accepted practices which are judgmental in nature; no specific description should be considered exact, but rather reflective of the anticipated material behavior. Extrapolation of in situ conditions can only be made to some limited extent beyond the sampling or test points. The extent depends on variability of the soil, rock, and groundwater conditions as influenced by geological processes, construction activity, and site use.

**VARYING OR UNEXPECTED CONDITIONS:** Should any site or subsurface conditions be encountered that are different from those described in this report or encountered at the test locations, Stantec must be notified immediately to assess if the varying or unexpected conditions are substantial and if reassessments of the report conclusions or recommendations are required. Stantec will not be responsible to any party for damages incurred as a result of failing to notify Stantec that differing site or sub-surface conditions are present upon becoming aware of such conditions.

**PLANNING, DESIGN, OR CONSTRUCTION:** Development or design plans and specifications should be reviewed by Stantec, sufficiently ahead of initiating the next project stage (property acquisition, tender, construction, etc.), to confirm that this report completely addresses the elaborated project specifics and that the contents of this report have been properly interpreted. Specialty quality assurance services (field observations and testing) during construction are a necessary part of the evaluation of sub-subsurface conditions and site preparation works. Site work relating to the recommendations included in this report should only be carried out in the presence of a qualified geotechnical engineer; Stantec cannot be responsible for site work carried out without being present.



# **APPENDIX B**

## **Borehole Location Plan**



TITLE  
LILIAN AVENUE  
1 OF 2

PROJECT NO. -  
DRAWING NO. -



**BH-13**

LILIAN AVE

POULIN DR


ST. MARY'S RD



TITLE  
LILIAN AVENUE  
2 OF 2

PROJECT NO.  
-  
DRAWING NO.  
-

SCALE: 1:250



**BH-14**


ST. MARY'S RD

CHAMPLAIN ST



TITLE	CHAMPLAIN STREET 1 OF 4
-------	----------------------------

PROJECT NO.	-
DRAWING NO.	-



CHAMPLAIN ST

CATON ST

HILLCREST AVE

**BH-15**

CHAMPLAIN ST



TITLE	CHAMPLAIN STREET 2 OF 4
-------	----------------------------

PROJECT NO.	-
DRAWING NO.	-



CHAMPLAIN ST

**BH-16**



TITLE

CHAMPLAIN STREET  
3 OF 4

PROJECT NO.

-

DRAWING NO.

-

SCALE: 1:250



CHAMPLAIN ST

NIVERVILLE AVE

**BH-17**



TITLE	CHAMPLAIN STREET 4 OF 4
-------	----------------------------

PROJECT NO.	-
DRAWING NO.	-



DUMOULIN ST

**BH-18**

LANGEVIN ST



SCALE: 1:250

TITLE

DUMOULIN STREET  
1 OF 5

PROJECT NO.

-

DRAWING NO.

-



DUMOULIN ST

**BH-19**



SCALE: 1:250

TITLE


DUMOULIN STREET  
2 OF 5

PROJECT NO.

-

DRAWING NO.

-



DUMOULIN ST

BH-20

ST. JEAN BAPTISTE ST



TITLE

DUMOULIN STREET  
3 OF 5

PROJECT NO.

-

DRAWING NO.

-

SCALE: 1:250



DUMOULIN ST

**BH-21**



TITLE

DUMOULIN STREET  
4 OF 5

SCALE: 1:250

PROJECT NO.

-

DRAWING NO.

-



DUMOULIN ST

THIBAUT ST

**BH-22**



SCALE: 1:250

TITLE


DUMOULIN STREET  
5 OF 5

PROJECT NO.

-


DRAWING NO.

-



TITLE	BAYWATER PLACE 1 OF 1
-------	--------------------------

PROJECT NO.	-
DRAWING NO.	-



**BH-34**

**BH-35**


BEAVERHILL BLVD

COURTWOOD PL



TITLE	COURTWOOD PL 1 OF 1
-------	------------------------

PROJECT NO.	-
DRAWING NO.	-



**BH-36** ●

**BH-37** ●

PANDORA AVE E

ROANOKE ST

MELROSE AVE E




SCALE: 1:250

TITLE

Roanoke St

PROJECT NO.

DRAWING NO.



LEOLA ST

MELROSE AVE E

BH-38

BH-39



SCALE: 1:250

TITLE

Melrose Ave E

PROJECT NO.

-

DRAWING NO.

-

# **APPENDIX C**

## **Borehole Records**

## SYMBOLS AND TERMS USED ON BOREHOLE AND TEST PIT RECORDS

### SOIL DESCRIPTION

#### Terminology describing common soil genesis:

<i>Rootmat</i>	- vegetation, roots and moss with organic matter and topsoil typically forming a mattress at the ground surface
<i>Topsoil</i>	- mixture of soil and humus capable of supporting vegetative growth
<i>Peat</i>	- mixture of visible and invisible fragments of decayed organic matter
<i>Till</i>	- unstratified glacial deposit which may range from clay to boulders
<i>Fill</i>	- material below the surface identified as placed by humans (excluding buried services)

#### Terminology describing soil structure:

<i>Desiccated</i>	- having visible signs of weathering by oxidization of clay minerals, shrinkage cracks, etc.
<i>Fissured</i>	- having cracks, and hence a blocky structure
<i>Varved</i>	- composed of regular alternating layers of silt and clay
<i>Stratified</i>	- composed of alternating successions of different soil types, e.g. silt and sand
<i>Layer</i>	- > 75 mm in thickness
<i>Seam</i>	- 2 mm to 75 mm in thickness
<i>Parting</i>	- < 2 mm in thickness

#### Terminology describing soil types:

The classification of soil types are made on the basis of grain size and plasticity in accordance with the Unified Soil Classification System (USCS) (ASTM D 2487 or D 2488) which excludes particles larger than 75 mm. For particles larger than 75 mm, and for defining percent clay fraction in hydrometer results, definitions proposed by Canadian Foundation Engineering Manual, 4<sup>th</sup> Edition are used. The USCS provides a group symbol (e.g. SM) and group name (e.g. silty sand) for identification.

#### Terminology describing cobbles, boulders, and non-matrix materials (organic matter or debris):

Terminology describing materials outside the USCS, (e.g. particles larger than 75 mm, visible organic matter, and construction debris) is based upon the proportion of these materials present:

<i>Trace, or occasional</i>	Less than 10%
<i>Some</i>	10-20%
<i>Frequent</i>	> 20%

#### Terminology describing compactness of cohesionless soils:

The standard terminology to describe cohesionless soils includes compactness (formerly "relative density"), as determined by the Standard Penetration Test (SPT) N-Value - also known as N-Index. The SPT N-Value is described further on page 3. A relationship between compactness condition and N-Value is shown in the following table.

Compactness Condition	SPT N-Value
<i>Very Loose</i>	<4
<i>Loose</i>	4-10
<i>Compact</i>	10-30
<i>Dense</i>	30-50
<i>Very Dense</i>	>50


#### Terminology describing consistency of cohesive soils:

The standard terminology to describe cohesive soils includes the consistency, which is based on undrained shear strength as measured by *in situ* vane tests, penetrometer tests, or unconfined compression tests. Consistency may be crudely estimated from SPT N-Value based on the correlation shown in the following table (Terzaghi and Peck, 1967). The correlation to SPT N-Value is used with caution as it is only very approximate.

Consistency	Undrained Shear Strength		Approximate SPT N-Value
	kips/sq.ft.	kPa	
<i>Very Soft</i>	<0.25	<12.5	<2
<i>Soft</i>	0.25 - 0.5	12.5 - 25	2-4
<i>Firm</i>	0.5 - 1.0	25 - 50	4-8
<i>Stiff</i>	1.0 - 2.0	50 - 100	8-15
<i>Very Stiff</i>	2.0 - 4.0	100 - 200	15-30
<i>Hard</i>	>4.0	>200	>30

## STRATA PLOT


Strata plots symbolize the soil or bedrock description. They are combinations of the following basic symbols. The dimensions within the strata symbols are not indicative of the particle size, layer thickness, etc.



## SAMPLE TYPE

SS	Split spoon sample (obtained by performing the Standard Penetration Test)
ST	Shelby tube or thin wall tube
DP	Direct-Push sample (small diameter tube sampler hydraulically advanced)
PS	Piston sample
BS	Bulk sample
HQ, NQ, BQ, etc.	Rock core samples obtained with the use of standard size diamond coring bits.

## WATER LEVEL MEASUREMENT



## RECOVERY

For soil samples, the recovery is recorded as the length of the soil sample recovered. For rock core, recovery is defined as the total cumulative length of all core recovered in the core barrel divided by the length drilled and is recorded as a percentage on a per run basis.

## N-VALUE

Numbers in this column are the field results of the Standard Penetration Test: the number of blows of a 140 pound (63.5 kg) hammer falling 30 inches (760 mm), required to drive a 2 inch (50.8 mm) O.D. split spoon sampler one foot (300 mm) into the soil. In accordance with ASTM D1586, the N-Value equals the sum of the number of blows (N) required to drive the sampler over the interval of 6 to 18 in. (150 to 450 mm). However, when a 24 in. (610 mm) sampler is used, the number of blows (N) required to drive the sampler over the interval of 12 to 24 in. (300 to 610 mm) may be reported if this value is lower. For split spoon samples where insufficient penetration was achieved and N-Values cannot be presented, the number of blows are reported over sampler penetration in millimetres (e.g. 50/75). Some design methods make use of N-values corrected for various factors such as overburden pressure, energy ratio, borehole diameter, etc. No corrections have been applied to the N-values presented on the log.

## DYNAMIC CONE PENETRATION TEST (DCPT)

Dynamic cone penetration tests are performed using a standard 60 degree apex cone connected to 'A' size drill rods with the same standard fall height and weight as the Standard Penetration Test. The DCPT value is the number of blows of the hammer required to drive the cone one foot (300 mm) into the soil. The DCPT is used as a probe to assess soil variability.

## OTHER TESTS

S	Sieve analysis
H	Hydrometer analysis
k	Laboratory permeability
$\gamma$	Unit weight
$G_s$	Specific gravity of soil particles
CD	Consolidated drained triaxial
CU	Consolidated undrained triaxial with pore pressure measurements
UU	Unconsolidated undrained triaxial
DS	Direct Shear
C	Consolidation
$Q_u$	Unconfined compression
$I_p$	Point Load Index ( $I_p$ on Borehole Record equals $I_p(50)$ in which the index is corrected to a reference diameter of 50 mm)

	Single packer permeability test; test interval from depth shown to bottom of borehole
	Double packer permeability test; test interval as indicated
	Falling head permeability test using casing
	Falling head permeability test using well point or piezometer





CLIENT: Dillon Consulting Ltd.  
 PROJECT: 24-R-06 Geotechnical Investigation  
 LOCATION: Lilian Avenue  
 DATE BORED: January 17 2024

PROJECT NO.: 123316892  
 BH ELEVATION: N/A  
 DATUM: N/A  
 WATER LEVEL: N/A

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION (MUSCS)	STRATA PLOT	SAMPLES				OTHER TESTS / REMARKS	UNDRAINED SHEAR STRENGTH, Cu (kPa)				BACKFILL	ELEVATION (m)
				TYPE	NUMBER	RECOVERY (mm) or TCR %	N-VALUE or RQD %		50 kPa	100 kPa	150 kPa	200 kPa		
0		CONCRETE	AS						WATER CONTENT & ATTERBERG LIMITS <span style="float: right;">W<sub>p</sub>   W   W<sub>L</sub></span> * SPT (N-value) BLOWS/0.3m 10   20   30   40   50   60   70   80 <small>Water Content (%) and Blow Count</small>					
		Firm brown fat CLAY (CH) - silty, trace sand	AS						WATER CONTENT & ATTERBERG LIMITS <span style="float: right;">W<sub>p</sub>   W   W<sub>L</sub></span> * SPT (N-value) BLOWS/0.3m 10   20   30   40   50   60   70   80 <small>Water Content (%) and Blow Count</small>					
1		<b>End of Borehole</b> • Auger refusal at a depth of 0.51 m on suspected concrete. • No groundwater seepage or soil sloughing was observed during or upon completion of drilling. • Borehole surface backfilled as per City of Winnipeg Street Cuts Manual.												
2														
3														
4														

BACKFILL SYMBOL	ASPHALT	GROUT	CONCRETE
BENTONITE	DRILL CUTTINGS	SAND	SLOUGH

Drilling Contractor: Paddock Drilling Ltd.	Logged By: RB
Drilling Method: 125 mm SSA	Reviewed By: GB
Completion Depth: 0.51 m	Page 1 of 1

# **APPENDIX D**

## **Core Photographs**




Figure 11 – Core No. 11 (Lilian Ave)



Figure 12 – Core No. 12 (Lilian Ave)



Figure 13 – Core No. 13 (Lilian Ave)



Figure 14 – Core No. 14 (Champlain St)



Figure 15 – Core no. 15 (Champlain St)



Figure 16 – Core No. 16 (Champlain St)



Figure 17 – Core No.17 (Champlain St)



Figure 18 – Core No. 18 (Dumoulin St)



Figure 19 – Core No. 19 (Dumoulin St)




Figure 20 – Core No. 20 (Dumoulin St)



Figure 21 – Core No.21 (Dumoulin St)



Figure 22 – Core No. 22 (Dumoulin St)






Figure 32 – Core No. 32 (Baywater PI)




Figure 33 – Core No. 33 (Baywater PI)



Figure 34 – Core No. 34 (Courtwood PI)



Figure 35 – Core No. 35 (Courtwood PI)



# **APPENDIX E**

## **Laboratory Test Reports**

## ASTM D4318 - LIQUID LIMIT, PLASTIC LIMIT AND PLASTICITY INDEX OF SOILS (LL METHOD B - ONE-POINT)

TO Dillon Consulting Ltd.  
 300 - 100 Innovation Drive  
 Winnipeg, Manitoba  
 R3T 6A8

PROJECT 24-R-06 - Local Street Package - Geotechnical Investigation

PROJECT NO. 123316892

ATTN Caleb Olfert

REPORT NO. 8

DATE SAMPLED: 2024.Jan.17  
 SAMPLED BY: Stantec Consulting Ltd.

DATE RECEIVED: 2024.Jan.17  
 SUBMITTED BY: Stantec Consulting Ltd.

DATE TESTED: 2024.Jan.31  
 TESTED BY: Larry Presado

**MATERIAL IDENTIFICATION**


CLIENT FIELD ID BH-11, 710 mm

STANTEC SAMPLE NO. 4000

TRIAL	LIQUID LIMIT	
	1	2
BLOWS	27	28
MC (%)	63	71

TRIAL	PLASTIC LIMIT	
	1	2
MC (%)	22	21

LIQUID LIMIT, LL	68
PLASTIC LIMIT, PL	21
PLASTICITY INDEX, PI	46
AS REC'D MC (%)	31.60



COMMENTS  
 No comments.

REPORT DATE 2024.Feb.01

  
 REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D7928 - PARTICLE-SIZE DISTRIBUTION OF FINE-GRAINED SOILS USING THE SEDIMENTATION ANALYSIS

TO Dillon Consulting Ltd.  
 300 - 100 Innovation Drive  
 Winnipeg, Manitoba  
 R3T 6A8

PROJECT 24-R-06 - Local Streets Package -  
 Geotechnical Investigation

PROJECT NO. 123316892

ATTN Caleb Olfert

REPORT NO. 8

DATE SAMPLED: 2024.Jan.17

DATE RECEIVED: 2024.Jan.17

DATE TESTED: 2024.Jan.23

SAMPLED BY: Stantec Consulting Ltd.


SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Larry Presado

**MATERIAL IDENTIFICATION**

CLIENT FIELD ID BH-11, 710 mm

STANTEC SAMPLE NO. 4000



Sieve Size (mm)	% Passing
50.0	100.0
40.0	100.0
25.0	100.0
20.0	100.0
16.0	100.0
12.5	100.0
9.5	100.0
4.75	100.0
2.36	99.9
2.00	99.8
1.18	99.4
0.600	98.8
0.300	98.3
0.150	97.3
0.075	91.1
0.005	45.9
0.002	38.2
0.001	34.1

Gravel	Sand			Silt	Clay	Colloids
	Coarse	Medium	Fine			
0.0	0.2	1.3	7.4	52.9	38.2	34.1

COMMENTS  
 No comments.



REPORT DATE 2024.Jan.25

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D7928 - PARTICLE-SIZE DISTRIBUTION OF FINE-GRAINED SOILS USING THE SEDIMENTATION ANALYSIS

TO Dillon Consulting Ltd.  
 300 - 100 Innovation Drive  
 Winnipeg, Manitoba  
 R3T 6A8

PROJECT 24-R-06 - Local Streets Package -  
 Geotechnical Investigation

PROJECT NO. 123316892

ATTN Caleb Olfert

REPORT NO. 9

DATE SAMPLED: 2024.Jan.17

DATE RECEIVED: 2024.Jan.17

DATE TESTED: 2024.Jan.23

SAMPLED BY: Stantec Consulting Ltd.


SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Larry Presado

**MATERIAL IDENTIFICATION**

CLIENT FIELD ID BH-12, 775 mm

STANTEC SAMPLE NO. 4001



Sieve Size (mm)	% Passing
50.0	100.0
40.0	100.0
25.0	100.0
20.0	100.0
16.0	100.0
12.5	100.0
9.5	100.0
4.75	97.0
2.36	96.2
2.00	96.0
1.18	94.0
0.600	91.6
0.300	89.3
0.150	86.9
0.075	84.4
0.005	44.3
0.002	35.8
0.001	31.2

Gravel	Sand			Silt	Clay	Colloids
	Coarse	Medium	Fine			
3.0	1.0	5.7	5.9	48.6	35.8	31.2

COMMENTS  
 No comments.



REPORT DATE 2024.Jan.25

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

# PROCTOR TEST REPORT

TO Dillon Consulting Ltd.  
 300 - 100 Innovation Dr.  
 Winnipeg, MB  
 R3T 6A8


CLIENT Dillon Consulting Ltd.  
 C.C.

ATTN: Ali Campbell

PROJECT 24-R-06 - Local Streets Package

PROJECT NO. 123316892  
 PROCTOR NO. 1 DATE SAMPLED 2024.Jan.15 DATE RECEIVED 2024.Jan.15 DATE TESTED 2024.Jan.19

INSITU MOISTURE	36.7 %	COMPACTION STANDARD	Standard Proctor, ASTM D698
TESTED BY	Donald Eliazar	COMPACTION PROCEDURE	A: 101.6mm Mold, Passing 4.75mm
MATERIAL IDENTIFICATION		RAMMER TYPE	Manual
MAJOR COMPONENT	Backfill	PREPARATION	Moist
SIZE	Fat Clay (CH)	OVERSIZE CORRECTION METHOD	None
DESCRIPTION	Existing Materials	RETAINED 4.75mm SCREEN	N/A %
SUPPLIER			
SOURCE	Kanata Street - BH-01, 0.740 m		



TRIAL NUMBER	WET DENSITY (kg/m³)	DRY DENSITY (kg/m³)	MOISTURE CONTENT (%)
1	1646	1417	16.2
2	1736	1444	20.2
3	1857	1493	24.4
4	1881	1466	28.3

	MAXIMUM DRY DENSITY (kg/m³)	OPTIMUM MOISTURE CONTENT (%)
CALCULATED	1500	25.5
OVERSIZE CORRECTED		

**COMMENTS**

Stantec Sample No. 2967.

# PROCTOR TEST REPORT

TO Dillon Consulting Ltd.  
 300 - 100 Innovation Dr.  
 Winnipeg, MB  
 R3T 6A8


CLIENT Dillon Consulting Ltd.  
 C.C.

ATTN: Ali Campbell

PROJECT 24-R-06 - Local Streets Package

PROJECT NO. 123316892  
 PROCTOR NO. 2 DATE SAMPLED 2024.Jan.15 DATE RECEIVED 2024.Jan.15 DATE TESTED 2024.Jan.22

INSITU MOISTURE	46.2 %	COMPACTION STANDARD	Standard Proctor, ASTM
TESTED BY	Donald Eliazar		D698
MATERIAL IDENTIFICATION		COMPACTION PROCEDURE	A: 101.6mm Mold, Passing 4.75mm
MAJOR COMPONENT	Subgrade	RAMMER TYPE	Manual
SIZE	Fat Clay (CH)	PREPARATION	Moist
DESCRIPTION		OVERSIZE CORRECTION METHOD	None
SUPPLIER	Existing Materials	RETAINED 4.75mm SCREEN	N/A %
SOURCE	Kanata Street - BH-02 , 0.780 m		



TRIAL NUMBER	WET DENSITY (kg/m³)	DRY DENSITY (kg/m³)	MOISTURE CONTENT (%)
1	1631	1358	20.1
2	1722	1385	24.3
3	1824	1422	28.3
4	1796	1358	32.3

	MAXIMUM DRY DENSITY (kg/m³)	OPTIMUM MOISTURE CONTENT (%)
CALCULATED	1420	28.5
OVERSIZE CORRECTED		

**COMMENTS**

Stantec Sample No. 2968.

# PROCTOR TEST REPORT

TO Dillon Consulting Ltd.  
 300 - 100 Innovation Dr.  
 Winnipeg, MB  
 R3T 6A8


CLIENT Dillon Consulting Ltd.  
 C.C.

ATTN: Ali Campbell

PROJECT 24-R-06 - Local Streets Package

PROJECT NO. 123316892  
 PROCTOR NO. 3 DATE SAMPLED 2024.Jan.15 DATE RECEIVED 2024.Jan.15 DATE TESTED 2024.Jan.23

INSITU MOISTURE	33.5 %	COMPACTION STANDARD	Standard Proctor, ASTM D698
TESTED BY	Donald Eliazar	COMPACTION PROCEDURE	A: 101.6mm Mold, Passing 4.75mm
MATERIAL IDENTIFICATION		RAMMER TYPE	Manual
MAJOR COMPONENT	Backfill	PREPARATION	Moist
SIZE	Fat Clay (CH)	OVERSIZE CORRECTION METHOD	None
DESCRIPTION		RETAINED 4.75mm SCREEN	N/A %
SUPPLIER	Existing Materials		
SOURCE	Kanata Street - BH-04, 0.780 m		



TRIAL NUMBER	WET DENSITY (kg/m³)	DRY DENSITY (kg/m³)	MOISTURE CONTENT (%)
1	1751	1559	12.3
2	1860	1601	16.2
3	1961	1633	20.1
4	1989	1601	24.2

	MAXIMUM DRY DENSITY (kg/m³)	OPTIMUM MOISTURE CONTENT (%)
CALCULATED	1630	20.5
OVERSIZE CORRECTED		

**COMMENTS**

Stantec Sample No. 2969.

# PROCTOR TEST REPORT

TO Dillon Consulting Ltd.  
 300 - 100 Innovation Dr.  
 Winnipeg, MB  
 R3T 6A8


CLIENT Dillon Consulting Ltd.  
 C.C.

ATTN: Ali Campbell

PROJECT 24-R-06 - Local Streets Package

PROJECT NO. 123316892  
 PROCTOR NO. 4 DATE SAMPLED 2024.Jan.15 DATE RECEIVED 2024.Jan.15 DATE TESTED 2024.Jan.23

INSITU MOISTURE	27.9 %	COMPACTION STANDARD	Standard Proctor, ASTM D698
TESTED BY	Pervez Safdar	COMPACTION PROCEDURE	A: 101.6mm Mold, Passing 4.75mm
MATERIAL IDENTIFICATION		RAMMER TYPE	Manual
MAJOR COMPONENT	Backfill	PREPARATION	Moist
SIZE	Fat Clay (CH)	OVERSIZE CORRECTION METHOD	None
DESCRIPTION		RETAINED 4.75mm SCREEN	N/A %
SUPPLIER	Existing Materials		
SOURCE	Wabasha Street - BH-05, 0.745 m		



TRIAL NUMBER	WET DENSITY (kg/m³)	DRY DENSITY (kg/m³)	MOISTURE CONTENT (%)
1	1711	1471	16.3
2	1831	1521	20.4
3	1924	1548	24.3
4	1890	1474	28.2

	MAXIMUM DRY DENSITY (kg/m³)	OPTIMUM MOISTURE CONTENT (%)
CALCULATED	1550	24.0
OVERSIZE CORRECTED		

**COMMENTS**

Stantec Sample No. 2970.

# PROCTOR TEST REPORT

TO Dillon Consulting Ltd.  
 300 - 100 Innovation Dr.  
 Winnipeg, MB  
 R3T 6A8


CLIENT Dillon Consulting Ltd.  
 C.C.

ATTN: Ali Campbell

PROJECT 24-R-06 - Local Streets Package

PROJECT NO. 123316892  
 PROCTOR NO. 5 DATE SAMPLED 2024.Jan.15 DATE RECEIVED 2024.Jan.15 DATE TESTED 2024.Jan.23

INSITU MOISTURE	33.9 %	COMPACTION STANDARD	Standard Proctor, ASTM
TESTED BY	Donald Eliazar		D698
MATERIAL IDENTIFICATION		COMPACTION PROCEDURE	A: 101.6mm Mold, Passing 4.75mm
MAJOR COMPONENT	Backfill	RAMMER TYPE	Manual
SIZE	Fat Clay (CH)	PREPARATION	Moist
DESCRIPTION		OVERSIZE CORRECTION METHOD	None
SUPPLIER	Existing Materials	RETAINED 4.75mm SCREEN	N/A %
SOURCE	Wabasha Street - BH-07, 0.765 m		



TRIAL NUMBER	WET DENSITY (kg/m³)	DRY DENSITY (kg/m³)	MOISTURE CONTENT (%)
1	1601	1378	16.2
2	1709	1422	20.2
3	1807	1453	24.4
4	1856	1449	28.1

	MAXIMUM DRY DENSITY (kg/m³)	OPTIMUM MOISTURE CONTENT (%)
CALCULATED	1460	26.0
OVERSIZE CORRECTED		

**COMMENTS**

Stantec Sample No. 2971.

# PROCTOR TEST REPORT

TO Dillon Consulting Ltd.  
 300 - 100 Innovation Dr.  
 Winnipeg, MB  
 R3T 6A8


CLIENT Dillon Consulting Ltd.  
 C.C.

ATTN: Ali Campbell

PROJECT 24-R-06 - Local Streets Package

PROJECT NO. 123316892  
 PROCTOR NO. 8 DATE SAMPLED 2024.Jan.17 DATE RECEIVED 2024.Jan.17 DATE TESTED 2024.Feb.05

INSITU MOISTURE	27.8 %	COMPACTION STANDARD	Standard Proctor, ASTM D698
TESTED BY	Donald Eliazar	COMPACTION PROCEDURE	A: 101.6mm Mold, Passing 4.75mm
MATERIAL IDENTIFICATION		RAMMER TYPE	Manual
MAJOR COMPONENT	Subgrade	PREPARATION	Moist
SIZE	Fat Clay (CH)	OVERSIZE CORRECTION METHOD	None
DESCRIPTION		RETAINED 4.75mm SCREEN	N/A %
SUPPLIER	Existing Materials		
SOURCE	Lilian Ave - BH-11, 0.710 m		



TRIAL NUMBER	WET DENSITY (kg/m³)	DRY DENSITY (kg/m³)	MOISTURE CONTENT (%)
1	1714	1471	16.5
2	1828	1517	20.5
3	1923	1540	24.9
4	1904	1478	28.8

	MAXIMUM DRY DENSITY (kg/m³)	OPTIMUM MOISTURE CONTENT (%)
CALCULATED	1540	24.0
OVERSIZE CORRECTED		

**COMMENTS**

Stantec Sample No. 4000.

# PROCTOR TEST REPORT

TO Dillon Consulting Ltd.  
 300 - 100 Innovation Dr.  
 Winnipeg, MB  
 R3T 6A8


CLIENT Dillon Consulting Ltd.  
 C.C.

ATTN: Ali Campbell

PROJECT 24-R-06 - Local Streets Package

PROJECT NO. 123316892  
 PROCTOR NO. 9 DATE SAMPLED 2024.Jan.17 DATE RECEIVED 2024.Jan.17 DATE TESTED 2024.Feb.05

INSITU MOISTURE	36.6 %	COMPACTION STANDARD	Standard Proctor, ASTM D698
TESTED BY	Donald Eliazar	COMPACTION PROCEDURE	A: 101.6mm Mold, Passing 4.75mm
MATERIAL IDENTIFICATION		RAMMER TYPE	Manual
MAJOR COMPONENT	Subgrade	PREPARATION	Moist
SIZE	Fat Clay with Sand (CH)	OVERSIZE CORRECTION METHOD	None
DESCRIPTION	Existing Materials	RETAINED 4.75mm SCREEN	N/A %
SUPPLIER	Lilian Ave - BH-12, 0.775 m		



TRIAL NUMBER	WET DENSITY (kg/m³)	DRY DENSITY (kg/m³)	MOISTURE CONTENT (%)
1	1616	1400	15.4
2	1729	1444	19.7
3	1831	1480	23.7
4	1867	1467	27.3

	MAXIMUM DRY DENSITY (kg/m³)	OPTIMUM MOISTURE CONTENT (%)
CALCULATED	1480	25.0
OVERSIZE CORRECTED		

**COMMENTS**

Stantec Sample No. 4001.

# ASTM D1883 - CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOILS

TO Dillon Consulting Ltd.  
 300 - 100 Innovation Drive  
 Winnipeg, Manitoba  
 R3T 6A8

PROJECT 24-R-06 - Local Streets Package -  
 Geotechnical Investigation

PROJECT NO. 123316892

ATTN Ali Campbell

REPORT NO. 8

DATE SAMPLED: 2024.Jan.17  
 SAMPLED BY: Stantec Consulting Ltd.

DATE RECEIVED: 2024.Jan.17  
 SUBMITTED BY: Stantec Consulting Ltd.

DATE TESTED: 2024.Feb.19  
 TESTED BY: Donald Eliazar


**MATERIAL IDENTIFICATION**

MATERIAL USE Subgrade  
 MAX. NOMINAL SIZE 4.75 mm  
 MATERIAL TYPE Fat Clay (CH)  
 SPECIFICATION ID Not Applicable

SUPPLIER Existing Material  
 SOURCE Existing Material  
 SAMPLE LOCATION BH-11, 0.710 m  
 STANTEC SAMPLE NO. 4000

IMMERSION PERIOD 96 ± 2 hr  
 CONDITION OF SAMPLE Soaked  
 SURCHARGE MASS 4.54 kg  
 +19 mm OVERSIZE 0 %  
 SWELL OF SAMPLE 1.51 %  
 POST-TEST MOISTURE 30.4 %

TARGET MAX. DRY DENSITY 1540 kg/m<sup>3</sup>  
 TARGET OPTIMUM MOISTURE 24.0 %  
 AS-COMPACTED DRY DENSITY 1462 kg/m<sup>3</sup>  
 AS-COMPACTED MOISTURE 24.1 %  
 AS-COMPACTED % COMPACTION 95 %



**CBR VALUE AT 2.54 mm  
 PENETRATION  
 4.8**

**CBR VALUE AT 5.08 mm  
 PENETRATION  
 4.2**

**COMMENTS**

Sample prepared to 95% of the maximum dry density at the optimum moisture content as determined from ASTM D698.

REPORT DATE 2024.Feb.26

REVIEWED BY  Jason Thompson, C.E.T.  
 Principal - Manager of Materials Testing Services

## ASTM D1883 - CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOILS

TO Dillon Consulting Ltd.  
 300 - 100 Innovation Drive  
 Winnipeg, Manitoba  
 R3T 6A8

PROJECT 24-R-06 - Local Streets Package -  
 Geotechnical Investigation

PROJECT NO. 123316892

ATTN Ali Campbell

REPORT NO. 9

DATE SAMPLED: 2024.Jan.17

DATE RECEIVED: 2024.Jan.17

DATE TESTED: 2024.Feb.19


SAMPLED BY: Stantec Consulting Ltd.

SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Donald Eliazar

**MATERIAL IDENTIFICATION**

MATERIAL USE	Subgrade	SUPPLIER	Existing Material
MAX. NOMINAL SIZE	4.75 mm	SOURCE	Existing Material
MATERIAL TYPE	Fat CLAY with sand (CH)	SAMPLE LOCATION	BH-12, 0.775 m
SPECIFICATION ID	Not Applicable	STANTEC SAMPLE NO.	4001
IMMERSION PERIOD	96 ± 2 hr	TARGET MAX. DRY DENSITY	1480 kg/m <sup>3</sup>
CONDITION OF SAMPLE	Soaked	TARGET OPTIMUM MOISTURE	25.0 %
SURCHARGE MASS	4.54 kg		
+19 mm OVERSIZE	0 %	AS-COMPACTED DRY DENSITY	1407 kg/m <sup>3</sup>
SWELL OF SAMPLE	3.02 %	AS-COMPACTED MOISTURE	25.0 %
POST-TEST MOISTURE	37.1 %	AS-COMPACTED % COMPACTION	95 %




**CBR VALUE AT 2.54 mm  
PENETRATION**  
3.5

**CBR VALUE AT 5.08 mm  
PENETRATION**  
3.1

**COMMENTS**

Sample prepared to 95% of the maximum dry density at the optimum moisture content as determined from ASTM D698.

REPORT DATE 2024.Feb.26

REVIEWED BY  Jason Thompson, C.E.T.  
 Principal - Manager of Materials Testing Services

**Table 2 - Compressive Strength Test Data**

Street	Core ID	Diameter (mm)	Length (mm)	L/D Ratio	Correction Factor	Peak Load (kN)	Compressive Strength (MPa)			
							Measured	Corrected		
Champlain St	BH-14	75.45	150.50	1.995	0.9996	215.19	48.13	48.11		
Champlain St	BH-16	75.60	171.34	2.266	1.0000	210.35	46.86	46.86		
Dumoulin St	BH-19	76.09	142.27	1.870	0.9896	290.85	63.96	63.30		
Dumoulin St	BH-22	87.98	176.16	2.002	1.0000	313.85	51.63	51.63		
[REDACTED]										
Baywater PI	BH-32	75.85	92.35	1.218	0.9223	149.23	33.03	30.46		
Baywater PI	BH-33	75.82	142.71	1.882	0.9906	133.84	29.64	29.36		
Courtwood PI	BH-34	75.79	113.32	1.495	0.9594	146.07	32.38	31.06		
Courtwood PI	BH-35	<i>Concrete core sample crumbled; unsuitable for testing.</i>								
[REDACTED]										