



- LEGEND**
- 1 SUPPLY & INSTALL 65mm CAL. TREES (5) AS PER SCD-517. TREE SPECIES TO BE APPROVED BY CONTRACT ADMINISTRATOR
  - 2 SUPPLY & INSTALL BENCH AS PER SCD-121 (4)
  - 3 SUPPLY & INSTALL WASTE RECEPTACLE AS PER SCD-119 (1)
  - 4 SUPPLY & INSTALL ACCESSIBLE PICNIC TABLE AS PER SCD-122 (1)
  - 5 SUPPLY & INSTALL WOOD MULCH GROUNDCOVER AS PER DETAIL 3/P.9-K-09 (30 SM)
  - 6 SUPPLY & INSTALL 2-12 PLAY EQUIPMENT AND 2-BAY SWING SET (2 BELT SWINGS, 2 INFANT SWINGS) WITH ENGINEERED WOOD FIBRE SAFETY SURFACING C/W ADDITIONAL 150mm DEPTH DRAINAGE STONE (340 SM)
  - 7 SUPPLY & INSTALL 2-TIER (22 LM) AND 3-TIER (28 LM) TIMBER EDGING AS PER SCD-651A. EXTENTS AS PER AS PER P.9-K-04
  - 8 SUPPLY & INSTALL 4-TIER (31 LM) AND 5-TIER (21 LM) REINFORCED TIMBER RETAINING WALL AS PER DETAIL 1/P.9-K-08. EXTENTS AS PER P.9-K-04
  - 9 SUPPLY & INSTALL TIERED LIMESTONE SEATING BLOCKS (11) AS PER DETAIL 2/P.9-K-08
  - 10 SUPPLY & INSTALL TOPSOIL AND SOD (1195 SM, PROJECT TOTAL)
  - 11 SUPPLY & INSTALL ASPHALT PATHWAY (102 TONNES) C/W SEPARATION GEOTEXTILE FABRIC (LIGHT GREY, 431 SM) OR COMBIGRID REINFORCING GEOTXTILE (DARK GREY, 134 SM), SUB-BASE COURSE (204 TONNES) AND BASE COURSE (29 CM) AS PER SCD-648 (GEOTEXTILE) OR DETAIL 2/P.9-K-08 (COMBIGRID). ALL QUANTITIES ARE PROJECT TOTALS
  - 12 SUPPLY & INSTALL DRAIN BASIN (1) AS PER SCD- 668 WITH SUBSURFACE DRAINAGE AS PER SCD-661 (18 LM) TIED INTO EXISTING CATCH BASIN
- ACCESSIBLE ENTRY (2) AS PER SCD-651C  
 APPROXIMATE LOCATION OF ACCESSIBLE ELEVATED PLATFORM ENTRY TO PLAY STRUCTURE (DETAIL 2/P.9-K-08 & 3/P.9-K-08). EXACT LOCATION OF PLATFORM ENTRY WITHIN THE LANDING AREA TO BE DETERMINED BY BIDDER

- MATERIAL NOTES**
1. ALL WORK TO CONFORM TO CURRENT CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS AND DETAILS UNLESS OTHERWISE NOTED.
  2. DIMENSIONS ARE IN METERS UNLESS OTHERWISE NOTED.
  3. DO NOT SCALE DRAWING.
  4. PROTECT EXISTING TREES TO REMAIN WITHIN CONSTRUCTION FENCING, TYP.



CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

<p>THE CITY OF WINNIPEG Planning, Property and Development Department Planning and Land Use Division Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)</p>	DESIGNED BY	CHECKED BY	MANAGER, PARK AND OPEN SPACES	DATE	DRAWING TITLE <b>PACIFIC JUNCTION PLAYGROUND REDEVELOPMENT MATERIALS PLAN AREA A</b>	DRAWING NO. <b>P.9-K-02</b>	
	DRAWN BY <b>TB</b>	APPROVED BY					MANAGER, PLANNING AND LAND USE DIVISION
	HORIZ. SCALE VERT. SCALE <b>1:250</b>	DATE <b>MARCH 2024</b>	SITE ADDRESS <b>685 CATHCART STREET</b>				