




**ENGINEERS
GEOSCIENTISTS
MANITOBA**

Certificate of Authorization

WSP Canada Inc.

No. 5750

1. ALL WORK AND MATERIALS TO BE IN ACCORDANCE WITH THE LATEST REVISION OF THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS.
2. CONTRACTOR TO CONFIRM THE LOCATION OF ALL UTILITIES/SERVICES IN THE FIELD PRIOR TO CONSTRUCTION.
3. ALL ROADWAY DIMENSIONS SHOWN ARE TO BACK OF CURB/EDGE OF PAVEMENT.
4. EXISTING ASPHALT PLANED AS SHOWN OR AS DIRECTED BY CONTRACT ADMINISTRATOR.
5. AS EXISTING CONCRETE RUBBLIZED AS SHOWN OR AS DIRECTED BY CONTRACT ADMINISTRATOR.
6. SAWCUT EXISTING CURB AND GUTTER ALONG LINE OF GUTTER AND REMOVE.
7. CLASS A GEORGD TO BE INSTALLED OVERLAYING RUBBLIZED CONCRETE AS DIRECTED BY CONTRACT ADMINISTRATOR.
8. 200mm PARTIAL CONCRETE SLAB PATCHES SHOWN ARE ONLY A REPRESENTATIVE APPROXIMATION OF THE TENDERED QUANTITIES.
9. STOCKPILE REQUIRED EXCAVATED MATERIAL ALONG MEDIAN SHOULDER TO REGRADE BOULEVARD WHERE PROPOSED PAVEMENT DRAINS TO THE NORTH.
10. ALL BOULEVARDS HYDRANTS, MANHOLES, AND CATCH BASINS IN WORK AREA TO GRADE.
11. ADJUST ALL WATER VALVES, HYDRANTS, MANHOLES, AND CATCH BASINS IN WORK AREA TO GRADE.

 Winnipeg	<h1 style="margin: 0;">THE CITY OF WINNIPEG</h1> <h2 style="margin: 0;">PUBLIC WORKS DEPARTMENT</h2> <h3 style="margin: 0;">ENGINEERING SERVICES DIVISION</h3>
<h2 style="margin: 0;">ABINOJII MIKANAH WESTBOUND - RUBBLIZATION AND MILL & FILL</h2> <p style="margin: 0;">ST. MARY'S RD /ABINOJII MIKANAH INTERSECTION</p> <p style="margin: 0;">PAVEMENT RENEWAL</p>	
<div style="border: 1px solid black; display: inline-block; padding: 2px;"> CITY DRAWING NUMBER P-3592-05 </div>	
<div style="border: 1px solid black; display: inline-block; padding: 2px;"> SHEET 05 OF 25 </div>	
<div style="border: 1px solid black; display: inline-block; padding: 2px;"> TENDER NO. 166-2025 </div>	