



NOTE:  
THE PROFILE SLOPE PROVIDED IS THE VERTICAL PROFILE OF THE  
COMPLETED BRIDGE FOLLOWING CONSTRUCTION. SLOPES GIVEN  
ALONG CONTROL LINE GOING UP STATION. UNLESS OTHERWISE  
ACCOUNTED FOR THE BEARING DESIGNER, THE BEARING SOLE PLATE  
SHALL BE TAPERED TO BE LEVEL FOLLOWING BRIDGE CONSTRUCTION.

